



Final Environmental Impact Statement for the Disposal and Reuse of the Department of Defense Housing Facility Novato, California



Volume I

November 1997



19971121 045

Engineering Field Activity, West
Naval Facilities Engineering Command

DTIC QUALITY INSPECTED 3

PAGES 1 THRU 33 IS PART OF A PRELIMINARY
TRANSCRIPT AND INTENTIONALLY LEFT OUT

PER: GARY MUNEKAWA

(415) 244-3022

NAVAL FACILITIES ENGINEERING COMD

SAN BRUNO, CALIF.



DEPARTMENT OF THE NAVY

ENGINEERING FIELD ACTIVITY, WEST
NAVAL FACILITIES ENGINEERING COMMAND
900 COMMODORE DRIVE
SAN BRUNO, CALIFORNIA 94066-5006

IN REPLY REFER TO:

5090.1B
7032GM/EP8-1377
19 November 1997

SUBJECT: NOTICE OF AVAILABILITY OF FINAL ENVIRONMENTAL
IMPACT STATEMENT (EIS) FOR THE DISPOSAL AND PROPOSED
REUSE OF THE DEPARTMENT OF DEFENSE HOUSING FACILITY
(DODHF) NOVATO, CA.

The Department of Defense Housing Facility (DODHF) Novato closed on September 30, 1996 pursuant to the Defense Base Closure and Realignment Act (Public Law 101-510) of 1990, as implemented by the base closure process of 1993.

As part of this process, the Department of the Navy prepared a Final Environmental Impact Statement (EIS) to evaluate the potential for significant environmental direct impacts from Navy disposal and indirect impacts from community reuse of the DODHF Novato property and structures in Novato, California. The Final EIS has been prepared in accordance with Section 102 (2)(c) of the National Environmental Policy Act (NEPA) of 1969 as implemented by the Council on Environmental Quality regulations (40 CFR Parts 1500 - 1508).

The Hamilton Reuse Planning Authority (HRPA) developed a Final Reuse Plan (Hamilton Army Airfield Reuse Plan) for the DODHF Novato property that was adopted by the City of Novato in October 1995. The Reuse Plan was subsequently revised in February 1996, and again in November 1996. The preferred reuse alternative in the Final EIS is the Revised Reuse Plan Alternative. The Revised Reuse Plan proposes demolishing existing housing and constructing new housing units at Rafael Village and reusing existing Main Site buildings and structures for uses similar to historic uses.

In addition to the Revised Reuse Plan Alternative, the other alternatives analyzed in the Final EIS include an Open Space Alternative that would be similar to the Revised Reuse Plan, but would have 500 fewer housing units, more open space, and more community facilities. A "No Action" Alternative that would result in the DODHF Novato property remaining in federal government ownership in a caretaker status was also analyzed.

There are no significant impacts associated with the Navy disposal action or the No Action Alternative. The only significant and unmitigable impact would be to the continued exposure of existing housing areas to noise levels above 60 decibels under each reuse alternative. Potentially significant and mitigable environmental impacts from reuse would occur to biological resources, geology and soils, water resources, traffic and circulation, air quality, and from generation of waste from demolition and construction activities. Implementation of mitigation measures identified in the Final EIS would reduce these environmental impacts to not significant or acceptable levels for all impacts except noise.

Public and agencies' review comments received on the Draft EIS have been incorporated and are responded to in the Final EIS.

The Final EIS is enclosed. It is also available at the following public libraries in the vicinity of DODHF Novato:

| | | |
|-------------------------------|-----------------------|----------------|
| Novato Public Library | 1720 Novato Boulevard | Novato, CA |
| Marin County Library | Marin Civic Center | San Rafael, CA |
| Petaluma Regional Library | 100 Fairgrounds Drive | Petaluma, CA |
| Sonoma County Central Library | 3rd and E Streets | Santa Rosa, CA |


Announcement of the availability of the Final EIS is being published in the November 21, 1997 Federal Register. This publication commences the 30-day Final EIS no action period. The 30-day no action period ends on December 22, 1997. After the 30-day no action period, the Navy will make a final decision and publish them in a Record of Decision.

Should you have questions or comments, please contact Mr. Gary J. MuneKawa at:

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
Attn: Mr. Gary J. MuneKawa, Environmental Planning Branch,
Code 7032GM,
900 Commodore Drive
San Bruno, California, 94066-5006
Telephone (650) 244-3022 or fax (650) 244-3206

For information concerning the community reuse planning process, please contact Mr. Ken Bell at telephone (714) 855-5738 or fax (714) 472-8122.

Thank you for participating in this process.


JOHN H. KENNEDY
Head, Environmental Planning Branch

Enclosure

FINAL
ENVIRONMENTAL IMPACT STATEMENT FOR THE
DISPOSAL AND REUSE OF DEPARTMENT OF DEFENSE HOUSING FACILITY
NOVATO, CALIFORNIA

Lead Agency: US Department of the Navy

Title of the Proposed Action: Environmental Impact Statement for the Disposal and Reuse of the Department of Defense Housing Facility Novato, California

Affected Jurisdictions: City of Novato and Marin County, California

Designation: Final Environmental Impact Statement

ABSTRACT


Pursuant to the Defense Base Closure and Realignment Act (Public Law 101-510) and the base closure decisions approved by Congress in 1993, the Department of Defense Housing Facility Novato (DODHF Novato) in Novato, California, was closed in September 1996. DODHF Novato includes two Navy-owned areas at the former Hamilton Air Force Base—the Main Site property and the off-site Rafael Village housing property. This environmental impact statement (EIS) analyzes the potential significant environmental consequences from the proposed Navy disposal of federal surplus property and structures and community reuse of DODHF Novato property, and has been prepared in accordance with the National Environmental Policy Act. The City of Novato may use this EIS in place of an environmental impact report, pursuant to the California Environmental Quality Act (CEQA) Guidelines, Section 15221.

The Preferred Alternative evaluated in this EIS is the disposal of federal surplus property and structures by the Navy and subsequent reuse as described by the Hamilton Army Airfield Reuse Plan of October 1995, as amended and approved in February 1996 by the City of Novato, and incorporating technical updates published in November 1996. The Revised Reuse Plan proposes demolishing existing housing and constructing new housing units at Rafael Village and reusing existing Main Site buildings and structures for uses similar to historic uses. An Open Space Alternative and the required No Action Alternative also are evaluated. This EIS includes analysis of potential direct environmental impacts from disposal and the No Action Alternative and indirect environmental impacts from community reuse related to land use, aesthetics and scenic resources, socioeconomics, public services, utilities, cultural resources, biological resources, geology and soils, water resources, traffic and circulation, air quality, noise, and hazardous materials and waste.

The only significant and unmitigable impact would be due to the continued exposure of existing housing areas to existing noise levels above 60 decibels under each of the reuse alternatives. No significant environmental impacts would result from disposal or from the No Action Alternative. Potentially significant and mitigable environmental impacts from reuse would occur to biological resources, geology and soils, water resources, traffic and circulation, and air quality and from generation of waste from demolition and construction activities. Implementation of mitigation measures identified in this EIS would reduce these environmental impacts to not significant or acceptable levels for all impacts except noise. Remediation of contaminated areas will continue to be the responsibility of the Navy.

For Further Information:

US Navy
Engineering Field Activity West
900 Commodore Drive
San Bruno, California 94066-5006
Attn: Mr. Gary J. Munekawa, Code 7032GM
Phone: (650) 244-3022 Fax: (650) 244-3206



November 1997

DOD QUALITY DISTRIBUTION 3

TABLE OF CONTENTS

Page No.

| | |
|---|------|
| EXECUTIVE SUMMARY..... | ES-1 |
| 1. PURPOSE OF AND NEED FOR ACTION..... | 1-1 |
| 1.1 PURPOSE AND NEED..... | 1-1 |
| 1.2 LOCATION AND HISTORY | 1-2 |
| 1.2.1 Location..... | 1-2 |
| 1.2.2 History | 1-2 |
| 1.3 RELATED PROCESSES AND DOCUMENTATION | 1-5 |
| 1.3.1 Property Disposal | 1-8 |
| 1.3.2 Environmental Cleanup..... | 1-11 |
| 1.4 DOCUMENT ORGANIZATION..... | 1-12 |
| 1.5 PUBLIC INVOLVEMENT | 1-13 |
| 1.5.1 Scoping Process..... | 1-14 |
| 1.5.2 Summary of Scoping Issues | 1-14 |
| 1.5.3 Public Review | 1-15 |
| 2. PROPOSED ACTION AND ALTERNATIVES..... | 2-1 |
| 2.1 DEVELOPMENT OF ALTERNATIVES..... | 2-1 |
| 2.1.1 Community Reuse Planning Process..... | 2-1 |
| 2.1.2 Selection of Alternatives | 2-2 |
| 2.2 DESCRIPTION OF ALTERNATIVES..... | 2-3 |
| 2.2.1 Navy Disposal Action..... | 2-4 |
| 2.2.2 Revised Reuse Plan Alternative - Preferred Alternative..... | 2-5 |
| 2.2.3 Open Space Alternative..... | 2-17 |
| 2.2.4 No Action Alternative | 2-18 |
| 2.3 ENVIRONMENTALLY PREFERABLE ALTERNATIVE..... | 2-26 |
| 2.4 ALTERNATIVES ELIMINATED FROM DETAILED CONSIDERATION | 2-26 |
| 2.4.1 Retain Existing Rafael Village Housing Units | 2-26 |
| 2.4.2 High Density Residential Development | 2-27 |
| 3. AFFECTED ENVIRONMENT | 3-1 |
| 3.1 LAND USE..... | 3-1 |
| 3.1.1 Land Use Plans and Regulations for DODHF Novato | 3-1 |
| 3.1.2 Land Use Regulations for Areas Surrounding DODHF Novato | 3-6 |
| 3.1.3 DODHF Novato Land Uses..... | 3-8 |
| 3.1.4 Surrounding Land Uses..... | 3-13 |
| 3.2 AESTHETICS AND SCENIC RESOURCES..... | 3-17 |
| 3.2.1 Aesthetic and Scenic Resource Policies..... | 3-17 |
| 3.2.2 Visual Characteristics of DODHF Novato Planning Areas | 3-17 |
| 3.3 SOCIOECONOMICS..... | 3-21 |
| 3.3.1 Regional Employment | 3-21 |
| 3.3.2 Population and Housing | 3-24 |
| 3.3.3 Schools..... | 3-28 |
| 3.3.4 Recreation..... | 3-30 |
| 3.3.5 Environmental Justice..... | 3-32 |
| 3.4 PUBLIC SERVICES..... | 3-35 |
| 3.4.1 Plans and Policies..... | 3-35 |
| 3.4.2 Fire Protection and Emergency Medical Services | 3-36 |
| 3.4.3 Police Protection..... | 3-37 |

TABLE OF CONTENTS *(continued)*

| | <u>Page No.</u> |
|--|-----------------|
| 3.5 UTILITIES | 3-38 |
| 3.5.1 Utility Regulations..... | 3-38 |
| 3.5.2 Water Distribution System | 3-38 |
| 3.5.3 Sanitary Sewer System | 3-40 |
| 3.5.4 Storm Drainage..... | 3-43 |
| 3.5.5 Electrical System | 3-46 |
| 3.5.6 Natural Gas..... | 3-47 |
| 3.5.7 Telephone System..... | 3-47 |
| 3.5.8 Cable Television..... | 3-48 |
| 3.5.9 Solid Waste Management | 3-48 |
| 3.6 CULTURAL RESOURCES | 3-49 |
| 3.6.1 Regulatory Framework..... | 3-50 |
| 3.6.2 Archeology | 3-50 |
| 3.6.3 History | 3-52 |
| 3.7 BIOLOGICAL RESOURCES | 3-56 |
| 3.7.1 Plans and Policies | 3-56 |
| 3.7.2 Vegetation..... | 3-58 |
| 3.7.3 Wildlife | 3-60 |
| 3.7.4 Sensitive Species | 3-60 |
| 3.7.5 Sensitive Habitats..... | 3-63 |
| 3.8 GEOLOGY AND SOILS | 3-68 |
| 3.8.1 Plans and Policies..... | 3-68 |
| 3.8.2 Regional and Site Geology | 3-69 |
| 3.8.3 Seismicity | 3-74 |
| 3.8.4 Soils..... | 3-76 |
| 3.8.5 Slope Stability | 3-76 |
| 3.9 WATER RESOURCES..... | 3-80 |
| 3.9.1 Plans and Policies | 3-80 |
| 3.9.2 Surface Water | 3-82 |
| 3.9.3 Flooding..... | 3-84 |
| 3.9.4 Ground Water..... | 3-87 |
| 3.9.5 Water Quality | 3-88 |
| 3.10 TRAFFIC AND CIRCULATION | 3-89 |
| 3.10.1 Regional Circulation | 3-89 |
| 3.10.2 Local Circulation | 3-93 |
| 3.10.3 Transit Facilities and Service | 3-100 |
| 3.10.4 Pedestrian and Bicycle Circulation..... | 3-102 |
| 3.10.5 Transportation Plans and Regulations..... | 3-102 |
| 3.11 AIR QUALITY | 3-104 |
| 3.11.1 Climate and Meteorology | 3-104 |
| 3.11.2 Ambient Air Quality Standards | 3-104 |
| 3.11.3 Existing Air Quality Conditions..... | 3-104 |
| 3.11.4 Air Emission Sources at DODHF Novato..... | 3-106 |
| 3.11.5 Air Quality Planning | 3-106 |
| 3.11.6 Regulatory Considerations..... | 3-107 |
| 3.12 NOISE | 3-109 |
| 3.12.1 Noise Terminology..... | 3-109 |
| 3.12.2 Existing Noise Conditions | 3-109 |
| 3.12.3 Noise Level Guidelines | 3-110 |

TABLE OF CONTENTS *(continued)*

| | <u>Page No.</u> |
|---|-----------------|
| 3.13 HAZARDOUS MATERIALS AND WASTE..... | 3-113 |
| 3.13.1 Hazardous Materials Regulations | 3-114 |
| 3.13.2 Hazardous Materials Management..... | 3-116 |
| 3.13.3 Hazardous Waste Management..... | 3-116 |
| 3.13.4 Installation Restoration Program | 3-116 |
| 3.13.5 Asbestos | 3-117 |
| 3.13.6 Polychlorinated Biphenyls (PCBs) | 3-118 |
| 3.13.7 Storage Tanks and Oil/Water Separators | 3-119 |
| 3.13.8 Pesticides | 3-123 |
| 3.13.9 Lead..... | 3-124 |
| 3.13.10 Radiological..... | 3-125 |
| 3.13.11 Medical And Biohazardous Waste | 3-125 |
| 3.13.12 Ordnance | 3-125 |
| 3.13.13 Radon..... | 3-125 |
| 4. ENVIRONMENTAL CONSEQUENCES..... | 4-1 |
| 4.1 LAND USE | 4-2 |
| 4.1.1 Disposal | 4-4 |
| 4.1.2 Revised Reuse Plan Alternative | 4-4 |
| 4.1.3 Open Space Alternative..... | 4-7 |
| 4.1.4 No Action Alternative..... | 4-9 |
| 4.2 AESTHETICS AND SCENIC RESOURCES | 4-10 |
| 4.2.1 Disposal | 4-11 |
| 4.2.2 Revised Reuse Plan Alternative..... | 4-11 |
| 4.2.3 Open Space Alternative..... | 4-12 |
| 4.2.4 No Action Alternative..... | 4-12 |
| 4.3 SOCIOECONOMICS | 4-14 |
| 4.3.1 Disposal | 4-16 |
| 4.3.2 Revised Reuse Plan Alternative..... | 4-18 |
| 4.3.3 Open Space Alternative..... | 4-23 |
| 4.3.4 No Action Alternative..... | 4-25 |
| 4.4 PUBLIC SERVICES..... | 4-27 |
| 4.4.1 Disposal | 4-28 |
| 4.4.2 Revised Reuse Plan Alternative..... | 4-28 |
| 4.4.3 Open Space Alternative..... | 4-29 |
| 4.4.4 No Action Alternative..... | 4-29 |
| 4.5 UTILITIES | 4-30 |
| 4.5.1 Disposal | 4-31 |
| 4.5.2 Revised Reuse Plan Alternative..... | 4-31 |
| 4.5.3 Open Space Alternative..... | 4-34 |
| 4.5.4 No Action Alternative..... | 4-35 |
| 4.6 CULTURAL RESOURCES | 4-36 |
| 4.6.1 Disposal | 4-38 |
| 4.6.2 Revised Reuse Plan Alternative..... | 4-39 |
| 4.6.3 Open Space Alternative..... | 4-40 |
| 4.6.4 No Action Alternative..... | 4-41 |

TABLE OF CONTENTS *(continued)*

| | <u>Page No.</u> |
|---|-----------------|
| 4.7 BIOLOGICAL RESOURCES | 4-42 |
| 4.7.1 Disposal | 4-45 |
| 4.7.2 Revised Reuse Plan Alternative | 4-45 |
| 4.7.3 Open Space Alternative..... | 4-46 |
| 4.7.4 No Action Alternative..... | 4-47 |
| 4.8 GEOLOGY AND SOILS | 4-48 |
| 4.8.1 Disposal | 4-49 |
| 4.8.2 Revised Reuse Plan Alternative | 4-49 |
| 4.8.3 Open Space Alternative..... | 4-51 |
| 4.8.4 No Action Alternative..... | 4-51 |
| 4.9 WATER RESOURCES..... | 4-53 |
| 4.9.1 Disposal | 4-54 |
| 4.9.2 Revised Reuse Plan Alternative | 4-55 |
| 4.9.3 Open Space Alternative..... | 4-60 |
| 4.9.4 No Action Alternative..... | 4-61 |
| 4.10 TRAFFIC AND CIRCULATION | 4-62 |
| 4.10.1 Disposal | 4-68 |
| 4.10.2 Revised Reuse Plan Alternative | 4-68 |
| 4.10.3 Open Space Alternative..... | 4-72 |
| 4.10.4 No Action Alternative..... | 4-74 |
| 4.11 AIR QUALITY..... | 4-77 |
| 4.11.1 Disposal | 4-78 |
| 4.11.2 Revised Reuse Plan Alternative | 4-78 |
| 4.11.3 Open Space Alternative..... | 4-82 |
| 4.11.4 No Action Alternative..... | 4-83 |
| 4.12 NOISE..... | 4-84 |
| 4.12.1 Disposal | 4-85 |
| 4.12.2 Revised Reuse Plan Alternative | 4-85 |
| 4.12.3 Open Space Alternative..... | 4-88 |
| 4.12.4 No Action Alternative..... | 4-89 |
| 4.13 HAZARDOUS MATERIALS AND WASTE..... | 4-90 |
| 4.13.1 Disposal | 4-92 |
| 4.13.2 Revised Reuse Plan Alternative | 4-93 |
| 4.13.3 Open Space Alternative..... | 4-96 |
| 4.13.4 No Action Alternative..... | 4-97 |
| 5. OTHER CONSIDERATIONS REQUIRED BY NEPA | 5-1 |
| 5.1 CUMULATIVE IMPACTS | 5-1 |
| 5.1.1 Major Cumulative Projects in the Vicinity of the Proposed Action..... | 5-2 |
| 5.1.2 Cumulative Effects of Reuse Alternatives | 5-5 |
| 5.2 GROWTH-INDUCING IMPACTS..... | 5-15 |
| 5.3 UNAVOIDABLE ADVERSE EFFECTS | 5-16 |
| 5.4 SHORT-TERM USES AND LONG-TERM PRODUCTIVITY | 5-16 |
| 5.5 IRREVERSIBLE /IRRETRIEVABLE COMMITMENT OF RESOURCES | 5-17 |
| 5.6 ENVIRONMENTAL JUSTICE | 5-18 |
| 6. CONSULTATION AND COORDINATION..... | 6-1 |
| 6.1 REPORT PREPARATION..... | 6-1 |
| 6.2 SCOPING | 6-2 |

TABLE OF CONTENTS *(continued)*

| | <u>Page No.</u> |
|-----------------------------------|-----------------|
| 7. LIST OF PREPARERS | 7-1 |
| 8. REFERENCES | 8-1 |
| 8.1 BIBLIOGRAPHY | 8-1 |
| 8.2 PERSONAL COMMUNICATIONS | 8-9 |
| 9. INDEX AND GLOSSARY | 9-1 |
| 9.1 INDEX | 9-1 |
| 9.2 GLOSSARY | 9-5 |
| 10. DISTRIBUTION LIST | 10-1 |

COMMENTS AND RESPONSES

APPENDICES

VOLUME I:

| | |
|------------|--------------------------|
| Appendix A | Photograph Documentation |
| Appendix B | Public Involvement |

VOLUME II:

| | |
|------------|-------------------------------------|
| Appendix C | Land Use |
| Appendix D | Utilities |
| Appendix E | Cultural Resources |
| Appendix F | Biological Resources |
| Appendix G | Traffic and Circulation |
| Appendix H | Final Environmental Baseline Survey |

LIST OF FIGURES

| | <u>Page No.</u> |
|---|-----------------|
| Figure ES-1 DODHF Novato Regional Location..... | ES-1 |
| Figure ES-2 Primary Elements of the Military Base Disposal Process..... | ES-3 |
| Figure ES-3 DODHF Novato Ownership..... | ES-5 |
| Figure ES-4 DODHF Novato Planning Areas..... | ES-6 |
| Figure 1-1 Regional Location Map | 1-3 |
| Figure 1-2 Local Vicinity Map..... | 1-4 |
| Figure 1-3 Ownership Map | 1-6 |
| Figure 1-4 Elements of Military Base Closure and Disposal Process..... | 1-7 |
| Figure 2-1 Comparison of Alternatives | 2-4 |
| Figure 2-2 DODHF Novato Planning Areas..... | 2-6 |
| Figure 2-3 DODHF Novato Rafael Village | 2-7 |
| Figure 2-4 DODHF Novato Main Site..... | 2-8 |
| Figure 3-1 Rafael Village and Surrounding Area Land Use..... | 3-9 |
| Figure 3-2 Main Site and Surrounding Area Land Use | 3-11 |
| Figure 3-3 Job Composition in Marin County (ROI) (1980 & 1995) | 3-23 |
| Figure 3-4 ROI Employment Growth (1990-2020)..... | 3-24 |
| Figure 3-5 Race/Ethnic Composition of Novato | 3-33 |
| Figure 3-6 Hamilton Army Airfield Historic District..... | 3-55 |
| Figure 3-7 Vegetation Communities..... | 3-59 |
| Figure 3-8 Rafael Village Wetlands | 3-66 |
| Figure 3-9 Main Site Wetlands..... | 3-67 |
| Figure 3-10 Locations of Principal Active Regional Faults | 3-71 |
| Figure 3-11 Geology..... | 3-73 |
| Figure 3-12 Map of Soils at DODHF Novato | 3-77 |
| Figure 3-13 Unstable Slopes at DODHF Novato..... | 3-79 |
| Figure 3-14 Regional Surface Water..... | 3-83 |
| Figure 3-15 100-Year Flood Area..... | 3-85 |
| Figure 3-16 Regional Transportation System | 3-90 |
| Figure 3-17 Existing Freeway Level of Service..... | 3-92 |
| Figure 3-18 Existing Street Classifications | 3-94 |
| Figure 3-19 Existing Intersection Operations | 3-98 |
| Figure 3-20 Existing Transit Routes and Park and Ride Lots | 3-101 |
| Figure 3-21 UST and AST Locations | 3-122 |
| Figure 4-1 Traffic Distribution Assumptions | 4-66 |
| Figure 4-2 Intersection Operations..... | 4-69 |
| Figure 4-3 Freeway Level of Service | 4-71 |
| Figure 5-1 Cumulative Project Location..... | 5-3 |
| Figure A-1 DODHF Planning Areas..... | A-2 |
| Figure D-1a Main Site Water Distribution System..... | D-2 |
| Figure D-1b Rafael Village Water Distribution System | D-3 |
| Figure D-2a Main Site Sanitary Sewer System..... | D-4 |
| Figure D-2b Rafael Village Sanitary Sewer System | D-5 |

LIST OF FIGURES *(continued)*

| | <u>Page No.</u> |
|--|-----------------|
| Figure D-3a Main Site Electrical System..... | D-6 |
| Figure D-3b Rafael Village Electrical System..... | D-7 |
| Figure D-4a Main Site Natural Gas System..... | D-8 |
| Figure D-4b Rafael Village Natural Gas System | D-9 |
| Figure F-1 Regional Location Map | F-37 |
| Figure F-2 DODHF Planning Areas..... | F-38 |
| Figure F-3 Rafael Village Survey Areas and Wetlands..... | F-40 |
| Figure F-4 Main Site Survey Areas and Wetlands..... | F-41 |
| Figure G-1 DODHF Novato Intersection Identification..... | G-5 |
| Figure G-2 Existing Intersection Operations (1-11) | G-6 |
| Figure G-3 Existing Intersection Operations (12-20)..... | G-7 |
| Figure G-4 Revised Reuse Plan Alternative Intersection Operations (1-11) | G-16 |
| Figure G-5 Revised Reuse Plan Alternative Intersection Operations (12-20)..... | G-17 |
| Figure G-6 Open Space Alternative Intersection Operations (1-11)..... | G-20 |
| Figure G-7 Open Space Alternative Intersection Operations (12-20) | G-21 |
| Figure G-8 No Action Alternative Intersection Operations (1-11) | G-24 |
| Figure G-9 No Action Alternative Intersection Operations (12-20) | G-25 |
| Figure H-1 EBS Zone Map | H-2 |

LIST OF TABLES

| | <u>Page No.</u> |
|---|-----------------|
| Table ES-1 Summary of Impacts and Significance..... | ES-9 |
| Table 2-1 DODHF Novato Alternatives..... | 2-19 |
| Table 2-2 Summary of Environmental Impacts and Mitigations from the Disposal and Reuse Alternatives..... | 2-20 |
| Table 3-1 Relation of Novato General Plan Chapters to State-Mandated Elements..... | 3-3 |
| Table 3-2 Novato General Plan Land Use Designations for DODHF Novato..... | 3-4 |
| Table 3-3 Land Use Planning Area Statistics..... | 3-8 |
| Table 3-4 Summary of New Hamilton Partnership Master Plan | 3-15 |
| Table 3-5 1980 and 1995 Labor Force and Employment Data for Marin County..... | 3-21 |
| Table 3-6 Historical Employment Composition for the ROI..... | 3-22 |
| Table 3-7 ROI Employment Projections (1995-2020) | 3-23 |
| Table 3-8 Historical and Projected Population, 1980-2020..... | 3-25 |
| Table 3-9 Number and Type of Housing, Novato 1995 | 3-26 |
| Table 3-10 Housing by Type of Tenure, Novato | 3-26 |
| Table 3-11 Value of Owner-occupied Housing Units in Novato, 1990 | 3-26 |
| Table 3-12 Monthly Rental Ranges, Novato 1994 | 3-27 |
| Table 3-13 Characteristics of Households, 1980-2020 | 3-28 |
| Table 3-14 Novato Unified School District Enrollment and Capacity | 3-29 |
| Table 3-15 Student Generation Factors | 3-30 |
| Table 3-16 Existing DODHF Novato Recreational Facilities..... | 3-31 |
| Table 3-17 1990 Race/Ethnic Composition and Poverty Status | 3-33 |
| Table 3-18 National Register Status of Known Archeological Sites Within the Project Area | 3-53 |
| Table 3-19 Sensitive Species Within the ROI..... | 3-61 |
| Table 3-20 Ambient Air Quality Standards Applicable in California..... | 3-105 |
| Table 3-21 Summary of Recent Air Quality Monitoring Data for Marin County..... | 3-106 |
| Table 3-22 Noise and Land Use Compatibility Standards | 3-112 |
| Table 3-23 Underground Storage Tanks | 3-120 |
| Table 3-24 Aboveground Storage Tanks..... | 3-123 |
| Table 4-1 Summary of Land Use Impacts..... | 4-3 |
| Table 4-2 Summary of Aesthetics and Scenic Resource Impacts | 4-10 |
| Table 4-3 Summary of Socioeconomic Impacts | 4-14 |
| Table 4-4 Environmental Justice..... | 4-17 |
| Table 4-5 Direct Job Generation | 4-19 |
| Table 4-6 Analysis of Job Impacts in Novato and Marin County..... | 4-20 |
| Table 4-7 Analysis of Population Impacts in Novato and the ROI Resulting From Reuse Alternatives..... | 4-21 |
| Table 4-8 Impact on School District Enrollments | 4-22 |
| Table 4-9 Recreation Facilities Proposed for Reuse Planning Areas..... | 4-23 |
| Table 4-10 Summary of Public Service Impacts..... | 4-27 |
| Table 4-11 Summary of Utilities Impacts | 4-30 |
| Table 4-12 Summary of Eligible Properties by Area..... | 4-38 |

LIST OF TABLES *(continued)*

| | <u>Page No.</u> |
|---|-----------------|
| Table 4-13 Summary of Biological Resource Impacts | 4-43 |
| Table 4-14 Sensitive Species that May Exist Within the ROI..... | 4-44 |
| Table 4-15 Summary of Geologic and Soils Impacts | 4-48 |
| Table 4-16 Summary of Water Resources Impacts..... | 4-53 |
| Table 4-17 Summary of Traffic and Circulation Impacts..... | 4-63 |
| Table 4-18 Net New Trip Generation Summary for All Alternatives | 4-65 |
| Table 4-19 Summary of Air Quality Impacts | 4-78 |
| Table 4-20 Comparison of Vehicle Travel and Emission Estimates for Alternatives | 4-80 |
| Table 4-21 Summary of Carbon Monoxide Dispersion Modeling Results | 4-81 |
| Table 4-22 Summary of Noise Impacts..... | 4-85 |
| Table 4-23 Summary of Traffic Noise Modeling Results | 4-86 |
| Table 4-24 Summary of Hazardous Material and Waste Impacts..... | 4-91 |
| Table 4-25 Hazardous Material Usage By Land Use Category..... | 4-93 |
| Table 5-1 Cumulative Projects..... | 5-2 |
| Table 5-2 Cumulative Intersection Levels of Service AM Peak Hour | 5-10 |
| Table 5-3 Cumulative Intersection Levels of Service PM Peak Hour..... | 5-11 |
| Table 5-4 Cumulative Freeway Levels of Service | 5-13 |
| Table B-1 DODHF Novato Disposal and Reuse EIS Scoping Comment Summary..... | B-12 |
| Table C-1 Summary of DODHF Novato Residential Buildings..... | C-2 |
| Table C-2 Summary of DODHF Novato Nonresidential Buildings | C-3 |
| Table E-1 Historic Status of DODHF Novato Buildings..... | E-2 |
| Table G-1 Level of Service Criteria for Basic Freeway Sections | G-1 |
| Table G-2 Level of Service Criteria for Intersections | G-2 |
| Table G-3 June 1995 Peak Hour LOS for Key Segments of Regional Freeways | G-3 |
| Table G-4 Functional Route Classification | G-4 |
| Table G-5 Trip Rates, Reduction Factors, and Sources..... | G-8 |
| Table G-6 Traffic Distribution Assumptions..... | G-9 |
| Table G-7 Intersection Levels of Service AM Peak Hour..... | G-10 |
| Table G-8 Intersection Levels of Service PM Peak Hour | G-11 |
| Table G-9 Freeway Levels of Service AM Peak Hour..... | G-12 |
| Table G-10 Freeway Levels of Service PM Peak Hour | G-13 |
| Table G-11 Revised Reuse Plan Alternative (Preferred Alternative) Trip Generation | G-14 |
| Table G-12 Open Space Alternative Trip Generation | G-18 |
| Table G-13 No Action Alternative Trip Generation..... | G-22 |

ACRONYMS AND ABBREVIATIONS

| | |
|----------------------------------|---|
| A-2 | Limited Agriculture |
| A-60 | Agriculture |
| A-P | Administrative Professional |
| AB | Assembly Bill |
| ABAG | Association of Bay Area Governments |
| AC | Asbestos Cement |
| ACHP | Advisory Council on Historic Preservation |
| ACM | asbestos-containing material |
| AHERA | Asbestos Hazards Emergency Response Act |
| AM | before noon |
| AST | aboveground storage tank |
| BAAQMD | Bay Area Air Quality Management District |
| Basin | Basin Research Associates, Inc. |
| BCDC | Bay Conservation and Development Commission |
| BCP | BRAC Cleanup Plan |
| bgs | below ground surface |
| BMP | Best Management Practices |
| BOQ | Bachelor Officers Quarters |
| BRAC | Base Realignment and Closure |
| BRAC 1990 | Defense Base Closure and Realignment Act of 1990 |
| C-1 | Retail Commercial |
| C-2 | General Business Commercial |
| C-P | Planned Commercial |
| C ₂ H ₃ Cl | vinyl chloride |
| Cal EPA | California Environmental Protection Agency |
| CARB | California Air Resources Board |
| CBC | California Building Code |
| CCR | California Code of Regulations |
| CDFG | California Department of Fish and Game |
| CEQ | Council on Environmental Quality |
| CEQA | California Environmental Quality Act |
| CERCLA | Comprehensive Environmental Response, Compensation, and Liability Act |
| CERFA | Community Environmental Response Facilitation Act |
| CFCU | Community Facilities and Civic Uses |
| CFR | Code of Federal Regulations |
| cfs | cubic feet per second |
| CI | cast iron |
| CIWMB | California Integrated Waste Management Board |
| CMA | Congestion Management Agency |
| CNEL | community noise equivalent level |
| CNO | Chief of Naval Operations |
| CNPS | California Native Plant Service |
| CO | carbon monoxide |
| COE | Army Corps of Engineers |
| CWA | Clean Water Act |
| CZMA | Coastal Zone Management Act |
| dB | decibel |
| dBA | A-weighted decibel scale |
| DBCRA | Defense Base Closure and Realignment Act |
| DI | ductile iron |
| DOD | Department of Defense |

ACRONYMS AND ABBREVIATIONS *(continued)*

| | |
|------------------|--|
| DODHF | Department of Defense Housing Facility |
| Dr. | Drive |
| DTSC | Department of Toxic Substance Control |
| EB | east bound |
| EBS | Environmental Baseline Survey |
| EFA West | Engineering Field Activity West |
| EIR | Environmental Impact Report |
| EIS | Environmental Impact Statement |
| EPA | United States Environmental Protection Agency |
| ESA | Endangered Species Act |
| FAR | floor area ratio |
| FCM | Federated Coast Miwok |
| F.I.R.E. | Finance/Insurance/Real Estate |
| FEMA | Federal Emergency Management Agency |
| FFSRA | Federal Facility Site Remediation Agreement |
| FIFRA | Federal Insecticide, Fungicide and Rodenticide Act |
| FOSL | Finding of Suitability to Lease |
| FOST | Finding of Suitability to Transfer |
| FPMR | Federal Property Management Regulations |
| GGBHTD | Golden Gate Bridge, Highway, and Transportation District |
| GSA | General Services Administration |
| H ₂ S | hydrogen sulfide |
| HAAF | Hamilton Army Airfield |
| HABS | Historic American Building Survey |
| HAC | Hamilton Advisory Committee |
| HCM | Highway Capacity Manual |
| HRPA | Hamilton Reuse Planning Authority |
| HUD | United States Department of Housing and Urban Development |
| HWCL | Hazardous Waste Control Law |
| HWL | high water line |
| kV | kilovolt |
| LBP | lead-based paint |
| Ldn | day-night average noise level |
| Leq | equivalent noise levels |
| LOS | level of service |
| LRA | Local Redevelopment Authority |
| LTMS | Long Term Management Strategy |
| M-2 | Heavy Industrial |
| M-P | Planned Industrial |
| MAB | Multi-Agency Board |
| MCFCWCD | Marin County Flood Control and Water Conservation District |
| MCTD | Marin County Transit District |
| MG | million gallons |
| mgd | million gallons per day |
| MPH | miles per hour |
| msl | mean sea level |
| NAGPRA | Native American Graves Protection and Repatriation Act |
| NB | north bound |
| NCO | Noncommissioned Officer |
| NEH | Northbay Ecumenical Homes |
| NEPA | National Environmental Policy Act |
| NESHAP | National Emissions Standards for Hazardous Air Pollutants |


ACRONYMS AND ABBREVIATIONS *(continued)*

| | |
|------------------|---|
| NFPD | Novato Fire Protection District |
| NHP | New Hamilton Partnership |
| NHPA | National Historic Preservation Act |
| N/O | north of |
| NO ₂ | nitrogen dioxide |
| NO _x | nitrogen oxides |
| NOI | Notice of Intent |
| NPDES | National Pollution Discharge Elimination System |
| NPL | National Priorities List |
| NRHP | National Register of Historic Places |
| NSD | Novato Sanitary District |
| NUSD | Novato Unified School District |
| NWIC | Northwest Information Center |
| NWP | Northwest Pacific Railroad |
| O ₃ | ozone |
| OSHA | Occupational Safety and Health Administration |
| OVRFL | overflow |
| OWS | oil/water separator |
| P-C | Planned Community |
| PA | Planning Area |
| PAR | PAR Environmental Services, Inc. |
| Pb | lead |
| PCBs | polychlorinated biphenyls |
| pCi/L | picocuries per liter |
| PG&E | Pacific Gas and Electric Company |
| PL | Public Law |
| PM | afternoon |
| PM ₁₀ | inhalable particulate matter (under 10 microns in diameter) |
| ppm | parts per million |
| psig | pounds per square inch gauge |
| PVC | polyvinyl chloride |
| PWCSFB | Public Works Center, San Francisco Bay |
| R-1 | Single Family |
| R-2-H | Duplex Residential |
| R-3 | Multiple Residential |
| R-P | Planned Residential |
| RC | reinforced concrete |
| RCP | reinforced concrete pipe |
| RCRA | Resource Conservation and Recovery Act |
| ROD | Record of Decision |
| ROG | reactive organic compounds |
| ROI | Region of Influence |
| RPM | reinforced plastic mortar |
| RWQCB | Regional Water Quality Control Board |
| SARA | Superfund Amendments and Reauthorization Act |
| SB | Senate Bill |
| SECNAV | Secretary of the Navy |
| SHPO | State Historic Preservation Officer |
| S/O | south of |
| SO ₂ | sulfur dioxide |
| SO ₄ | sulfate particles |
| sp. | species |

ACRONYMS AND ABBREVIATIONS *(continued)*

| | |
|--------|--|
| ssp. | subspecies |
| St. | Street |
| SWPPP | Storm Water Pollution Prevention Plan |
| TAC | Technical Advisory Committee |
| TAZ | Traffic Analysis Zones |
| TDM | Transportation Demand management |
| TSCA | Toxic Substances Control Act |
| TSDF | Treatment, Storage, and Disposal Facility |
| UBC | Uniform Building Code |
| US 101 | United States Highway Route 101 |
| USACE | US Army Corps of Engineers |
| USC | United States Code |
| USCG | United States Coast Guard |
| USFWS | United States Fish and Wildlife Service |
| UST | underground storage tank |
| V | volt |
| VCP | vittrified clay pipe |
| V/C | volume to capacity ratio |
| VMT | vehicle miles traveled |
| WB | west bound |
| WGCEP | Working Group on California Earthquake Probabilities |

**DODHF
Novato**



EXECUTIVE SUMMARY

| | |
|--|-------|
| BACKGROUND | ES-1 |
| PURPOSE AND NEED | ES-2 |
| DOCUMENT PURPOSE | ES-2 |
| DISPOSAL PROCESS | ES-3 |
| RELATED PROCESSES AND DOCUMENTATION | ES-3 |
| PUBLIC INVOLVEMENT | ES-4 |
| PREFERRED ALTERNATIVE AND ALTERNATIVES | ES-4 |
| AFFECTED ENVIRONMENT | ES-8 |
| ENVIRONMENTAL CONSEQUENCES | ES-8 |
| OTHER CONSIDERATIONS REQUIRED BY NEPA | ES-14 |


EXECUTIVE SUMMARY

This environmental impact statement (EIS) evaluates the potentially significant impacts to the environment that may result from the Navy disposal and community reuse of the Department of Defense Housing Facility Novato (DODHF Novato) in Novato, California. DODHF Novato closed pursuant to the Defense Base Closure and Realignment Act of 1990 (Part A of Title XXIX of Public Law 101-510 [DBCRA]), as amended. This document has been prepared in accordance with the National Environmental Policy Act (NEPA) of 1969, the Council on Environmental Quality regulations on implementing NEPA, Navy policy (OPNAVINST 5090.1B), and the 1990 DBCRA, as amended by the 1993 Base Realignment and Closure (BRAC) process. The federal action evaluated in this EIS is the disposal of federal surplus property and structures at DODHF Novato, while the local action evaluated is the proposed reuse of DODHF Novato.

BACKGROUND

DODHF Novato is located in the southeast portion of the City of Novato, in eastern Marin County, California, approximately 20 miles north of San Francisco. DODHF Novato consists of approximately 411 acres of Navy-owned land on two sites. The 304-acre Main Site includes military family housing, a commissary, a post exchange, community service areas, a bowling alley, officers' club, and recreational fields. The 107-acre Rafael Village, located one mile northwest of the Main Site, includes 503 housing units (Figure ES-1).

Figure ES-1
DODHF Novato Regional Location



DODHF Novato was the housing and community services portion of the former Hamilton Air Force Base. Other parts of the former base, adjacent to DODHF Novato but not part of the Navy disposal and community reuse action, include the 720-acre former Hamilton Army Air Field and the 415-acre site being developed under the New Hamilton Partnership Master Plan. A six-acre US Coast Guard (USCG) parcel and a 105-foot railroad right-of-way owned by the Golden Gate Bridge, Highway, and Transportation District (GGBHTD) also are located adjacent to DODHF Novato.

PURPOSE AND NEED

The Department of Defense has for the past several years been reducing its basing and staffing requirements to match current force structure plans. Congressional action, under the provisions of the Defense Authorization Amendments and the DBCRA, established a process to close and realign military bases. Public Works Center San Francisco Bay (PWCSFB), which owns DODHF Novato, was identified for disestablishment in the BRAC recommendation approved by Congress in October 1993. All property owned by PWCSFB, including DODHF Novato, will be closed and disposed of (transferred or sold). DODHF Novato Main Site was closed on September 30, 1996. A portion of DODHF Novato, the Rafael Village housing area, was closed on September 30, 1995.

Decisions regarding which bases to close, relocate, or realign were exempted by Congress from NEPA documentation requirements under the DBCRA. However, under NEPA, the Navy must consider the environmental effects of reasonable alternatives to the disposal and reuse of property at closing bases. The disposal process is regulated by the DBCRA of 1994 (Public Law 103-160); the Federal Property and Administrative Services Act of 1949, as amended; the Surplus Property Act of 1944; and the Federal Property Management Regulations (FPMR). The Base Closure Community Development and Homeless Assistance Act of 1994 (PL 103-421) also addresses disposal methods associated with base closure. The Navy also must comply with the 1994 Defense Authorization Act and other laws and regulations, including Title 10 of the US Code and Navy regulations affecting the disposition of real property.

DOCUMENT PURPOSE


This EIS is intended to provide a general level of information on the potential environmental impacts resulting from Navy disposal and community reuse of DODHF Novato. The reuse alternatives evaluated in the EIS were developed based on the Hamilton Army Airfield Final Reuse Plan (Hamilton Reuse Planning Authority 1995b) and the community planning process. The EIS is not intended to provide information on site-specific development options. The

Navy will use the EIS in its consideration of disposal options in its Record of Decision (ROD). The ROD will consider significant impacts and mitigations as the result of Navy disposal. The City of Novato may use the EIS in place of an environmental impact report (EIR) pursuant to the California Environmental Quality Act (CEQA) Guidelines, Section 15221. This EIS is being prepared at a program level of detail. When site-specific development plans are submitted the necessary level of project description detail required for CEQA compliance will need to be reviewed and verified. Following disposal, no additional NEPA review by the Navy would be required.

DISPOSAL PROCESS

Numerous sequential actions are required before BRAC property can be disposed of (Figure ES-2). The Navy is responsible for environmental cleanup (see Section 3.13), property disposal (see Section 1.3.1), and environmental impact analysis (preparation of this EIS). The City of Novato and Hamilton Reuse Planning Authority are responsible for community reuse planning (see Section 2.1.1).

Figure ES-2
Primary Elements of the Military Base Disposal Process



RELATED PROCESSES AND DOCUMENTATION

DOD policy requires the preparation of an environmental baseline survey (EBS) prior to the sale, lease, or transfer of real property. The EBS also is used to comply with the requirements of the Community Environmental Response Facilitation Act, an amendment of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA-Section 120(h)). The basewide EBS for DODHF Novato was completed in October 1995 (US Navy 1995a) and documented the environmental conditions of real property at DODHF Novato and adjacent properties.

The BRAC Cleanup Plan (BCP) for a closing base documents the status of environmental restoration and associated compliance programs and was mandated by President Clinton's July 2, 1993 plan to expedite cleanup and promote early reuse of closing bases. The BCP for DODHF Novato (US Navy 1995b) was completed in March 1995 and updated in March 1996 (US Navy 1996a). The findings of the EBS and BCP are summarized in Section 3.13, Hazardous Materials and Waste.

PUBLIC INVOLVEMENT

The EIS process is designed to involve the public in federal decision-making. Opportunities to comment on and participate in the process have been provided during the preparation of this EIS (see Section 1.5 and Appendix B). Comments from agencies and the public are solicited throughout the process to help identify the primary issues associated with the site's disposal and proposed reuse. Efforts have been made during the public notification process to include all interested regulatory agencies, Novato area residents, and community organizations. In accordance with Executive Order 12898 on Environmental Justice, particular attention has been paid to assure participation by minority and low-income populations in the area potentially affected by disposal and reuse.

PREFERRED ALTERNATIVE AND ALTERNATIVES

The Preferred Alternative considered in this EIS is the disposal of federal surplus land at DODHF Novato by the Navy and subsequent community reuse consistent with the revised Reuse Plan. The reuse alternatives considered in this EIS are based upon the Reuse Plan developed by the Hamilton Reuse Planning Authority through the community planning process described below.


Community Reuse Planning

The reuse planning process for DODHF Novato began when Congress approved closure of the facility in October 1993. The primary objective of the planning process was to develop a community reuse plan for the entire former Hamilton Air Force Base complex that reflects community consensus through substantial public involvement. A second objective was to identify affordable housing opportunities to satisfy a significant portion of Novato's state-mandated affordable housing quotas and to assist homeless providers.

In 1974, the land that comprised the former Hamilton Air Force Base was parceled out to the US Army, the US Navy, the USCG, the GGBHTD, and the General Services Administration. The USCG and GGBHTD are retaining their parcels. The General Services Administration retained ownership of a


415-acre parcel that it auctioned off in 1984 to the Berg-Revoir Corporation; the Berg-Revoir Corporation later sold the land to the Martin Group for development under the New Hamilton Partnership Master Plan. Current land ownership patterns are shown on Figure ES-3. The reuse planning process divided the remaining former Hamilton Air Force Base into 10 planning areas and a runway area (Figure ES-4). Eight of the planning areas encompassed Navy-owned land (DODHF Novato), while one remaining planning area and runway area encompassed Army-owned land (Hamilton Army Airfield) and the other remaining planning area encompassed the Spanish Housing area, which is being transferred to USCG ownership. The terms "Hamilton Air Force Base" and "Hamilton Army Airfield" often are used interchangeably to refer to the entire facility before it was divided among different DOD and federal entities. This EIS uses "former Hamilton Air Force Base" when referencing the entire facility.

Figure ES-3
DODHF Novato Ownership



In March 1994, the City of Novato and Marin County agreed to establish a procedure for joint participation in the reuse planning process for the former Hamilton Air Force Base to ensure the protection of local and regional interests. The procedure included the creation of the Hamilton Advisory Committee (HAC), Technical Advisory Committee (TAC), and Multi-Agency Board (MAB).

Figure ES-4
DODHF Novato Planning Areas



Starting in February 1995, HAC held a series of public hearings to obtain public input in the formulation of reuse alternatives for the different planning areas. Based on this input, HAC developed reuse alternatives and forwarded them to the MAB. HAC did not recommend a preferred alternative nor did it recommend any policy direction on the various planning issues that arose during the public participation process. In July 1995, MAB selected preferred land use plans, which were then developed into the *Draft Hamilton Army Airfield Reuse Plan* released in August 1995. The Novato City Council adopted the final Reuse Plan in October 1995.

The final Reuse Plan took into account the original Department of Veterans Affairs and USCG transfer requests (Section 1.3.1). Since October 1995, the Department of Veterans Affairs has withdrawn its request for property and the specific footprint of the USCG property transfer changed. The MAB recommended adoption of the revised USCG request on January 16, 1996, and the City of Novato approved the revised USCG request on February 13, 1996. Under the revised request, the USCG would own the 142 acres of Spanish Housing land and facilities. This revised scenario was included in an updated Reuse Plan published in November 1996 and is reflected in the EIS Revised Reuse Plan Alternative.

Reuse Alternatives Overview

Reuse alternatives analyzed in this EIS include the Revised Reuse Plan Alternative (Preferred Alternative) and the Open Space Alternative.

Revised Reuse Plan Alternative - Preferred Alternative

The EIS Preferred Alternative is the implementation of the revised Reuse Plan. As described above and in Section 2.1.1 of this EIS, the revised Reuse Plan reflects the most current plans for the residential and nonresidential lands within Hamilton Army Airfield and DODHF Novato and provides land use direction for the City of Novato. The EIS analyzes the revised Reuse Plan as the Preferred Alternative since it reflects the scenario most likely to be implemented. The revised USCG footprint includes transfer of all Spanish Housing land and facilities.

The revised Reuse Plan can be characterized as promoting adaptive reuse of existing buildings and retention of existing land use patterns. Most existing structures at DODHF Novato are and would remain housing units under the revised Reuse Plan. The nonresidential buildings would be adapted for new uses but would retain their basic structure and appearance. Some buildings would be demolished or restored. The revised Reuse Plan identifies land uses for each planning area. The EIS analyzes the effects of these proposed land uses contained in the plan and evaluates the potential environmental impacts at buildout of the plan.

Open Space Alternative

One additional alternative has been developed to take advantage of the flexibility of demolition at Rafael Village. Under the Open Space Alternative, Rafael Village would be used for open space and parkland instead of residential uses. Developments could include creek restoration, playing fields, jogging and bike paths, playgrounds, and sitting areas. The Main Site uses would be similar to those under the Revised Reuse Plan Alternative except corporation yards would be allowed in the Commissary and Exchange Triangle planning areas, and all of the Town Center area would be used for community facilities. In addition, there would be less developed parkland and more open space in the Ballfields planning area.

No Action Alternative

Inclusion of the No Action Alternative is required by NEPA. The closure of the DODHF Novato property has been mandated by law and must be implemented. For this reason, the No Action Alternative evaluates the facility as closed but remaining indefinitely in federal ownership. Under the No

Action Alternative most of DODHF Novato would remain in federal ownership in a caretaker status after closure.

Environmentally Preferable Alternative

NEPA requires that an environmentally preferable alternative be identified. The No Action Alternative would be the environmentally preferable alternative, as described in Section 2.3.

AFFECTED ENVIRONMENT

The EIS provides a description of the existing environmental and socioeconomic conditions at DODHF Novato and surrounding properties. The setting discussion for each resource area identifies the region of influence (ROI) applicable to the specific resource area. An ROI is a geographic area in which impacts for a particular resource likely would occur. The ROI area for a resource having regional impacts will be different than the ROI area for a resource with localized impacts. Existing conditions are described for the following resources: land use, aesthetics and scenic resources, socioeconomics, public services, utilities, cultural resources, biological resources, geology and soils, water resources, traffic and circulation, air quality, noise, and hazardous materials and waste.

ENVIRONMENTAL CONSEQUENCES

The EIS evaluates the potential environmental consequences associated with Navy disposal and community reuse of DODHF Novato (Chapter 4). Table ES-1 summarizes the greatest level of significance for each alternative by resource area. These impacts have been separated into those that would result from Navy disposal and the No Action Alternative, and those that would result from implementing community reuse alternatives including the Revised Reuse Plan Alternative (Preferred Alternative) and the Open Space Alternative.

For purposes of the Navy NEPA analysis, direct environmental consequences or impacts are those associated with Navy disposal of surplus property and the No Action Alternative. Indirect impacts are those associated with community reuse of Navy surplus property. The Navy's roles and responsibilities for disclosing indirect reuse-related environmental impacts is to address reasonably foreseeable impacts. However, property reuse will occur after it is conveyed from federal ownership and in support of local reuse actions. Implementation of mitigation measures for reuse environmental impacts is a local responsibility and not the responsibility of the Navy.

As shown in Table ES-1, federal disposal and the No Action Alternative would have no impact or not significant impacts. Community reuse would result primarily in not significant or significant but mitigable impacts with the exception of noise, which would have a significant unmitigable impact from residential reuse in areas that would be exposed to existing high ambient noise levels (Section 4.12). Environmental consequences associated with each resource area are summarized below.

Table ES-1
Summary of Impacts and Significance

| Impact Issues | NAVY | | COMMUNITY REUSE | |
|---------------------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Land Use | ○ | ○ | ⊖ | ⊖ |
| Aesthetics and Scenic Resources | ○ | ⊖ | ⊖ | ⊖ |
| Socioeconomics | ○ | ○ | ⊖ | ⊖ |
| Public Services | ○ | ⊖ | ⊖ | ⊖ |
| Utilities | ○ | ○ | ◐ | ◐ |
| Cultural Resources | ⊖ | ⊖ | ⊖ | ⊖ |
| Biological Resources | ○ | ○ | ◐ | ◐ |
| Geology and Soils | ○ | ○ | ◐ | ◐ |
| Water Resources | ○ | ⊖ | ◐ | ◐ |
| Traffic and Circulation | ○ | ○ | ◐ | ◐ |
| Air Quality | ○ | ○ | ◐ | ◐ |
| Noise | ○ | ○ | ● | ● |
| Hazardous Materials and Waste | ○ | ⊖ | ⊖ | ⊖ |

LEGEND:

Level of Impact

- - Significant impact
- ◐ - Significant and mitigable impact
- ⊖ - Not significant impact
- - No impact

Land Use

The disposal of DODHF Novato would not result in any land use impacts. The reuse of DODHF Novato would not result in any significant land use impacts. Demolition and construction activities at the Rafael Village, Commissary Triangle, and Exchange Triangle planning areas would have temporary effects on surrounding residential areas. These would be of short duration and not significant. Reuse of the Commissary Triangle and Exchange Triangle planning areas as detailed under the reuse alternatives would be compatible with surrounding land uses. The Reuse Plan specifies land use policies 3.6.2.5.1 through 3.6.2.5.7 as measures to achieve compatible land use

with Lanham Village and other adjacent uses. No impacts would result from reuse of the other planning areas as the type of land use would not change.

Aesthetics and Scenic Resources

Disposal of DODHF Novato would have no impact on aesthetic and scenic resources. Reuse of DODHF Novato would have no significant impact on aesthetic and scenic resources. Construction and demolition activities could have short-term visual effects but these would not be significant. Reuse of Rafael Village for new residential housing (Revised Reuse Plan Alternative) or as open space (Open Space Alternative) would have a beneficial visual effect.

Socioeconomics

Disposal of DODHF Novato would have no impacts on socioeconomic factors. Reuse of DODHF Novato would have a beneficial effect on the regional economy and recreational opportunities. Reuse would not significantly affect population, housing, or schools in the region. Reuse would have a beneficial effect on the homeless and low-income population of the area through the creation of affordable housing and transitional/ emergency shelter housing.

Public Services

Disposal of DODHF Novato would have no impacts on police, fire, or emergency medical services in the Novato area. Reuse of DODHF Novato would have no significant impacts on police, fire, or emergency medical services in the Novato area. Any increase in service needed as a result of reuse would be funded with taxes generated by the new development.

Utilities

Disposal of DODHF Novato would have no impacts on utilities including electric, natural gas, telephone, water, and sanitary sewer capacity. Reuse of DODHF Novato would have no significant impacts on electric, natural gas, telephone, and water utilities, water supply, sanitary sewer capacity, or landfill life. A significant and mitigable impact would result if demolition of Rafael Village structures prevented Marin County from meeting the Cal EPA solid waste reduction standards of 50 percent by 2000. The California Integrated Waste Management Board has been exploring ways to assist localities to divert construction and demolition debris from landfills through reuse, recycling, and other strategies.

Cultural Resources

No significant effects to National Register of Historic Places-eligible resources would occur from Navy disposal of DODHF Novato because historic properties would be transferred through National Park Service conveyances that assure preservation of historic property. No significant impacts to historic resources would result from community reuse because reuse of these properties would be restricted through the conditions of the public benefit conveyances in a manner that assures the continued preservation of these resources. No significant impacts to subsurface prehistoric and historic archeological resources or noncontributing structures would occur under reuse.

Biological Resources

No impacts to biological resources would result from disposal of DODHF Novato. Increased erosion could result in a significant and mitigable indirect impact to sensitive wetland and riparian habitats in San Jose Creek adjacent to the southern boundary of Rafael Village and other wetland habitats. These impacts could be reduced to less than significant levels by implementing standard erosion control measures. No significant impacts are expected to nonsensitive species or habitats from the reuse of DODHF Novato. No significant impacts would result in the upland sensitive habitats (valley oak woodland and California bay forest) since reuse activities would not occur within these areas and the existing uses of these areas would not change.

Geology and Soils

Disposal of DODHF Novato would have no impact on geology and soils. A potentially significant and mitigable impact could occur if demolition and new construction in Rafael Village undermines or weakens unstable slopes. A significant and mitigable impact could result if existing and proposed improvements in certain Main Site areas, particularly those on reclaimed land underlain by imported fill and bay mud, were exposed to potentially damaging levels of ground shaking during a large earthquake centered on one of the three nearest active faults. These impacts would be mitigable by identifying geologic hazards through geotechnical studies and performing seismic studies on existing structures to determine necessary upgrades.

Water Resources

Disposal of DODHF Novato would have no impact on water resources. Significant and mitigable impacts could result from grading, demolition, and construction of new Rafael Village area houses by disturbing the soil and increasing erosion/sedimentation into San Jose Creek, affecting surface water

quality. Significant and mitigable impacts also could result from grading, demolition, and construction of new buildings in any of the Main Site planning areas from soil disturbance and increased erosion/sedimentation into Pacheco Creek and downstream in Ignacio Reservoir, Novato Creek, and San Pablo Bay. These impacts could be mitigated to not significant levels through implementation of standards erosion control measures.

Significant and mitigable impacts could result if new Rafael Village area houses are developed in mapped 100-year floods from San Jose Creek, subjecting those houses to potential flood hazards. This impact could be mitigated by restricting development to outside of the flood plain boundaries. Significant and mitigable impacts could result if development and reuse of Commissary Triangle and the Exchange Triangle subjected residents, workers, and other occupants of those areas to flood hazards in the event of a 100-year flood on Pacheco Creek. This impact would be mitigated by limiting reuse of these areas until after completion of the planned new levees west of the airfield or raising the base level of developed areas of the site to a minimum of 10 feet (mean sea level).

Significant and mitigable impacts could result from the existing Rafael Village storm drain system, which was designed to handle a 10-year recurrence interval rainfall, being inconsistent with the City of Novato's 25-year recurrence interval standard. To mitigate this impact the city should require upgrade of system upon redevelopment of Rafael Village. Significant and mitigable flood hazard impacts also could occur if constrictions in the drainage facilities downstream of Main Gate Road resulted in flooding of the Exchange Triangle area and adjacent lands along Pacheco Creek immediately upstream of that area during 100-year storm events. To mitigate this impact, the deficient drainage facilities should be replaced and expanded as necessary to convey 100-year flood flows concurrent with the redevelopment of the Exchange Triangle area.

Traffic and Circulation

Disposal of DODHF Novato would have no impact on traffic and circulation. Reuse of DODHF Novato would have no significant impacts on local intersection operations or regional freeways. A significant and mitigable impact would result from the increase in demand for transit services from reuse of DODHF Novato under the reuse alternatives. This impact could be mitigated by constructing or improving internal roadways to accommodate transit vehicles or by providing a shuttle service. Reuse of DODHF Novato would contribute cumulatively to the regional traffic conditions, but to a less significant degree than under the City of Novato Preferred General Plan. This is because the reuse alternatives would generate fewer vehicle trips than projected vehicle trips for DODHF Novato under the Preferred General Plan.

Air Quality

Disposal of DODHF Novato would not result in any air quality impacts. Property disposal actions generally qualify as de minimis actions under EPA's Clean Air Act conformity determination rule. A significant and mitigable impact could result from building demolition, renovation, and construction activities generating localized dust nuisance conditions. Implementation of dust control measures would reduce potential impacts to a not significant level. No significant air quality impacts would result from traffic-related ozone precursor emissions or carbon monoxide.

Noise

Disposal of DODHF Novato would not result in any noise impacts. Significant and mitigable noise impacts from building demolition, renovation, and construction activities associated with reuse of the Rafael Village, Commissary Triangle, and Exchange Triangle planning areas would occur from causing temporary noise disturbances to adjacent land uses. Limiting the use of heavy construction equipment and outdoor power tools to normal daytime hours would reduce potential noise impacts to a less than significant level. A significant unmitigable noise impact would result from residential reuse in areas that would be exposed to existing ambient noise levels significantly above the land use compatibility guidelines provided in the Novato General Plan. While not completely mitigable, the City of Novato and California Department of Transportation should evaluate the feasibility of additional sound walls along US 101 in order to reduce traffic noise impacts on adjacent properties. During detailed planning for new housing units in Rafael Village, the City of Novato should consider site designs that provide for sound walls along Ignacio Boulevard. No significant impacts to surrounding land uses would result from on-site traffic resulting from reuse.

Hazardous Materials and Waste

Disposal of DODHF Novato would not result in any hazardous materials or waste-related impacts. Reuse of DODHF Novato would not result in any significant hazardous materials or waste-related impacts. Hazardous materials used and waste generated under the reuse alternatives would be regulated by existing state and federal regulations. Remediation of contaminated areas will continue to be the responsibility of the Navy, subject to applicable federal and state regulations.

OTHER CONSIDERATIONS REQUIRED BY NEPA

Chapter 5 discusses other topics required by NEPA; these include an analysis of cumulative impacts, identification of growth-inducing impacts, unavoidable adverse effects, and irreversible or irretrievable commitment of resources, the relationship between short-term uses and long-term productivity, identification of any unavoidable adverse impacts from the alternatives, and environmental justice. These topics are summarized below.

Cumulative Impacts

The reuse alternatives, in conjunction with other major military and nonmilitary projects in the region, would result in cumulative impacts to several resources. Some of these impacts, such as land use and socioeconomics, would be beneficial. Other impacts would be fully or potentially offset through the planning process or specific mitigation measures. Potentially significant unmitigable cumulative impacts have been identified for traffic and circulation.

Growth-inducing Impacts

The reuse alternatives would not be projected to cause significant adverse growth-inducing impacts.

Unavoidable Adverse Effects

The Revised Reuse Plan Alternative and the Open Space Alternative would result in unavoidable adverse impacts by exposing new residents of the Capehart Housing and Rafael Village areas to noise levels above land use compatibility guidelines outlined in the Novato General Plan. The Open Space Alternative would similarly expose residents of Capehart Housing to noise levels above guidelines.

Short-term Uses and Long-term Productivity


The productivity of DODHF Novato historically has been related to its operation as a military housing support facility, and the resulting military jobs and services it has provided. The reuse alternatives would make use of properties that would otherwise be left unused, improving both the short-term and long-term economic productivity of the City of Novato and Marin County over conditions that would occur with a closed, inactive facility. Additional long-term benefits include environmental cleanup of contaminated sites, provision of jobs, housing, and recreational opportunities, maintenance of open space, and maintenance of various infrastructures on the site.

Irreversible/Irretrievable Commitment of Resources

None of the alternatives would require significant commitments of energy and resources.

Environmental Justice

None of the alternatives would have a disproportionately high and adverse effect on minority or low-income communities.



1.0 PURPOSE OF AND NEED FOR ACTION

| | | |
|-----|-------------------------------------|------|
| 1.1 | PURPOSE AND NEED | 1-1 |
| 1.2 | LOCATION AND HISTORY | 1-2 |
| 1.3 | RELATED PROCESSES AND DOCUMENTATION | 1-5 |
| 1.4 | DOCUMENT ORGANIZATION | 1-12 |
| 1.5 | PUBLIC INVOLVEMENT | 1-13 |

1. PURPOSE OF AND NEED FOR ACTION

This environmental impact statement (EIS) evaluates the potentially significant impacts to the environment that may result from the Navy disposal and community reuse of the Department of Defense Housing Facility Novato (DODHF Novato) in Novato, California. DODHF Novato closed pursuant to the Defense Base Closure and Realignment Act of 1990 (Part A of Title XXIX of Public Law 101-510 [DBCRA]), as amended. This document has been prepared in accordance with the National Environmental Policy Act (NEPA) of 1969, the Council on Environmental Quality (CEQ) regulations on implementing NEPA, Navy guidelines (OPNAVINST 5090.1B), and the 1990 DBCRA, as amended by the 1993 Base Realignment and Closure (BRAC) process.

The federal action evaluated in this EIS is the disposal of federal surplus property and structures at DODHF Novato, while the local action evaluated is the proposed reuse of DODHF Novato. The City of Novato may use the EIS in place of an environmental impact report (EIR) pursuant to the California Environmental Quality Act (CEQA) Guidelines, Section 15221. This EIS is being prepared at a program level of detail. Following disposal, no additional NEPA review by the Navy would be required.

1.1 PURPOSE AND NEED

The Department of Defense (DOD) has for the past several years been reducing its basing and staffing requirements to match current force structure plans. Congressional action, under the provisions of the Defense Authorization Amendments and the DBCRA, established a process to close and realign military bases. The Navy Public Works Center San Francisco Bay (PWCSFB), which owns DODHF Novato, was recommended for disestablishment in the BRAC recommendation approved by the President and accepted by Congress in 1993. All property owned by PWCSFB, including the DODHF Novato Main Site will be closed and disposed of. DODHF Novato, was closed on September 30, 1996. The portion of DODHF Novato known as the Rafael Village housing area was closed on September 30, 1995.

Decisions regarding which bases to close, relocate, or realign were exempted by Congress from NEPA documentation requirements under the Defense Base Closure and Realignment Act (P.L. 101-510, Section 2905). However, under NEPA, the Navy must consider the environmental effects of reasonable alternatives for the disposal and reuse of property at closing bases. Requirements under Public Law 101-510 and NEPA relevant to DODHF Novato property disposal include the following:

1. Purpose of and Need for Action

- Compliance with NEPA and related laws;
- Environmental restoration of the property as soon as possible with funds made available for such restoration;
- Consideration of the portions of the Hamilton Army Airfield Reuse Plan (Reuse Plan) pertaining to DODHF Novato property prior to disposal; and
- Compliance with specific federal property disposal laws and regulations.

1.2 LOCATION AND HISTORY

1.2.1 Location


DODHF Novato is located in the southeast portion of the City of Novato, eastern Marin County, California, approximately 20 miles north of San Francisco (Figure 1-1). Most development in Marin County is concentrated in the eastern portion of the county along US Highway 101 (US 101), the primary north-south highway connecting Marin County with San Francisco to the south and Sonoma County to the north. Marin County can be characterized as a high-income suburban area that becomes increasingly rural to the north and west as the commuting range from San Francisco is reached. Novato, the second largest city in Marin County, lies along US 101 near the northern border of the county.

DODHF Novato is composed of approximately 411 acres of Navy-owned land on two sites separated by US 101. The 304-acre Main Site includes military family housing, a commissary, a naval exchange, community service areas, a bowling alley, an officers' club, and recreational fields. The 107-acre Rafael Village military housing area is about one mile northwest of the Main Site (Figure 1-2).

DODHF Novato was the housing and community services portion of the former Hamilton Air Force Base. Other parts of the former air base, adjacent to DODHF Novato but not part of this disposal and reuse action, include a six-acre US Coast Guard (USCG) parcel, a 105-foot railroad right-of-way owned by the Golden Gate Bridge, Highway, and Transportation District (GGBHTD), the 720-acre former Hamilton Army Air Field, and the 415-acre site being developed under the New Hamilton Partnership (NHP) Master Plan.

1.2.2 History

Established on San Pablo Bay just north of San Francisco in the early 1930s, Hamilton Field was an integral part of the Army's Pacific Coast defense




Regional Location Map

DOD Housing Facility
Novato, California

Figure 1-1

Located approximately 20 miles north of San Francisco, the DOD Housing Facility Novato housed military personnel stationed at installations throughout the Bay Area.

Developed by Tetra Tech 1995



The DODHF Novato includes community facilities and housing on the former Hamilton Air Force Base and the off-site Rafael Village housing area. The railroad corridor through the Main Site is owned by the Golden Gate Bridge, Highway, and Transportation District.

Local Vicinity Map

DOD Housing Facility
Novato, California

0 1,500 3,000
Approximate Scale in Feet

LEGEND:

— Approximate boundaries
of DODHF Novato

Figure 1-2

Source: USGS 7.5 minute series topographic maps, Novato, California (1980) and Petaluma Point (1980)


mission and was a state-of-the-art aviation station. After the initial construction of the permanent base in 1932-1935, Hamilton Field operated as a bombing center and a temporary pursuit plane station until the United States actually entered World War II. During the war, the primary mission of the base was to support training operations and the activities of the Air Transport Command, which made it an important jumping off point for units destined for various locations in the Pacific war theater. During the war years, the appearance of the base was transformed by the urgent need for temporary housing, which quickly outnumbered the permanent buildings on the base, filling nearly all of the available space.

From 1947 through 1960, the newly established US Air Force conducted defense and training operations at Hamilton Field, renaming it Hamilton Air Force Base. The base continued to develop but at a reduced level. In addition to the 132 housing units constructed in the 1930s, 505 housing units were built in Rafael Village in 1951 to accommodate the increase in base personnel during the Cold War-era military buildup. An additional 560 units were constructed in an area known as Capehart Housing between 1960 and 1963, as the base's population continued to increase (US Army Corps of Engineers 1993). Base expansion ended in the 1970s, when Hamilton Air Force Base was closed by the Department of Defense. By 1974 the Air Force had closed its operations at Hamilton, and the base was parceled out to other defense branches and to the General Services Administration (GSA). After Hamilton Air Force Base was decommissioned, the Navy took over ownership and operation of housing and community services to form DODHF Novato. The Army took over the runway and associated structures to form Hamilton Army Airfield. The GSA retained ownership of a 415-acre parcel that it auctioned off in 1984 to the Berg-Revoir Corporation; the Berg-Revoir Corporation later sold the land to the Martin Group for development under the NHP Master Plan. The USCG and GGBHTD also retained ownership of small portions of the former Hamilton Air Force Base.

The terms "Hamilton Air Force Base" and "Hamilton Army Airfield" are often used interchangeably to refer to the entire facility before it was divided among different DOD and federal entities. This EIS uses "the former Hamilton Air Force Base" when referencing the entire facility. Current land ownership is shown on Figure 1-3.






1.3 RELATED PROCESSES AND DOCUMENTATION

Numerous sequential actions are required before BRAC property can be disposed of. Figure 1-4 shows milestones of four major processes that must occur—property disposal, environmental cleanup, community reuse planning, and environmental analysis. Property disposal and aspects of the environmental analysis and environmental cleanup process are discussed



In 1930, Marin County deeded much of the Hamilton property to the Army Air Corps for establishment of a West Coast Army air base. In 1947, Hamilton Field became Hamilton Air Force Base. The base was decommissioned in 1974 and slowly excessed. Current land ownership patterns are shown here.

LEGEND:


-  Department of the Navy
-  Department of the Army
-  New Hamilton Partnership
-  Coast Guard
-  Golden Gate Bridge, Highway, and Transit District

Ownership Map

DOD Housing Facility
Novato, California

Figure 1-3

Source: Developed by Tetra Tech, 1995



After a decision to close a base, four sequential processes take place prior to property transfer.

Elements of Military Base Closure and Disposal Process

DOD Housing Facility
Novato, California

Figure 1-4

Source: Developed by Tetra Tech, 1995

below. The community reuse planning process is discussed in Chapter 2. The status of environmental cleanup processes is detailed in Section 3.13, Hazardous Materials and Waste.

1.3.1 Property Disposal

The disposal process for the DODHF Novato property is regulated by the Defense Base Closure and Realignment Act of 1994 (Public Law 103-160); the Federal Property and Administrative Services Act of 1949, as amended; the Surplus Property Act of 1944; and the Federal Property Management Regulations (FPMR). The Base Closure Community Development and Homeless Assistance Act of 1994 (PL 103-421) also addresses disposal methods associated with base closure. The Navy also must comply with the 1994 Defense Authorization Act and other laws and regulations, including Title 10 of the US Code and Navy regulations affecting the disposition of real property.

Prior to property disposal, DODHF Novato must undergo contaminated site cleanup. Cleanup of contaminated sites at DODHF Novato is the responsibility of the Navy, and site characterization and remediation is ongoing. Remediation of all sites will be complete before transfer of the property from the Navy.

Facilities at DODHF Novato may be leased on an interim basis prior to Navy disposal. Such leasing could create jobs, increase public and private income, and help preserve the infrastructure through continued use. Interim use of facilities by a non-Navy entity prior to property transfer can be accomplished through the execution of leases, licenses, or permits. The Military Leasing Act of 1956 (10 USC 2667), as amended, permits the Navy to implement interim leasing of excess facilities if it is in the public interest. Interim leases may be instituted if the proposed use would promote national defense or be in the public interest. Interim uses cannot preclude any future Navy options or irrevocably commit resources. Prior to any leasing or permitting, the Navy must complete a Finding of Suitability to Lease (FOSL), documenting that the facility is safe and suitable to use. Appropriate NEPA and related documentation would be completed prior to potential Navy approval of interim leases or parcel transfers.

Property Screening Process

The Navy conducted a property screening process pursuant to the FPMR (41 CFR 101-47). The 1994 Defense Authorization Act (Public Law 103-160), also known as the Pryor Amendment, provides additional methods for disposing of real property.

DOD and Federal Agency Screening. The Navy has completed the DOD and federal screening process for DODHF Novato. Although no DOD agencies expressed an interest in the property, two federal agencies did express interest. The USCG initially requested a portion of the Capehart Housing planning area known as the Hillside Housing subarea. The Department of Veterans Affairs requested use of 54 housing units in the Knoll Housing subarea of the Spanish Housing planning area. These requests were included in the final Hamilton Army Airfield Reuse Plan. Since adoption of the Reuse Plan, the Department of Veterans Affairs has withdrawn its request and the USCG has twice revised its request. Instead of Hillside Housing, USCG first requested all of the Spanish Housing, Bowling Alley, and Officers' Club planning areas and a portion of the Ballfields planning area. (Detailed descriptions and maps of the various planning areas are provided in Chapter 2.) The original revised USCG request was approved by the Novato City Council on February 13, 1996. Subsequently, USCG further revised its request to include only the land and facilities in the 142-acre Spanish Housing planning area. This revised scenario was included in an updated Reuse Plan published in November 1996.

McKinney Act Screening. The McKinney Act requires DOD and other federal agencies to give priority consideration for homeless assistance over other uses for property that is considered excess, surplus, or underutilized by federal agencies. The US Department of Housing and Urban Development (HUD) screens properties in these categories for suitability for homeless assistance. Congress passed the Base Closure Community Redevelopment and Homeless Assistance Act of 1994, which was signed into law by the president on October 25, 1994. Under this legislation, future base closure properties will no longer be subject to the McKinney Act but will fall under new procedures that require the needs of the homeless to be considered during the reuse planning process and to be balanced with the need for other economic redevelopment. Local redevelopment authorities (LRAs) for BRAC 1993 actions, including DODHF Novato, were allowed to follow either the original McKinney Act screening process or the procedures outlined in the 1994 law. The City of Novato elected to proceed under the new procedures.

Screening for state, local, and homeless assistance needs has been accomplished by the LRA for DODHF Novato, the Hamilton Reuse Planning Authority (HRPA). The Reuse Plan accepted by the Novato City Council in October 1995 contains provisions for an 80-bed homeless shelter in the northernmost corner of the Commissary Triangle area and 60 units of transitional housing in Capehart Housing. In December 1995 the HRPA and a coalition of homeless providers, the Hamilton Homes Task Force, negotiated an agreement to create an 80-bed permanent emergency shelter, 60 units of transitional housing units, a child care facility, office and meeting rooms for transitional units, warehouse space, and an employment facility at the DODHF Novato Main Site. The Reuse Plan was approved by HUD in March 1996 for its homeless assistance element.

1. Purpose of and Need for Action

The Hamilton Service Center, a temporary 80-bed homeless shelter, was located on property leased from New Hamilton Partnership. The Hamilton Service Center provided shelter, food and clothing over a six-month winter period of October to April. The lease on the property expired and a relocation lease site on DODHF Novato has been identified to house a new temporary structure. The new site is a 1.4-acre parcel in the northern corner of the Commissary Triangle planning area with a proposed lease term of one year. An Environmental Assessment for the proposed shelter was prepared in August 1996 and a Finding of No Significant Impact was issued in September 1996 (US Navy 1996c).

State and Local Screening. Property not transferred to other federal agencies or acquired under the revised McKinney Act procedures will be available for transfer to state and local agencies.

The following local entities expressed an interest in DODHF Novato property:

- College of Marin for a corporate yard;
- Marin County Office of Education for property to support educational purposes;
- Novato Unified School District for a vehicle maintenance educational facility;
- City of Novato/HRPA for all DODHF Novato property and structures;
- Marin County Free Library for property to build a public library;
- Marin Municipal Water District for property to provide operations for potable and/or reclaimed water deliveries;
- Novato Fire Protection District for property for storage purposes;
- North Marin Water District for property to support operations for water and recycled water; and
- Golden Gate Bridge, Highway, and Transportation District for a transit center.

The interested local entities are now in the process of submitting formal applications for property at DODHF Novato.

Methods of Conveyance

Under the FPMR and following base closure and environmental remediation, and completion of NEPA requirements, the Navy may transfer property to other federal agencies or convey property to state, local, or private entities. Federal law provides for a variety of conveyance methods to implement Navy property disposal decisions after completion of the NEPA process.

1. Purpose of and Need for Action

Transfer to Another Federal Agency. The Navy will transfer the Spanish Housing area of DODHF Novato to the Coast Guard. This transfer is addressed under a discussion of cumulative impacts in this EIS.

Public Benefit Discount Conveyance. State or local government agencies or other qualified entities may obtain property at less than fair market value when sponsored by a federal agency for uses that would benefit the public. Public benefit conveyances typically restrict uses to airports, ports, prisons, educational facilities, recreational facilities, public health, wildlife conservation, historic monuments, and memorials.

Negotiated Sale. State and local government agencies or other qualified entities may request a sale at fair market value with negotiation of the payment terms.

Economic Development Conveyance. Economic development conveyances are mechanisms to convey property to an LRA at or below fair market value using flexible payment terms for the purpose of economic development and job creation. To qualify for this conveyance, the LRA must submit a request to the Department of the Navy describing its proposed economic development and job creation program. The conveyance mechanism further requires that the Navy prepare a statement to explain if fair market value was not received.

Competitive Sale. Sale to the public would occur through either an invitation for bids or an auction.

1.3.2 Environmental Cleanup

DOD policy requires the preparation of an environmental baseline survey (EBS) prior to the sale, lease, or transfer of real property. A basewide EBS report is a factual representation of the environmental conditions for all property at an installation. The EBS is used to meet the requirements of the Community Environmental Response Facilitation Act (CERFA). The basewide EBS and CERFA Report for DODHF Novato was completed in October 1995 (US Navy 1995a) and documented the environmental conditions of real property at DODHF Novato and adjacent properties. DODHF Novato parcels were given one of seven classifications based on storage, release, disposal, or migration of hazardous substances. Uncontaminated parcels also were identified by this classification process (as Type 1).

The BRAC Cleanup Plan (BCP) for a closing base documents the status of environmental restoration and associated compliance programs. The BCP for DODHF Novato (US Navy 1996a) was completed in March 1995, and updated in March 1996. The BCP provides a thorough evaluation of the status

of various cleanup programs and summarizes the items that require further evaluation and compliance. The document will be updated annually or as necessary, recording the changing conditions and level of completion of these restoration programs until restoration is complete. Findings of the BCP are summarized in Section 3.13, Hazardous Materials and Waste.

Cleanup of DODHF Novato is being conducted under the guidance of the California Department of Toxic Substances Control (DTSC).

1.4 DOCUMENT ORGANIZATION

The organization of this document is outlined below.

Chapter 1, Purpose of and Need for Action, provides the reader with an overview of the reasons for the disposal and reuse of the facility. This chapter discusses the Navy disposal and potential community reuse of the DODHF Novato property. It describes NEPA requirements for EIS content and approach, the decision process for closing the installation, the disposal process, and the process used to solicit public and agency input on potentially significant environmental impacts.

Chapter 2, Proposed Action and Alternatives, describes the proposed Navy disposal action and summarizes the EIS public involvement process and the community planning process leading to the formulation of the community reuse alternatives. In addition to Navy disposal and the Preferred (Reuse) Alternative, this EIS analyzes the Navy No Action Alternative and one other community reuse alternative.

Chapter 3, Affected Environment, describes the existing environmental conditions at DODHF Novato.

Chapter 4, Environmental Consequences, identifies the potential environmental impacts to resources on the DODHF Novato property and in a region of influence resulting from Navy disposal and community reuse of DODHF Novato. This EIS assesses the impacts of the Preferred Alternative and other alternatives in order to provide the public, interested agencies, and decision-makers with a clear understanding of the environmental effects of adopting each alternative. Mitigation measures are provided to reduce or eliminate any identified significant environmental impacts.

Chapter 5, Other Considerations Required by NEPA, addresses other topics required by NEPA including cumulative impacts, growth-inducing impacts, unavoidable adverse impacts, the relationship of short-term uses to long-term productivity, irreversible and irretrievable commitment of resources, and a discussion of environmental justice.

Chapters 6 through 10 provide background information including consultation with interested and responsible agencies, a list of references, a list of preparers, an index, and a distribution list.

Response to Comments and technical appendices follow these chapters.

1.5 PUBLIC INVOLVEMENT

The process of preparing an EIS is designed to involve the public in federal decision-making. Public opportunities to comment on and participate in the process have been provided during the preparation of this EIS, as outlined below. Comments from agencies and the public have been solicited to help identify the potential environmental issues associated with the DODHF Novato property disposal and reuse. The public notification process included the full spectrum of area residents and community organizations. Appendix B provides copies of public involvement materials. Chapter 10 includes a copy of the current mailing list for the EIS. Methods to involve the public in the EIS process have included the following:

- Conducting a public scoping meeting in Novato to solicit comments and identify issues of concern;
- Conducting a public meeting to receive comments on the Draft EIS and providing the required 45-day public comment period;
- Providing copies of the Draft EIS at local libraries;
- Conducting a public meeting in Novato to receive comments on the Draft EIS and providing the required 45-day public comment period;
- Publishing public notices of hearings in three local newspapers, mailing public announcements, and coordinating media coverage, press releases, and feature articles; and
- Creating and updating a mailing list to disseminate information.

The goal for public involvement, under Executive Order 12898 regarding Environmental Justice, is to include all affected low-income and minority populations in the public participation process. To achieve this, the following actions were implemented:

- Notified and requested comments from several neighborhood associations and community organizations that may be affected by or interested in the proposed action; and

- Announced the public meetings in newspapers with a wide circulation and encouraged written comments for those unable to attend the meetings.

1.5.1 Scoping Process

The purpose of scoping is to identify potential environmental issues that would be raised by disposal and reuse. The scoping process for the DODHF Novato Disposal and Reuse EIS included placing notices in the Federal Register and newspapers, conducting a public meeting, and using direct mail. The Navy and the EIS consulting team have considered comments received during the scoping period in determining the issues to be evaluated in the EIS. The main issues identified during the scoping period are summarized in Section 1.5.2 below and are addressed in specific technical sections in Chapters 3 and 4.

The public was notified of the Navy's intent to prepare this EIS by a notice of intent (NOI) published in the October 31, 1995, issue of the Federal Register. Legal ads were published in local newspapers, including the San Francisco Chronicle and Marin Independent Journal, on November 5 and 6, 1995, and the Novato Advance on November 15, 1995.

Letters announcing a scoping meeting, including a project description and summary of the reuse plan, were mailed to all public agencies, public interest groups, and individuals either known to have or thought to have an interest in the disposal and reuse of DODHF Novato. The scoping letter invited written comments and announced the public hearing for 7:00 PM on November 16, 1995, at the San Marin High School Student Center in Novato, California. Approximately 20 individuals attended the scoping hearing, including local agency representatives and members of the public. Issues identified at the meeting and in subsequent letters are summarized in Section 1.5.2 below.

1.5.2 Summary of Scoping Issues

During the EIS scoping process, which ended December 1, 1995, twelve letters were received from members of the public, interested groups, and federal, state, and local agencies. In addition to these written comments, seven people made verbal comments at the scoping meeting. The main issues of concern identified through the scoping process were the effects of demolition of the Rafael Village housing units on air quality, water quality, noise, traffic, and area landfills; the effects of reuse on open space areas, native trees, wetlands and riparian areas, creeks, and other biological resources; the impacts of reuse on traffic; and the impacts of reuse on surrounding neighborhoods, particularly Lanham Village. These issues and concerns are detailed in Table B-1, Appendix B, and are incorporated into the EIS.

1.5.3 Public Review

Public review is an important part of the NEPA process. Public review periods are typically 45 days under NEPA. Responses to comments received on the Draft EIS are provided in the Final EIS. NEPA provides for a 30-day no action review period after preparation of the Final EIS.


Draft EIS

The public was invited to review and comment on the Draft EIS. Public notices were mailed to those on the mailing list and press releases were furnished to the local news media. A notice of availability was published in the Federal Register on January 31, 1997. Legal ads were published in local newspapers, including the San Francisco Chronicle and Marin Independent Journal, on February 16 and 17th, 1997, and the Novato Advance on February 19, 1997. The Draft EIS was circulated for public and agency review from January 31, 1997 to March 17, 1997. This public comment period (required to be at least 45 days) provided an opportunity for the public to review the issues addressed in the impact analysis and to offer comments on any aspect of the process. The distribution list is included as Chapter 10.

A public hearing was held on February 27, 1997 to formally receive verbal and written comments on the Draft EIS. The location, date, and time of the meeting was announced in the media and were included in the transmittal letter accompanying the Draft EIS. Approximately 40 individuals from the public attended this hearing and 21 individuals presented oral comments. Comments and responses to the comments is provided in this Final EIS.

Final EIS

This Final EIS, incorporates and responds to comments received on the Draft EIS. As required under NEPA, there will be a 30-day waiting period (no action period) after the Final EIS (see Figure 1-4) is published. During this period, the public may comment on the adequacy of responses to comments. After the waiting period, a Record of Decision (ROD) will be prepared.



2.0 PROPOSED ACTION AND ALTERNATIVES

| | | |
|-----|--|------|
| 2.1 | DEVELOPMENT OF ALTERNATIVES | 2-1 |
| 2.2 | DESCRIPTION OF ALTERNATIVES | 2-3 |
| 2.3 | ENVIRONMENTALLY PREFERABLE ALTERNATIVE | 2-26 |
| 2.4 | ALTERNATIVES ELIMINATED FROM DETAILED CONSIDERATION | 2-26 |

2. PROPOSED ACTION AND ALTERNATIVES

This chapter describes the process the community used to develop its reuse plan, the selection criteria for reuse alternatives, the disposal action, and the reuse alternatives considered in the EIS. Reuse alternatives that were considered but eliminated from detailed review also are described. The proposed action subject to NEPA is the Navy's disposal of DODHF Novato. For purposes of Navy NEPA analysis, direct environmental impacts are those associated with Navy disposal and the No Action Alternative, while indirect impacts are associated with implementing the community reuse of surplus land at DODHF Novato. Community reuse alternatives analyzed in this EIS include the Revised Reuse Plan Alternative, which is based on the revised community Reuse Plan, and the Open Space Alternative. The activities required for disposal, described in Section 1.3, are assumed to be a part of each alternative except the No Action Alternative.

This EIS addresses only that part of the former Hamilton Air Force Base that is being disposed of by the US Navy. The Reuse Plan, developed by the community and upon which the Revised Reuse Plan Alternative is based, includes land owned by the US Army and the USCG. The Reuse Plan also summarizes the development plan for the adjacent land currently being developed by New Hamilton Partnership. The reuse of these adjacent lands, while not included in the Revised Reuse Plan Alternative, is addressed in Section 5.1, Cumulative Impacts.

2.1 DEVELOPMENT OF ALTERNATIVES

2.1.1 Community Reuse Planning Process

The reuse planning process for DODHF Novato began when the President approved and Congress accepted closure of the facility in October 1993. The Hamilton Reuse Planning Authority (HRPA) developed the Reuse Plan with support and assistance from the Navy. In March 1994, the City of Novato and the County of Marin agreed to establish a procedure for joint participation in the reuse planning process for the former Hamilton Air Force Base to ensure the protection of local and regional interests. The procedure included creation of the Hamilton Advisory Commission (HAC), a citizens' committee of 25 representatives of numerous stakeholder groups; a Technical Advisory Committee (TAC); and a Multi-agency Board (MAB) composed of two members from the Novato City Council, one member selected by the city council, two members of the County Board of Supervisors, and one individual selected by the board. The role of MAB was to review the recommendations of HAC and make a recommendation to the Novato City Council regarding adoption of the plan.

The primary objective of the planning process was to develop a community reuse plan for the entire former Hamilton Air Force Base complex that reflects community consensus through substantial public involvement. A second objective was to identify affordable housing opportunities to satisfy a significant portion of Novato's state-mandated affordable housing quotas and to assist homeless providers.

Starting in February 1995, HAC held a series of nine public hearings to obtain public input in the formulation of reuse alternatives. HAC divided the former Hamilton Air Force Base complex into 10 planning areas and the runway parcel. Based on public input, HAC developed reuse alternatives for each of the 10 planning areas (eight of which are owned by the Navy and considered in this EIS), as well as the runway parcel and forwarded them to MAB. The alternatives are presented in a series of land use maps and written land use designations and include assumptions used by HAC to guide the planning process. HAC did not recommend a preferred alternative, nor did it recommend any policy direction on the various planning issues that arose during the public participation process. In July 1995, MAB selected preferred land use plans for each of the 10 planning areas and the runway parcel. These preferred plans were then developed into the draft Reuse Plan, which was released in August 1995. The Novato City Council adopted the final Reuse Plan in October 1995.

The final Reuse Plan adopted in October 1995 took into account the original Department of Veterans Affairs and USCG federal property requests as described in Section 1.3.1 of this EIS. After city adoption of the Reuse Plan, the Department of Veterans Affairs withdrew its request for property and the USCG revised its request for property to the Spanish Housing area instead of the Hillside/Capehart Housing area. The MAB recommended adoption of the revised USCG request on January 16, 1996 and the City of Novato approved the revised USCG request on February 13, 1996. This revised scenario was published in an updated Reuse Plan in November 1996. Because the transfer of the Spanish Housing property to the USCG involves transfer of federal property between two federal agencies, there is no surplus property disposal. Therefore, this action is not considered to be part of the disposal action addressed in this EIS. However, USCG use of the Spanish Housing facilities is included in the cumulative impact analysis in Chapter 5.

2.1.2 Selection of Alternatives

An EIS must consider a range of reasonable alternatives that are evaluated at the same level of detail as the Preferred Alternative. The EIS Preferred Alternative is the federal disposal of surplus federal land at DODHF Novato and the subsequent reuse of DODHF Novato, as recommended in the revised Reuse Plan. Since the Revised Reuse Plan Alternative retains most DODHF

Novato structures and facilities, except for the Rafael Village housing units, the Preferred Alternative can best be characterized as adaptive reuse.

EIS alternatives to the Revised Reuse Plan Alternative include an Open Space Alternative and the required No Action Alternative. The reuse alternatives are designed to provide a range of choices that will allow federal and local decision-makers, interested agencies, and the public to understand the environmental effects of Navy disposal and potential community reuse. The reuse alternatives, including the Preferred Alternative, are identified at a relatively general program level. Specific uses of buildings and sites would be determined as the Reuse Plan is implemented.

2.2 DESCRIPTION OF ALTERNATIVES


Federal disposal is assumed to be part of each alternative except the No Action Alternative. Potential effects resulting from implementation of the alternatives are described in Chapter 4, Environmental Consequences.

This section describes the following Navy disposal and community reuse alternatives in detail:

- **Revised Reuse Plan Alternative (Preferred Alternative)**—The Navy would dispose of its surplus property at DODHF Novato, and a local entity or entities would implement the Reuse Plan for each of the remaining Navy-owned planning areas. In conformance with the revised Reuse Plan, no corporation yards would be allowed under this alternative.
- **Open Space Alternative**—Under this alternative, the existing housing units at Rafael Village would be demolished and the area would be graded and revegetated. Reuse of the Main Site generally would be the same as described for the Preferred Alternative but would allow the development of corporation yards.
- **No Action Alternative**—Under this alternative, all of the property and facilities at DODHF Novato would remain under federal ownership in caretaker status.

Figure 2-1 presents an overview and comparison of the land uses proposed for the Revised Reuse Plan Alternative and the Open Space Alternative.

Figure 2-1
Comparison of Alternatives



2.2.1 Navy Disposal Action


Navy disposal is included in this document to evaluate the impacts that would occur from the disposal of the DODHF Novato property out of federal ownership. For example, if disposal of the property would lessen the protection afforded to a sensitive resource, this would be discussed in Chapter 4, Environmental Consequences, as an impact under Navy disposal.

2.2.2 Revised Reuse Plan Alternative - Preferred Alternative

The EIS Preferred Alternative is the implementation of the revised Reuse Plan. The Revised Reuse Plan Alternative reflects the community's goals developed during the reuse planning process and the most current plans for reuse of the residential and nonresidential lands within the former Hamilton Air Force Base. The Reuse Plan also provides land use direction for the City of Novato. The EIS evaluates the Revised Reuse Plan Alternative as the Preferred Alternative since it reflects the scenario most likely to occur.

The Reuse Plan identifies 10 planning areas and a runway area at the former Hamilton Air Force Base. However, the land and facilities in two of these planning areas are not owned by the Navy and are therefore not part of this disposal and reuse action. The Hospital Hill planning area is owned by the US Army and the Spanish Housing planning area will be transferred to the US Coast Guard. Only the community reuse of the eight Navy-owned planning areas within DODHF Novato is evaluated in this EIS. DODHF Novato planning areas are shown on Figure 2-2. Figures 2-3 and 2-4 show detailed views of Rafael Village and the Main Site planning areas, respectively. Photographs showing facilities and representative views of each planning area are contained in Appendix A.

The Reuse Plan can be characterized as promoting adaptive reuse of existing buildings and retention of existing land use patterns. Most existing structures at DODHF Novato are housing units and would remain as housing units under the Reuse Plan. The nonresidential buildings would be adapted for new uses, but would retain their basic structure and appearance. Some buildings would be demolished or restored. The Reuse Plan identifies land use designations for each planning area. The EIS analyzes the effects of the proposed land uses contained in the plan and evaluates the potential environmental impacts at buildout of the plan. The EIS also identifies assumed land ownership in conjunction with proposed reuse.




DODHF Novato Planning Areas

DOD Housing Facility
Novato, California


Figure 2-2

The Hamilton Army Airfield Reuse Plan divides the former base into 10 planning areas. This EIS evaluates the disposal and reuse of the eight Navy-owned planning areas. The two remaining planning areas, Hospital Hill and Spanish Housing, are owned by the Army and USCG, respectively.

Source: Hamilton Reuse Planning Authority 1995




DODHF Novato
Rafael Village
 DOD Housing Facility
 Novato, California
Figure 2-3



Rafael Village, located one mile northwest of the Main Site across US 101, was constructed in the 1950s to provide housing for military families.

Source: Hamilton Reuse Planning Authority




The Main Site includes housing and community service facilities.

LEGEND:

- | | |
|-----------------------|------------------|
| ② Capehart Housing | ⑧ Bowling Alley |
| ④ Commissary Triangle | ⑨ Officers' Club |
| ⑤ Exchange Triangle | ⑩ Ballfields |
| ⑥ Town Center | |


***DODHF Novato
Main Site***
**DOD Housing Facility
 Novato, California
 Figure 2-4**

Planning Area 1. Rafael Village


Rafael Village is approximately one mile northwest of the Main Site, west of US 101 along Ignacio Boulevard. The 107-acre suburban residential development is characterized by nonlinear streets and mature landscaping, with greenbelt areas mixed among the units. The development contains primarily single-family units in the western portion and duplexes in the eastern portion. The 1950-era Wherry-style housing units are similar to each other in color, design, and material, and show signs of age and wear. Rafael Village is surrounded by private residences.

A community center and a maintenance yard also are located at Rafael Village. The community center is in Building 404-1 on Owen Drive between Morgan and Norman Drives. The 5,000 square foot maintenance yard is located off Dickson Drive behind Buildings 890 and 892 and contains no structures. Rafael Village was closed in September 1995, and the Navy has boarded up the structures.

The Revised Reuse Plan Alternative would demolish the 503 Rafael Village structures and rebuild the property with residences, open space, and parkland. The proposed 500 dwelling units on 86 acres would include 275 low-density units, 125 medium-density units, and 100 medium-density multiple-family units. The Revised Reuse Plan Alternative would include up to seven acres of parkland in areas not yet designated and seven acres of open space along Ignacio Boulevard and San Jose Creek.



Planning Area 2. Capehart Housing




Capehart Housing is a 216-acre suburban residential development set in an open space hillside area. Primary access to the site is from Main Gate Road. Secondary access is from Bolling Drive, an entry that can be gated. Capehart Housing has 708 residential units, including townhouses and duplexes. The Hillside Housing subarea consists of 25 buildings with six units per building for a total of 150 units of the 708 units in the planning area. These units are newer than the other units in Capehart Housing.

The visual character of the Capehart Housing planning area is dominated by the nonlinear street and residential layout, mature oak trees, rock outcroppings, and the steep hillside area. The structures and landscaping appear well maintained, and the housing units are of varied architectural styles. The hilltops allow expansive views of San Pablo Bay and the wooded hills of Novato.

Railroad tracks and a 105-foot right-of-way owned by the GGBHTD run along the east side of the Capehart Housing planning area.


Land uses under the Revised Reuse Plan Alternative include reuse of the 100 acres of existing housing, with nine acres of parkland and 107 acres of open space. Sixty of the residential units at Capehart Housing would be used for transitional housing.



Planning Area 3. Spanish Housing


Spanish Housing is being transferred to the U.S. Coast Guard and is addressed under Cumulative Impacts, Section 5.1.


Planning Area 4. Commissary Triangle



The Commissary Triangle is a 13-acre site on State Access Road just inside the north gate. Christmas Tree Hill borders the area to the west, providing a buffer between the planning area and Nave Drive and US 101. Commissary Triangle consists of nine warehouse-style buildings, including the Commissary (Building 804) and adjacent parking lots. The site has minimal landscaping.


The Revised Reuse Plan Alternative would reserve the area for community facility and civic uses. Specific uses allowed under this alternative would include the Hamilton Service Center, an 80-bed temporary homeless shelter on 3.9 acres.




Planning Area 5. Exchange Triangle

The Exchange Triangle is a flat developed area with extensive parking lots and a variety of old and new, large and small buildings. The Exchange Triangle consists of two sites—a primary site north and east of the nonmilitary Lanham Village housing development and a secondary site directly south of Lanham Village at the corner of Main Gate Road and Nave Drive. The two sites in the Exchange Triangle planning area total 28 acres and include 14 nonresidential structures including the exchange building with retail stores, a credit union, youth centers, a tot lot, a skateboard ramp, a gas station, maintenance buildings, administration buildings, and parking lots.

The Revised Reuse Plan Alternative would designate 26 acres of the site for Community Facility and Civic uses - Special Uses Permitted. Specific uses could include a transit center, library, charter school, homeless shelter, child care facility, and up to 210 units of senior housing. Two acres would be designated for neighborhood commercial uses to accommodate residents.




Planning Area 6. Town Center



The Town Center consists of eight acres at the terminus of Palm Drive. It is a well-maintained public area characterized by mature landscaping and Spanish Eclectic architecture. Structures in this planning area include the security/arts building, movie theater, chapel, former infirmary, noncommissioned officers' (NCO) club, and former officers mess. Large landscaped areas surround the buildings.

The Revised Reuse Plan Alternative would use four acres of the site as a neighborhood commercial area that could accommodate a theater, offices, cafes, specialty shops, personal service shops, or artist workspaces. Two acres would be used for community facilities, such as the existing chapel, and two acres would serve as a central plaza.


Southeast of Planning Areas 6 and 7, the Navy also owns a parcel of land known as the Amphitheater site. The Navy anticipates leasing to the City of Novato and its anticipated sublessee, the New Hamilton Partnership, to refurbish the existing facilities in this area for use as a park. Although not designated as part of a planning area in the Reuse Plan, the disposal and reuse of this parcel is included in the EIS.



Planning Area 7. Hospital Hill


Hospital Hill is administered by the U.S. Army and is addressed under Cumulative Impacts, Section 5.1.

Planning Area 8. Bowling Alley




The Bowling Alley planning area consists of two buildings on three acres with a parking lot on the opposite side of San Pablo Avenue. The buildings include the bowling alley with gym (constructed in 1945 and renovated in 1982) and the racquetball courts (constructed in 1994). The parking lot is backed by the landscaped hill of the Officers' Club planning area.

The Revised Reuse Plan Alternative would use the three-acre site for recreation enterprises, such as the existing bowling alley and gymnasium facility.




Planning Area 9. Officers' Club




The Officers' Club is a five-acre landscaped hill area with two Spanish Eclectic-style buildings, the vacant bachelor officers' quarters (BOQ) (constructed in 1934) and a community center (constructed in 1930).

The Revised Reuse Plan Alternative would designate three acres for community facilities and civic uses. Specific uses would include a cultural center, community center, library, and/or similar resident-supporting uses. Two acres would be designated as visitor serving commercial.




Planning Area 10. Ballfields



The Ballfields planning area is a 31-acre open space with partially developed recreational facilities and parking lots. The area, which includes four baseball fields, a swimming pool, and a poolhouse, has expansive views toward San Pablo Bay to the east.

The Revised Reuse Plan Alternative would designate the entire 31-acre site as a park and would retain the swimming pool complex for recreational uses.



2.2.3 Open Space Alternative

Under the Open Space Alternative, the Rafael Village area would be used for open space and parkland instead of residential uses after the demolition of the existing housing units. Planning areas with proposed reuses that differ from the Revised Reuse Plan Alternative are described below.

Planning Area 1. Rafael Village

As under the Revised Reuse Plan Alternative, all 503 existing structures at Rafael Village would be demolished. New housing structures would not be built; rather, the property would be designated for open space and parkland. Developments could include creek restoration, playing fields, jogging and bike paths, playgrounds, and sitting areas.

Planning Area 4. Commissary Triangle

The Open Space Alternative would include 13 acres for community facilities and civic uses similar to the Revised Reuse Plan Alternative, except the proposed homeless shelter would not be permanently located in this planning area. Also, unlike the Revised Reuse Plan Alternative, corporate yards would be permitted.

Planning Area 5. Exchange Triangle

The Open Space Alternative would include 26 acres for community facility and civic uses as permitted in the Revised Reuse Plan Alternative. The proposed homeless shelter would be located in this planning area, and corporate yards would be permitted. This alternative also would include two acres of neighborhood commercial uses.

Planning Area 6. Town Center

The Open Space Alternative would use all eight acres of the site as community facilities and would not include commercial uses.

Planning Area 10. Ballfields

The Open Space Alternative would designate seven acres as parkland and 24 acres as open space.

2.2.4 No Action Alternative

Inclusion of the No Action Alternative in the environmental analysis and documentation is required by the Council on Environmental Quality (CEQ), which implements NEPA. The closure of DODHF Novato is mandated by base closure statute and must be implemented, unless otherwise directed by Congress. For this reason, the No Action Alternative evaluates the facility closed but remaining indefinitely in federal ownership.

Under the No Action Alternative, DODHF Novato would remain in federal ownership in a caretaker status after closure. On-site activities associated with Navy caretaker status could include the following:

- Periodic landscape maintenance around unoccupied structures to protect them from fire or nuisance conditions and to preserve the visual character of the area;
- Continuation of security patrols or augmentation of city police services with private security where and as necessary;
- Maintenance of fire protection systems;
- Minimal maintenance of structures in a manner that facilitates interim use leasing or economical resumption of use; and
- Boarding up structures and capping utilities in structures not anticipated for reuse.

Table 2-1 provides a comparison of the alternatives by planning area. Table 2-2 lists the significant impacts and corresponding mitigation measures for each alternative. Table 2-2 may be used to compare the potential impacts of one alternative to those of another.

Table 2-1
DODHF Novato Alternatives

| Planning Area | Alternative | | |
|------------------------|---|---|-----------------------|
| | Revised Reuse Plan Alternative (Preferred Alternative) | Open Space Alternative | No Action Alternative |
| 1. Rafael Village | Residential - 500 u/86 ac Parkland - 7 ac Open Space - 7 ac (Roadways - 7 ac) | Open Space and Parkland - 100 ac (Roadways - 7 ac) | Navy Caretaker Status |
| 2. Capehart Housing | Residential - 708 u/100 ac Parkland - 9 ac Open Space - 107 ac | Same as Preferred Alternative | Navy Caretaker Status |
| 4. Commissary Triangle | Community Fac - 13 ac (including 80-bed homeless shelter; no corporate yards permitted) | Community Fac - 13 ac (without homeless shelter; corporate yards permitted) | Navy Caretaker Status |
| 5. Exchange Triangle | Community Fac - 26 ac (no corporate yards permitted) Neighborhood Commercial - 2 ac | Community Fac - 26 ac (including 80-bed homeless shelter; corporate yards permitted) Neighborhood Commercial - 2 ac | Navy Caretaker Status |
| 6. Town Center | Community Fac - 2 ac Neighborhood Commercial - 4 ac Parkland - 2 ac | Community Fac - 8 ac | Navy Caretaker Status |
| 8. Bowling Alley | Parkland - 3 ac | Same as Preferred Alternative | Navy Caretaker Status |
| 9. Officers' Club | Community Fac - 3 ac Visitor Serving Commercial - 2 ac | Same as Preferred Alternative | Navy Caretaker Status |
| 10. Ballfields | Parkland - 31 ac | Parkland - 7 ac Open Space - 24 ac | Navy Caretaker Status |

Notes: u = units; ac = acre;

Planning Areas 3, Spanish Housing, and 7, Hospital Hill, are not part of the Navy disposal and community reuse action. Reuse of these areas is discussed in Section 5.1, Cumulative Impacts.

Table 2-2
Summary of Environmental Impacts and Mitigations from the Disposal
and Reuse Alternatives

| Resource Category | DIRECT IMPACTS FROM NAVY ACTIONS | | INDIRECT IMPACTS FROM COMMUNITY REUSE | |
|---------------------------------|--------------------------------------|--------------------------------------|---|--|
| | Disposal | No Action Alternative | Revised Reuse Plan Alternative (Preferred Alternative) | Open Space Alternative |
| Land Use | No impacts are expected. | No impacts are expected. | No significant impacts are expected. | No significant impacts are expected. |
| Aesthetics and Scenic Resources | No impacts are expected. | No significant impacts are expected. | No significant impacts are expected. | No significant impacts are expected. |
| Socioeconomics | No impacts are expected. | No impacts are expected. | No significant impacts are expected. | No significant impacts are expected. |
| Public Services | No impacts are expected. | No impacts are expected. | No significant impacts are expected. | No significant impacts are expected. |
| Utilities | No impacts are expected. | No impacts are expected. | <i>Impact 1.</i> A significant and mitigable impact would result if demolition of Rafael Village structures prevented Marin County from meeting the Cal EPA solid waste reduction standards of 50 percent by 2000 (4-33). <i>Mitigation 1.</i> Implement the California Integrated Waste Management Board proposed projects to divert construction debris, including reusing building materials (4-33). | <i>Impact 1.</i> Same as Preferred Alternative (4-34). <i>Mitigation 1.</i> Same as Preferred Alternative (4-34). |
| Cultural Resources | No significant impacts are expected. | No significant impacts are expected. | No significant impacts are expected. | No significant impacts are expected. |
| Biological Resources | No impacts are expected. | No impacts are expected. | <i>Impact 1.</i> Increased erosion could result in a significant and mitigable impact to sensitive wetland and riparian habitats in San Jose Creek adjacent to the southern boundary of Rafael Village and other wetland habitats (4-45). <i>Mitigation 1.</i> Implement standard erosion control measures to minimize sedimentation into creeks and other wetlands during new construction to prevent significant impacts (4-46). | <i>Impact 1.</i> Same as Impact 1 for Preferred Alternative (4-46). <i>Mitigation 1.</i> Same as Mitigation 1 for Preferred Alternative (4-47). |

Table 2-2
Summary of Environmental Impacts and Mitigations from the Disposal
and Reuse Alternatives (continued)

| Resource Category | DIRECT IMPACTS FROM NAVY ACTIONS | | INDIRECT IMPACTS FROM COMMUNITY REUSE | |
|-------------------|----------------------------------|--------------------------------------|---|---|
| | Disposal | No Action Alternative | Revised Reuse Plan Alternative (Preferred Alternative) | Open Space Alternative |
| Geology and Soils | No impacts are expected. | No impacts are expected. | <p><u>Impact 1.</u> A potentially significant and mitigable impact could occur if demolition and new construction in Rafael Village undermines or weakens unstable slopes (4-49).</p> <p><u>Mitigation 1.</u> Geotechnical investigations would be conducted to identify potential geologic hazards that may affect new building sites (4-49).</p> <p><u>Impact 2.</u> A significant and mitigable impact could result if existing and proposed improvements in certain Main Site areas, particularly those on reclaimed land underlain by imported fill and bay mud, but also in areas underlain by alluvium, were exposed to potentially damaging levels of ground shaking during a large earthquake centered on one of the three nearest active faults (4-49).</p> <p><u>Mitigation 2.</u> An evaluation of the ability of existing structures to withstand site specific seismic forces should be performed to identify structures that should be upgraded to reduce injury, loss of life, or economic damage (4-50).</p> | <p><u>Impact 1.</u> Same as Impact 2 for the Preferred Alternative (4-451).</p> <p><u>Mitigation 1.</u> Same as Mitigation 2 for Preferred Alternative (4-51).</p> |
| | No impacts are expected. | No significant impacts are expected. | <p><u>Impact 1.</u> Significant and mitigable impacts could result from grading, demolition, and construction of new houses by disturbing the soil and increasing erosion/sedimentation into San Jose Creek, affecting surface water quality (4-554).</p> <p><u>Mitigation 1.</u> Prior to any site clearing or grading, develop erosion control plans consistent with the SWPPP. Include a Best Management Practices (BMP) program that focuses on containing/controlling land use activities that might affect water quality, preventing runoff, and treating runoff on-site (4-54).</p> | <p><u>Impact 1.</u> Same as Impact 1 for Preferred Alternative (4-59).</p> <p><u>Mitigation 1.</u> Same as Mitigation 1 for Preferred Alternative along with implementation of a revegetation/restoration program (4-59).</p> |
| | No impacts are expected. | No significant impacts are expected. | | |
| Water Resources | No impacts are expected. | No significant impacts are expected. | | |

Table 2-2
Summary of Environmental Impacts and Mitigations from the Disposal
and Reuse Alternatives (continued)

| Resource Category | DIRECT IMPACTS FROM NAVY ACTIONS | | INDIRECT IMPACTS FROM COMMUNITY REUSE | |
|--------------------------|----------------------------------|-----------------------|--|---|
| | Disposal | No Action Alternative | Revised Reuse Plan Alternative (Preferred Alternative) | Open Space Alternative |
| Water Resources (cont'd) | | | <p><u>Impact 2.</u> Significant and mitigable impacts could result if new Rafael Village area houses are developed in mapped 100-year floods from San Jose Creek, subjecting those houses to potential flood hazards (4-55).</p> <p><u>Mitigation 2.</u> Limit development to outside of flood area (4-55).</p> <p><u>Impact 3.</u> Significant and mitigable impacts could result from the existing storm drain system, which was designed to handle a 10-year recurrence interval rainfall, being inconsistent with the City of Novato's 25-year recurrence interval standard (4-55).</p> <p><u>Mitigation 3.</u> City shall require upgrade of system upon redevelopment of Rafael Village (4-55).</p> <p><u>Impact 4.</u> Significant and mitigable impacts could result from grading, demolition, and construction of new buildings in any of the Main Site planning areas from soil disturbance and increased erosion/sedimentation into Pacheco Creek and downstream in Ignacio Reservoir, Novato Creek, and San Pablo Bay (4-56).</p> <p><u>Mitigation 4.</u> Develop erosion control plans consistent with the SWPPP prior to any site clearing or grading. The SWPPP should include BMP's as described under Mitigation 1, above (4-56).</p> | |
| | | | | <p><u>Impact 2.</u> Same as Impact 4 for Preferred Alternative (4-59).</p> <p><u>Mitigation 2.</u> Same as Mitigation 4 for Preferred Alternative (4-59).</p> |

Table 2-2
Summary of Environmental Impacts and Mitigations from the Disposal
and Reuse Alternatives (continued)

| Resource Category | DIRECT IMPACTS FROM NAVY ACTIONS | | INDIRECT IMPACTS FROM COMMUNITY REUSE | |
|--------------------------|----------------------------------|-----------------------|---|--|
| | Disposal | No Action Alternative | Revised Reuse Plan Alternative (Preferred Alternative) | Open Space Alternative |
| Water Resources (cont'd) | | | <p><i>Impact 3.</i> Significant and mitigable impacts could result if development and reuse of Commissary Triangle and the Exchange Triangle subjected residents, workers, and other occupants of those areas to flood hazards in the event of a 100-year flood on Pacheco Creek (4-57).</p> | <p><i>Impact 3.</i> Same as Impact 5 for Preferred Alternative (4-59).</p> |
| | | | <p><i>Mitigation 5a.</i> Reuse of the Planning Areas subject to 100-year flood hazards should not occur until after completion of the planned new levees west of the airfield. Development should be set back from levees a sufficient distance as determined by Novato (4-57).</p> | <p><i>Mitigation 3a-3c.</i> Same as Mitigation 5a - 5c for Preferred Alternative (4-59).</p> |
| | | | <p><i>Mitigation 5b.</i> As an alternative to levee protection, any new development at sites below 10 feet msl should be protected from flooding by raising the base to a minimum 10 feet msl (4-57).</p> <p><i>Mitigation 5c.</i> The levees should be fitted with redundant pumping systems and an emergency power supply so adjacent low-lying areas are not flooded in a 100-year storm if power supply or pump fails (4-57).</p> | |

Table 2-2
Summary of Environmental Impacts and Mitigations from the Disposal
and Reuse Alternatives (continued)

| Resource Category | DIRECT IMPACTS FROM NAVY ACTIONS | | INDIRECT IMPACTS FROM COMMUNITY REUSE | |
|--------------------------|----------------------------------|--------------------------|---|---|
| | Disposal | No Action Alternative | Revised Reuse Plan Alternative (Preferred Alternative) | Open Space Alternative |
| Water Resources (cont'd) | | | <i>Impact 6.</i> Significant and mitigable flood hazard impacts could occur if constrictions in the drainage facilities downstream of Main Gate Road resulted in flooding of the Exchange Triangle area and adjacent lands along Pacheco Creek immediately upstream of that area during 100-year storm events (4-57). | <i>Impact 4.</i> Same as Impact 6 for Preferred Alternative (4-59). |
| | | | <i>Mitigation 6.</i> The deficient drainage facilities should be replaced and expanded as necessary to convey 100-year flood flows concurrent with the redevelopment of the Exchange Triangle area (4-58). | <i>Mitigation 4.</i> Same as Mitigation 6 for Preferred Alternative (4-59). |
| Traffic and Circulation | No impacts are expected. | No impacts are expected. | <i>Impact 1.</i> A significant and mitigable impact would result from the increase in demand for transit services from reuse of DODHF Novato under the reuse alternatives (4-71). | <i>Impact 1.</i> Same as Impact 1 for Preferred Alternative (4-73). |
| | | | <i>Mitigation 1.</i> Internal collector roadways at the Main Site should be constructed or improved to accommodate transit vehicles. Shuttle service should also be provided to bus stops on Nave Drive (4-71). | <i>Mitigation 1.</i> Same as Mitigation 1 for Preferred Alternative (4-73). |
| Air Quality | No impacts are expected. | No impacts are expected. | <i>Impact 1.</i> A significant and mitigable impact could result from building demolition, renovation, and construction activities generating localized dust nuisance conditions (4-77). | <i>Impact 1.</i> Same as Impact 1 for Preferred Alternative (4-81). |
| | | | <i>Mitigation 1.</i> Implement standard dust control practices to reduce impact to not significant level (4-78). | <i>Mitigation 1.</i> Same as Mitigation 1 for Preferred Alternative (4-81). |

Table 2-2
Summary of Environmental Impacts and Mitigations from the Disposal
and Reuse Alternatives (continued)

| Resource Category | DIRECT IMPACTS FROM NAVY ACTIONS | | INDIRECT IMPACTS FROM COMMUNITY REUSE | |
|-------------------------------|----------------------------------|--------------------------------------|---|--|
| | Disposal | No Action Alternative | Revised Reuse Plan Alternative (Preferred Alternative) | Open Space Alternative |
| Noise | No impacts are expected. | No impacts are expected. | <p><i>Impact 1.</i> Significant and mitigable noise impacts from building demolition, renovation, and construction activities associated with reuse of the Rafael Village, Commissary Triangle, and Exchange Triangle planning areas would occur from causing temporary noise disturbances to adjacent land uses (4-86).</p> <p><i>Mitigation 1.</i> Limit the use of heavy construction equipment and outdoor power tools to normal daytime hours during construction and demolition activities (4-86).</p> <p><i>Impact 2.</i> A significant unmitigable noise impact would result from residential reuse in areas that would be exposed to existing ambient noise levels significantly above the land use compatibility guidelines provided in the Novato General Plan (4-86).</p> <p><i>Mitigation 2.</i> Soundwall construction would reduce traffic noise impacts, but not to less than significant levels nearest US 101 (4-86).</p> | <p><i>Impact 1.</i> Same as Impact 1 for Preferred Alternative with fewer construction related impacts around Rafael Village (4-87).</p> <p><i>Mitigation 1.</i> Same as Mitigation 1 for Preferred Alternative (4-87).</p> <p><i>Impact 2.</i> Same as Impact 2 for Preferred Alternative except for Rafael Village, which would result in better land use compatibility (4-87).</p> <p><i>Mitigation 2.</i> Same as Mitigation 2 for Preferred Alternative (4-87).</p> |
| Hazardous Materials and Waste | No impacts are expected. | No significant impacts are expected. | No significant impacts are expected. | No significant impacts are expected. |

Note: Numbers in parentheses 0 indicate page where specific impact or mitigation is discussed in detail.

2.3 ENVIRONMENTALLY PREFERABLE ALTERNATIVE

NEPA requires that an EIS identify the alternative that is considered to be environmentally preferable (40 CFR 1505.2(b)). The environmentally preferable alternative would be the alternative that would promote the national environmental policy as expressed in NEPA. Generally, this would be the alternative that would cause the least damage to the biological and physical environment, and that would best protect, preserve, and enhance historic, cultural, and other natural resource while still meeting the purpose and need for the proposed action.

Because implementation of the No Action Alternative would not result in any significant impacts, the No Action Alternative would be considered the environmentally preferable alternative. An evaluation of the impact summary tables in Chapter 4 shows that each of the reuse alternatives would result in significant and mitigable impacts to utilities, biological resources, geology and soils, water resources, traffic and circulation, and air quality. In addition, the reuse alternatives would result in significant unmitigable impacts to noise. The No Action Alternative would avoid all significant impacts, both mitigable and unmitigable, and for this reason would be the environmentally preferable alternative.

2.4 ALTERNATIVES ELIMINATED FROM DETAILED CONSIDERATION

Most reuse options that were identified during the public scoping process have been incorporated into one or more of the alternatives analyzed in the EIS. Because reuse of the DODHF Novato property would consist mainly of the utilization of existing structures and the retention of historic land uses, the number of reasonable alternatives are limited. However, several land use alternatives for Rafael Village were considered and eliminated from detailed review in this EIS, as described below.

2.4.1 Retain Existing Rafael Village Housing Units

The option of retaining, repairing, and reusing the existing housing structures at Rafael Village was considered but eliminated from detailed consideration. The Hamilton Reuse Planning Authority, in analyzing reuse options, performed a structural analysis of select housing units in Rafael Village. The housing units to be examined were chosen by the Hamilton Homes Task Force, the coalition of homeless providers in the area that was interested in the units for transitional housing purposes. The findings of this analysis, contained in the Reuse Plan Existing Conditions Report (Hamilton Reuse Planning Authority 1995a), along with findings in the Navy report "Economic Analysis of 505 Family Housing Units at Rafael Village," determined that it

would be more costly to renovate the existing units and bring them up to local building code than to demolish them and construct new units. For this reason, the alternative of retaining the existing Rafael Village housing units has been eliminated from detailed consideration in this EIS.

2.4.2 High Density Residential Development

The alternative of developing a larger number of housing units, both on the Main Site and at Rafael Village, was considered but eliminated from detailed consideration. The primary reason for not considering this alternative was the traffic impacts that would result from substantially increased residential development. US 101 is currently experiencing a degraded level of service during certain time periods. Although the reuse alternatives would increase the residential population, the alternatives would generally reuse existing housing stock, or replace existing units at a roughly one to one ratio. Residential development at a substantially higher level also would result in the need for a costly new highway interchange at US 101. For these reasons, this alternative was eliminated from detailed consideration in this EIS.



3.0 AFFECTED ENVIRONMENT

| | | |
|------|---------------------------------|-------|
| 3.1 | LAND USE | 3-1 |
| 3.2 | AESTHETICS AND SCENIC RESOURCES | 3-17 |
| 3.3 | SOCIOECONOMICS | 3-21 |
| 3.4 | PUBLIC SERVICES | 3-35 |
| 3.5 | UTILITIES | 3-38 |
| 3.6 | CULTURAL RESOURCES | 3-49 |
| 3.7 | BIOLOGICAL RESOURCES | 3-56 |
| 3.8 | GEOLOGY AND SOILS | 3-68 |
| 3.9 | WATER RESOURCES | 3-80 |
| 3.10 | TRAFFIC AND CIRCULATION | 3-89 |
| 3.11 | AIR QUALITY | 3-104 |
| 3.12 | NOISE | 3-109 |
| 3.13 | HAZARDOUS MATERIALS AND WASTE | 3-113 |

3. AFFECTED ENVIRONMENT

This chapter provides a description of the existing environmental and socioeconomic conditions at DODHF Novato and the area surrounding the facility. This information is used in Chapter 4 to identify and evaluate environmental impacts resulting from the Navy disposal and community reuse of DODHF Novato.

Existing conditions as of 1995 are presented for most of the resources including land use, visual resources, public services, utilities, cultural resources, biological resources, geology and soils, water resources, and hazardous materials. In addition to existing conditions, several of the resource discussions, including socioeconomic, traffic, air quality, and noise, are supplemented by data from 1990, which provides information about conditions when DODHF Novato was fully occupied.

The setting discussion for each resource area also identifies the region of influence (ROI) applicable to the specific resource area. An ROI is a geographic area in which impacts for a particular resource likely would occur. The ROI for a resource having regional impacts will be different from the ROI for a resource with localized impacts.

3.1 LAND USE

DODHF Novato includes the Navy-owned sites at the former Hamilton Air Force Base (Main Site) and the Rafael Village housing area located approximately one mile northwest of the Main Site. This section describes existing land uses at DODHF Novato and surrounding areas. The ROI applicable to the land use discussion includes DODHF Novato and surrounding properties that could be affected by reuse. Figures 1-1 and 1-2 in Chapter 1 illustrate the regional location of DODHF Novato and the relative locations of Rafael Village and the Main Site.

3.1.1 Land Use Plans and Regulations for DODHF Novato

The following description is limited to plans and regulations pertaining to general land use at DODHF Novato. Regulations of certain specific resources or functions (e.g., biological resources, air quality, hazardous materials, and water resources) are discussed in other sections of this document. Consideration of regulations on surrounding land use is provided in Section 3.1.2. As federally-owned property, DODHF Novato has not been subject to local land use control, although the Navy has imposed its own controls. As parcels are transferred to the City of Novato or other nonfederal entities, land

use decisions regarding these parcels would be subject to Novato land use regulations under its general plan and zoning ordinance.

City of Novato Plans and Regulations

Novato General Plan

As part of the recent general plan update process, a vision statement was approved by the city's planning commission and adopted by the Novato City Council. The vision statement for Novato indicates that the small town character of the community and its beautiful setting and environment should be preserved and that new development within the community should reflect the quality of design and compatibility with the existing community character. The vision statement recognizes the changing demographics of the community, the need for a strong and diverse economy, and the need to resolve transportation problems. The Hamilton facility is specifically addressed in the city's vision statement, as follows:

"Hamilton Field is the largest remaining property left for development in Novato. It should be planned so that the development beneficially integrates into the rest of the community. Development should address Novato's jobs, housing and transportation needs while preserving wetlands and other biotic resources. In keeping with long-standing city policy based on voter direction, there shall be no aviation uses" (Novato 1995b).

The Novato General Plan is divided into nine chapters that correspond to the state mandated elements as shown in Table 3-1. Topics addressed in the land use element of the general plan apply to implementing the general plan land use map, growth management, constraints analysis for new developments, establishing the long range sphere of influence, and coordinating city services with other public agencies. The general plan assumes that the eventual total of housing units at both the Main Site and Rafael Village will not exceed the present 1,500 units.

The general plan specifies a standard of five acres of additional developed parkland per 1,000 residents for all new residential developments. It is assumed that this standard will be applied to the DODHF Novato residential developments in order to provide adequate parks and assure that off-site parks are not impacted by the increased population.

Table 3-1
Relation of Novato General Plan Chapters to State-Mandated Elements

| State-Mandated Elements | Novato General Plan Chapter |
|-------------------------|---|
| Land Use Element | Land Use Chapter |
| Circulation Element | Transportation Chapter |
| Housing Element | Housing Chapter |
| Conservation Element | Environment Chapter |
| Open Space Element | Environment Chapter |
| Safety Element | Safety Chapter |
| Noise Element | Safety Chapter |
| | Economic Development and Fiscal Vitality Chapter (optional) |
| | Human Services Chapter (optional) |
| | Public Facilities and Services Chapter (optional) |
| | Community Identify Chapter (optional) |

Source: Novato 1995b

Rafael Village General Plan Designations

The following section contains references to the land use designations found in the Novato General Plan; details of these designations are provided in Table 3-2. The Novato General Plan currently designates Rafael Village with the following land uses:

- Low Density Residential;
- Open Space;
- Medium Density Residential; and
- Medium Density Multiple Family Residential.

The medium density residential and medium density multiple family residential designations are located at the eastern end of Rafael Village near the existing commercial centers and US 101. The low density residential designations are located in the central and western portions of Rafael Village, while the open space designations extend in a linear fashion along San Jose Creek and Ignacio Boulevard.

Table 3-2
Novato General Plan Land Use Designations for DODHF Novato

| Designation | Uses Included | Allowable Density Range (Dwelling Units per Gross Acre) |
|---|--|---|
| Residential Designations | | |
| Low Density Residential | Detached or attached single-family dwellings, recreation, home occupations, community facilities, and other similar uses. | 1.1 to 5 |
| Medium Density Residential | Two-family dwellings, detached or attached single-family dwellings, recreation, home occupations, community facilities, and other similar uses. | 5.1 to 10 |
| Medium Density Multiple Family Residential | Multiple-family dwellings, two-family dwellings, detached or attached single-family dwellings, recreation, home occupations, community facilities, and other similar uses. | 10.1 to 20 |
| Office, Commercial, and Industrial Designations | | |
| General Commercial | Established commercial areas with off-street parking and/or clusters of street front stores; regional and local-serving retail establishments; specialty shops, banks, professional offices; motels; business and personal services; and other similar uses. This designation is typically assigned to larger parcels, located on a major arterial street. | Floor Area Ratio (FAR) of 0.4 |
| Neighborhood Commercial | Established neighborhood shopping areas, to meet the retail and service needs of nearby residents. This land use designation allows a variety of retail stores, and personal services such as grocery stores, dry cleaners, professional and administrative offices, restaurants, and other similar uses. Multi-family housing integrated with commercial uses is permitted. | FAR of 0.4, with an increase to 0.6 if housing is included, provided the difference between FAR of 0.4 and 0.6 is used for housing. |
| Conservation, Agricultural and Public Use Designations | | |
| Open Space | Publicly-owned land that is largely unimproved and devoted to the preservation of natural resources, outdoor recreation, floodways and flood control, and the maintenance of public health and safety. | Not applicable. |
| Parkland | Existing and undeveloped active and passive parks, recreation areas, and community playfields. Permitted uses include shelters, rest rooms, storage sheds, other structures needed to accommodate public use or provide for maintenance of the land, and cultural and recreational facilities. | Not applicable. |
| Community Facilities and Civic Uses | Public buildings, recreation and cultural facilities, museums, public libraries, city offices, fire and police stations, hospitals, and privately-owned uses operating in conjunction with public uses. | FAR of 0.25 |

Source: City of Novato 1996

Main Site General Plan Designations

Capehart Housing

General plan land use designations in Capehart Housing include the following:

- Medium Density Residential;
- Open Space; and
- Community Facilities, Public Facilities, and Civic Uses.

The medium density residential designations are located primarily in the northern portion of this planning area but also extend to the southeast. The open space designations are located in the center of the hillside areas and a small strip along the western boundary. The general plan designates the land along the existing unused railroad tracks as community facilities and civic uses.

Commissary Triangle

The entire Commissary Triangle planning area is designated for community facilities, public facilities, and civic uses.

Exchange Triangle

The Exchange Triangle planning area is designated for two acres of neighborhood commercial located somewhere along Main Gate Road and the remainder is designated for community facilities, public facilities, and civic uses.

Town Center

The Town Center planning area is designated for parkland, neighborhood commercial, and community facilities, public facilities, and civic uses.

Bowling Alley

The entire Bowling Alley planning area is designated for parkland.

Officers' Club

The Officers' Club planning area is designated for general commercial and community facilities, public facilities, and civic uses.

Ballfields

This planning area is designated in the General Plan as parkland.

Zoning

Zoning for Rafael Village and Main Site currently is not designated by the City of Novato. Zoning will be developed at the time of reuse plan implementation and will be consistent with the general plan designations described above.

Marin Countywide Plan

The Marin Countywide Plan is a long-range comprehensive plan that governs growth and development in the unincorporated areas of the county. The county's general plan divides the county into three environmental corridors—the city-centered corridor, the inland rural corridor, and the coastal recreation corridor. The city-centered corridor along US 101 and adjacent to the bay includes the Novato Planning Area and the former Hamilton facility. In general, the county's general plan defers to the general plans of incorporated cities within Marin County. The countywide plan states that it should be used as a guide in the development of each city's general plan.

The Marin Countywide Plan addresses future use of the Hamilton facility in the community development element section describing the Novato planning area. The plan recommends that the City of Novato consider including a mix of office and industrial uses in any development at the facility. It also recommends that the facility should be considered for additional housing development (Marin County 1994).

3.1.2 Land Use Regulations for Areas Surrounding DODHF Novato

City of Novato

The land use regulations currently applicable to areas surrounding DODHF Novato are the same City of Novato general plan and zoning regulations that would apply to the DODHF Novato property following disposal.

Properties surrounding Rafael Village are zoned P-C, R-P, R-1 (Single-family), R-2-H (Duplex Residential), R-3 (Multiple Residential), C-P (Planned Commercial), C-1 (Retail Commercial), C-2 (General Business Commercial), and A-2 (Limited Agricultural). The zoning of parcels surrounding Main Site is a mixture of PC, C-1, C-2, M-2 (Heavy Industrial), R-P, R-3, M-P (Planned Industrial), A-P (Administrative Professional), and A-60 (Agriculture).

Marin Countywide Plan

Policy T-3.1 of the countywide plan reflects the county objection to reuse of the Hamilton facility for general aviation uses. This policy states that Gness

Field, located north of the City of Novato in an unincorporated area of the county, shall be the only civilian airport facility and be used only for general aviation.

The Marin Countywide Plan designates the lands south of Hamilton Field as public facility, urban and conservation reserve, and tidelands.

Other relevant policies promote enhancement of wildlife and aquatic habitats in bayfront lands, and restoration of levee historic marshland to tidal status, seasonal wetlands, agricultural uses, flood basin, and wastewater reclamation areas.

San Francisco Bay Plan

The San Francisco Bay Conservation and Development Commission's (BCDC's) San Francisco Bay Plan was prepared to guide the future protection and use of San Francisco Bay and its shoreline. For the former Hamilton Army Airfield, the Bay Plan had a policy advocating that the site be retained for general aviation use when it was no longer needed by the Department of the Army. In addition, the plan stated that areas valuable for wildlife habitat or potentially restorable wetlands should be developed and managed for those purposes in a manner assuring general aviation uses.

The priority land use designation for the Hamilton runway has been reconsidered. BCDC deleted the airport priority use designation on the DODHF Novato property and changed the airport priority use to wildlife priority use on the Hamilton Army Airfield property. In addition, a new policy was added to read, "Hamilton Field: develop comprehensive wetlands habitat plan and long-term management program for restoring and enhancing wetlands habitat in diked former tidal wetlands. Dredged materials should be used whenever feasible and environmentally acceptable to facilitate wetlands restoration."

Federal Consistency Review

The authority to evaluate projects conducted, funded, or permitted by the federal government is granted to coastal states through the federal Coastal Zone Management Act (CZMA) of 1972, as amended. Under CZMA, any federal projects or activities affecting the coastal zone must be consistent to the maximum extent possible with the provisions of federally approved state coastal plans, even if the projects or activities occur inland of the coastal zone. The State Coastal Plan for San Francisco is the San Francisco Bay Plan, developed by BCDC, and the San Francisco Bay Area Seaport Plan, developed jointly by BCDC and the Metropolitan Transportation Commission. BCDC considers the DODHF Novato property outside of its jurisdiction.

Regional Airport System Plan

The Metropolitan Transportation Commission recently updated the Regional Airport System Plan for the San Francisco Bay Area, deleting the Hamilton Army Airfield as a future regional general reliever airport. The plan update also recommends that if the airfield itself is flooded or used for wetlands restoration, the acreage should be banked as mitigation for possible development of other airport projects in the Bay Area.

3.1.3 DODHF Novato Land Uses

The following descriptions of DODHF Novato are organized by the planning areas identified in the reuse plan and identify predominant existing land uses according to buildings, open space, and specialized facilities or areas. The descriptions are based on a November 1995 site visit and information contained in the 1995 Hamilton Army Airfield Existing Conditions Analysis. Table 3-3 summarizes the land use statistics of each planning area, and Figure 2-2 shows the boundary of each planning area.


Table 3-3
Land Use Planning Area Statistics

| Planning Area | Acreage | Dwelling Units | Open Space Acres |
|--------------------------|---------|----------------|------------------|
| PA 1 Rafael Village | 107 | 503 | 7 |
| PA 2 Capehart Housing | 216 | 708 | 85 |
| PA 4 Commissary Triangle | 13 | 0 | 0 |
| PA 5 Exchange Triangle | 28 | 0 | 0 |
| PA 6 Town Center | 8 | 0 | 0 |
| PA 8 Bowling Alley | 3 | 0 | 0 |
| PA 9 Officers' Club | 5 | 0 | 0 |
| PA 10 Ballfields | 31 | 0 | 0 |
| TOTAL | 411 | 1,211 | 92 |


Source: Hamilton Reuse Planning Authority 1995b

Planning Area 1. Rafael Village


Residential. Rafael Village is a residential subdivision with nonlinear streets located on the floor of a steep-sided valley and includes 503 units on 107 acres. There are approximately 209 single-family units, located primarily in the western portion, and 294 duplexes, located primarily in the eastern portion. Among the residences are four tot lots and numerous small-scale open space areas. As military housing, the units are generally not separated by yard fences and do not have property lines. Figure 3-1 illustrates the physical



Rafael Village is a residential area surrounded mostly by residential and open space land uses.



Legend:



DODHF Property Line
On Site Residential
On Site Open Space/Parkland

Approximate Boundaries of Existing Land Use

Rafael Village and Surrounding Area Land Use

DOD Housing Facility
Novato, California

Figure 3-1

Source: Tetra Tech 1995

layout and significant features of the Rafael Village planning area. Appendix C, Table C-1, details the specific characteristics of residential buildings in each planning area.

The units were constructed in 1950 and were upgraded in 1962 but are currently in varying degrees of disrepair; some are suitable for occupation, but most are uninhabitable due to deterioration. The housing units are boarded up to discourage vandalism and to minimize maintenance.

Nonresidential. A community center and a maintenance yard also are located at Rafael Village. The community center is in Building 404-1 on Owen Drive between Morgan and Norman Drives. This building is approximately 1,000 square feet and historically has been used as an exchange, a community center, and a laundry facility for the residents of Rafael Village; most recently it has been used as a karate center. The maintenance yard is located off Dickson Drive behind Buildings 890 and 892. The yard is approximately 5,000 square feet and contains no structures. Appendix C, Table C-2, details the specific characteristics of nonresidential buildings in each planning area.


The San Jose Creek corridor crosses Ignacio Boulevard twice and borders the southern edge of the planning area. The creek is further discussed in the Biological and Water Resources sections of this EIS.

Planning Area 2. Capehart Housing

Residential. Capehart Housing consists of military-style, residential housing and a large hillside open space area. The planning area includes 708 residential units on 216 acres of which 312 are townhouses and 246 are duplexes. All of these units were constructed in about 1960. The Hillside Housing subarea consists of 150 units in six-unit buildings constructed in 1988. Six tot lots are located in the planning area. Figure 3-2 illustrates the physical layout and significant features of the Main Site planning areas (Hamilton Reuse Planning Authority 1995a).

Nonresidential. Open space areas total 85 acres in this planning area and include the steep hill areas near the center of the planning area and Pacheco Creek, which runs along the western edge of the planning area. The hill area is characterized as having steep and unstable slopes, rock outcroppings, hiking trails, and mature oak trees.

The Golden Gate Bridge, Highway, and Transportation District owns the railroad tracks and a 105-foot right-of-way through DODHF Novato. This rail is currently inactive but is intended for use as a commuter rail line. The right-of-way runs from the east side of the Capehart Housing planning area through the Exchange Triangle and Commissary Triangle planning areas. This issue is further discussed in Section 3.10, Traffic and Circulation.




The Main Site and surrounding land uses are a mix of residential, open space, and community facilities. Section 2.2 maps highlight features within each planning area.

0 600 1200
Approximate Scale in Feet



Legend:



NHP Boundary

DODHF Property Line

Residential

Open Space/Parkland

Administrative/Community Support

**Main Site and
Surrounding Area Land Use**
DOD Housing Facility
Novato, California

Figure 3-2

Planning Area 4. Commissary Triangle

Commissary Triangle is a 13-acre site located north of Lanham Village near the northwestern corner of the Main Site. The nine warehouse-style buildings in this area were constructed just before or during World War II and historically served as an administrative and staff support area. After the closure of the Air Force Base, the operation of the base commissary continued as a staff support function. This planning area contains no residential units.

The three buildings served as the commissary were originally constructed as warehouses and are in fair to poor condition. One of the buildings is the actual store, one is used to warehouse the food, and one is used for administration. The large parking lot in front of the store accommodates 180 automobiles. Some of the other buildings in the planning area are vacant, while others are used for storage, an auto hobby shop, a carpentry shop, and vehicle storage.

Planning Area 5. Exchange Triangle

Exchange Triangle is located on flat ground and historically served as an administrative and staff support area near the western edge of the Main Site. This planning area consists of two sites— the primary site is north and east of Lanham Village, and the secondary site is directly south of Lanham Village at the corner of Main Gate Road and Nave Drive. The two sites in the Exchange Triangle planning area include 14 nonresidential structures and total 28 acres.

Recent uses of the buildings included retail stores in the exchange building, a credit union, youth centers, a gas station, maintenance buildings, administration buildings, and parking lots. With the exception of the gas station building and the exchange building, which were built in 1974 and 1975 and are in good condition, these facilities were constructed during World War II and are in fair to poor condition. Recreational facilities in the planning area include a tot lot and skateboard ramp.

Planning Area 6. Town Center

Town Center consists of eight acres at the terminus of Palm Drive and was historically used as an administrative and staff support area. Structures in this planning area include the security/arts building, movie theater, chapel, former infirmary, and former officers' mess. Buildings were constructed in the Spanish Eclectic architecture style.

Planning Area 8. Bowling Alley

The Bowling Alley consists of two buildings on three acres with a parking lot on the opposite side of San Pablo Avenue. The buildings house recreational facilities, including a bowling alley with a gym (constructed in 1945 and renovated in 1982) and racquetball courts in the second building, which was constructed in 1994. The areas around these buildings are landscaped.

Planning Area 9. Officers' Club

The Officers' Club planning area is a five-acre landscaped site with two large buildings—the vacant bachelor officers' quarters, constructed in 1934, and the community center, which was constructed in 1930.

Planning Area 10. Ballfields

The Ballfields planning area contains 31 acres and includes recreational fields (little league baseball fields), a swimming pool, and a pool house. Access to this area is via Caliente Real from San Pablo Avenue.

3.1.4 Surrounding Land Uses

Land uses surrounding the project area are discussed in the following section. Consideration of surrounding land uses provides background information for the Chapter 4 analysis describing the compatibility between proposed land uses at DODHF Novato and land uses on the surrounding properties.

Rafael Village Surrounding Land Use

Rafael Village is surrounded by residential, open space, institutional, commercial, and recreational areas. The following descriptions provide details of these surrounding areas.

North. To the north of Rafael Village are single-family residential subdivisions characterized as having fairly new, large, and well-maintained structures. From the east side of Highland Drive, the Nativity of Christ Greek Orthodox Church overlooks Rafael Village, and from this point a large open space area centered around Palmer Drive extends north of Rafael Village. The open space has steep slopes that extend from Rafael Village to the top of the hillside near Redwood Boulevard. Also to the north of Rafael Village is Mackey Terrace, an independent living development for very low income elderly and physically disabled residents. Access to Mackey Terrace and some of the other residential subdivisions is provided via Rafael Village.

East. Between Rafael Village and US 101 are apartment buildings and two commercial centers—Ignacio Plaza, located at Enfrente and Entrada, and Pacheco Plaza on the north side of Ignacio Boulevard. A Novato Fire Protection District fire station is located on Ignacio Boulevard near US 101.

South. South of Rafael Village and Ignacio Boulevard are single-family residential and multi-family neighborhoods. Country Club Estates, a well-maintained single-family neighborhood constructed in the 1970s, is located south of Ignacio Boulevard off Country Club Drive. An apartment complex is located south of Rafael Village and north of Ignacio Boulevard and is separated from Rafael Village by San Jose Creek. The Marin Country Club and Golf Course is also located south of Rafael Village; one of the fairways lies along the south side of and is visible from Ignacio Boulevard. Domingo Canyon, a residential neighborhood constructed in the 1960s and 1970s, is south of Ignacio Boulevard and adjacent to the two isolated portions of Rafael Village. San Jose Creek flows behind the neighborhoods south of Ignacio Boulevard (Hamilton Reuse Planning Authority 1995a).

Northwest. To the northwest of Rafael Village is San Jose Middle School and additional residential subdivisions.

Main Site Surrounding Land Use

The Main Site is surrounded by residential, commercial, open space, and US 101. These uses are detailed below.

North. North and east of DODHF Novato is the New Hamilton Partnership Master Plan area. When this development is completed, it will consist of approximately 920 residences on 415 acres, and several other land uses. This area was previously a part of the Hamilton Air Force Base, but has been transferred to private ownership. A summary of the approved New Hamilton Partnership Master Plan is shown in Table 3-4 and is described in detail in the Reuse Plan.

The Novato Sanitary District's (NSD) dechlorination plant is located on land owned by the State Lands Commission immediately north and east of the airfield. A buried outfall pipeline from the district's treatment plant runs along the northeastern property line of the airfield.

East. East of DODHF Novato are the hospital hill area of Hamilton Army Airfield and the runway parcel of Hamilton Army Airfield. The hospital hill area is currently Army property that is being excessed through the federal real estate screening process with the Department of Veterans Affairs having expressed interest in the acquiring the property. The area contains several buildings including the Hamilton Army Airfield military hospital that is still in partial use by the USCG and nonmedical Army personnel.

Table 3-4
Summary of New Hamilton Partnership Master Plan

| Land Use | Gross Acreage | Dwelling Units |
|----------------------|---------------|----------------|
| Mixed Use Areas | 9.4 | 920 |
| Office Uses | 25.7 | |
| Residential Uses | 131.7 | |
| Town Center | 3 | |
| Transit Center | 3.6 | |
| Major Roads | 21.1 | |
| Level | 8.5 | |
| Open Space | 167 | |
| Parks and Recreation | 45 | |
| Total | 415 | 920 |

Source: Hamilton Reuse Planning Authority 1995a

The Army runway parcel consists of 703 acres and includes the 6,000-foot runway and parking apron complex as well as the undeveloped floodplain to the east of the runway. The parcel is seven to 10 feet below sea level and is protected from flooding by a levee system. The Army is in the process of transferring this to the State Lands Commission as a floodplain. Details of the plan are provided in the Hamilton Army Airfield Disposal and Reuse EIS (US Army 1996).

South. Immediately south of Main Site is the Spanish Housing planning area, which is being transferred to the USCG for use as personnel housing.

The St. Vincent's and Silveira land holdings consist of approximately 1,500 acres of mostly open space in an unincorporated portion of Marin County south of the Capehart planning area and the USCG's Spanish Housing residential area. The land currently is used for grazing and hay production as well as the St. Vincent's School for Boys.

The majority of the St. Vincent's and Silveira land holdings are within the City of San Rafael's Sphere of Influence and urban service area and were studied during preparation of the 1988 General Plan Update. The San Rafael General Plan policies for this area allow mixed use development with up to 2,100 homes, 100,000 square feet of commercial uses, 261,000 square feet of office uses, and open space areas.

The Marin County Club Mobile Home Park is located on 165 acres immediately south of the Hillside subarea of the Capehart Housing planning area. The facility contains 315 mobile homes. The steep hills west of the mobile home park are contiguous with the open space areas inside the Capehart Housing planning area.

West. A small commercial and retail area is centered around Bolling Drive between Nave Drive and the Capehart Housing planning area. The Novato School District owns a 15-acre parcel south of Main Gate Road that has been developed with the Hamilton Elementary School and playground that serve the children of current Main Site residents.

Lanham Village is an 18-acre civilian residential development located between Main Gate Road and State Access Road along Nave Drive. This site was previously part of the Hamilton Army Airfield and consists of 154 units, accompanying parking areas, and open space areas. The property was transferred to the City of Novato by HUD. The Exchange Triangle and Commissary Triangle planning areas are located on the eastern and northern edge of Lanham Village. US 101 runs north/south along most of the western edge of the Main Site and is described in greater detail in the Transportation section.

3.2 AESTHETICS AND SCENIC RESOURCES

Aesthetic and scenic resources consider the natural and built features that make up the distinguishable character of the overall landscape. The ROI for visual resources includes DODHF Novato and the viewshed within five miles of DODHF Novato. A distance of five miles was selected because visual resources at a distance greater than five miles become indistinguishable from the general background of a viewshed.

Since the Proposed Action is primarily adaptive reuse of existing structures and continuation of established land use patterns, a generalized approach to visual assessment has been used for this analysis. The assessment process is based on review of photographs, a site visit in November 1995, and review of material in the Existing Conditions Report (Hamilton Reuse Planning Authority 1995a). For each planning area, the general and dominant visual characteristics are described. The relative importance of the site in terms of the number of viewers and frequency of viewing opportunities also is discussed. Photographs of DODHF Novato are provided in Appendix A.

3.2.1 Aesthetic and Scenic Resource Policies

The City of Novato will have jurisdiction over visual policies after disposal of DODHF Novato. Current Novato visual resource policies found in the General Plan apply mainly to the protection of visual resources on hillsides and ridgelines and would not apply directly to DODHF Novato. The city has a Design Review Committee to review the design features of new developments, such as those proposed at DODHF Novato during the reuse phase. The committee does not have a set of standards by which to review new projects but rather reviews each project on an individual basis in order to consider the appropriateness of the design features with the surrounding community.

The Reuse Plan contains a chapter focusing on urban design guidelines, and the Novato General Plan addresses visual resources in the Community Identity chapter. These two documents contain extensive goals and policies that will serve to guide future development in Novato.

3.2.2 Visual Characteristics of DODHF Novato Planning Areas

Planning Area 1. Rafael Village

The general appearance of Rafael Village is that of a suburban residential housing development with nonlinear streets and mature landscaping. Uniformity dominates the appearance of Rafael Village due to the painting, landscaping, and architectural similarity of the residences. All of the units are

painted the same shade of blue, have a similar level of front yard landscaping, and were constructed using the same design and materials. The uniformity creates a visually monotonous character that contrasts sharply with the varied architectural appearance of surrounding neighborhoods.

Visually enriching attributes of the site include the greenbelt areas mixed among the housing units and mature trees in the yards. Detracting attributes of the site include the architectural monotony, deteriorated condition of the boarded up houses, and the overhead utility lines.

The development was built in 1951, was upgraded in 1962, and shows many signs of age and wear. From the outside, many of the units are in obviously poor condition, with deteriorated landscaping, peeling paint, missing fascia boards, sagging supports, broken gates, and visible termite damage. The windows are boarded up to reduce vandalism, which, combined with the deteriorating structures, detracts from the visual appeal of Rafael Village and the surrounding community. Indications of vandalism include graffiti and scattered trash in the carports. The unoccupied and deteriorating structures contrast with the many newer and well-maintained residences in the surrounding neighborhoods.

The site is prominent because it is on Ignacio Boulevard, the main access road for the surrounding developments. Some of these can be accessed only by driving through Rafael Village. San Jose Boulevard, Dickson Drive, Palmer Drive, Ransome Drive, and Shaeffer Drive are routes to homes in the Highland Knolls and Marin Glen developments.

Views from Rafael Village to the surrounding areas are unremarkable and consist primarily of the residential developments and wooded undeveloped hillsides. Views toward Rafael Village from the surrounding hillsides are enhanced by the mature deciduous trees, which partially obscure the site. During the winter, however, these trees fail to fully obscure the unoccupied homes and overhead utility lines in Rafael Village.

Planning Area 2. Capehart Housing

The general appearance of Capehart Housing is that of a suburban residential housing development set among an open space hillside area. The visual character of Capehart Housing is dominated by the nonlinear street and residential layout and four steep hillside areas that range from 180 to 250 feet in elevation.

The structures and landscaping appear well-maintained and do not have the visually monotonous character of Rafael Village. The residential buildings in the planning area are typically single- and double-story multi-family housing units with attached carports. The nonlinear streets, mature landscaping, and

3.2 Aesthetics and Scenic Resources

hillside areas serve to segment the visual flow and to reduce the apparent density of the buildings. These buildings were constructed in the late 1950s and early 1960s and reflect the design of woodframe construction during that era. The range of exterior colors includes warm sand, white, and beige.

The west edge of the planning area along Bolling Drive has views of the adjacent USCG Spanish Housing area. The hilltops allow expansive views of San Pablo Bay and the wooded hills of Novato. Views of the planning area from other sites are fairly limited due to the surrounding hills and vegetation that block adjacent viewing areas.

Planning Area 4. Commissary Triangle

The general appearance of the relatively flat Commissary Triangle is that of a warehouse and parking lot area. This site has minimal landscaping and is dominated by the large amount of paved area and lack of cohesion between the buildings. None of the buildings have remarkable design features.

The site is highly visible due to the immediate proximity of State Access Road, which allows direct visual access.

Planning Area 5. Exchange Triangle

The general appearance of Exchange Triangle is that of a flat developed area with extensive parking lots and a variety of old and new buildings. These buildings vary in size from the 1,750 square foot youth scouting buildings to the large 18,000 square foot public works building. As discussed in the Land Use section, this planning area actually consists of two sites, one north of Main Gate Road and one south. The site north of Main Gate Road contains a landscaped area and a white stucco administration building that enhance visual appeal.

The site south of Main Gate Road has minimal landscaping and unremarkable design features on the buildings. The asphalt, age of the buildings, and lack of visual cohesion among the buildings dominate the visual character of this area. The site has fairly high visibility due to its immediate proximity to Main Gate Road and State Access Road, which allow direct visual access.

Planning Area 6. Town Center

The general appearance of Town Center is that of a well-maintained public area. Visual attributes of the site include the mature landscaping, Spanish Eclectic architecture of the buildings, and Palm Drive, the tree-lined road that serves as a visual gateway to the site.

The large amount of landscaped area surrounding the buildings imparts a visually open character to this planning area. Views of this area are primarily from locations in the off-site USCG Spanish Housing and Hospital Hill areas.

Planning Area 8. Bowling Alley

The general appearance of the Bowling Alley is that of two large buildings and an associated parking lot. When viewed from the parking lot, the landscaped hill of the Officers' Club provides a visually attractive background for this planning area.

The white stucco buildings provide some consistency with design features of the surrounding planning areas, but the lack of other design attributes makes the buildings less visually appealing than the surrounding areas. Visual access to this area is primarily limited to on-site viewers, including those using San Pablo Road as access to the Ballfields planning area.

Planning Area 9. Officers' Club

The general appearance of the Officers' Club is that of a landscaped hill area with two buildings. The buildings are visually attractive and were constructed using the same Spanish Eclectic style architecture found in the adjacent USCG Spanish Housing. The use of the matching architecture style provides aesthetic continuity between the two planning areas. Visual access to this area is limited to on-site viewers with some adjacent viewpoints provided in the Bowling Alley and off-site Spanish Housing planning areas.

Planning Area 10. Ballfields

The general appearance of the Ballfields is that of an open space with partially developed recreational facilities and parking lots. Visually enhancing characteristics of the site include the landscaping and the expansive easterly views toward San Pablo Bay. Viewing opportunities of the site and from the site are fairly limited due to the shielding effect of hills in the adjacent USCG Spanish Housing area.

3.3 SOCIOECONOMICS

This section describes the regional socioeconomic setting. Socioeconomic conditions addressed include employment, population, income, housing, schools, and recreation. This setting describes the social and economic indicators of the region that may be significantly affected by disposal and reuse.

The projected conditions are described for 1996, the year DODHF Novato will close. Socioeconomic data is available up until 1995, and socioeconomic conditions are not expected to differ substantially in 1996. Where more recent or reliable data is unavailable, 1990 census data is used.

Marin County is the ROI for social and economic impacts. This definition was selected because 60 percent of residents of Marin County also work within the county (US Census 1990). Thus the county population and economy will be the area primarily affected by the DODHF Novato closure.

The disposal and subsequent reuse of DODHF Novato is not expected to affect all areas of the ROI equally. Some effects will be felt only within the City of Novato, and specific socioeconomic data is given in those cases.

3.3.1 Regional Employment

Employment

To illustrate employment trends, general and specific employment data for Marin County is given on Tables 3-5 and 3-6 for the years 1980 and 1995.

Table 3-5
1980 and 1995 Labor Force and Employment Data
for Marin County (amount in thousands)

| Indicators | Marin County | | |
|-------------------|-----------------|--------------|----------------|
| | 1980 (Annl Avg) | October 1995 | Percent Change |
| Labor Force | 112.1 | 132.7 | 18.4% |
| Number Employed | 106.8 | 127.3 | 19.2% |
| Number Unemployed | 5.3 | 5.4 | 1.9% |
| Unemployment Rate | 4.7% | 4.1% | - |

Source: California Employment Development Department 1995; ERA

Table 3-6
Historical Employment Composition for the ROI


| Employment | Marin County (ROI) | | | | |
|-------------------------------|--------------------|---------|----------------------|-----------------------|-----------------------|
| | 1980 | 1995 | 1995 Job Composition | Change from 1980-1995 | Annual Rate of Change |
| Agriculture & Mining | 621 | 960 | 1% | 55% | 2.9% |
| Construction | 4,190 | 5,940 | 6% | 42% | 2.4% |
| Manufacturing | 4,829 | 4,520 | 4% | -6% | -0.4% |
| Transp., Comm., Utilities | 4,640 | 4,130 | 4% | -11% | -0.8% |
| Wholesale Trade | 2,514 | 4,830 | 5% | 92% | 4.4% |
| Retail Trade | 19,852 | 22,360 | 22% | 13% | 0.8% |
| Finance/Insurance/Real Estate | 11,549 | 10,420 | 10% | -10% | -0.7% |
| Services | 26,818 | 42,910 | 42% | 60% | 3.2% |
| Government | 2,840 | 4,390 | 4% | 55% | 2.9% |
| Total All Industries | 77,853 | 102,455 | 100% | 32% | 1.8% |

Source: Association of Bay Area Governments 1993; ERA

According to October 1995 data, Marin County had a labor force of 132,700 people, 127,300 of whom are employed. Approximately 5,400 people, or 4.1 percent of the labor force, are unemployed. In comparison, the state's unemployment rate was 7.4 percent during the same period (California Employment Development Department 1995).

As indicated by Table 3-6, Marin County's largest employment industry in 1995 was the service sector (which includes business, repair, personal, entertainment, recreation, health, and educational services). The service sector accounts for 42 percent of total employment for the county. The next largest employment industry is retail trade, which accounts for 22 percent of total employment, and finance/insurance/real estate (F.I.R.E.), which accounts for 10 percent of total employment. The wholesale trade sector has been the fastest growing employment industry, with a 4.4 percent annual growth since 1980. This is followed by the services sector, with a 3.2 percent annual growth rate. Manufacturing, finance/insurance/real estate, transportation, communication and utilities jobs are all in decline. A comparison of Marin County job composition between 1980 and 1995 is shown in Figure 3-3. Overall, Marin County has displayed a 1.8 percent annual employment growth in the past 15 years, gaining 24,602 jobs between 1980 and 1995. Between 1995 and 2020, Marin County is projected to add 51,000 jobs (Table 3-7) (Association of Bay Area Governments 1993).

Figure 3-3
Job Composition in Marin County (ROI) (1980 & 1995)



Source: Association of Bay Area Governments 1993

Table 3-7
ROI Employment Projections (1995-2020)
(amount in thousands)


| Area | 1995 | 2000 | 2010 | 2020 ¹ |
|--------------------------------------|------------|------|------|-------------------|
| Marin County Jobs | 100 | 111 | 130 | 151 |
| Annual % Change from Previous Period | not avail. | 1.0% | 1.5% | 1.5% |
| City of Novato Jobs | 17 | 17 | 21 | 26 |
| Annual % Change from Previous Period | not avail. | 0.4% | 2.0% | 2.0% |

¹ Estimates based on annual growth rate from 2000 to 2010.
Source: Association of Bay Area Governments 1993; ERA

During the last 15 years (1980-1995), the number of jobs in Novato increased from 13,783 to 17,360. Novato is projected to add approximately 9,000 jobs between 1995 and 2020 (see Table 3-7 and Figure 3-4) (Association of Bay Area Governments 1993).

The projected increase in employment will affect the balance between jobs and housing. In 1995, there are more employed residents in Novato than there are jobs. This means that a significant proportion of employed residents commute outside the city. Increasing the number of jobs, particularly in the retail and

Figure 3-4
ROI Employment Growth (1990-2020)



Source: Association of Bay Area Governments 1993; ERA

service sectors, will result in an increased demand for affordable housing (Novato 1995d).

Personal Income

The mean household income in 1995 for Marin County was \$72,700. This is projected to increase to \$103,500 (a 1.4 percent annual increase from 1995) by 2020. These figures are expressed in constant 1990 dollars. The mean household income for the City of Novato in 1995 was lower at \$61,600. This figure is expected to steadily increase to \$89,800 (a 1.5 percent annual increase from 1995) by 2020 (Association of Bay Area Governments 1993).

3.3.2 Population and Housing

Population

Marin County's population growth has been one of the slowest of all Bay Area counties, averaging 0.6 percent annual growth or an absolute increase of 22,000 residents between 1980 and 1995. Marin County is expected to maintain low levels of population growth between 1995 and 2020, with an estimated increase of 26,000 residents or 0.4 percent annual growth during this period. Novato's population growth parallels that of the county, as shown in Table 3-8.

Table 3-8
Historical and Projected Population, 1980-2020
 (amount in thousands)

| Area | 1980 | 1995 | 2000 | 2010 | 2020 ¹ |
|---|------------|------|------|------|-------------------|
| <u>Marin County</u> | 223 | 245 | 254 | 261 | 270 |
| Annual % Change from Previous Period | not avail. | 0.6% | 0.7% | 0.3% | 0.3% |
| <u>City of Novato</u> | 51 | 56 | 59 | 61 | 64 |
| Annual % Change from Previous Period | not avail. | 0.6% | 1.0% | 0.4% | 0.4% |

¹ Estimates based on annual growth rate from 2000 to 2010.
 Source: Association of Bay Area Governments 1993; ERA

Housing at DODHF Novato and the City of Novato

Housing at DODHF Novato. DODHF Novato contains 1,490 residential units. Of these, 503 are located in Rafael Village, west of US 101. At the Main Site, there are 708 units in Capehart Housing, including 150 units in the subarea referred to as Hillside Housing. The housing units at Rafael Village are at the end of their lifespan with substandard structural conditions. The remaining housing units are generally in good building condition and are structurally adequate with correctable building code violations. There are also 282 units in the off-site USCG Spanish Housing area, of which 150 are located in the area called Knoll Housing.

As of January 1996, approximately 546 of the 1,490 units were occupied by Army, Navy, Air Force, USCG, and Marine military personnel. No one resides at the Rafael Village housing area. The 282 units in Spanish Housing are being transferred to the USCG.

Home Value and Housing Composition. Novato's housing stock includes a mixture of single-family and multi-family housing units (Table 3-9). Single-family homes represent 72 percent of Novato's 19,179 total residential units. Townhouses (attached dwellings) constitute about 20 percent of Novato's single-family housing, a far greater proportion than any of the other largest North Bay cities, which include Fairfield, Napa, Petaluma, San Rafael, Santa Rosa, Vacaville, and Vallejo. As shown in Table 3-10, homeowners occupy 60 percent of Novato homes, while renters occupy 37 percent (Novato Chamber of Commerce 1995; California Department of Finance 1995).

Table 3-9
Number and Type of Housing, Novato 1995

| Type of Housing | Number | Percent |
|--------------------|--------|---------|
| One Unit Detached | 10,450 | 55% |
| One Unit Attached | 3,535 | 18% |
| Two to Four Units | 1,073 | 6% |
| Five or More Units | 3,481 | 18% |
| Mobile Home | 640 | 3% |
| TOTAL Units | 19,179 | 100% |

Source: California Dept. of Finance 1995

Table 3-10
Housing by Type of Tenure, Novato

| Type of Tenure | City of Novato | |
|-----------------|-----------------|-----------------|
| | 1990 | |
| | Number of Units | As a % of Total |
| Owner-occupied | 11,289 | 60.1% |
| Renter-occupied | 6,947 | 37.0% |
| Vacant | 546 | 2.9% |
| Total | 18,782 | 100.0% |

Source: California Department of Finance 1995; US Census 1990; ERA

Housing Costs and Resale Prices. According to 1990 census data, the median value of a Novato home is \$279,600. This represents a 114 percent increase over the median value of \$130,754 in 1980. Table 3-11 shows the distribution of housing by value (Novato Chamber of Commerce 1995).

Table 3-11
Value of Owner-occupied Housing Units in Novato, 1990

| Value of Home | Percent of Novato Housing |
|------------------|---------------------------|
| Under \$100,000 | 1.0% |
| 100,000-150,000 | 5.4% |
| 150,000-200,000 | 7.7% |
| 200,000-250,000 | 20.3% |
| 250,000-300,000 | 22.9% |
| 300,000-400,000 | 25.4% |
| 400,000-500,000 | 8.6% |
| 500,000 and Over | 6.6% |

Source: Novato Chamber of Commerce 1995

The desirability of living in the Novato area, along with the supply of more affordable housing than southern Marin County, has created a steady demand and turnover of Novato housing. The 1990 census showed Novato median home value was \$279,600 compared to the Marin County median of \$354,200. About 1,300 Novato households a year in recent years have turned over in the form of resales or new tenants in rental units, according to the 1991 Novato Household Survey. In 1993, 646 homes were resold in Novato, about 21 percent of all sales in Marin County that year (Novato Chamber of Commerce 1995).

Housing Rental Costs. The Novato area offers nearly 7,000 rental housing units in a broad range of prices. Table 3-12 shows prevailing rental rates for all types of housing available in Novato (Novato Chamber of Commerce 1995).

Table 3-12
Monthly Rental Ranges, Novato 1994

| Type of Unit | Monthly Rental Range |
|------------------------|----------------------|
| Apartment | |
| 1 BR | \$550-735 |
| 2 BR | \$710-870 |
| 3 BR | \$900-1,050 |
| Townhouse/Condo | |
| 1 BR | \$600-800 |
| 2 BR | \$800-1,160 |
| 3-4 BR | \$1,030-1,375 |
| Detached Single-family | |
| 1-2 BR | \$850-975 |
| 3 BR | \$1,050-2,100 |
| 4 BR | \$1,450-2,500 |

Source: Novato Chamber of Commerce 1995

Vacancy Rate. The California Department of Finance reports a vacancy rate of three percent in 1994 in Novato. It is generally accepted that a vacancy rate of 4.5 percent is needed to provide for normal turnover in housing units. Novato's low vacancy rate indicates a continuing strong demand for rental housing in the community (Novato 1995d).

Below Market Rate Housing. Novato-based Northbay Ecumenical Homes (NEH) (formerly Novato Ecumenical Housing) is a non-profit corporation founded in 1978 to create affordable housing for rent or ownership. To date, NEH, in conjunction with the City of Novato, has helped develop, assisted, and/or sponsored over 1,500 housing units in the Novato area, 30 percent of which are affordable units. Within the Novato area, there are about 400 below-market rate housing units in the planning phase for low- and moderate-income families and seniors. The majority of these planned affordable housing

units are included in the privately developed New Hamilton Partnership project and proposed Bel Marin Keys housing developments (Novato Chamber of Commerce 1995).

The reuse of DODHF Novato will contribute to the creation of affordable units in Novato. The Reuse Plan specifies the location, number, and ownership structure of affordable residential units planned at DODHF Novato. A total of 718 affordable units are planned, with 324 units for ownership and 393 units for rental (Hamilton Reuse Planning Authority 1995b).

Household Size and Projections. Statistics on average size and numbers of households for the City of Novato and Marin County are presented in Table 3-13. Between 1980 and 1995 the number of households in Novato grew from 17,962 to 20,216, a 12.5 percent increase. This is compared to a seven percent increase in Marin County. The average household size in Novato in 1995 was estimated to be 2.64 persons per household, which is expected to decrease steadily to 2.55 by 2020 (Association of Bay Area Governments 1993).

Table 3-13
Characteristics of Households, 1980-2020

| Location | 1980 | 1990 | 1995 | 2000 | 2010 | 2020 ¹ |
|------------------------------|--------|--------|--------|---------|---------|-------------------|
| <u>Persons per Household</u> | | | | | | |
| Novato | 2.79 | 2.60 | 2.64 | 2.61 | 2.55 | 2.55 |
| Marin County | 2.43 | 2.33 | 2.38 | 2.35 | 2.31 | 2.31 |
| <u>Number of Households</u> | | | | | | |
| Novato | 17,962 | 20,216 | 21,040 | 22,330 | 23,630 | 25,330 |
| Marin County | 88,723 | 95,006 | 98,910 | 103,250 | 107,210 | 111,322 |

¹ Estimates of persons per household based on previous decade's average persons per household.

Number of households estimates based on annual growth rate from 2000 to 2010.

Source: Associations of Bay Area Governments 1993; ERA

The forecast household growth for the City of Novato from 1995 through 2020 is approximately 4,290 new households, or a 20 percent increase in a 25-year period. This reflects Novato's slow projected population growth, which has characterized overall growth in Marin County in the last few decades (Association of Bay Area Governments 1993).

3.3.3 Schools

The following discussion on area schools was adapted from the Hamilton Army Airfield Existing Conditions Analysis, May 1995 (Hamilton Reuse

Planning Authority 1995a) and the Existing Conditions Report, City of Novato General Plan Revision (Novato 1995d).

The Novato Unified School District (NUSD) serves the former Hamilton Air Base Field site with Novato High School, San Jose Middle School, and Hamilton Elementary School. The NUSD currently provides education to nearly 7,022 students at seven elementary schools, three middle schools, two high schools, one continuation high school, and one independent study school. The average class size in the district is 27.58 students. Specific capacity and enrollment data is given for these schools in Table 3-14.

Table 3-14
Novato Unified School District Enrollment and Capacity

| School | School Capacity | Enrollment (Feb. 95) | Enrollment/Capacity |
|---------------------------|-----------------|----------------------|---------------------|
| Elementary Schools | 3,584 | 3,170 | 88% |
| Hamilton | 672 | 507 | 75% |
| Loma Verde | 476 | 385 | 81% |
| Lu Sutton | 504 | 501 | 99% |
| Lynnwood | 448 | 373 | 83% |
| Olive | 476 | 403 | 85% |
| Pleasant Valley | 476 | 524 | 110% |
| Rancho San Ramon | 532 | 477 | 90% |
| Middle Schools | 2,024 | 1,880 | 93% |
| San Jose | 728 | 556 | 76% |
| Hill | 540 | 570 | 106% |
| Sinaloa | 756 | 754 | 100% |
| High Schools | 2,263 | 1,972 | 87% |
| Novato | 1,213 | 1,052 | 87% |
| San Marin | 1,050 | 920 | 88% |
| Total | 7,871 | 7,022 | 89% |

Source: Hamilton Reuse Planning Authority 1995a

Student enrollment has declined in recent years at each of the schools in the DODHF Novato area. Between 1993 and 1995, enrollments declined by 15.9 percent at Hamilton Elementary School, 6.1 percent at San Jose Middle School, and 9.5 percent at Novato High School, largely due to the reductions in the number of military families at the base. Based on the school capacity figures above, Hamilton Elementary School is operating at 25 percent below capacity, San Jose Middle School at 24 percent below capacity, and Novato High School at 13 percent below capacity.

The reuse of military housing by civilian families poses a significant challenge to the district in terms of short- and long-range planning. In the short term, the district will be faced with reduced revenues and the need to use and maintain the affected school facilities so that they can be readily reoccupied. In the long term, the district must try to anticipate the phasing of development and reoccupation of the Navy housing.

The NUSD has also expressed interest in acquiring additional land at DODHF Novato for school facilities. The request includes the following:

- Two acres adjacent to Hamilton Elementary School where the housing office is located,
- Two and one-half acres with light industrial zoning for educational purposes only—a vehicle maintenance building (Building 972) would house the NUSD automotive training program, the Marin Conservation Corps construction training class, and the County Regional Occupational program auto training class,
- One acre zoned for office use for a new administrative center, and
- Five to eight acres with institutional zoning for a charter school.

Table 3-15 shows NUSD assumptions for the number of students per household. These rates will be applied in estimating the additional enrollment associated with increases in housing units.

Table 3-15
Student Generation Factors

| Grade Range | No. of Students/Household Single-family Household |
|-------------|--|
| K-6 | 0.055 |
| 7-8 | 0.042 |
| 9-12 | 0.042 |

Source: Novato 1995d

3.3.4 Recreation

As a housing and community support facility, DODHF Novato owns and maintains the indoor and outdoor recreational facilities listed in Table 3-16.

Table 3-16
Existing DODHF Novato Recreational Facilities

| Planning Area | Recreational Facility |
|---------------------|---|
| Rafael Village | Four tot lots |
| Capehart Housing | Six tot lots |
| Commissary Triangle | None |
| Exchange Triangle | One tot lot; skate board ramp; youth center |
| Town Center | None |
| Bowling Alley | Gym; bowling alley; racquetball courts |
| Officers' Club | Community center |
| Ballfields | Pool; poolhouse; four ballfields |

Source: Hamilton Reuse Planning Authority 1995a

The City of Novato owns and maintains 59.16 acres of developed parks and recreation area. In addition, the city owns 140 acres of undeveloped future parklands and 26 acres of recently purchased wetlands known as Scottsdale Marsh. The bulk of its undeveloped parkland is the 100-acre Neil O'Hair Park site. There are numerous publicly-owned parks and recreation facilities, as well as privately-owned recreation facilities, within the Novato sphere of influence. City facilities include 13 mini-parks, five neighborhood parks, three district parks, seven specialized facilities, plus five other jointly developed recreation facilities (Novato 1995d).

Since 1970, the city and the Novato Unified School District have codeveloped recreation areas at four elementary school sites, providing another 12 acres of play fields and neighborhood parks. Within its inventory of public land, the city has title to approximately 550 acres of public open space. During fiscal year 1986/1987, title to 470 acres of open space was transferred to the Marin County Open Space District (Novato 1995d).

Under the Marin Countywide Plan Parks and Recreation Element, the county is proposing to increase support for local communities and districts and to assist these jurisdictions with providing local parks and recreation facilities. The local communities have been evaluated to assist with planning park and recreation facility improvements. Based on standards established under the maximum dedications of the Quimby Act, which permits an agency to require land dedications or to charge user fees to new residential subdivisions, the county estimates a shortage of 56 acres of parks within the Novato community (based on a five acre per 1,000 resident standard). Further, the county has identified those portions of individual communities that are currently lacking adequate park and recreation areas. All neighborhoods

within Novato are considered to be under provided with parks. Additionally, the Countywide Plan notes that all active recreation areas, community centers, and school sites with athletic fields are overused (Novato 1995d).

3.3.5 Environmental Justice

On February 11, 1994, President Clinton issued the Executive Order on Federal Actions to Address Environmental Justice in Minority and Low-Income Populations. This order requires that "Each Federal agency shall analyze the environmental effects, including human health, economic and social effects, of Federal actions including effects on minority communities and low-income communities, when such analysis is required, by the National Environmental Policy Act of 1969 (NEPA), 42 U.S.C. section 4321 et.seq. Mitigation measures outlined or analyzed in an environmental assessment, environmental impact statement, or record of decision, whenever feasible, should address significant and adverse environmental effects of proposed Federal actions on minority communities and low-income communities." Therefore, demographic information on ethnicity, race, and poverty status for the City of Novato has been included.

The City of Novato has been established as the primary ROI for analyzing environmental justice issues because the nature of the significant impacts associated with disposal and potential reuse would occur primarily at the local city and neighborhood levels. A discussion of environmental justice and potential impacts from disposal and reuse is presented in Chapter 5.


Based on the 1990 census data, 89.6 percent of Novato's population is Caucasian, 2.8 percent is African American, 5.0 percent is Asian and Pacific Islander, 0.5 percent is Native American, and the remaining 2.1 percent is made up of other groups (see Table 3-17 and Figure 3-5). Of the total city population, persons of Hispanic origin make up 7.4 percent. This figure is based on the number of persons who classify themselves as Hispanic based on their language, ancestry, and country of origin (i.e., Spain, Mexico, Puerto Rico, Dominican Republic, and any other Central and South American countries). Therefore, persons of Hispanic origin may be of any race.

Table 3-17
1990 Race/Ethnic Composition and Poverty Status

| Race/Ethnicity | City of Novato | | | |
|--------------------------|------------------|----------------------------|-----------------------------|----------------------------|
| | Total population | | Persons below poverty level | |
| | Number | As a % of Total Population | Number | As a % of Total In Poverty |
| African American | 1,328 | 2.8% | 75 | 3.8% |
| Caucasian | 42,622 | 89.6% | 1,671 | 84.8% |
| Asian & Pacific Islander | 2,390 | 5.0% | 92 | 4.7% |
| Native American | 237 | 0.5% | 3 | 0.2% |
| Other | <u>1,008</u> | <u>2.1%</u> | <u>130</u> | <u>6.6%</u> |
| Total | 47,585 | 100.0% | 1,971 | 100.0% |
| Hispanic ¹ | 3,522 | 7.4% | 352 | 17.9% |

¹ Persons of Hispanic origin may be of any race.
Source: US Census 1990; ERA

Figure 3-5
Race/Ethnic Composition of Novato



According to 1990 census data, approximately 1,971 of Novato's residents (4.1 percent of the population) were living in poverty. The Census Bureau determines poverty status for families and individuals based on 48 threshold variables; these include income, amount spent on food, family size, number of children under 18, and number of family members over 65. The average poverty threshold for a family of four persons was an income of \$12,674 or below in 1989 (US Census 1990).

Census tract data for the Lanham Village housing area, the closest residential area to DODHF Novato and one of the more affordable housing areas in Marin County, also were examined. Lanham Village is included in Census Tract 1050, a tract covering the entire area of the former Hamilton Air Force Base. An examination of Census Tract 1050 revealed minority and income status similar to other areas of Novato. The census tract also showed income levels in this area lower than the average Marin County income but well above the poverty level.

Of the residents classified as poor, people who identified themselves of Hispanic origin are disproportionately represented in Novato (see Table 3-17). Hispanics made up 7.4 percent of the population of Novato, but according to census data, they represent 17.9 percent of all persons below the poverty level.

3.4 PUBLIC SERVICES

This section describes the fire protection, emergency medical, and police protection services for DODHF Novato. These services and the agencies that provide them insure the protection of life, health, and property from fire, crime, and other emergencies. The ROI for public services is the City of Novato, which includes DODHF Novato. Regional fire protection, emergency medical services, and police protection are provided by agencies of the City of Novato. Services to DODHF Novato are provided through a contract with the Navy. The Navy also contracts with a private security firm to provide supplemental security services to DODHF Novato.

3.4.1 Plans and Policies

Novato General Plan

The general plan has several objectives related to public services, including the reduction of fire hazards and the maintenance of effective police and emergency medical services. To implement these objectives, the City of Novato and the Novato Fire Protection District (NFPD) have developed an ordinance prohibiting combustible roof materials, a vegetation abatement and fire hazard reduction program, a homeowner guide for survival of woodland fires, and a sprinkler ordinance. The sprinkler ordinance requires all new single-family dwellings and new buildings 2,500 square feet or larger to have automatic sprinkler systems. In addition, the city has established a minimum flow requirement in city fire hydrants of 1,000 gallons per minute with 20 pounds per square inch residual pressure.

In response to the objective for effective service, the NFPD has set a goal of responding to 90 percent of emergency incidents within five minutes. The Novato Police Department seeks to foster community-police cooperation in the prevention of crime and delinquency and to meet the public demands for noncrime police services. Approximately 85 percent of police calls are requests for service rather than responses to crime.

The City of Novato General Plan Revision, Existing Conditions Report (Novato 1995d) outlines the following fire protection policies: new residential projects proposed in areas with extreme fire hazards should be allowed only where it is determined that adequate on- or off-site fire suppression water supply is or can be made available; fire trails, fuel breaks, and fire-resistant plant materials should be used and required; and designated routes of safe pedestrian and vehicular evacuation should be required. The NFPD is working towards its goal of responding to 90 percent of emergency incidents within five minutes through the following activities: procurement of funds to purchase land for future fire station sites; continued analysis of disasters to

develop a learning base for future disaster preparedness; continued improvement of the disaster planning process with the City of Novato and Marin County; development of a procedural manual for NFPD operations during a natural or accidental disaster; and model fire prevention program with residents in Blackpoint, an unincorporated community located approximately five miles north of DODHF Novato along Highway 37.

New policies related to police protection include ensuring that through the city's regulatory measures and project review process each development will have adequate emergency access and promoting physical design measures that maximize security from crime and facilitate law enforcement. The plan states that there are 1.2 police officers per 1,000 residents, which is below the federally-accepted standard of 1.7 officers per 1,000 residents.

The Marin Countywide Plan

The plan states that a new fire station will be required to serve the DODHF Novato development. It also describes a 1992 county ordinance requiring the installation of automatic sprinklers in all new structures in the county and in most structures undergoing substantial remodeling.

3.4.2 Fire Protection and Emergency Medical Services

The NFPD is an independent agency that serves the fire protection needs of a 75 square mile area with a population of approximately 57,700. In 1995, the district received 3,726 emergency calls, an increase of 6.9 percent from 1994. Seventy-two emergency response personnel are employed by the district, at least 20 of whom are on duty at any one time. The NFPD maintains four fire stations, each with responsibilities for both primary and secondary response to fire emergencies. A mutual aid program has been established with other Marin County fire departments to provide additional equipment and personnel in the event of large fires or other emergencies. The NFPD has set a goal of responding to 90 percent of all emergency calls within five minutes. In 1995, the NFPD responded to 87 percent of calls within five minutes.

NFPD Station 4 on Enfrente Road is the primary response station and emergency service provider for DODHF Novato. The station has one fire engine staffed by three fire suppression personnel and one ambulance staffed with two paramedic personnel. The station has a total staff of 20 personnel who rotate through the five on-duty positions. Station 4 received 434 fire suppression calls in 1995, an increase of 19.6 percent from 1994 (Arendell, personal communication). Response times to incidents at the Main Site range from four minutes up to seven minutes when serious traffic delays are encountered. The response time to emergency incidents at Rafael Village is approximately two minutes.

The NFPD is also responsible for providing emergency medical services for the region. These incidents account for over 60 percent of the district's total emergency responses. Station 4 received 613 emergency medical calls in 1995, a decrease of 10.4 percent from 1994 (Arendell, personal communication). All uniformed personnel have dual responsibilities for fire suppression and emergency medical service. All NFPD personnel are qualified Emergency Medical Technicians or Paramedics (Novato 1995b). The nearest emergency room is within Novato Community Hospital, approximately four miles from DODHF Novato.

3.4.3 Police Protection

Police protection for the DODHF Novato is provided by the Novato Police Department, located on Machin Avenue. The department employs 58 sworn personnel and 22 nonsworn personnel, giving the city a ratio of 1.0 officer per 1,000 residents, the lowest ratio in Marin County (Barner, personal communication; Hamilton Reuse Planning Authority 1995a). The Novato Police Department has set itself a goal of 1.3 officers per 1,000 residents (Brady, personal communication). In 1995, the police department dispatched approximately 27,078 service calls, a decrease of 6.3 percent from 1994 (Brady, personal communication). In 1989/1990, the department was reorganized due to state budget cutbacks, and a few positions were eliminated. Due to fluctuations in state funding, the department has since been operating under a transitional plan that allows modifications to staffing levels. The department currently is increasing the number of staff (Barner, personal communication).

A private firm, under contract to the Navy, maintains a 20-person staff that provides on-site security service and nonemergency response to DODHF Novato. The police department provides police protection and criminal investigation services to DODHF Novato and works cooperatively with the private security firm. Both the department and the private security personnel respond to 911 emergency service calls. In 1994, Novato police responded to 2,062 incidents at Rafael Village and the Main Site and filed reports on 611 of those incidents.

3.5 UTILITIES

This section presents an overview of the utilities at the DODHF Novato property, including the water distribution, wastewater, storm drainage, electrical, natural gas, telephone, cable television, and solid waste management systems. Utility diagrams are included in Appendix D. Information on the system was obtained from the Hamilton Army Airfield Reuse Plan (Hamilton Reuse Planning Authority 1995b), the 1995 Existing Conditions Analysis (Hamilton Reuse Planning Authority 1995a), the 1986 DODHF Novato Master Plan (US Navy 1986), and personal communications with employees of EFA West, PWCSFB, and utility providers.

Potable water is provided to the DODHF Novato property from the Marin Municipal Water District and North Marin Water District, and the Novato Sanitary District (NSD) provides sanitary sewer treatment services. Electrical power and natural gas are provided by Pacific Gas and Electric Company (PG&E). Telephone systems and service are provided by Pacific Bell. Cable television service is provided by Horizon Cable Company. Solid waste disposal is provided by a private contractor to the PWCSFB. PWCSFB owns and operates most of the utility systems within the DODHF Novato property, including electrical, natural gas, telephone, water distribution, and wastewater collection systems. Exceptions are the cable television system; portions of the sanitary sewer system, owned by NSD; the electrical and natural gas systems at Rafael Village, owned by PG&E; and the telephone system at Rafael Village, owned by Pacific Bell. The ROI for utility service is the service areas of the individual service providers, because analysis for each utility will be analyzed based on potential effects within the service area of each service provider.

3.5.1 Utility Regulations

Each utility is subject to different local, state, or federal regulations. These may be in the form of municipal codes, permitting requirements, state legislation, or federal agency requirements. Applicable regulations are described under the individual utility system sections below.

3.5.2 Water Distribution System

DODHF Novato lies within the Marin Municipal Water District and the North Marin Water District service areas. The Marin Municipal Water District currently serves the DODHF Novato Main Site including the Commissary and Exchange Triangles and the majority of Capehart Housing. The North Marin Water District currently serves Rafael Village and a small portion of the development within Capehart Housing. The water system is shown in Appendix D, Figures D-1a and D-1b.

The DODHF Novato domestic water distribution system has been developed in stages since the early 1930s. The existing on-site water system receives water from local supplies and the Russian River via the Marin Municipal Water District and the North Marin Water District delivery systems. The water is then delivered to DODHF Novato through master water meters located at the boundaries of the base.

There are three major water distribution systems within DODHF Novato—Rafael Village, Capehart Housing, and the USCG Spanish Housing. Although Spanish Housing is not part of this project, the water system is described here because it interconnects to the rest of the water infrastructure at DODHF Novato. The water distribution system in Hillside Housing is a subpart of the Capehart Housing distribution system, while Commissary Triangle, Exchange Triangle, Town Center, Bowling Alley, Officers' Club, Ballfields, and the off-site Knoll Housing are subunits of the Spanish Housing distribution system.

Rafael Village

The North Marin Water District services Rafael Village from Pressure Zones 1 and 2. These pressure zones comply with the district's existing criteria. The original domestic water distribution system was built in 1950 and consists of galvanized steel and cast iron pipelines ranging in diameter from 2-inches to 10-inches. The 503 residential units are served via 57 master meters.

According to the North Marin Water District, the existing water system will not be accepted since it does not meet the existing district design criteria and would require extensive easements for the maintenance of the lines.

Capehart Housing

Most of the Capehart Housing area is within the North Marin Water District's service territory, though through a contract with DODHF Novato, water service is provided to the area by the Marin Municipal Water District. This arrangement has led to a long-standing dispute between the North Marin and Marin Municipal Water Districts. The two districts are working towards a settlement for this dispute.

The original domestic water distribution system was built in the late 1950s and includes 2-, 6-, 8-, and 10-inch asbestos cement (AC) and cast iron (CI) pipelines. The pipelines in Capehart Housing are located either in the front yard of the dwellings or in locations remote from the streets. The original installation of these pipelines was done in the same trench with cathodically protected natural gas pipelines. This cathodic protection system is no longer operated since it increased corrosion of the water piping system, which now may need to be abandoned and replaced. New Hamilton Partnership recently

installed new water piping along Main Gate Road to serve the New Hamilton Partnership development and a small portion of DODHF Novato.

The Marin Municipal Water District provides water to this development via the existing 1.0 million gallon (MG) air base tank owned and operated by the Marin Municipal Water District. The tank is situated south of the base at a pad elevation of 250 feet and high water line of 274 feet. This tank provides for adequate static pressure of over 60 pounds per square inch (psi) at the highest pad elevation within the Capehart Housing development. In addition, the Marin Municipal Water District has indicated that this tank can provide adequate storage for DODHF Novato.

The North Marin Water District supplies water to one master meter for 150 dwelling units at Hillside Housing, located at the southern end of Capehart Housing. This system, constructed in 1988, is completely separate from the remainder of Capehart Housing and consists of 2-1/2, 6-, and 8-inch polyvinyl chloride (PVC) pipe located in the front yard of the dwellings. The North Marin Water District provides adequate storage and supply for this development from its Zone 2 system.

Commissary and Exchange Triangles

The Commissary and Exchange Triangles are located to the north of Main Gate Road north of Capehart Housing.

The pipelines are located under the buildings and are not located in streets or in public rights-of-way. These facilities are about 30 years old and consist of 2-inch to 8-inch AC and CI pipelines. Fire flow tests carried out by the Marin Municipal Water District indicated that these pipelines are not capable of providing adequate commercial fire flow of 3,500 gpm for two hours.

Town Center, Bowling Alley, Officers' Club, and Ballfields

The domestic water system for the Town Center, Bowling Alley, Officers' Club, and Ballfields consists of pipelines ranging from 4-inch to 12-inch AC and CI. The pipelines are not located in streets or in public rights-of-way. These pipelines have been tentatively scheduled for replacement as part of the NHP project.

3.5.3 Sanitary Sewer System

The original DODHF Novato sewer system is over 45 years old and consists of gravity pipelines, force mains, and lift stations. This system also includes a new pump station constructed in 1983 known as East Hamilton Pumping Station. The sewage from DODHF Novato is discharged into the NSD sewer

system for conveyance and treatment at the Ignacio Sewage Treatment Plant. The sewer system is depicted in Appendix D, Figures D-2a and D-2b.

DODHF Novato is outside the NSD's service area, but an existing agreement with NSD allows the wastewater to be treated and disposed of in the NSD facilities. There are existing NSD-owned facilities located on the Hamilton Army Airfield, outside DODHF Novato boundaries. These facilities include the East Hamilton Pumping Station, 6-inch sewer in San Pablo Avenue from Escolta Avenue, 6- and 12-inch PVC force mains in Escolta Avenue, 15-inch sewer along the Northwestern Pacific Railroad, and the 12-inch force main to the Ignacio Sewage Treatment Plant (Figure D-2b).

The District's Ignacio wastewater treatment plant has an existing design capacity of 2.02 million gallons per day (MGD). In response to the Novato General Plan and Marin Countywide Plan, the district has projected in year 2010 a dry weather flow of 2.55 MGD. To meet this projected demand, the district would have to expand the Ignacio treatment plant and obtain an increase in the permitted discharge capacity from the Regional Water Quality Control Board. The 1996 average dry weather flow treated at the Ignacio wastewater treatment plant was 1.41 MGD. The estimated flow contributed by DODHF Novato when fully operational was 0.80 MGD. The DODHF Novato sewer system is split geographically into two areas— east and west of US 101. The area to the west of US 101 consists only of the Rafael Village Housing. The area to the east consists of the remainder of the DODHF Novato, which is also known as Main Site.

The district's board of directors adopted a policy on May 24, 1994, addressing the reuse of the existing DODHF Novato sewer facilities. The policy requires that any planning agency that proposes to reuse any portion of the existing sewer system as public sewers to be owned, operated, and maintained by the district, must thoroughly evaluate the conditions of those facilities and conclude through an engineering report that the existing system meets the district's current standards. If such studies are not performed, it should be assumed that all sewer facilities must be completely replaced.

As an alternative to the district owning and operating the sewer facilities within DODHF Novato, the district may be willing to provide contract services to another entity that would own the sewer facilities within DODHF Novato. This would be similar to the existing arrangement. Under this scenario, the owner, not the district, would be responsible for operating and maintaining the sewer system. However, even in the case of private ownership of sewer facilities, certain district standards would have to be met. Examples of this include, but are not limited to, infiltration/inflow limitations, requirements for points of connection, and easements for lines crossing other properties.

Rafael Village

The sewage flows by gravity into the NSD trunk sewer along Ignacio Boulevard. It is then conveyed to the Ignacio Sewage Treatment Plant. The gravity sewer system consists of vitrified clay pipe (VCP) and PVC pipe ranging from 4-inch to 10-inch. The NSD trunk sewers range from 6-inch to 15-inch VCP and CI pipe. There are approximately 150 manholes in the system.

The sewer pipelines in Rafael Village Housing are located in the rear yards of the dwellings. The manhole spacing throughout this system ranges between approximately 20 feet and 480 feet. Little is known about the conditions of the sewer system.

Capehart Housing

The sewer system consists of 6-, 8-, and 12-inch VCP and CI gravity pipelines, an 8-inch CI force main, and approximately 110 manholes. The sewer pipelines are located in the front yards of the dwellings and are not located in public rights-of-way. The manhole spacing throughout this development ranges between 20 feet and 440 feet. The sewer system also includes a lift station with a capacity of 150 gpm in Building 3132.

Most of the sewage flows by gravity in a northerly direction to the 12-inch pipeline running along West Kelly Drive. The 12-inch pipeline continues on until it connects with the NSD trunk sewer along the Northwestern Pacific Railroad. Approximately 6,300 feet of the total 27,700 feet of sewer pipeline in Capehart Housing was sliplined in 1983 as part of the extensive repair work done on the DODHF Novato sewer system.

Capehart Housing also includes Hillside Housing, a development with 150 dwelling units that was built in 1988. The wastewater generated from this development is collected by an 8-inch main that empties into the Building 3132 lift station.

The existing sewer system in Capehart Housing does not meet the current standards of the district.

Commissary and Exchange Triangles

The sewer system in the Commissary and Exchange Triangles, located to the north of Main Gate Road, consists of pipe diameters ranging from 4-inch to 12-inch VCP, CI, and reinforced concrete (RC) gravity pipelines, 8- and 12-inch PVC force mains, a 15-inch RC NSD trunk sewer, approximately 35 manholes, and an abandoned lift station with a capacity of 75 gpm.

Most of the sewage from the Commissary Triangle flows directly into the 15-inch NSD trunk sewer. The sewage from the Exchange Triangle flows by gravity into 12-inch pipelines. These pipelines then connect with the NSD trunk sewer at a point north of State Access Road.

The sewer system in the Commissary and Exchange Triangles is old, the condition of the pipelines is believed to be poor, and the system does not satisfy the current district standards.

Town Center, Bowling Alley, Officers' Club, and Ballfields

The Town Center, Bowling Alley, Officers' Club, and Ballfields are located along the eastern boundary of the off-site USCG Spanish Housing area. The sewer system includes 4-, 6-, 8-, and 16-inch CI, VCP, and ductile iron (DI) pipelines, force mains ranging from 4- to 12-inch CI, PVC, AC, steel and reinforced plastic mortar (RPM), and two pump stations. Several sewer pipelines are located under buildings and should be abandoned and replaced. The two pump stations are located in Buildings 89 and 125. In general, the system is in poor condition due to age and does not meet current district standards.

3.5.4 Storm Drainage

Overall, DODHF Novato maintains somewhat less than a 10-year level of flood protection. The DOD originally designed on-site drainage facilities for 10-year flows using rainfall data defined during the 1940s. Current City of Novato standards call for 25-year, on-site design with all habitable structures protected from a storm with a 100-year recurrence interval. Design rainfall information has been revised upward since most of the on-site project infrastructure was constructed. Flood protection is not provided in several areas for a 100-year storm. Section 3.9.3 describes current flood patterns and proposed projects that would affect these flood patterns.

Rafael Village

The site is drained by a local underground storm drain system discharging to earth swales that ultimately flow to San Jose Creek. San Jose Creek runs adjacent to the southerly planning area boundary, crossing Ignacio Boulevard near the easterly planning area boundary. In general, the system appears to be in fair to good condition with isolated areas in need of repair (Hamilton Reuse Planning Authority 1995a). Building pads are drained by concrete swales that collect runoff from the rear of the building pads and direct it to the street through parkway culverts. Some of these swales are above the adjacent area they are supposed to drain. Catchbasin placement and capacity appears adequate to serve the site. The local storm drain system was designed for a 10-year storm recurrence interval, which is inconsistent with the City of Novato

standard of a 25-year recurrence interval. A portion of the site is also drained by an open channel system adjacent to Norman Drive.

There is a need to regrade many areas where the ground slopes toward the dwelling units creating ponding problems. Some of the site concrete v-ditches also may need to be replaced subject to a grading study in the identified problem areas.

Capehart Housing

Capehart Housing is located along a ridge that rises to an elevation of about 260 feet. The site drainage system is comprised of concrete-lined interceptor ditches collecting runoff from around the housing units and conveying it to the local streets. Street flow is intercepted by standard inlets and conveyed to the local underground storm drain system. The storm drain system discharges to Pacheco Creek to the north and west, and to a detention pond to the west side ditch along USCG Spanish Housing to the south. All storm drain infrastructure in the Capehart Housing area was designed using a 10-year storm frequency.

In general, the facilities in Capehart Housing have sufficient capacity to convey discharges resulting from a 10-year storm. A chronic flooding problem exists at Building 140 on West Kelly Drive. Pacheco Creek passes near the housing area at this location just upstream of Main Gate Road. Previous studies determined that when the flow in Pacheco Creek exceeds 220 cubic feet per second (cfs), runoff begins backing up on West Kelly Drive in the subject area. When the discharge in Pacheco Creek exceeds 330 cfs, Main Gate Road is overtopped. These discharges correspond to rainfall events of about two years and five years, respectively.

The chronic flooding problems relating to the capacity of Pacheco Creek are primarily due to undersized restrictions where the creek flows underground into culverts downstream in off-site Lanham Village and on-site Exchange and Commissary Triangles.

Drainage from the eastern portion of Capehart Housing flows to an existing retention and detention basin located between the southeast Navy property line of the housing complex and the existing railway line embankment. A 36-inch outlet pipe discharges from the basin to St. Vincent's property; however, there is a significant amount of dead storage in the basin below the outlet pipe elevation. Sump inlets upstream of this basin do not have a secondary overflow outlet.

The flood control infrastructure is in generally good condition within Capehart Housing. The system was designed to convey runoff from a 10-year storm event and appears to have adequate capacity for this frequency.

Secondary overflow paths are required for sump basins on East and West Kelly Drive. Building 140 must be elevated out of the 100-year floodplain or Pacheco Creek must be improved to convey the predicted 100-year discharge. The local drainage around Building 140 appears poorly designed and regrading of this area may be the most economical solution. Adjacent units in these areas also may be within the 100-year floodplain of Pacheco Creek. The Reuse Plan recommends enhanced safety fencing and maintenance access for the site retention/detention basin along the southeast property line.

Commissary and Exchange Triangles, Town Center, Bowling Alley, Officers' Club, and Ballfields

The Commissary Triangle, Exchange Triangle, Town Center, Bowling Alley, Officers' Club, and Ballfields are served by underground storm drain systems and surface flow to gutters, ditches, and channels. In general, the systems were designed to convey 10-year discharges and appear to be in operable condition; however, some portions may be assumed to be nearing the end of their design life.

The condition of pavement in the street and parking areas is significant relative to the efficiency of surface drainage. Pavement deterioration and subsidence has created local undrained depressions in parking areas, gutters and streets. Additionally, some local inlets are in need of repair to replace broken grates and crushed entrances. Pacheco Creek flows adjacent to and west of the Commissary Triangle and the Exchange Triangle. A 60-inch reinforced concrete pipe (RCP) conveys flows from Main Gate Road to State Access Road. In addition, three 66-inch RCPs originate about 600 feet northerly, acting as an overflow system for the single 60-inch RCP; these pipes intercept surface overflow and convey it to a box culvert located north of the railroad tracks in the vicinity of the Navy Exchange. Pacheco Creek in this reach has the capacity to convey flows expected from a 10-year storm.

The Commissary Triangle and Exchange Triangle have acceptable local drainage facilities; however, these parcels are within the 100-year floodplain for Pacheco Creek. The undersized Pacheco Creek culvert systems described above require improvements to remove these parcels from the flood hazard. Local storm drain systems must be improved or installed in the Town Center, Officers' Club, and Bowling Alley areas.

The local storm drain system for the commercial area is generally inadequate to convey 10-year storm discharges. In many locations, City of Novato criteria is exceeded for the placement of catchbasins, resulting in unacceptable flooded widths on local streets. Deterioration of local pavement has created adverse slopes and local undrained sumps. The Bowling Alley and Officers' Club have inadequate or improper drainage facilities.

The Ballfields fall within the 100-year floodplain. Inadequate pumping capacity, coupled with inadequate capacity in the perimeter channels and underdesigned airfield levees create a condition wherein the Ballfields have flood protection for less than a 10-year event. Few local drainage improvements exist, and water collects in adjacent ditches when the airfield perimeter channels create an adverse backwater condition.

The new levee and pumping facilities for the NHP developments will provide flood protection for Ballfields 1 and 2 north of Caliente Real. Ballfields 3 and 4 south of Caliente Real would be subject to tidal flooding as a result of the proposed Hamilton Field wetlands restoration project.

3.5.5 Electrical System

PG&E provides electrical service to Rafael Village and the Main Site. The electrical system is shown in Appendix D, Figures D-3a and D-3b.

Rafael Village

The current power distribution system is a 12-kilovolt (kV) overhead line. This system is fed from PG&E with a single metering point. The 12-kV system is owned and maintained by PG&E. The existing equipment is in fair to poor condition with rust showing on some of the transformer enclosures.

Capehart Housing

The existing power distribution system is a 4,160-volt loop fed from the PG&E substation just northeast of the Capehart Housing area. The housing units are fed from pole-mounted step-down transformers.

The existing 4,160-volt system is unacceptable to PG&E, specifically because utilities are not undergrounded and 12 kilovolts primary power is not available.

Commissary and Exchange Triangles

The existing power distribution system is a 4,160-volt loop from the PG&E substation located southeast of these planning areas. The system is run overhead; feeders to the existing buildings are drops from pole-mounted transformers.

Town Center, Bowling Alley, Officers' Club, and Ballfields

The existing power distribution system is a 4,160-volt underground radial loop. The existing system is over 40 years old. The source for the power distribution is a substation located west of these planning areas.

3.5.6 Natural Gas

PG&E provides natural gas service to Rafael Village and the Main Site. These systems are shown in Appendix D, Figures D-4a and D-4b.

Rafael Village

The natural gas system was built in 1950 and is owned, maintained, and master metered by PG&E. A four-inch steel, underground pipe main supplies gas at five pounds per square inch gauge (psig) from a master meter and 50 psig regulator station; piping is located in the street. It is understood that the piping system is well maintained and has a cathodic protection system.

There has been a consistent upgrading of the system by keeping in concert with the development of the housing area. PG&E has indicated its willingness to continue to provide gas to the area.

Capehart Housing

Originally installed in 1957-1960, the gas piping system was upgraded in 1990. The system is served from a PG&E master meter and regulating station and is distributed at 15 psig.

Commissary and Exchange Triangles

PG&E has indicated that they would require a new primary gas distribution system to and within this area, as the existing system is old and does not have the capacity to serve potential future commercial users.

Town Center, Bowling Alley, Officers' Club, and Ballfields

The system is served from a PG&E master meter at 50 psig from PG&E and distributed at approximately 15 psig throughout the base via a pressure reducing station. Pipe routing is installed in the streets or public ways. Piping size is generally four-inch and three-inch.

3.5.7 Telephone System

Pacific Bell currently provides telephone service to DODHF Novato. Most of the telephone wires are run overhead on the electrical power poles. Exceptions are Town Center, Bowling Alley, Officers' Club, and Ballfields where the lines are run underground.

3.5.8 Cable Television

Horizon Cable Television Company provides service to the Rafael Village and Capehart Housing areas. The service is run overhead on the electrical power poles in Rafael Village and Capehart Housing.

3.5.9 Solid Waste Management

Bay Cities Refuse Company provides solid waste collection service to all government properties at the former Hamilton Air Force Base, including DODHF Novato (US Army 1996). The Novato Disposal Service provides solid waste collection service for the Novato Sanitary District, which includes the City of Novato and surrounding areas. Ninety-four percent of all solid waste generated in Marin County, including DODHF Novato, is disposed of at the Redwood Landfill, located four miles north of the City of Novato (Novato 1995d). Redwood Landfill is permitted as a Class II and III facility, capable of accepting solid waste, which includes mixed municipal refuse, construction/demolition materials, sewage sludge, leaves and yard clippings, tires, and asbestos, a hazardous waste.

Redwood Landfill has a life span of approximately 45 years, based on 1990 projections (Frost, personal communication). The total available capacity of the landfill is approximately 10.9 million tons.

In 1994, the most recent year for which data is available, government facilities at the former Hamilton Air Force Base, including DODHF Novato, generated approximately 1,893 tons of solid waste (Marin County Office of Waste Management 1996). At present, military families are issued two garbage cans, which is slightly greater than average within the City of Novato (Hamilton Reuse Authority 1995a).

The California Integrated Waste Management Act of 1989 (AB 939) requires every city and county to prepare a Solid Waste Source Reduction and Recycling Element for its general plan. The element must include a solid waste management program to achieve goals of diverting 25 percent of all solid waste from landfills by 1995 and 50 percent by 2000. Marin County and Novato have achieved the goal for 1995. In 1993, the most recent year for which recycling data for DODHF Novato were available from the Marin County Office of Waste Management, 254 tons of waste were diverted from landfills from curbside pickup at DODHF Novato.

3.6 CULTURAL RESOURCES

The term "cultural resources" includes any object, site, area, building, structure, or place that is archeologically or historically significant or that has traditional cultural significance because of its association with cultural practices or beliefs that are rooted in that community's history or are important in maintaining the continuing identity of the community (National Register No. 38, National Park Service). The definition includes assets significant in the architectural, scientific, engineering, economic, agricultural, educational, social, political, military, or cultural annals of California.

Background Studies

Cultural resources background studies for DODHF Novato have been ongoing for many years and include archeological and architectural inventories of the entire base undertaken both by the Navy and by the Army Corps of Engineers (COE), respectively. Recent archeological work within the Navy property occurred in 1995 and was conducted by Basin Research, Inc. (Basin) of San Leandro. A prehistoric and historic site record and literature search was completed by personnel of the Northwest Information Center of the Historical Resources File System, Sonoma State University, Rohnert Park (NWIC File No. 95-157). Material on file at the Bancroft Library, the Anthropology Library, and the Hearst Museum of Anthropology, all of the University of California, Berkeley, and Basin's extensive in-house library was also examined. A complete summary of archeological surveys and excavations completed at DODHF Novato to date is provided in Basin's report (Busby et al. 1995). The known sites are all prehistoric in nature; no historical archeological sites (e.g., sites dating from Spanish occupation to 1946) have been identified at DODHF Novato, and the potential for their existence is low. The potential for paleontological resources is also low, based on soil composition and geologic formation of the project area (McGowan, personal communication).

Pursuant to Section 106 of the National Historic Preservation Act (NHPA), the COE assumed the lead role during the excess property sale of GSA/Army land to the New Hamilton Partnership. The COE negotiated an agreement with the State Historic Preservation Officer (SHPO), Advisory Council on Historic Preservation (ACHP), and other agencies on the steps to be taken to mitigate and accept the transfer and/or demolition of individual buildings and structures. Mitigation measures included documentation of all contributing buildings and structures within the district to Historic American Buildings Survey standards (regardless of ownership), preparation of a documentary video chronicling the mission and history of the base, preparation of a brochure for public dissemination, assistance in developing a local curation facility dedicated to Hamilton's history, and identification and coordination of

inventorying and preparing records and maps for transfer to a federal archives facility.

The architectural inventory and historical evaluation of Hamilton Field, completed by PAR Environmental Services, Inc. (PAR) in 1993 for the COE, was used to assess the National Register status of buildings within DODHF Novato. PAR's work included extensive research at DOD archives, state agencies, National Archives, local historical societies, and local libraries. Oral interviews with a variety of people stationed at Hamilton Field during the 1930s and 1940s also were conducted. While this inventory and evaluation was completed for the COE, it included all buildings now owned by the Navy. The District was reevaluated by the Navy in 1997 because of extensive changes that have occurred since 1993. This latest work revised the National Register status of buildings within DODHF Novato.

3.6.1 Regulatory Framework

Section 106 of the NHPA and implementing regulations (36 CFR 800) require federal agencies to consider the effects of their actions on properties listed or eligible for listing in the National Register of Historic Places (NRHP). It also requires that agencies allow the ACHP an opportunity to comment on actions that will directly or indirectly affect such resources. In addition to NHPA, the Archeological and Historic Preservation Act of 1974 (P.L. 93-291 and 96-625) and cultural resources requirements of DOD and the US Navy (DOD Directive 4710.1 of 21 June 1984, Archeological and Historic Resources Management; Department of the Navy OPNAVINST 5090.1B, Historic and Archeological Resources Protection, 1 November 1994, Chapter 23) require the Navy to consider the effects of its undertakings on cultural resources.

3.6.2 Archeology

DODHF Novato is situated in an area near the western shores of San Pablo Bay. Seasonal freshwater streams enhanced a sheltered coastal environment with abundant resources from both the sea and the inland ecosystem. These resources served to make the project area attractive as an occupation site. Information gleaned from extensive excavations in the Bay Area, including numerous sites in Marin County, suggests that the Hamilton Field area was occupied as early as 5,000 years ago. The aboriginal population may have been impacted by fluctuating sea levels during the Holocene, which would have resulted in changing settlement and resource-gathering locations (Bickel 1978a, 1978b; Moratto et al. 1978). Use of the region appears to have been continual until the historic period (Busby et al. 1995).

The project area appears to have been prehistorically within the range of the Southern or Marin dialect group of the Coast Miwok. The area of Native

American occupation nearest to the project area is *puyuku*, located south of the present town of Ignacio. The reader is referred to Chavez (1986) and Goerke and Cowan (1983) for more ethnographic information related to the project area (Busby et al. 1995). The Coast Miwok people followed a hunting and gathering lifeway. Their way of life disappeared by the mid-1800s, following impact of the mission system, introduced diseases, and a declining birth rate (Busby et al. 1995; Kelly 1978).

Numerous prehistoric archeological sites have been identified in and around DODHF Novato. These consist primarily of shell mounds with some flaked stone tools and other cultural artifacts. Two prehistoric sites, CA-MRN-166 and CA-MRN-168, are located within or partially within Rafael Village. These have been described as shell mounds (Busby et al. 1995). CA-MRN-168 was subjected to salvage excavations in 1969 by Archaeological Survey, a group associated with the Adan E. Treganza Museum at San Francisco State University (Melander and Slaymaker 1969). Another site, CA-MRN-165, is situated south of San Jose Creek, adjacent to DODHF Novato. Eight additional archeological sites are located within one-half mile of Rafael Village.

Prehistoric sites also have been documented in the Main Site area. CA-MRN-150 and CA-MRN-158 were recorded in the early twentieth century and were categorized as shell heaps. Both were located in Capehart Housing. CA-MRN-151, also recorded as a shell deposit, is just outside DODHF Novato near Capehart housing. CA-MRN-149 also was recorded many years ago (Busby et al. 1995). In addition, two other possible prehistoric archeological sites have been reported at North Circle and Long Point within Spanish Housing but have not been recorded formally. Ten additional archeological sites are within one-half mile of the Main Site.

During construction of Hamilton Field in 1932 the local newspapers reported that Native American burials were uncovered while grading for a new school site in North Circle, within the Spanish Housing Planning Area (San Rafael Independent 1932). According to the newspaper, the remains were within a mound that measures about 250 feet in diameter and four feet in height. The remains were removed and transported to the base office, along with associated artifacts (mortars and pestles, stone hammers, projectile points). The mound was then leveled and construction proceeded. Building 227 now occupies the leveled mound area.

In accordance with the Navy's responsibilities under the Native American Graves Protection and Repatriation Act (NAGPRA), a focused effort was made by Basin to locate the skeletal remains and artifacts removed from North Circle in 1932. NAGPRA's intent is to ensure that museums and federal agencies identify human remains and cultural items in their collections that may be affiliated with contemporary Native American peoples and to return them as appropriate. In addition to the archives and repositories visited

(discussed above), Basin contacted the Novato History Museum, Marin Museum of the American Indian, and the Miwok Archaeological Preserve of Marin to identify the repository of the skeletal remains removed from North Circle. No further information was obtained regarding the collection from the archival/literature search or consultation with knowledgeable parties, and the only data on the site and collection are contained in the newspaper accounts from 1932 (Busby et al. 1995).

The Navy property was subjected to an archeological survey during the summer of 1995 by Basin. In Rafael Village, four areas with a surface scatter of shell, corresponding to locations of CA-MRN-166 and CA-MRN-168, were identified and subsequently tested with an auger to ascertain the presence of a subsurface deposit. Although some evidence of a cultural deposit was found, these sites have been impacted by development and do not appear to meet NRHP criteria as important resources (Busby et al. 1995). Test excavations at three locations on the Main Site with surface shell exposures did not expose intact cultural deposits. No evidence was found of the recorded sites on the Main Site. The reader is referred to Busby et al. (1995) for a more comprehensive description of their testing program and conclusions. See Table 3-18 for a list of archeological sites within the project area.

In February 1996 the Navy and COE staff met with representatives of the Federated Coast Miwok (FCM), a group of approximately 200 individuals of Miwok ancestry. The FCM are in the process of becoming federally recognized as a tribe. They are concerned about potential Native American burials at North Circle and future provisions to stop work if burials are discovered. North Circle is within the Spanish Housing area that will be transferred to the US Coast Guard and will continue to be protected by Federal preservation laws.

3.63 History

DODHF Novato is within the historical Rancho San Jose, granted to Ignacio Pacheco as a temporary grant in 1833 and finalized in 1840. By 1850 Marin County was formed, one of the original 27 counties in California. Until 1930 DODHF Novato was used for grazing and agricultural production and remained undeveloped (Beck and Haase 1974; Maniery et al. 1993).

The history of the project area is intimately tied to formation of an airfield in the early 1930s. Established on San Pablo Bay just north of San Francisco in the early 1930s, Hamilton Field was an integral part of the Army's Pacific Coast defense mission, as well as an example of a modern aviation station. The initial construction of the permanent base occurred between 1932 and 1935, under the direction of Captain Howard B. Nurse, Construction

Table 3-18
National Register Status of Known Archeological Sites Within the Project Area

| Site | Location | Description | National Register Status |
|------------------|-------------------------------------|--|---|
| CA-MRN-166 | Rafael Village | Reported shell mound; minimal cultural deposit present on Navy property | Determined ineligible, SHPO concurred on 6/26/97 |
| CA-MRN-168 | Rafael Village | Reported shell mound; small cultural deposit represents impacted remnants of a former site | SHPO agreed on 6/26/97 that there is no evidence of this site on Navy property. |
| West Kelly Drive | Main Site - Capehart Housing | Surface shell flecks; not a cultural deposit | SHPO concurred on 6/26/97 that the deposit is not a historic property |
| Westover Circle- | Main Site - Capehart Housing N/A | Surface shell flecks; not a cultural deposit | SHPO concurred on 6/26/97 that the deposit is not a historic property |

Source: Busby et al. 1995

Quartermaster. Nurse chose a Spanish Eclectic design for the base, in appreciation for the Spanish Mission heritage of the region. His carefully planned landscaping, which incorporated natural oak groves, knolls, and hills, cohesive building design, and the conception of an Army base as a planned community, were creative and daring innovations in the 1930s and represented a significant departure from traditional Army base layout and architecture.


Hamilton Field operated as a bombing center and a temporary pursuit plane station until the onset of World War II. During World War II, the primary mission of the base was to support training operations and the activities of the Air Transport Command, making the base an important "jumping off" point from which units were ferried to various places in the Pacific war theater. During the war years, the appearance of the base was altered by the emergency need for temporary housing, administration, and training facilities, which quickly outnumbered the permanent buildings on the base and continued to fill nearly every available building space.

From 1947 through 1960, the Air Force conducted defense and training operations at Hamilton Field, renaming it Hamilton Air Force Base. During this period, the base continued to develop architecturally, but at a reduced level and without further alteration of the original base appearance. In addition to the 132 housing units constructed in the 1930s, 505 housing units were built in Rafael Village in 1951 to accommodate the increase in base personnel during the Cold War-era military buildup. An additional 560 units in Capehart Housing were constructed between 1960 and 1963, as base

population continued to increase (Maniery et al. 1993). The major base expansion period ended in the 1970s when Hamilton Air Force Base was excessed by DOD. By 1974 the Air Force ceased operations and over the next decade the facilities were transferred to other defense branches and to the General Services Administration. The housing and community services portions of the base were transferred to the Navy and named DODHF Novato. The Army took possession of the runway and associated facilities and in 1984 named their portion of the base Hamilton Army Airfield. Although major building construction ended on base at this time, 96 medium-density multiple-family units were built on a knoll near Radio Hill (now called Knoll Housing) by the Navy in 1986.


The architectural resources within DODHF Novato were included in PAR's 1993 National Register evaluation of Hamilton Field (Maniery et al. 1993). At that time the buildings, structures, objects, and landscaping associated with Hamilton from 1931 to 1946 were determined eligible for inclusion in the National Register as a historic district under Criteria A (historical importance) and C (architectural significance). The district was reevaluated in 1996 because of extensive changes that have occurred in the historic district since 1993 (Maniery 1997). The reevaluation eliminated from eligibility the World War II-era buildings and structures and revised the district boundaries to form a discontinuous historic district. This revised district appears eligible for inclusion in the National Register under Criteria A and C. Figure 3-6 shows the boundaries of the Hamilton Army Air Field Discontinuous Historic District. Appendix E contains a copy of a letter of concurrence from the SHPO. Only four historic properties within the Hamilton Army Airfield Discontinuous Historic District are under Navy control. These historic properties are the War Department Theater (Building 507), the Amphitheater (unnumbered), the Bachelor Officers' Quarters (Building 201), and the Swimming Pool (Building 205). The remainder of the historic properties that contribute to the Hamilton Army Air Field Discontinuous Historic District are under Army, USCG, or New Hamilton Partnership control.

Units within Rafael Village were constructed in 1951 and those in Capehart Village and Knoll Housing in the early 1960s and 1986, respectively. These areas were developed after the period of significance established for the base and as such are not eligible for inclusion in the National Register as historic properties. The SHPO concurred with this finding on May 9, 1997. The buildings in the Commissary Triangle, Ballfields, Exchange Triangle, and Bowling Alley, and all but one building in Town Center were constructed during the World War II buildup on base. These buildings were reevaluated as ineligible for inclusion to the National Register of Historic Places due to the demolition of the majority of similar buildings on Army and New Hamilton Partnership lands and the subsequent loss of historical integrity by the district (Maniery 1997). The SHPO concurred with this finding on May 9, 1997.



A reevaluation of the Hamilton Army Air Field was performed in 1996. The reevaluation found that the historic district is now comprised of three discontiguous areas. The SHPO concurred with this finding in May 1997. The Rafael Village housing units, constructed in 1951, are not eligible.

LEGEND:



Department of the Navy
Department of the Army
New Hamilton Partnership
U.S. Coast Guard

Hamilton Army Air Field *Discontiguous Historic District* DOD Housing Facility Novato, California **Figure 3-6**

3.7 BIOLOGICAL RESOURCES

Biological resources addressed in this analysis include vegetation, wildlife, sensitive species, and sensitive habitats on the site and in surrounding areas. Rafael Village, Capehart Housing, and adjacent areas contain the native habitats found within DODHF Novato. Other parts of DODHF Novato, such as the ballfields, contain only developed, paved, regularly mowed, or landscaped areas. The ROI for biological resources includes DODHF Novato and the surrounding areas within one-half mile to provide an area large enough to include any species that may use habitats on DODHF Novato but small enough to not include species that regularly use habitats not found within DODHF Novato.

Information regarding biological resources was obtained from the California Natural Diversity Database (California Department of Fish and Game 1996a), a scoping letter from the US Fish and Wildlife Service (USFWS), the Fish and Wildlife Management Plan (US Navy 1988), the Flood Control and Maintenance Plan for San Jose Creek and Pacheco Creek (US Navy 1987a), the Master Plan (US Navy 1986), and the Hamilton Army Airfield Reuse Plan (Hamilton Reuse Planning Authority 1995b). Site visits were conducted on July 20 and November 13, 1995, and biological surveys were completed on January 22, 25, 26, and 29, 1996 (Appendix F). All wetlands that provide potential habitat for the red-legged frog were surveyed on April 10, 22, and 29 (spring surveys) and on June 9 and July 24, 1996 (summer surveys)(US Navy 1996b).

3.7.1 Plans and Policies

Endangered Species Act (Section 7 and 10a Consultation)

Federal law directs that all federal agencies and departments use their authority to conserve endangered and threatened species under the guidance of the federal Endangered Species Act (ESA).

The ESA requires that the USFWS issue a permit prior to actions that would result in the killing, harming, or harassing of a federally-listed endangered or threatened species. This permit process is directed under Section 7 of the ESA for actions in which a federal agency is involved and in a similar process under Section 10a of the ESA for state and local agencies, as well as for individuals. Federal agencies are required to consult with the USFWS prior to undertaking actions that may adversely affect endangered species and to confer with the USFWS prior to undertakings that may adversely affect species proposed for listing. A federal agency is required to obtain a biological opinion from the USFWS on whether its actions may jeopardize the continued existence of any threatened or endangered species. Federal agencies are prohibited from

enacting activities that would jeopardize the continued existence of these species. This EIS will be used as a biological assessment for purposes of consultation and conference under Section 7 of the ESA.

Upon disposal of the federal property at DODHF Novato, all nonfederally held lands would be subject to ESA Section 10a requirements. Actions of the City of Novato or other nonfederal entities would be subject to these requirements and to state endangered species laws.

California provides similar procedures under the California Endangered Species Act, California Fish and Game Code Section 2090. The California Department of Fish and Game (CDFG) can adopt a federal biological opinion as a state biological opinion under California Fish and Game Code Section 2095. Plants listed as rare by the CDFG are listed under the Native Plant Protection Act, California Fish and Game Code Section 1900. Consultation with the CDFG is not required under this act but is recommended (Shaffer, personal communication).

Wetlands Regulations

Wetlands are considered sensitive and declining resources by several regulatory agencies, including the CDFG and the USFWS. The Army Corps of Engineers (COE) considers wetlands to be important to the public interest in that they perform significant biological functions, such as providing nesting, breeding, foraging, and spawning habitat for a wide variety of resident and migratory animal species (33 CFR 320.4). Wetlands also provide for the movement of water and sediments, ground water recharge, water purification, and storage of stormwater runoff.

Under Section 404 of the Clean Water Act (CWA) wetlands are defined as "those areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions." Indicators of all three wetlands parameters (hydric soils, hydrophytic vegetation, wetlands hydrology) must be present for a site to be considered a jurisdictional wetland (Environmental Laboratory 1987).

Pursuant to Section 401 of the CWA, any applicant for a federal permit to conduct any activity that may result in any discharge into navigable waters must provide a certification from the regional water quality control board that such discharge will comply with the CWA. Water quality certification is a certification that there is reasonable assurance that an activity that may result in discharge to navigable waters of the United States will not violate water quality standards, where the activity requires a federal license or permit

(Section 3830 of the California Administrative Code). This requirement would be applicable to state, local, or federal actions.

The CDFG has the authority to reach an agreement with an individual proposing to affect intermittent or permanent streams and other wetlands pursuant to Section 1603 of the California Fish and Game Code. In accordance with its policy of "no net loss" of wetland habitat, the CDFG encourages completion of a streambed alteration agreement, which includes a mitigation program for impacts to all wetlands, regardless of acreage.


3.7.2 Vegetation

Ten vegetation communities were mapped during January 1996 surveys at DODHF Novato (Figure 3-7). Five of these are considered sensitive communities by the CDFG and are discussed in Section 3.7.5 below as sensitive habitats.

Nonnative grasslands are found throughout DODHF Novato. This vegetation community is characterized as annual grass cover that generally produces green and flowering cover in the spring with plants dead in the summer and fall months (Holland 1986). Nonnative grasslands are often found at elevations below 3,000 feet on clay soils adjacent to oak woodlands, as is the case at DODHF Novato. Nonnative grasslands at DODHF Novato support many annual species, including wild oats (*Avena fatua*), soft chess (*Bromus mollis*), ripgut brome (*Bromus diandrus*), red brome (*Bromus rubens*), foxtail fescue (*Festuca megalura*), broadleaf filaree (*Erodium botrys*), redstem filaree (*Erodium ciutarium*), turkey mullein (*Eremocarpus setigerus*), sweet clover (*Melilotus* spp.), and bur clover (*Medicago hispida*) (Hamilton Reuse Planning Authority 1995a).

Coast live oak woodland is found within Capehart Housing and adjacent to Rafael Village. The coast live oak (*Quercus agrifolia*) is the dominant species in this community, which is found at elevations below 4,000 feet and also may contain a mixture of other oaks and broad-leaved trees (Holland 1986), as is the case at DODHF Novato. Other species within this community at DODHF Novato include valley oaks (*Quercus lobata*), Oregon white oak (*Quercus garryana*), California bay (*Umbellularia californicus*), and poison oak (*Toxicodendron diversilobum*).

Mixed native/nonnative woodland is defined here as a vegetation community that supports many native tree species within it but also contains nonnative species, landscaping species, and sometimes has an understory that is regularly maintained. This community is found in several patches within Capehart



0709101vegglies - 3/6/96 - HC

LEGEND:

- | | | | |
|--|-----------------------------|--|---------------------------------|
| | Native/nonnative grasslands | | Coast live oak woodland |
| | Freshwater marsh | | California bay forest |
| | Riparian forest | | Eucalyptus woodland |
| | Valley oak woodland | | Mixed native/nonnative woodland |
| | DODHF property line | | Developed/landscaped |
| | | | Drainage ditch |

Rafael Village is characterized by developed and landscaped areas bordered by nonnative grassland, California bay forest, coast live oak woodland, valley oak woodland to the north, and a riparian corridor to the south. Spanish and Capehart Housing are dominated by developed areas and landscaped vegetation with nonnative grasslands, coast live oak woodlands, valley oak woodlands, and riparian/wetland communities in surrounding areas.

Source: Buescher Biological Consulting 1996

Vegetation Communities

DOD Housing Facility
Novato, California
Figure 3-7

Housing. Dominant species found in this community include native species, such as coast live oak, valley oak, and California bay, and nonnative species such as Monterey pine (*Pinus radiata*), maple (*Acer* spp.), date palm (*Phoenix dactylifera*), fan palm (*Washingtonia* sp.), and blue gum.

Developed/landscaped areas include areas that are primarily paved or completely landscaped and maintained with nonnative trees, shrubs, and grasses. This community generally provides very little habitat for native plant and animal species.

3.7.3 Wildlife

Wildlife present in the ROI is typical of that found in urban areas in the San Francisco region and includes invertebrates, reptiles, birds, and mammals. Reptile species common to the area include the western fence lizard (*Sceloporus occidentalis*) and gopher snake (*Pituophis melanoleucus*). Bird species detected at the facility include the common crow (*Corvus brachyrhynchos*), European starling (*Sturnus vulgaris*), house sparrow (*Passer domesticus*), and rock dove (*Columba livia*) in the urbanized areas and great blue heron (*Ardea herodias*), belted kingfisher (*Ceryle alcyon*), scrub jay (*Aphelocoma coerulescens*), brown towhee (*Pipilo fuscus*), and black phoebe (*Sayornis nigricans*) in the riparian (streamside) area. Mammal species common to the project area include the house mouse (*Mus musculus*), California ground squirrel (*Spermophilus beecheyi*), black-tailed hare (*Lepus californicus*), and mule deer (*Odocoileus hemionus*).

3.7.4 3.7.4 Sensitive Species

Sensitive species include those that are listed by USFWS or by the CDFG as endangered, threatened, proposed for endangered or threatened status, or candidate species for endangered or threatened status. Also included as sensitive species are those plants listed by the California Native Plant Society (CNPS) and species of special concern to the CDFG. Table 3-19 lists sensitive species known or suspected to transit, forage in, or inhabit the ROI. This discussion focuses on those species listed by either the USFWS or CDFG as endangered or threatened and those proposed for listing as endangered or threatened. Proposed species are included here because these species may be officially listed prior to the completion of this EIS.

Plants

No plant species listed by the USFWS or CDFG as endangered or threatened are known or are likely to inhabit the DODHF Novato due to the highly

Table 3-19
Sensitive Species Within the ROI

| Common Name | Scientific Name | Federal Status | State Status | CNPS Status | Habitat at DODHF |
|--|--|----------------|--------------|-------------|------------------|
| ENDANGERED AND THREATENED SPECIES | | | | | |
| <i>Plants</i> | | | | | |
| soft bird's beak | <i>Cordylanthus mollis</i> ssp. <i>mollis</i> | PE | R | 1B | N |
| Marin western flax | <i>Hesperolinon congestum</i> | T | T | 1B | N |
| <i>Fish</i> | | | | | |
| tidewater goby | <i>Eucyclogobius newberryi</i> | E | CSC | none | Y |
| winter-run chinook salmon | <i>Oncorhynchus tshawytscha</i> | E | E | none | Y |
| <i>Amphibians</i> | | | | | |
| California red-legged frog | <i>Rana aurora draytonii</i> | T | CSC | none | Y |
| <i>Birds</i> | | | | | |
| California black rail | <i>Laterallus jamaicensis coturniculus</i> | SC | T | none | N |
| California clapper rail | <i>Rallus longirostris obsoletus</i> | E | E | none | N |
| <i>Mammals</i> | | | | | |
| salt marsh harvest mouse | <i>Reithrodontomys raviventris</i> | E | E | none | N |
| OTHER SENSITIVE SPECIES | | | | | |
| <i>Plants</i> | | | | | |
| Point Reyes bird's-beak | <i>Cordylanthus maritimus</i> ssp. <i>palustris</i> | SC | none | 1B | N |
| dwarf downingia | <i>Downingia pusilla</i> | C3c | none | 2 | Y |
| fragrant fritillary | <i>Fritillaria liliacea</i> | SC | none | 1B | Y |
| Baker's navarretia | <i>Navarretia leucocephala</i> ssp. <i>bakeri</i> | none | none | 1B | Y |
| Marin knotweed | <i>Polygonum marinense</i> | SC | none | 3 | N |
| Mount Tamalpais jewelflower | <i>Streptanthus glandulosus</i> var. <i>pulchellus</i> | C3c | none | 1B | Y |
| <i>Invertebrates</i> | | | | | |
| California brackishwater snail | <i>Tryonia imitator</i> | SC | none | none | N |
| <i>Fish</i> | | | | | |
| green sturgeon | <i>Acipenser medirostris</i> | SC | none | none | N |
| longfin smelt | <i>Spirinchus thaleichthys</i> | SC | CSC | none | Y |
| <i>Amphibians</i> | | | | | |
| foothill yellow-legged frog | <i>Rana boylei</i> | SC | CSC | none | Y |
| <i>Reptiles</i> | | | | | |
| northwestern pond turtle | <i>Clemmys marmorata marmorata</i> | SC | CSC | none | N |
| <i>Birds</i> | | | | | |
| Cooper's hawk | <i>Accipiter cooperi</i> | none | CSC | none | Y |
| burrowing owl | <i>Athene cunicularia</i> | none | CSC | none | Y |
| California horned lark | <i>Eremophila alpestris</i> | SC | CSC | none | Y |
| loggerhead shrike | <i>Lanius ludovicianus</i> | SC | CSC | none | Y |
| <i>Mammals</i> | | | | | |
| Point Reyes jumping mouse | <i>Zapus trinotatus orarius</i> | SC | CSC | none | N |
| Point Reyes mountain beaver | <i>Aplodontia rufa phaea</i> | SC | CSC | none | N |
| pallid bat | <i>Antrozous pallidus</i> | SC | CSC | none | Y |
| Townsend's western big-eared bat | <i>Plecotus townsendii townsendii</i> | SC | CSC | none | Y |
| California mastiff bat | <i>Eumops perotis californicus</i> | SC | CSC | none | Y |

Source: CDFG 1994, 1996a, 1996b, 1996c, 1996d; USFWS 1994a, 1994b, 1995a, 1995b, 1995c, 1996

| Federal Status | State Status | California Native Plant Society (CNPS) Status | Habitat at DODHF Novato? |
|---|---|--|--------------------------|
| E = Endangered | E = Endangered | 1B = Plants rare and endangered in California and elsewhere | N = No |
| PE = Proposed endangered | T = Threatened | 2 = Plants rare and endangered in California but more common elsewhere | Y = Yes |
| T = Threatened | R = Rare | 3 = Plants about which additional data are needed. | |
| SC = Species of Concern (Former C2)* | CSC = California Species of Special Concern | | |
| SCR = Proposed for Species of Concern* | | | |
| C3c = Too widespread or not threatened* | | | |

disturbed nature of the site. Two listed species, the soft bird's-beak (*Cordylanthus mollis* ssp. *mollis*) and the Marin western flax (*Hesperolinon congestum*), may inhabit areas near the ROI.

Soft bird's-beak is an annual hemiparasite in the snapdragon family. This species is restricted to salt and brackish water marshes in the northern Bay Area. Potential habitat is not present in the ROI but is found in the northernmost parts of Hamilton Airfield just north of the ROI boundary. No observations of this species have been recorded within the ROI.

The USFWS no longer maintains a list of C2 or C3 species, but remains concerned about the conservation status of these species and retains information on them in case future reviews are conducted.

Marin western flax inhabits chaparral and valley foothill grasslands on serpentine soils. Serpentine soils are not present on DODHF Novato. The closest known location of this species, recorded in 1992, is three miles southwest of Rafael Village (CDFG 1996a).

Four other sensitive plant species that are considered Species of Concern by USFWS or are listed by CNPS could inhabit DODHF Novato. The dwarf downingia (*Downingia pusilla*) inhabits ditch areas of heavy clay soils, and the fragrant fritillary (*Fritillaria liliacea*), Baker's navarretia (*Navarretia leucocephala* ssp. *bakeri*), and Mount Tamalpais jewelflower (*Streptanthus glandulosus* var. *pulchellus*) inhabit hilly grasslands and oak woodlands within the ROI (Skinner and Pavlik 1994).

Wildlife

Two fish, one amphibian, two bird, and one mammal species that are state- or federally-listed as endangered or threatened have been observed near the ROI. Habitat for two of these species exists at DODHF Novato. All of these species are discussed separately below.

The tidewater goby (*Eucyclogobius newberryi*) inhabits brackish and freshwater lagoons and streams where water is slow moving and aquatic vegetation is present. The tidewater goby has disappeared from about 50 percent of its historic range in California (Biosystems Books 1994). This species has not been detected in the DODHF Novato but marginal habitat for this species exists in the lower reaches of San Jose Creek adjacent to Rafael Village. The closest known location of this species, recorded in 1984, is two miles north of Rafael Village (CDFG 1996a).

The winter-run chinook salmon (*Oncorhynchus tshawytscha*) does not currently have an established migration "run" in the creeks in this area, but salmon historically may have inhabited the San Jose drainage (US Navy 1987b)

and habitat for such a run does exist in San Jose Creek. The closest known location of this species is from salmon observed in 1990 at Mare Island in the Napa River drainage, over five miles to the northeast.

The California red-legged frog (*Rana aurora draytonii*) requires a permanent or semipermanent pond or slow-moving water source with deeper pools and extensive aquatic vegetation in which to breed. Suitable breeding habitat exists in San Jose Creek within and adjacent to Rafael Village, Pacheco Creek within Capehart Housing, and several of the drainage ditches surrounding Rafael Village and Capehart Housing. No observations of California red-legged frogs have been recorded within the ROI, but the DODHF Novato is located within the historic range of this species. Although suitable habitat is present at DODHF Novato, no California red-legged frogs were observed at the site during surveys conducted in the spring and summer of 1996 (US Navy 1996b). Appendix F contains the final survey reports for the California red-legged frog.

The California black rail (*Laterallus jamaicensis coturniculus*) and California clapper rail (*Rallus longirostris obsoletus*) inhabit northern coastal saltmarsh areas outside the ROI. The closest known locations of these species, recorded in 1986 and 1975 respectively, is at the mouth of Novato Creek, about one-half mile north of Capehart Housing (CDFG 1996a).

One endangered mammal species, the salt marsh harvest mouse (*Reithrodontomys raviventris*), inhabits the region. The salt marsh harvest mouse lives in tidal wetland habitats dominated by pickleweed (*Salicornia virginica*). No habitat for this species exists within the ROI. The closest known location of this species, recorded in 1986, is over four miles to the south of the DODHF Novato (CDFG 1996a).

Several other sensitive species listed in Table 3-19 may inhabit DODHF Novato. San Jose and Pacheco Creeks and associated riparian areas may provide habitat for the longfin smelt (*Spirinchus thaleichthys*), foothill yellow-legged frog (*Rana boylei*), and Cooper's hawk (*Accipiter cooperi*). Grasslands and valley oak woodlands (which have a grassland understory) may provide habitat for the burrowing owl (*Athene cunicularia*), California horned lark (*Eremophila alpestris*), and loggerhead shrike (*Lanius ludovicianus*). Vacant buildings could provide habitat for three sensitive bat species, the pallid bat (*Antrozous pallidus*), Townsend's western big-eared bat (*Plecotus townsendii*), and California mastiff bat (*Eumops perotis californicus*).

3.7.5 Sensitive Habitats

Sensitive habitats are ecosystems that provide a vital role in the health of the local natural environment, that are protected by regulatory agencies, or that are of local concern. Several of the vegetation communities found at and

adjacent to DODHF Novato are listed by the CDFG as sensitive communities including coastal and valley freshwater marsh, central coast live oak riparian forest, central coast riparian scrub, valley oak woodland, and California bay forest. Central coast live oak riparian forest, central coast riparian scrub, and valley oak woodland are found within DODHF Novato. Additionally, several areas within and adjacent to DODHF Novato would likely be considered jurisdictional wetlands under the qualifications used by the COE.

Riparian corridors and stream beds are protected by the CDFG and are important resources to most wildlife species, providing water, cover, nesting habitat, and foraging habitat. Riparian areas associated with San Jose and Pacheco Creeks support a mixture of central coast live oak riparian forest and central coast riparian scrub. Central coast live oak riparian forest is generally dominated by coast live oak and found in canyon bottoms and floodplains from Sonoma County south to Point Conception, California (Holland 1986). Central coast riparian scrub is characterized as a scrubby streamside thicket dominated by willows (*Salix* spp.) that varies from being fairly open to nearly impenetrable and is found along most perennial and many intermittent streams between the Bay Area and Point Conception, California (Holland 1986). Other species associated with the riparian areas of San Jose and Pacheco Creeks include the red willow (*Salix laevigata*), yellow willow (*Salix lasiandra*), valley oak, California bay, white alder (*Alnus rhombifolia*), Oregon ash (*Fraxinus latifolia*), and hinds walnut (*Juglans hindsii*) (Hamilton Reuse Planning Authority 1995a). The riparian area surrounding Pacheco Creek within the Capehart Housing area also supports a mixture of central coast live oak riparian forest and central coast riparian scrub.


Some areas of oak woodland within the Capehart Housing area are valley oak woodland. Valley oak woodland typically occurs at elevations below 2,000 feet, contains only one tree species, the valley oak, and forms an understory of grassland instead of a more closed woodland such as coast live oak woodland. The valley oak is California's largest broad-leaved tree and may grow to 110 feet at maturity (Holland 1986).

Coastal and valley freshwater marsh is a vegetation community seasonally found adjacent to Capehart Housing within the railroad right-of-way and within the agricultural fields between Capehart and the off-site Spanish Housing area. This community typically is dominated by tules (*Scripus* spp.) and cattails (*Typha* spp.) (Holland 1986).

California bay forest is found in two small areas adjacent to Rafael Village to the southwest and northeast. This vegetation community typically consists entirely of a dense stand of California bay with little or no understory. Most stands of California bay forest are small and found at elevations below 3,000 feet (Holland 1986).


3.7 Biological Resources

Wetlands are a declining resource that are considered sensitive habitats by the CDFG and the USFWS. The US Congress has declared wetlands to be important to the public interest in that they perform significant biological functions, such as providing nesting, breeding, foraging, and spawning habitat for a variety of resident and migratory animal species. Wetlands also provide for the movement of water and sediments, ground water recharge, flood control, water purification, and stormwater runoff storage. No formal wetlands delineations have been performed at DODHF Novato and none were performed as a part of the January 1996 surveys. San Jose Creek, Pacheco Creek, and the drainage ditches on DODHF Novato would likely qualify as jurisdictional wetlands, warranting protection by the COE under Section 404 of the Clean Water Act. The National Wetlands Inventory map for the area depicts San Jose Creek and Pacheco Creek as wetlands (National Wetlands Inventory 1985). Figures 3-8 and 3-9 depict wetlands on and adjacent to DODHF Novato, as determined by preliminary assessment from the January 1996 surveys and the National Wetlands Inventory map.



Wetlands in Rafael Village and the surrounding area include San Jose Creek and a drainage ditch in the northeastern area of Rafael Village.


LEGEND:



Wetlands



Creek




DODHF boundary

Rafael Village Wetlands

DOD Housing Facility
Novato, California

Figure 3-8

Source: National Wetlands Inventory 1985; Buescher Biological Consulting 1998



Wetlands on the main site and adjacent areas include Pacheco Creek, drainage ditches, and marshes.

LEGEND:



Wetlands



DODHF boundary

Main Site Wetlands

DOD Housing Facility
Novato, California

Figure 3-9

Source: National Wetlands Inventory 1985; Buescher Biological Consulting 1996

3.8 GEOLOGY AND SOILS

The geology of DODHF Novato is discussed in this section in the context of the regional geologic setting. Issues related to geological conditions in the area of the proposed action include seismic hazards, slope stability, and soil erosion. The ROI for the proposed action includes lands within the boundaries of DODHF Novato and immediately adjacent lands.

3.8.1 Plans and Policies

California Building Code, Seismic Design Requirements

The California Code of Regulations (CCR), Title 24, Part 2, also known as the California Building Code (CBC), contains enforceable state building standards. Earthquake design requirements are contained in Chapter 16, Division III, and other selected portions of the CBC. The 1995 edition of the CBC incorporates by reference the 1994 edition of the Uniform Building Code (UBC, International Conference of Building Officials, 1994), with the applicable California amendments. A more stringent set of standards applies to construction of public schools and medical facilities. These regulations are promulgated by the Division of the State Architect/Structural Safety Section, and the Office of Statewide Health Planning and Development. The provisions of the 1995 edition of the CBC became effective on December 28, 1995 (180 days after the date of publication, July 1, 1995). The California Building Standards Commission is responsible for coordinating all building standards in California. The City of Novato Department of Public Works is responsible for enforcing these standards within the City of Novato.

DODHF Novato is located within seismic zone 4, as defined in the CBC. UBC seismic standards represent minimum requirements for new construction within zone 4. Zone 4 is a region in which the effective peak ground acceleration assumed in design calculations is 0.4 times the acceleration of gravity(g). In areas in which effective peak ground accelerations are likely to be greater than 0.4 g, the minimum UBC requirements may not be adequate. The UBC defines two alternative methods for calculating design seismic forces—a static procedure and a dynamic procedure. The dynamic procedure must be used in designing certain structures, such as those that have an irregular shape or that exceed certain height limitations.

Alquist-Priolo Earthquake Fault Zoning Act

Under the Alquist-Priolo Earthquake Fault Zoning Act, the California Division of Mines and Geology has delineated seismic zones that are deemed to be “sufficiently active and well-defined as to constitute a potential hazard to structures from surface faulting or fault creep.” The state geologist also is

required to review continually new geologic and seismic data and to revise the earthquake fault zones or delineate new zones based on new information. No active faults have been identified within the boundaries of DODHF Novato. The nearest delineated active fault zone is the Hayward Fault, located approximately seven miles southeast of DODHF Novato.

Marin Countywide Plan

The Marin Countywide Plan presents extensive policies regarding urban development in areas of geologic and seismic hazards. Specific issues addressed by these policies include protection from ground rupture, protection from ground shaking, protection from slope stability and landslide hazards, and protection from subsidence and differential settlement hazards. The policies and actions address these issues through requirements for geologic studies, identification of areas where development shall not occur (Alquist-Priolo Study Zone), and minimum construction standards to reduce potential hazards.

Novato General Plan

The 1996 Novato General Plan provides a detailed list of objectives and programs related to geologic conditions in the Environment and Safety and Noise Chapters of the document. Three objectives define the City of Novato's position on geologic resources:

1. Protect mineral resources;
2. Reduce seismic hazards; and,
3. Minimize the risk of personal injury and property damage resulting from slope and soil instability.

For each objective, the City of Novato has developed one or more specific programs to achieve these objectives. The city has designated a department of city government with the responsibility for carrying out these programs.

3.8.2 Regional and Site Geology

Physiography

DODHF Novato is located within the Coast Ranges geologic area. The Coast Ranges consist of diverse geologically young terrains. The dominant geological processes that have shaped the landscape include faulting associated with the San Andreas fault system and fluctuations in sea level associated with geologically recent glaciation. North of San Francisco Bay the Coast Ranges

are typically more than 40 miles wide and reach elevations of up to 8,000 feet (Christensen 1966).

The region surrounding DODHF Novato west of US 101 is characterized by steep, narrow, northwest-trending ridges and linear drainages, with topographic relief on the order of 1,000 to 1,600 feet. Land elevations in Rafael Village range between about 30 feet above mean sea level at the eastern end of the property to about 160 feet above mean sea level on the west. Rafael Village is located along the north bank of San Jose Creek. The channel of the creek is incised about 20 feet below the surrounding valley floor.

Elevations in the planning areas east of US 101 range from sea level to about 260 feet above mean sea level. The highest elevations are in the Capehart Housing area, which covers the north shoulder of Pacheco Hill. Developed areas are concentrated on lower slopes surrounding the central ridge, at elevations between about 10 to 120 feet above mean sea level. Pacheco Creek runs along the western boundary of Capehart Housing and the Exchange Triangle.


The Exchange Triangle is located on the northern extension of the central ridge of Capehart Housing. The land slopes from an elevation of about 50 feet along the Main Gate Road to about 30 feet along the rail line marking its eastern margin.

The Commissary Triangle, northwest of the Exchange Triangle, slopes gently northeast from about 40 feet to about 25 feet along the rail line that marks its northeast boundary. A narrow strip along the south side of Main Gate Road and west of Capehart Housing, with elevations over 40 feet above mean sea level, also belongs to the Exchange Triangle.

Elevations in Town Center, located at the base of two low hills, range between 30 feet on the west to 20 feet above mean sea level on the east. The Officers' Club is located on a small knoll that rises from about 35 to 80 feet above mean sea level. The Bowling Alley lies in a swale, with elevations ranging between about 20 feet to 10 feet above mean sea level. The Ballfields area contains some of the lowest-lying land, with elevations ranging from about 30 feet adjacent to Spanish Housing down to sea level.

Regional Geology

Bay Area geology is dominated by the San Andreas Fault system, a collection of northwest-trending strike-slip faults. The locations of the principal active faults in the Bay Area are shown on Figure 3-10. Active faults are those for which there is evidence of movement during the past 11,000 years. The active faults within a radius of 20 miles of the project area include the San Andreas



Three major active faults are located within the DODHF Novato Region: the San Andreas, Burdell Mountain, and Tolay Faults.

LEGEND:

- Active fault. Fault has the evidence of surface displacement within the last 11,000 years.
- Active fault concealed
- Potentially active fault concealed

Locations of Principal Active Regional Faults

DOD Housing Facility
Novato, California

Figure 3-10

Fault, the San Gregorio Fault, the Hayward Fault, and the Rogers Creek Fault (Wallace 1990). The Burdell Mountain Fault, located about two miles north of the project area, is a Quaternary fault (evidence of movement within the past 1.6 million years).

Most of the Coast Ranges in the region of the site are underlain by marine cherts, sandstone, and volcanic rocks of the Franciscan assemblage. North of Novato, Miocene (about 5 to 20 million years ago) volcanic mudflow deposits belonging to the Tolay Volcanics group are present on the south side of the Quaternary Burdell Mountain Fault. Small outcrops of Pliocene (1.6 to 5 million years ago) volcanic ash deposits belonging to the Sonoma Volcanics also are exposed in this area.

DODHF Novato lies within a portion of the Franciscan assemblage called melange, which consists of sheared, interbedded, fine-grained mudstone and sandstone, with minor amounts of greenish radiolarian-bearing volcanic ash deposits (Wahrhaftig and Wakabayashi 1989). This melange weathers to clay that is gray to greenish, generally expansive and plastic.


Blake, et al. (1974) state that most geologic contacts within this portion of the Franciscan are probably faults. Their geologic mapping of the area indicates a fault beneath the channel of San Jose Creek, which is buried except for occasional exposures and extends from near the east end of Rafael Village to the south end of the adjacent USCG Spanish Housing area. The age of the fault is not reported but it is not considered to be active.

In the region of DODHF Novato, hills and ridges consist mainly of massive sandstone and shale (Novato 1995d; Rice 1973). These weather to sandy and silty soils that erode easily and are susceptible to liquefaction during periods of very heavy rainfall.

The San Francisco Bay basin is underlain by a thick sequence of fine-grained sediments called the Bay Mud, which consists of clays and silty clays, with lenses of sand or shell material. Locally, the underlying sediments consist largely of alluvium carried to the bay by the Petaluma River or smaller streams that emanate from the Coast Ranges to the west. Much of the land east of US 101 lies within the historic margin of San Francisco Bay and has been reclaimed by filling. Figure 3-11 shows the geology in the vicinity of DODHF Novato.

Site Geology

Rafael Village is underlain by colluvial deposits consisting of loose sand, gravel, silt, and clay derived from the Franciscan sandstone and shale that form the nearby hillslopes. The depth to bedrock beneath the colluvium is not



Geology

DOD Housing Facility
Novato, California

Figure 3-11

LEGEND:

- Qmf = Bay Mud
- Qal = Alluvium
- KJf = Franciscan Formation
- = DODHF Boundary

Much of the area east of US 101 lies within the historic margin of the San Francisco bay that has been reclaimed by filling.

Source: USGS 1978

known. Most of the Main Site planning areas are located directly on exposures of weathered Franciscan bedrock, consisting primarily of sandstone, shale, and greenstone, with minor amounts of other lithologies. Alluvial deposits derived from erosion of the adjacent hillslopes skirt the base of the hills. The bottom lands consist of imported fill placed on the historic tidal flats.

3.8.3 Seismicity

DODHF Novato is located approximately 12 miles east of the trace of the San Andreas fault, about eight miles west of the trace of the Rogers Creek Fault, and roughly seven miles northwest of the Hayward Fault. The only other fault within a 20-mile radius of DODHF Novato that is known to have been active within the past 10,000 years is the southern segment of the West Napa Fault.

Earthquake magnitude is a measure of the amount of energy released at the origin of an earthquake within the earth's crust and is expressed as a number on the Richter Magnitude scale. Each integer increase in magnitude represents a 10-fold increase in energy released. The maximum earthquake magnitude that could reasonable be expected for the Hayward, San Andreas, and Rogers Creek Faults are 7.5, 8.3, and 7.2, respectively.

Incorporating data from the Loma Prieta earthquake of October 17, 1989, the US Geological Survey (1990) estimated a 67 percent probability that one or more large earthquakes (magnitude 7.0 or greater) would occur on the San Andreas, Hayward, or Rogers Creek Faults during the next 30 years (WGCEP 1990).

The amount of damage caused by an earthquake is dependent on a wide range of factors. These include the distance of the source of the earthquake from the site, the nature of the geologic materials underlying the site, the duration of the shaking, and the nature of the structure. For an earthquake of a given magnitude, duration, and distance from the site, the intensity of ground shaking is highly dependent on the way in which the seismic waves are transmitted by the underlying geologic materials. Dense bedrock tends to cause the least amount of shaking, while thick unconsolidated materials tend to amplify seismic waves, resulting in stronger shaking.

A recent report prepared by the Association of Bay Area Governments (Association of Bay Area Governments 1995; Perkins and Boatwright 1995), indicates that the amplification of seismic waves on land underlain by Bay Mud east of US 101 would be "extremely high," while west of US 101 the amplification varies from low to very high depending on the nature of the underlying materials. The results of the ABAG study also indicate that the intensity of ground shaking at DODHF Novato would be most severe for

earthquakes centered on the northern segment of the Hayward Fault or on the Rogers Creek Fault.

The ABAG study provides an estimate of the intensity of ground shaking in the region of DODHF Novato, with a margin of error of about one intensity unit on the modified Mercali scale. This scale provides a description of the amount of damage that can be expected under earthquakes of varying intensities and ranges from I (least) to XII (greatest). In the vicinity of Rafael Village, and in most of the planning areas east of US 101, the modified Mercali intensity is expected to range from VII to VIII for a 7.1 magnitude earthquake on the Rogers Creek Fault or the northern Hayward Fault. Nonstructural to moderate structural damage is commonly associated with this intensity range. At a Mercali intensity of VII, plaster and weak masonry materials may be damaged, and weak slopes in sand or gravel banks may collapse. At a Mercali intensity of VIII, damage would occur to good quality reinforced masonry, chimneys may fall, and frame houses may move on foundations if not bolted down. Local conditions can increase the hazards.

The ABAG study suggests that the most severe ground shaking at DODHF Novato would occur in areas underlain by Bay Mud east of the USCG Spanish Housing area. This would apply to most of the Ballfields planning area and to the Town Center planning area. Areas underlain by Bay Mud are expected to be subject to a Mercali intensity of IX for a magnitude 7.1 earthquake centered on the northern Hayward Fault. At a modified Mercali intensity of IX, good quality reinforced masonry is seriously damaged, underground pipes are broken, and unreinforced structures may collapse.

In addition to ground shaking, structural damage can be caused directly by differential movement along faults, or by collapse of the ground surface and can be caused indirectly by flooding from seismically-generated sea waves or collapse of dams. Ground failure may include liquefaction, differential settlement, or lateral spreading. Liquefaction tends to occur in sandy materials with a shallow water table. Liquefaction potential is low in most of the planning areas due to the relatively high clay content of the soil, but it could be a factor locally, in imported fill areas or areas underlain by sandy alluvium. High water table conditions probably occur only at the base of the hills in the Main Site planning areas. Likewise, differential settlement is not expected to be a severe problem in most planning areas because of the relative cohesiveness of clayey soils but it could be a factor locally in filled areas. Lateral spreading can be induced by ground shaking in soft, saturated materials. Lateral spreading is likely to be limited to the Ballfields area but also could affect other areas built on fill, such as Town Center.

3.8.4 Soils


Figure 3-12 shows the distribution of major soil units at DODHF Novato. Surface soils throughout Rafael Village, the Commissary Triangle, the Exchange Triangle, the Town Center, the Bowling Alley, the Ballfields, and the western edge of Capehart Housing consist of a combined unit called xerorthents-urban land complex, which occurs on valley floors in urban areas with 0 to 9 percent slopes (Kashiwagi 1985). Xerorthents consist of cut or fill areas and are characterized by mixed soils containing man-made debris and imported materials. Urban land consists of areas covered by roads, driveways, houses, parking lots, and other structures.

Surface soils in most of the upland areas of Capehart Housing, as well as the Officers' Club, consist of the Saurin-Urban land-Bonnydoon complex, which occurs on 30 to 50 percent slopes. The complex is 30 percent Saurin clay loam (on convex side slopes), 25 percent urban land, and 20 percent Bonnydoon gravelly loam (on ridgetops). These areas also include bare rock outcrops. Saurin soil is derived from sandstone or shale and is moderately deep and well drained. Depth to bedrock ranges from 20 to 40 inches. The main limitation of the soil for homesite development is steepness of slope. The soil tends to erode easily.

3.8.5 Slope Stability

Slope stability is related to a combination of factors including the nature of the geologic materials supporting the slope, the steepness of the slope, and the amount of water that infiltrates the materials underlying the slope. Slope failure can be gradual or rapid. Rapid slope failures include landslides, debris flows, and debris avalanches. Gradual processes include earthflows, creep, and erosion. Rapid slope failure in susceptible areas may be triggered by seismic events, rainfall, undercutting of slopes by construction activities, and overloading of upslope deposits.

Davenport (1984) analyzed slope failures that occurred in selected study areas in eastern Marin County as a result of a major storm on January 3rd and 4th, 1982. No evidence of slope failures was identified near DODHF Novato from evaluation of aerial photographs. The report concluded that most slope failures following the storm occurred on slopes of between 26 to 45 degrees (about 1:2 to 1:1 slopes, respectively), although slope failures were common in colluvial materials on slopes of 18 to 26 degrees (about 1:3 to 1:2 slopes, respectively). The maximum slopes on the hills north of Rafael Village are about 26 degrees.



Map of Soils at DODHF Novato


DOD Housing Facility
Novato, California

Figure 3-12

LEGEND:


- 202 Urban land - Xerotherms, 0.8% slopes
- 203 Xerotherms - fill
- 204 Xerotherms - Urban land, 0.8% slopes
- 166 Sawrin - Urban land - Bonnydoon, 30-50% slopes
- 158 Reyes Clay
- DODHF Boundary

Xerotherms is the primary soil type at Rafael Village.
Sawrin is the primary soil type at the Main Site.




Source: Kashiwagi, 1985

The area upslope of Rafael Village was included in a slope stability study performed by Rice (1973). Most of the area upslope of Rafael Village was assigned to the most stable or next-to-most stable slope categories, based on a four-point rating scale. Existing landslide deposits are an indication of general slope instability. No existing landslide deposits were identified by Rice (1973) upslope of Rafael Village. Saturation of slope deposits can reduce the cohesiveness of the deposits, leading to slope failure. Springs or seeps have been observed at the base of some of the slopes north of Rafael Village. As a result, slope stability has been identified as a concern in planning the development of the area upslope of Rafael Village (Balestro, personal communication). No areas within DODHF Novato are identified in the City of Novato General Plan as having unstable slopes (Novato 1995b). Figure 3-13 shows the areas with steep slopes and areas with identified landslide potential.



There are two areas of potential slope instability at DODHF Novato, one in the southwest part of the Main Site area and one north of the Novato Housing area.

LEGEND:

 Lands with unstable slopes

Unstable Slopes at DODHF Novato

**DOD Housing Facility
Novato, California**

Figure 3-13

Source: City of Novato 1995b

3.9 WATER RESOURCES

Water resource issues relevant to the proposed action include flood hazards, surface and ground water quality, and drainage issues. Flood hazards at the site are associated with high tides, substandard levees and other drainage facilities, and high runoff in Pacheco Creek and its tributaries. Flood hazards at the Rafael Village site are associated with substandard storm drain systems and high flows in San Jose Creek. Water quality impacts can result from ground water contamination (see Section 3.13, Hazardous Materials and Waste), construction and demolition activities, and cumulative discharge of pollutants into local and regional receiving waters including San Pablo Bay. Drainage is addressed in this chapter as it affects flood hazards; storm drain systems are addressed in Section 3.5, Utilities.

The ROI for water resources is limited to the immediate DODHF Novato sites, areas directly downstream from those sites, and surrounding receiving water bodies (Novato Creek, western San Pablo Bay, and adjacent wetlands).

3.9.1 Plans and Policies

City of Novato

The project site lies within the City of Novato and would fall under the city's jurisdiction upon transfer from the Navy. The Safety and Environment chapters of the 1996 Novato General Plan include policies that promote the protection of wetlands and riparian areas; that preserve, protect, and enhance streams, wetlands, marshes, and other bodies of water; that preserve, protect, and enhance water resources and water quality; that control flooding problems and reduce flood hazards; and that prepare a plan for responding to a potential rise in sea level. The General Plan restricts new development in 100-year floodplains east of US 101.

The City of Novato has adopted Development Requirements that include drainage facility design. Under these requirements, the city Public Works Department must approve plans for the project's on-site drainage system as well as for any required off-site system improvements. On-site culverts and drainage improvements must be designed to accommodate runoff from a rainfall with a 25-year recurrence interval, and drainage plans must demonstrate that a proposed project will not alter off-site flow characteristics of runoff. Major drainage systems, such as Pacheco Creek, must be designed to accommodate runoff from a 100-year recurrence interval storm.

The city also has adopted a Flood Damage Protection Ordinance (Chapter 5-31 of the Municipal Code) that establishes requirements for construction within city-designated 100-year floodplains. The ordinance also establishes

floodplain zoning districts, depending on the likelihood and extent of flood hazards, and regulates development within those districts. These regulations generally limit the construction of new structures to above the 100-year flood elevation. The project site is not located within a city-designated flood zone district; however, portions of the site are within Federal Emergency Management Agency (FEMA)-mapped 100-year flood zones and, as such, the city requires that all on-site structures be protected from 100-year floods, and project development must not worsen existing 100-year flood conditions on adjoining properties or elsewhere in the Pacheco Creek or San Jose Creek Drainage Basins (EIP Associates, Inc. 1993). The city also has developed a Multi-hazard Emergency Plan that includes provisions to respond to flooding.

Marin County

Most of the upstream reaches of Pacheco and San Jose Creeks fall under the jurisdiction of the Marin County Flood Control and Water Conservation District (MCFCWCD). The District does not maintain Pacheco Creek at Hamilton. The City of Novato relies on the MCFCWCD for review of projects that may significantly affect major drainage facilities such as Pacheco and San Jose Creeks. MCFCWCD's review would seek to ensure that the project would not adversely affect the capacity of Pacheco and San Jose Creeks, that all proposed buildings are either raised above 100-year flood level or protected from flooding by levees, and that the project's internal storm drain system has sufficient capacity to accommodate anticipated peak storm water runoff.

State of California

Stream channels in the state of California are subject to Sections 1600-1603 of the Fish and Game Code. These regulations require landowners to obtain permits prior to modifying any existing natural stream channel, up to the top of the bank. Any proposed stream modifications should be designed and sited to prevent increased erosion, scour, or contaminant discharge and to avoid adverse impacts to riparian areas and wetlands.

Federal Government

Water quality in surface water bodies, including Pacheco and San Jose Creeks and San Pablo Bay, is subject to the Federal Clean Water Act. As part of that act, the National Pollution Discharge Elimination System (NPDES) program was developed to control and reduce the addition of pollutants to water bodies from point sources, such as industrial facilities and stormwater sewers. In the Bay Area, the program is implemented by the San Francisco Bay Regional Water Quality Control Board (RWQCB), a state agency. Pursuant to Section 319 of the Clean Water Act, the state has the lead role in identifying and controlling nonpoint sources of pollution. The RWQCB implements the

NPDES program through the issuance of permits for construction and industrial discharges.

The RWQCB also regulates water quality in accordance with state laws and policies identified in the San Francisco Basin Plan. The basin plan identifies beneficial uses of surface and ground waters, wetlands, and marshes and sets forth water quality objectives to protect the beneficial uses. Beneficial uses of the inland surface waters on the site (Pacheco and San Jose Creeks) are limited primarily to wildlife habitat. The related water quality objectives specify that the presence or concentration of constituents, including floating, suspended, or settleable materials, oil and grease, biostimulatory substances, sediment, bacterial and toxic substances, among others, shall not cause a nuisance or adversely affect beneficial uses. Beneficial uses for San Pablo Bay include industrial uses, navigation, contact and noncontact recreation, fishing, wildlife habitat, species preservation, and fisheries habitat.

3.9.2 Surface Water

The project area is located on the eastern side of the Marin portion of the California Coast Ranges. Drainage from this side of the range flows generally eastward towards San Pablo Bay. Regional surface water is shown on Figure 3-14. Precipitation in the project area is about 28 inches annually, falling mostly during the October through April rainy season.

The project site is comprised of two distinct areas separated by US 101; the 107-acre Rafael Village located in a valley west of the highway and the 304-acre Main Site on the bay plain east of the highway.

The Main Site includes several small hills and a portion of the broad floodplain at the edge of San Pablo Bay. Runoff from the area east of the hills flows eastward through a series of swales, ditches and culverts through the New Hamilton Partnership property, discharging into San Pablo Bay via three pump stations that lift runoff over existing levees east of the site. Runoff from the area west of the hills flows westward and northward to drainage ditches and Pacheco Creek. Pacheco Creek originates in the hills west of US 101, crossing to the east side of the freeway about half a mile south of the Capehart Housing. It then flows northward through the Capehart area and crosses Main Gate Road via five 60-inch culverts (terminating in twin box culverts) that carry it under the Commissary Triangle and State Access Road to a trestle at the Northwestern Pacific Railroad right-of-way. Past environmental documentation has noted that several of the culverts are clogged and carry very little water (EIP Associates, Inc. 1993). Northeast of the railroad trestle, Pacheco Creek enters a concrete-lined channel that winds north and west, intersecting the base boundary about 900 feet east of US 101. The channel



Surface water in the vicinity of DODHF Novato flows to the San Pablo Bay.

LEGEND:

 DODHF Novato Boundary



0 1,000 2,000
Approximate Scale in Feet

Regional Surface Water

DOD Housing Facility
Novato, California

Figure 3-14

veers north just north of the base and follows the base boundary to the north end of Ammo Hill, where it joins San Jose Creek, which flows northward to its discharge into Pacheco Pond.


Pacheco Pond is a 120-acre wetland managed jointly by the MCFCWCD and the CDFG as a flood protection retention basin and seasonal freshwater wetlands and permanent wildlife habitat. When the pond is filled, discharge from Pacheco Creek and San Jose Creek (also called Arroyo San Jose) flows through a ditch to Novato Creek at Bel Marin Keys. Novato Creek empties into San Pablo Bay about three miles northeast of the site. Discharge is controlled by weirs, tide gates, and siphons.

Rafael Village is adjacent to, and in the drainage area of, San Jose Creek. The southern portions of this planning area drain directly to that creek, while the northern parts of Rafael Village drain into swales and storm drains that, in turn, discharge into the creek.

3.9.3 Flooding

Many low-lying areas of the base are subject to flooding during a 100-year flood event. FEMA has mapped 100-year flood areas on the base (see Figure 3-15). Low-lying areas at the base of the small hills on the site, including the eastern edge of Town Center, the Bowling Alley, and the Ballfields, are mapped as subject to 100-year flood hazards. The Little League fields, which are part of the Ballfields planning area, serve as a detention basin in heavy rainfall events. In addition, the southern and southeastern portions of Capehart Housing, as well as the western fringe of Capehart Housing along Pacheco Creek, are subject to flooding. Other areas along Pacheco Creek, including portions of the Exchange Triangle, the Commissary Triangle, Main Gate Road, and State Access Road, are in the FEMA-mapped floodplain. Pacheco Creek frequently floods along West Kelley Drive, across the Main Gate Road, and into the commissary area. (US Department of Agriculture 1987). The Comprehensive Drainage Study for the base notes that Main Gate Road is subject to flooding in the five-year event. (A-N West, Inc. 1989) According to the Base Master Plan (US Navy 1986), additional residential areas just outside of the FEMA flood areas on the east side of Capehart Housing also are subject to periodic flooding.

The eastern edge of the base is protected from tidal flooding by levees. Existing levees are deficient to protect against the 10-year tidal runoff, and have a 2,575-foot long gap southeast of the runway parcel. This allows flooding of low-lying areas east of the hills on the site during major tidal/storm events. Runoff reaching the levees is pumped to San Pablo Bay by a series of pump stations. Three pump stations serve an area of about 1,600 acres of the Hamilton site.



The Federal Emergency Management Agency (FEMA) has mapped 100-year flood areas at the former Hamilton Air Force Base. Most of the DODHF Novato property falls outside of the flood areas. Rafael Village is not within the 100-year flood area, though FEMA has mapped a narrow corridor along most of San Jose Creek adjacent to Rafael Village as an area of special flood hazard subject to inundation in a 100-year flood (see Figure 3-8).

LEGEND:



100 Year Flood Zone



Proposed NHP
Master Plan Levee



DODHF Boundary

100-Year Flood Area

DOD Housing Facility
Novato, California

Figure 3-15

Combined operating capacity of the three pumps is about 160 cfs, less than 20 percent of peak runoff (950 cfs) calculated by the Corps of Engineers for the drainage area in a 10-year storm. In addition, none of the pumps have backup power, and the largest pump must be started manually. Discharge to San Pablo Bay is via 18 36-inch diameter steel culverts. The pumping stations currently are being refurbished (Miller, personal communication). Flows exceeding the pumps' capacity back up behind the levees north of the runway. Flooding occurs frequently in this area during rainy periods; however, because of available flood storage capacity in the area, significant flooding occurs only when high runoff coincides with high tides (EIP Associates, Inc. 1993).

Tidal flooding issues and drainage to the bay are in the process of being altered due to the recent start of construction on two projects adjacent to the site on the east. These are the NHP mixed-use development and the Hamilton Field Wetlands Restoration project. The NHP project currently is upgrading drainage through the portion of the base to the east of Planning Areas 4-10. The drainage system, when completed, will be sized to accommodate the 25-year runoff, in conformance with city standards. Major creek channels and pump facilities serving that area will be sized to carry the 100-year flows (EIP Associates, Inc. 1993). The drainage system for that area assumes existing flows from upstream areas, including the Main Site and Rafael Village areas.

The wetlands restoration project would flood the existing 700-acre runway area directly east of the NHP area and Ballfields 3 and 4 outside the NHP levee. This project will result in the removal of the existing substandard levees protecting low-lying areas of the base from tidal flooding. This will allow regular tidal flooding of areas below seven feet above mean sea level (msl). A new levee will be constructed to the west of the runway to an elevation of 10 feet msl. This levee is intended to protect low-lying areas from 100-year high tides and to allow for future local subsidence/settlement. With the new levee in place, stormwater runoff from the Navy housing area and part of the NHP site would no longer be able to drain by gravity to the existing pump station. The new pump station will be constructed where the proposed new flood control levee crosses Caliente Real and intersects the hills in the USCG Spanish Housing. The pumps would be sized to accommodate 100-year flows from both the NHP site and the contributing DODHF Novato areas. The portion of the Ballfields south of Caliente Real would be used for emergency flood storage in the event of a major pump failure.

In the Rafael Village area, FEMA has mapped a narrow corridor along most of the reach of San Jose Creek adjacent to Rafael Village designated as an area of special flood hazard subject to inundation in the 100-year flood (FEMA 1989). The FEMA map indicates that flooding in a 100-year event would spread across Ignacio Boulevard between its intersection with San Jose Boulevard west of Ransome Street and its intersection with San Jose Boulevard east of Fairway Drive. Due to the deeply incised stream channel, the mapped 100-

year floodplain of San Jose Creek adjacent to Rafael Village is very narrow, and flooding probably affects only the yards of existing Rafael Village houses adjacent to the creek, not the houses themselves.

Flood hazards in low-lying areas of the base would be exacerbated if rising sea levels restricted or backed up flows from local drainages, or if levees were overtopped. There are wide variations in the predictions of future accelerated sea level rise due to global warming. The EPA recently projected a 50 percent likelihood that by 2025 sea levels will rise four inches and by 2050 sea levels will rise about eight inches. This rise is the middle probability of sea level estimates that range from zero to over 18 inches by 2050 (USEPA 1995). Actual measurements of sea level rise at the Presidio in San Francisco indicated an average annual rise of 0.05 inches over the past 100 years, with an average rise of 0.07 inches/year over the past 19 years. These rates of rise equate to 2 to 3 inches by 2025 and 4 to 5 inches by 2075 (ESA Associates, Inc. 1993). In addition, the San Francisco Bay Area is experiencing land sinking of about two inches per century due to tectonic factors. Local settlement of bay muds is also occurring and would exacerbate flood hazards to low-lying parts of the site and vicinity.

3.9.4 Ground Water

Depth to ground water underlying the low-lying parts of the Main Site range from near zero to about eight feet below the ground surface (bgs). Ground water in these areas fluctuates with water levels in Pacheco Creek, tidal fluctuations, and seasonal precipitation. Ground water underlying the hilly portions of the site lies at greater depths. Ground water flows at the Main Site generally reflect surface topography. Runoff from the eastern side of the Main Site drains into San Pablo Bay. Runoff from the western side drains into Pacheco Creek, which travels north to Pacheco Pond. Shallow ground water tends to be brackish and of low quality because of its proximity to San Pablo Bay. There are no potable uses of this ground water, and it is unlikely that percolated ground water from the site helps to recharge deeper, higher quality ground water aquifers (EIP Associates, Inc. 1993).

There is little information available on the occurrence or quality of ground water in the Rafael Village area. San Jose Creek is a perennial stream, and its base flow may represent outflow from the adjacent aquifers. If so, then ground water may be expected to occur about 10 to 15 feet below most of the area. Reported ground water seepage at the toes of the slopes north of Rafael Village also are indicative of shallow ground water tables. Ground water flows in Rafael Village generally are expected to be towards the incised stream channel. The water table may vary seasonally in response to recharge from rainfall and infiltration from San Jose Creek. Some deeper ground water may occur in fractures in the Franciscan bedrock underlying the area; however

these flows are expected to be limited because the fractures would tend to become clogged by the clay minerals that weather from the Franciscan rocks.

3.9.5 Water Quality

Little data is available regarding water quality of surface water on the Main Site and Rafael Village areas. Section 3.13, Hazardous Materials and Waste, describes areas of the base that may have been subject to surface or ground water contamination from spills and/or dumping of hazardous materials. Runoff from most developed areas of the site is likely contaminated by urban pollutants commonly found in developed areas. This "nonpoint source" pollution contains dissolved or suspended residues of urban land uses, including silt, organic fertilizers and pesticides, heavy metals, oils and grease, tire fragments, decaying vegetation, and debris. These contaminants are commonly discharged into area surface waters via surface runoff, storm drains, and pump stations, and accumulate in Pacheco Pond and San Pablo Bay, where they contribute incrementally to a cumulative decline in water quality. Elevated levels of metals, including high lead levels and petroleum hydrocarbons, have been found in sediments of the upper intertidal zone of the salt marsh in the vicinity of the pump station outfall (US Army 1995). High turbidity in Pacheco Creek floodwaters provides evidence of ongoing erosion within the creek's upper watershed. These sediments degrade downstream water quality and affect water quality and flood storage capacity in Pacheco Pond (EIP Associates, Inc. 1993). There are no point-source discharges (e.g., industrial or sewage treatment plant outfalls) on the project site.

Shallow ground water quality in localized areas at the base has been affected by hazardous and toxic wastes. The primary contaminants of concern that have been found in ground water are petroleum hydrocarbons, such as gasoline and oils and solvents (US Army 1995). The specific areas of contamination and the regulatory processes to control and clean up ground water contamination at the base are described in Section 3.13 of this report.

3.10 TRAFFIC AND CIRCULATION

Traffic evaluation for this EIS provides an analysis of traffic conditions and the circulation system providing access to and within DODHF Novato. The ROI for this traffic analysis includes regional freeway (US 101 and State Route 37) and transit systems, because access to the project site is provided primarily by these traffic links. The ROI also includes local access routes, as well as the City of Novato's street system because of their potential to be impacted by the project. The ROI for traffic and circulation analysis is shown in Figure 3-16.

The circulation system in the DODHF Novato area includes freeways, streets, and intersections. Traffic operations for these facilities are described based on the difference between traffic volumes and available capacity. Typically, as traffic volumes increase, the amount of available capacity is reduced, and congestion occurs. As congestion increases, travel speeds decrease, resulting in longer travel times between trip origins and destinations.


For both roadways and intersections, the Level of Service (LOS) scale is used to measure traffic operations. The LOS scale for freeways is based on the number of passenger cars per hour per lane. The LOS scale for intersections is based on average delay in seconds per vehicle at a particular intersection. Service levels vary from A, the best, to F, the worst. Currently, Novato and Caltrans use LOS D operation as the poorest acceptable level of service during peak traffic periods. For analysis purposes, Novato minimum standards have been assumed for evaluation of the DODHF Novato circulation system. Appendix Table G-1 describes the LOS scale for basic freeway segments and Table G-2 describes the LOS scale for intersections.

3.10.1 Regional Circulation

DODHF Novato is located in southern Novato just south of the junction of US 101 and State Route 37. The majority of DODHF Novato, the Main Site area, is located on the eastern side of US 101. Rafael Village is located on the west side of the freeway along Ignacio Boulevard. Figure 3-16 shows the locations of the regional freeways described below.

Regional Freeways and Freeway Operation

The primary regional access roadways are US 101 in the north-south direction and State Route 37 in the east-west direction.



The ROI for this EIS includes regional systems and the surrounding community street system.

Regional Transportation System

DOD Housing Facility
Novato, California

Figure 3-16

Source: Fehr & Peers Associates, 1996

US 101


US 101 is the major regional connector serving Marin County. It bisects the county and in many locations there are no alternative travel routes between areas. It serves as a connector from Sonoma and parts of Napa to Marin and San Francisco counties. US 101 provides three travel lanes in each direction in the project area with additional auxiliary lanes provided between many interchanges. North of Atherton Avenue, near the Sonoma County line, US 101 narrows to two lanes in each direction and loses freeway status as at-grade intersections are permitted.

Several segments along US 101 currently experience considerable congestion (LOS D or worse) during the peak hours in the major travel directions (AM southbound and PM northbound). There is a high level of variation in the degree and hours in which people encounter heavy congestion on US 101 and in recent years peak period congestion has been spreading, meaning that the periods of congestion have been elongating as people change their traveling hours to avoid the typical peak periods (7 to 9 AM and 4 to 6 PM). Although congestion occurs along the entire length of US 101 in Marin County, certain segments consistently constrict traffic flow resulting in long lines of traffic throughout US 101. Figure 3-17 and Appendix Table G-3 summarizes the existing operational characteristics of US 101 and State Route 37 during peak hour periods.

AM Peak Hour Southbound. Currently, the AM peak hour bottleneck on US 101 that causes traffic backups into the project area is the approach to Puerto Suello Hill, near North San Pedro Road. Additionally, the segment of US 101 north of Atherton Avenue, where the freeway narrows to two lanes in each direction, meters traffic traveling into the project area from Sonoma County. In the southbound direction US 101 south of Ignacio Boulevard operates at LOS D during the AM peak hour. The southbound approach to US 101 between State Route 37 and Ignacio Boulevard operates at LOS E during the AM peak hour. See Figure 3-17.

PM Peak Hour Northbound. During the PM peak hour, the bottleneck on US 101 north of Atherton Avenue causes traffic to back up to project area. These are further exacerbated by through-traffic destined for Central Novato and the weaving area at the US 101/State Route 37 interchange. South of the project area, congestion in Central San Rafael results in delays for vehicles traveling into the Northgate area of San Rafael and Novato. In the northbound direction, US 101 between State Route 37 and Ignacio Boulevard operates at LOS E during the PM peak hour. The northbound approach on US 101, north of Atherton and south of Ignacio Boulevard, operates at LOS E during the PM peak hour. See Figure 3-17.

Other segments of US 101 operate at LOS B or better. See Figure 3-17.



The Level of Service (LOS) scale is used to measure traffic operations. LOS A is the best while LOS F is the worst.

Existing Freeway Level of Service

DOD Housing Facility
Novato, California

Figure 3-17

Source: Fehr & Peers Associates, 1996

State Route 37

State Route 37 links Novato to the Napa and Sonoma Valleys. The highway provides four travel lanes in the project area. State Route 37 currently operates with little or no delay during all time periods. Appendix Table G-3 summarizes the existing operational characteristics of State Route 37 during peak hour periods.

3.10.2 Local Circulation

In this section, the operational characteristics of the local and DODHF Novato internal circulation systems are described. The streets within and serving DODHF Novato are classified as freeways, primary arterials, secondary arterials, primary collectors, or local streets. Functional classification of the streets within and serving DODHF Novato are shown on Figure 3-18. Table G-4 in Appendix G provides definitions for each of the functional classifications.


Local Roadways

The primary local roadways providing access to the Main Site and Rafael Village are Ignacio/Bel Marin Keys Boulevard, Nave Drive, Alameda del Prado, and Enfrente Boulevard. Each of these roadways is described below.

Ignacio/Bel Marin Keys Boulevard

Ignacio/Bel Marin Keys Boulevard is the most heavily used east-west arterial in the project area, providing the major connection to US 101. Figure 3-18 shows the alignment of the Ignacio/Bel Marin Keys Boulevard corridor within the project area. In addition, much of the traffic from Nave Drive and Alameda del Prado feed onto Ignacio Boulevard to reach US 101 or access other areas of southern Novato. To the west, Ignacio Boulevard provides access to Indian Valley College but also can be used as a connection to Central Novato via Sunset Parkway or Palmer Drive. Along its length, Ignacio Boulevard provides four travel lanes (two in each direction), left-turn lanes at most intersections, and a continuous bicycle lane and sidewalks. It has a posted speed of 45 miles per hour (MPH) near its interchange with US 101.

On the east side of US 101, Ignacio Boulevard becomes Bel Marin Keys Boulevard, which provides access to the Bel Marin Keys industrial area and the Bel Marin Keys residential area. Nearest to US 101, Bel Marin Keys Boulevard also provides four travel lanes (two in each direction), left-turn lanes at most intersections, and a continuous bicycle lane and sidewalks. It has a posted speed limit of 35 MPH along most of its length.



Existing Street Classifications

DOD Housing Facility
Novato, California

Figure 3-18

Nave Drive

Nave Drive is a frontage road on the east side of US 101 providing two lanes (one in each direction) along its length except near its intersection with Ignacio Boulevard, where it widens to four lanes. Figure 3-18 shows the alignment of Nave Drive within the project area. Nave Drive has a posted speed limit of 35 MPH except near the Ignacio interchange where the posted speed increases to 40 MPH. All vehicular traffic with origins or destinations at the Main Site currently use Nave Drive. Both commercial and residential uses are served by Nave Drive, and parking is prohibited.

Alameda del Prado

Alameda del Prado is a frontage road on the west side of US 101 providing two travel lanes. Figure 3-18 shows the alignment of this facility within the project area. The southern half of Alameda del Prado, near the US 101 southbound ramps, is a commercial area with no parking permitted and a posted speed limit of 45 MPH. The northern half of the road traverses a residential area where the posted speed limit is 25 MPH, parking is permitted on-street, and opposing travel lanes are separated by a raised landscaped median.

Enfrente Boulevard

Enfrente Boulevard is a very short segment of street providing a connection between the US 101 southbound off-ramp at Entrada/Enfrente to Ignacio Boulevard. Enfrente Boulevard provides two travel lanes with turn lanes and channelization provided to side streets and commercial uses along its length. It has a posted speed limit of 45 MPH.

State Access Road

State Access Road provides direct access to the Main Site. Although this facility is internal to the project, it operates under the ownership of the New Hamilton Partnership (NHP). State Access Road currently functions as a primary collector providing one through lane in each direction. No parking is provided. Under the NHP Master Plan, State Access Road will be terminated at the rail tracks. Current volumes on the road are estimated at about 2,350 vehicles per day.

Main Gate Road

Main Gate Road also provides direct access to the Main Site and operates under the jurisdiction of the New Hamilton Partnership. Main Gate Road functions as a primary collector providing one through lane in each direction, turn pockets at most intersections and significant channelization at its

intersection with Nave Drive. No parking is provided. Main Gate Road is currently under construction; hence, limited traffic is permitted to use this facility. However, under normal operating conditions, traffic volumes on the road are estimated at about 5,200 vehicles per day.

Internal Roadways - Main Site

The primary collectors providing access to the Main Site are Palm Drive, Randolph Drive, Bolling Drive, and Escolta Avenue. Each of these roads is described below.

Palm Drive

When Main Gate Road crosses the Northwest Pacific railroad (NWP) at its grade-separated overcrossing, it becomes Palm Drive. Currently Palm Drive provides two travel lanes (each is only 12 feet wide on the NWP bridge), no parking, and limited pedestrian and bicycle access across the NWP bridge (there is a wooden pedestrian bridge on the north side only). Its intersection with Escolta Avenue is very atypical and fully channelized with a series of merge areas but no turning conflicts. Functioning as a half traffic circle might, no operational problems were observed at this location. However, its intersection to Oakwood Avenue is a two-way stop with severe approach angles. In addition, there are sight and turning radii problems with this intersection.

Randolph Drive

Randolph Drive is a primary collector between Main Gate Road and Bolling Drive. It provides one travel lane in each direction, continuous sidewalks and striped pedestrian crossings at intersections.

Bolling Drive

Bolling Drive is another primary collector in the area. It is open during both peaks and provides two travel lanes, parking on both sides of the street, and sidewalks. Traffic volumes (1995 counts) on Bolling Drive are estimated at less than 3,000 daily vehicles. However, with the recent closure of Main Gate Road, Bolling Drive is fully functional throughout the day, with most of the Main Gate traffic shifting to Bolling Drive.

Escolta Avenue

Escolta Avenue functions as a primary collector providing one through lane in each direction and adequate width for parking on both sides.

Internal Roadways - Rafael Village

The major streets providing access to Rafael Village are Ignacio Boulevard, Entrada Drive, Palmer Drive, and San Jose Boulevard. Ignacio Boulevard is described in Section 3.10.2, Local Roadways (above), and the remainder of the streets are discussed below.

Entrada Drive

Entrada Drive serves as a primary collector connecting Enfrente Drive from the US 101 southbound off-ramp to Ignacio Boulevard. It provides one travel lane in each direction with parking permitted on both sides within the project area. Current daily traffic volume on Entrada Drive is about 1,700 vehicles.

Palmer Drive

Palmer Drive is a primary collector providing access from local streets to Ignacio Boulevard, but also carrying some through traffic from Redwood Boulevard. Current daily traffic volume on Palmer Drive is about 1,450 vehicles.


San Jose Boulevard

San Jose Boulevard is a secondary collector providing access to the houses along its frontage and to local streets. Current traffic loads are about 900 vehicles daily.

Local Roadway Intersection Operations

In assessing the local circulation system, new traffic volume data for 20 intersections within the DODHF Novato area (AM and PM peak period counts) were collected during March of 1995. These data, along with the geometric configurations of the intersections, were compared to previous data in the area and were used to assess each intersection's operations.

Intersection analysis was conducted using the 1994 Highway Capacity Manual (HCM) techniques (Transportation Research Board 1994). Appendix Table G-2 shows the level of service criteria for each technique used in this study and also provides definitions for measures of effectiveness. The City of Novato designates level of service D as the lowest acceptable level of service. Appendix Figure G-1 presents the intersection location, and Figures G-2 and G-3 present existing intersection turning movement volumes, geometries, and levels of service. Figure 3-19 shows the existing intersection operations for the study intersections. Most of the key intersections operate at acceptable levels of service, with the exception of the following three:



Twenty intersections within the DODHF Novato area were examined in March, 1995. All but three of the intersections operated at acceptable levels of service.

| Key to LOS Conditions |
|-----------------------|
| Existing Condition |
| A (B) = am (pm) |

Existing Intersections Operations

DOD Housing Facility
Novato, California

Figure 3-19

Ignacio Boulevard @ Sunset Parkway (Figure 3-19, Node 1)

This intersection is all-way stop controlled with multiple lanes on all approaches. Under current conditions, vehicles experience considerable delays during the peak hours, waiting nearly 90 seconds during the AM peak hour and 40 seconds during the PM peak hour, before being able to traverse the intersection. This level of delay constitutes LOS F and E conditions, respectively. However, no operational or safety issues were observed at this intersection, so the current impact to drivers at this intersection is limited to delay. In other words, although side street traffic experiences considerable delays, adequate gaps in traffic eventually allow side street traffic to enter Ignacio Boulevard safely.

Ignacio Boulevard @ Safeway Access (Figure 3-19, Node 6)

This is a four-legged two-way stop controlled intersection. The intersection operates at LOS A and C during the AM and PM peak hours, respectively. This reported LOS is based on a weighted average of delay at individual turning movements. The east-west traffic on Ignacio Boulevard experiences no delay (it is not controlled) and represents the bulk of the traffic at the intersection, hence a weighted average of delay yields LOS C conditions during the PM peak hour. However, on the southbound approach (the Safeway driveway) during the PM peak hour, vehicles wait an average of about one minute before getting out onto Ignacio Boulevard.

Signal warrants analysis conducted by the City of Novato at this intersection has shown that this intersection would warrant a traffic signal. However, meeting signal warrants is not in itself a justification for installing a signal. Signalization needs to be considered in the context of its impact on overall circulation and traffic safety in the area. The introduction of a signal at this location would generate greater delays and potentially higher incidence of accidents on Ignacio Boulevard. This potential needs to be evaluated against the possible time saved by traffic using side streets.

Ignacio Boulevard @ Nave Drive (Figure 3-19, Node 10)

This signalized intersection operates at LOS E during the PM peak hour. This condition results from the sheer volume of traffic on every approach to the intersection.

3.10.3 Transit Facilities and Service

Transit Service


The GGBHTD, in cooperation with the Marin County Transit District (MCTD), is charged with providing transit service in Novato. Current transit facilities in the project area include bus stops on Nave Drive and Alameda del Prado, served by local and regional bus service, and a Caltrans park and ride lot on Alameda del Prado at the southbound US 101 ramps. The park and ride lot provides an estimated 110 parking spaces and has been observed to be 100 percent occupied by 7:00 AM. Figure 3-20 shows the location of the park and ride lot. This level of occupancy, as well as observed parking violations by drivers creating spaces, are indicative of demand for the parking lot exceeding the supply of parking spaces.

Bus routes in the area include Routes 1, 48, 50, 51, 52, 54, 70, 71, 80, and 90. Route 1, which stops along Alameda del Prado and Ignacio Boulevard, provides local bus service to central Novato, Indian Valley College, and key San Rafael destinations. Figure 3-20 shows the existing transit routes serving the project area. Route 1 has a number of stops and generally uses local streets resulting in long travel times, hence it is mainly used for local trips. Routes 48, 51, 52, 54, and 71 provide commute service from bus pads at the Ignacio Boulevard Interchange and travel into San Francisco or provide connections to ferries serving San Francisco. Route 48 also has stops along Ignacio Boulevard in Rafael Village. Routes 50, 70, 80, and 90 provide daily service to San Francisco with bus pads at the Ignacio and Alameda del Prado Interchanges. Route 50 also serves bus pads along Nave Drive adjacent to Main Gate.

The New Hamilton Partnership improvements include improving bus pads on Nave Drive and upgrading on-site roadways to accommodate future bus service.

Northwest Pacific (NWP) Right-of-Way

The NWP is an inactive railroad right-of-way through Hamilton Field. It is owned by the GGBHTD. The NWP provides a potential opportunity to the people of Marin and Sonoma Counties for use as a transitway. Figure 3-20 shows the alignment of this potential transitway. One of the major components of the Sonoma-Marín Transportation and Land Use Study is to look at the potential use of this corridor for commuter rail, and maybe even to improve its feasibility by adopting or encouraging land use patterns that would support its use as a transitway.



Ten bus routes provide local and commute service in the DODHF Novato area.

Existing Transit Routes and Park and Ride Lots

DOD Housing Facility
Novato, California

Figure 3-20

Source: Fehr & Peers Associates, 1996

In addition, Caltrans recently completed a feasibility study of the NWP corridor between Eureka and Corte Madera (Caltrans 1994). The Caltrans study did not specifically address the use of the corridor for commuter rail, but it did find that a very basic passenger rail service could be feasible in the area.

3.10.4 Pedestrian and Bicycle Circulation

The majority of streets in the project area provide four- to six-foot sidewalks and intersection crosswalks. Pedestrians in the project area are well served with these amenities, with the exception of the bridge crossing the NWP on Main Gate Road/Palm Drive. There is an old wooden pedestrian bridge on the north side but no pedestrian access on the south side of the bridge.

Pedestrian actuated signals are in place at the Ignacio and Bel Marin Keys intersections with US 101. Pedestrian activity was observed to be low during the AM and PM peak periods in the vicinity of the Ignacio Boulevard/US 101 intersection.

The project area is generally well served by Class II bikeways. A Class II bikeway provides a striped lane with a standard four-foot travel width, for one-way bike travel on a street or highway. Ignacio Boulevard, Alameda del Prado, and sections of Bel Marin Keys Boulevard provide Class II bikeways on both sides of the street. Both the Ignacio Boulevard overcrossing and the Bel Marin Keys overcrossing provide bike lanes in both directions. Nave Drive has bike lanes in both directions between Bolling Drive and State Access Road and from a point south of Roblar to Ignacio Boulevard.

3.10.5 Transportation Plans and Regulations

DODHF Novato is located within the City of Novato. As such, when the military releases control of the property, the city would take responsibility for the maintenance and operation of transportation facilities. In addition, reuse plans would be subject to the approval processes of the City of Novato. Improvements identified for cumulative conditions (Chapter 5) would require the approval of the city, and the implementation of these improvements would be the responsibility of the City of Novato.

The analysis approach and techniques employed for this transportation analysis are consistent with the requirements of the City of Novato. Significance criteria and LOS standards (LOS D) are consistent with previous work performed in the City of Novato for the Hamilton Field area. In addition, the city's recently adopted General Plan traffic forecasts (Preferred General Plan scenario) were used to represent future baseline conditions.

3.10 Traffic and Circulation

US 101 and SR 37 are owned and maintained by Caltrans, as are on- and off-ramps to these facilities and the park and ride lot on Alameda del Prado. Any mitigation identified for these facilities would require Caltrans' approval and would be the responsibility of Caltrans. It should also be noted that where on-ramp improvements have been required, Caltrans has also required that on-ramps be reconstructed to accommodate ramp metering.

3.11 AIR QUALITY

The ROI appropriate for air quality issues varies with the type of air pollution discussed. Primary pollutants, such as carbon monoxide and directly emitted particulate matter, have localized regions of influence generally restricted to the immediate vicinity of the emission source. Secondary pollutants, such as ozone and secondary particulate matter, have an ROI that includes the entire metropolitan San Francisco Bay Area.

3.11.1 Climate and Meteorology

Novato experiences a Mediterranean type climate characterized by mild temperature conditions. Daily temperature variations are typically 40 degrees Fahrenheit to 60 degrees Fahrenheit during the winter and 50 degrees Fahrenheit to 80 degrees Fahrenheit during the summer. Annual precipitation averages about 28 inches per year, with most precipitation occurring from October through April (Novato 1995d).

The prevailing wind direction in the Novato area is from the northwest. Mean wind speeds range from five to 10 mph, with calm winds occurring 31 percent of the time (California Air Resources Board 1984).

3.11.2 Ambient Air Quality Standards

Both the state of California and the federal government have established ambient air quality standards for several different pollutants (Table 3-20). Pollutants covered by federal or state ambient air quality standards often are referred to as criteria pollutants. As indicated in Table 3-20, ambient standards for some criteria pollutants have been set for both short and long periods. Most ambient air quality standards have been set to protect public health. State ambient air quality standards for some pollutants are based on other considerations (e.g., protection of crops, materials, or avoidance of nuisance conditions). Air quality standards for particulate matter are based on the inhalable component of suspended particulate matter.

3.11.3 Existing Air Quality Conditions

The California Air Resources Board (CARB) monitors air quality throughout California. There is one monitoring station to monitor gaseous and particulate matter in Marin County, located in San Rafael, approximately seven miles south of Rafael Village. The 1991, 1992, 1993, and 1994 monitoring results for pollutants of concern in the Bay Area, including ozone, carbon monoxide, and inhalable particulate matter, are shown in Table 3-21. The Bay Area has experienced exceedances of federal or state standards for these pollutants in the past.

Table 3-20
Ambient Air Quality Standards Applicable in California

| Pollutant | Symbol | Averaging Time | Standard, as parts per million by volume | | Standard, as micrograms per cubic meter | | Violation Criteria | |
|------------------------------|----------------------------------|------------------------|--|---------|---|---------|------------------------|--|
| | | | California | Federal | California | Federal | California | Federal |
| Ozone | O ₃ | 1 Hour | 0.09 | 0.12 | 180 | 235 | If exceeded | If exceeded on more than 3 days in 3 years |
| Carbon Monoxide | CO | 8 Hours | 9.0 | 9 | 10,000 | 10,000 | If exceeded | If exceeded more than 1 day per year |
| Inhalable Particulate Matter | PM ₁₀ | Annual Geometric Mean | — | — | 30 | — | If exceeded | If exceeded more than 1 day per year |
| | | Annual Arithmetic Mean | — | — | — | 50 | | |
| | | 24 Hours | — | — | 50 | 150 | If exceeded | |
| Nitrogen Dioxide | NO ₂ | Annual Average | — | 0.053 | — | 100 | | If exceeded |
| | | 1 Hour | 0.25 | — | 470 | — | If exceeded | |
| Sulfur Dioxide | SO ₂ | Annual Average | — | 0.03 | — | 80 | | If exceeded more than 1 day per year |
| | | 24 Hours | 0.04 | 0.14 | 105 | 365 | If exceeded | |
| | | 1 Hour | 0.25 | — | 655 | — | If exceeded | |
| Lead Particles | Pb | Calendar Quarter | — | — | — | 1.5 | | If exceeded more than 1 day per year |
| | | 30 Days | — | — | 1.5 | — | If equaled or exceeded | |
| Sulfate Particles | SO ₄ | 24 Hours | — | — | 25 | — | If equaled or exceeded | |
| Hydrogen Sulfide | H ₂ S | 1 Hour | 0.03 | — | 42 | — | If equaled or exceeded | |
| Vinyl Chloride | C ₂ H ₃ Cl | 24 Hours | 0.010 | — | 26 | — | If equaled or exceeded | |

Notes: All standards are based on measurements at 25 degrees C and 1 atmosphere pressure.
 Decimal places shown for standards reflect the rounding precision used for evaluating compliance.
 National standards shown are the primary (health effects) standards.

Source: California Air Resources Board 1993a

Table 3-21
Summary of Recent Air Quality Monitoring Data for Marin County

| Pollutant | Parameter | 1991 | 1992 | 1993 | 1994 |
|--|---|-------|------|------|------|
| Ozone | Peak 1-hour value (ppm) | 0.08 | 0.07 | 0.08 | 0.09 |
| | Days above federal standard | 0.0 | 0.0 | 0.0 | 0.0 |
| | Days above state standard | 0.0 | 0.0 | 0.0 | 0.0 |
| Carbon Monoxide | Peak 1-hour value (ppm) | 10.0 | 8.0 | 9.0 | 6.0 |
| | Peak 8-hour value (ppm) | 5.7 | 5.0 | 4.0 | 3.0 |
| | Days above federal standard | 0.0 | 0.0 | 0.0 | 0.0 |
| | Days above state standard | 0.0 | 0.0 | 0.0 | 0.0 |
| Inhalable Particulate Matter (PM ₁₀) | Peak 24-hour value (µg/m ³) | 115.0 | 63.0 | 69.0 | 72.0 |
| | Annual geometric mean (µg/m ³) | 26.4 | 22.0 | 21.3 | 21.6 |
| | Annual arithmetic mean (µg/m ³) | 30.4 | 24.5 | 23.3 | 24.1 |
| | Number of 24-hour samples | 60.0 | 61.0 | 61.0 | 61.0 |
| | % of samples above federal standard | 0.0% | 0.0% | 0.0% | 0.0% |
| | % of samples above state standard | 16.7% | 8.2% | 1.6% | 6.5% |

Notes: All data from the Marin County-San Rafael monitoring station.

ppm = parts per million by volume.

µg/m³ = micrograms per cubic meter.

Federal 1-hour ozone standard is 0.12 ppm; state 1-hour ozone standard is 0.09 ppm.

Federal 1-hour carbon monoxide standard is 35 ppm; state 1-hour carbon monoxide standard is 20 ppm.

Federal 8-hour carbon monoxide standard is 9 ppm; state 8-hour carbon monoxide standard is 9.0 ppm.

Federal PM₁₀ standards: 50 µg/m³, annual arithmetic mean; 150 µg/m³, 24-hour average.

State PM₁₀ standards: 30 µg/m³, annual geometric mean; 50 µg/m³, 24-hour average.

Source: California Air Resources Board 1991a; California Air Resources Board 1992a; California Air Resources Board 1993a; California Air Resources Board 1994.

As Table 3-21 indicates, no exceedances of federal standards have occurred in the four most recent years of monitoring. The state PM₁₀ standard has been exceeded a few times in each of the past four years.

3.11.4 Air Emission Sources at DODHF Novato

As a housing and community services facility, Novato has no major industrial emission sources. Primary sources of air pollution associated with residential use include space and water heaters, household paints and solvents, fireplaces and woodstoves, and lawn mowers and other equipment. Vehicle emissions constitute the largest source of air emissions at DODHF Novato.

3.11.5 Air Quality Planning

Federal Requirements

The federal Clean Air Act imposes deadlines for achieving the federal ambient air quality standards. These deadlines vary according to the severity of existing air quality problems. The San Francisco Bay Area was recently

reclassified from a moderate nonattainment area to a maintenance area for the federal ozone standard. The urbanized portions of the San Francisco Bay Area are presently categorized as moderate nonattainment areas for the federal carbon monoxide standards. The Bay Area currently is not classified for the federal inhalable particulate matter standard.

The Bay Area Air Quality Management District (BAAQMD), the agency responsible for achieving and maintaining the federal and state standards for the Bay Area, believes that the San Francisco Bay Area has also achieved the federal carbon monoxide and inhalable particulate matter standards, and the BAAQMD has requested redesignation to an attainment status for these pollutants. A formal designation of the San Francisco Bay Area as being in attainment of the federal inhalable particulate matter standard also is expected to occur within the year.

State Requirements

The California Clean Air Act of 1988, as amended requires air pollution control districts and air quality management districts to develop air quality management plans for meeting state ambient air quality standards for ozone (O₃), carbon monoxide (CO), sulfur dioxide (SO₂) and nitrogen dioxide (NO₂). CARB is responsible for developing a plan for meeting state PM₁₀ standards.

The California Clean Air Act does not set specific deadlines for achieving state air quality standards. Instead, attainment is required "as expeditiously as practicable," with various mandated emission control program requirements based on the nonattainment classification for ozone and carbon monoxide.

3.11.6 Regulatory Considerations

Air pollution control programs were established in California prior to the enactment of federal requirements. Responsibility for air quality management programs in California is divided between CARB as the primary state air quality management agency and air pollution control districts as the primary local air quality management agencies. Federal Clean Air Act legislation in the 1970s resulted in a gradual merger of local and federal air quality programs, particularly industrial source air quality permit programs.

The roles and responsibilities of both CARB and local air pollution control districts have been expanded by the California Clean Air Act of 1988. Local air pollution control districts also have been given added responsibility and authority to adopt transportation control measure programs and emission reduction programs for indirect and areawide emission sources.

Air Quality Permits

Many types of industrial and commercial facilities require air quality permits for their equipment and operations. The BAAQMD has the primary air quality permit authority throughout the San Francisco Bay Area. Permit authority is derived from a combination of state and federal legislation and can be categorized into construction or installation authorizations for individual pieces of equipment and permits for continued operation of equipment and facilities.

In general, federally-required air quality permit programs have been integrated into the pre-existing state and local permit program. This results in a two-step permit process—an initial authority to construct permit and a subsequent permit to operate.

Clean Air Act Conformity Requirements

Section 176 of the Clean Air Act requires federal agencies to ensure that their actions are consistent with the Clean Air Act and with federally enforceable air quality management plans. EPA has promulgated separate rules that establish conformity analysis procedures for transportation-related actions and for other (general) federal agency actions.

A formal conformity determination is required for federal actions occurring in nonattainment or maintenance areas when the total direct and indirect emissions of nonattainment pollutants (or their precursors) exceed specified thresholds. The federal nonattainment and maintenance pollutants subject to conformity analyses in the San Francisco Bay Area are ozone precursors (reactive organic compounds and nitrogen oxides) and carbon monoxide. Applicable threshold levels for federal actions in the San Francisco Bay Area are 100 tons per year of reactive organic compounds, 100 tons per year of nitrogen oxides, and 100 tons per year of carbon monoxide.

Certain federal actions, such as transfers of ownership, interests and titles in land, facilities, and real and personal properties are exempt from the General Conformity rule (40 CFR 51.853[c]). Subsequent reuse by a federal agency to which the property, in this case a portion of DODHF Novato, is transferred, would require that agency to determine the applicability of the General Conformity Rule to its action.

Lease arrangements may also be subject to the requirements of the conformity rule (depending on the extent to which lease terms allow the Navy to control the activities of the lessee) and are subject to Navy evaluation of conformity as part of the separate NEPA analysis that would be done for potential interim leases.

3.12 NOISE

The decrease in noise levels with increasing distance from the noise source results in a fairly limited ROI for noise issues. For this EIS, the overall ROI is the City of Novato. A more localized ROI is appropriate for some discrete noise sources; such localized areas of influence are generally within one-half mile of the noise source.

3.12.1 Noise Terminology

Sound travels through the air as waves of minute air pressure fluctuations caused by some type of vibration. Sound level meters measure pressure fluctuations from sound waves, with separate measurements made for different sound frequency ranges. These measurements are reported in a logarithmic decibel (dB) scale. Because the human ear is not equally sensitive to all frequencies, the "A-weighted" decibel scale (dBA) is used to weight the meter's response to approximate that of the human ear.

Equivalent noise levels (Leq) are used to develop single-value descriptions of average noise exposure over various periods. Average noise exposure over a 24-hour period is often presented as a community noise equivalent level (CNEL) or as a day-night average noise level (Ldn). CNEL values are calculated from hourly Leq values, with the Leq values for the evening period (7 PM to 10 PM) increased by five dB and Leq values for the nighttime period (10 PM to 7 AM) increased by 10 dB. Ldn values are very similar to CNEL values but do not include any weighting factor for evening period noise levels. The weighting of evening and nighttime noise levels reflects the greater disturbance potential from nighttime noises.

3.12.2 Existing Noise Conditions

Sensitive Receptors

Sensitive receptors are land uses such as residences, schools, libraries, hospitals, and other similar uses that are considered to be sensitive to noise. Sensitive on-site noise receptors in the DODHF Novato area include the DODHF Novato housing sites (Rafael Village and Capehart Housing) and Hamilton Elementary School. Sensitive off-site noise receptors include USCG Spanish Housing, the childcare center in the Spanish Housing area, the Lanham Village residential development located adjacent to the DODHF Novato Main Site, and parks, residences, and San Jose Middle School located off Ignacio Boulevard. These sites are depicted on Figures 3-1 and 3-2 in Section 3.1, Land Use, in this EIS.

Noise Conditions

The primary source of noise at the Main Site and Rafael Village areas is vehicular traffic. Roadways in the DODHF Novato area include US 101, Ignacio Boulevard, Nave Drive, Main Gate Road, and State Access Road (see Figure 3-18). Occasional aircraft flight activity from the former Hamilton Army Airfield is not a significant contributor to noise levels in the area. The railroad right-of-way through the Main Site is also not a contributor to noise levels because it is not currently active.

The City of Novato General Plan reports noise levels of 65-70 Ldn along Nave Drive and Ignacio Boulevard (Novato 1995b). The US Army estimated existing noise levels of 53-67 Ldn at DODHF Novato residential areas, 56-68 Ldn at Lanham Village, 58-68 Ldn at Hamilton School, and 55-68 Ldn for residences west of US 101 (US Army 1996). The noise level in each area depends upon the proximity to US 101.

3.12.3 Noise Level Guidelines

Federal Agency Guidelines

The federal Noise Control Act of 1972 (Public Law 92-574) established a requirement that all federal agencies must comply with applicable federal, state, interstate, and local noise control regulations. Federal agencies also were directed to administer their programs in a manner that promotes an environment free from noise that jeopardizes public health or welfare.

The Department of Defense evaluates the acceptability of noise levels at military installations according to three noise level zones—CNEL levels below 65 dB (Zone 1), CNEL levels of 65-75 dB (Zone 2), and CNEL levels above 75 dB (Zone 3). All land uses are considered compatible with Zone 1 noise levels. Educational and residential land uses generally are not compatible with Zone 2 noise levels unless special acoustic treatments and designs are used to ensure acceptable interior noise levels. Residential and educational land uses are not compatible with Zone 3 noise levels. Industrial and manufacturing land uses may be acceptable in Zone 3 areas if special building designs and other measures are implemented.

State Agency Guidelines

The California Department of Housing and Community Development has adopted noise insulation performance standards for new hotels, motels, and dwellings other than detached single-family structures. These standards require that hotels, motels, and multiple-unit dwellings be constructed so that outdoor noise sources will not cause interior noise levels to exceed an annual average CNEL value of 45 dB with the windows closed.

The California Department of Health Services (1987) has published guidelines for the noise element of local general plans. These guidelines include a noise level/land use compatibility chart that categorizes various outdoor CNEL ranges into as many as four compatibility categories (normally acceptable, conditionally acceptable, normally unacceptable, and clearly unacceptable), depending on land use.

The state noise element guidelines chart identifies normally acceptable noise levels for low-density residential uses as CNEL values below 60 dB. The normally acceptable range for high-density residential uses is identified as CNEL values below 65 dB. For educational and medical facilities, CNEL values of 60 to 70 dB are identified as conditionally acceptable. For office and commercial land uses, CNEL values of 67.5 to 77.5 are categorized as conditionally acceptable.

Novato General Plan

Novato has adopted noise standards that are at least as strict as the state standards in the Safety and Noise Element of the City of Novato General Plan (Table 3-22). The General Plan contains objectives, policies, and programs to reduce noise levels in the Novato area. The applicable objectives include the following:

Objective 11: Ensure compatibility of new development with existing and future noise levels.


Objective 12: Prevent land uses that increase the noise level above acceptable standards or require mitigation to reduce noise to acceptable standards.

Objective 13: Reduce noise to acceptable levels where it now exceeds those standards whenever possible.

In addition to these three objectives, the General Plan contains policies to maintain noise and land use compatibility standards and to mitigate noise impacts.

Table 3-22
Noise and Land Use Compatibility Standards

| LAND USE CATEGORY | Sound Levels and Land Use Consequences (see explanation below) L _{dn} Value in Decibels | | | | | |
|---|--|----|----|----|----|----|
| | 55 | 60 | 65 | 70 | 75 | 80 |
| RESIDENCES, HOTELS, AND MOTELS | | | | | | |
| OUTDOOR SPORTS AND RECREATION, NEIGHBORHOOD PARKS AND PLAYGROUNDS | | | | | | |
| SCHOOLS, LIBRARIES, MUSEUMS, HOSPITALS, PERSONAL CARE, MEETING HALLS, CHURCHES | | | | | | |
| OFFICE BUILDINGS, BUSINESS COMMERCIAL, AND PROFESSIONAL | | | | | | |
| AUDITORIUMS, CONCERT HALLS, AMPHITHEATERS | | | | | | |
| INDUSTRIAL, MANUFACTURING, UTILITIES, AND AGRICULTURE | | | | | | |



Normally Acceptable: Specified land use is satisfactory, based upon the assumption that buildings involved are of normal conventional construction, without any special noise insulation requirements.



Conditionally Acceptable: New construction or development should be undertaken only after a detailed analysis of the noise reduction requirements is made and needed noise insulation features included in the design. Conventional construction, but with closed windows and fresh air supply systems or air conditioning will normally suffice.



Unacceptable: New construction or development should generally not be undertaken because mitigation is usually not feasible to comply with noise element policies.

Source: City of Novato 1995b

3.13 HAZARDOUS MATERIALS AND WASTE

DODHF Novato has been operated as a military installation since the early 1930s. Its primary use has been for military personnel housing, with support and service areas for the housing and for other base activities. These activities have included vehicle and building maintenance and fueling and have involved the storage and use of hazardous materials. The age of most DODHF Novato buildings also presents the potential for the presence of lead-based paints and asbestos-containing materials (ACM).

DOD policy requires the preparation of an environmental baseline survey (EBS) prior to the sale, lease, or transfer of real property. The EBS is a preliminary evaluation and summary of all known and suspected areas where hazardous substances or petroleum products have been handled, stored, disposed of, or released within the boundaries of DODHF Novato and adjacent areas. The EBS for DODHF Novato (US Navy 1995a) documented the environmental conditions of real property at DODHF Novato and adjacent properties. It also documented storage tanks, asbestos, pesticides and herbicides, PCBs, radon, lead, storm water discharge, and air emissions. DODHF Novato parcels were given one of seven BRAC classifications based on storage, release, disposal, or migration of hazardous substances. The EBS also is used to meet the requirements of the Community Environmental Response Facilitation Act (CERFA). Uncontaminated parcels were also identified by this classification process (as Type 1, "CERFA-Clean").

CERFA requires a process and schedule for identification of uncontaminated sites. The final DODHF Novato basewide EBS, developed in cooperation with the regulatory community, identified 35 of 128 parcels as "CERFA-Clean." These 35 parcels have received formal written concurrence from regulatory agencies.

A phase 1 supplemental EBS is being developed to incorporate additional data and investigation results not incorporated in the Final Basewide EBS. This new information will result in reclassification of parcels that will be suitable for transfer.

The BRAC Cleanup Plan (BCP) for a closing base documents the status of environmental restoration and associated compliance programs. The BCP for DODHF Novato (US Navy 1995b) was completed in March 1995 and was updated in March 1996 (US Navy 1996a). The BCP provides an evaluation of the status of various cleanup programs and summarizes the items that require further evaluation and compliance. It provides a plan and schedule for remediation. The document is intended to be updated annually or as necessary, recording the changing conditions and level of completion of these restoration programs until restoration is complete.

The hazardous materials and waste information provided in this section reflects the most current data available for each area of concern. Information is based primarily on survey data from the EBS and BCP. Where applicable, the description of hazardous materials at DODHF Novato has been organized by reuse area, consistent with the Reuse Plan.

The region of influence relative to hazardous materials and waste is DODHF Novato and any surrounding areas that may have been affected by hazardous materials or hazardous wastes originating at DODHF Novato or from which hazardous materials or wastes could migrate onto the facility. The off-site Rafael Village housing area is included in the region of influence.

3.13.1 Hazardous Materials Regulations

The following is a brief discussion of the major federal laws and regulations that apply to hazardous materials and waste at DODHF Novato.

Resource Conservation and Recovery Act

In response to the need to more closely regulate the on-going handling, storage, transportation, and disposal of hazardous wastes, the US Congress passed the Resource Conservation and Recovery Act (RCRA) of 1976. RCRA presents the federal regulations for the operation of hazardous waste storage, treatment, and disposal sites. Prior to RCRA, the state of California had passed the Hazardous Waste Control Law (HWCL) in 1972. This law provides regulations that equal or exceed the federal standards set by RCRA for hazardous waste management. The state of California was given "interim authorization" to implement RCRA through enforcement of the HWCL. Final authorization for the state to implement RCRA was given in 1993. The responsible agency for enforcement of RCRA and HWCL is the California Environmental Protection Agency (Cal EPA), Department of Toxic Substances Control.

Comprehensive Environmental Response, Compensation, and Liability Act

Originally passed in 1980, CERCLA created national policies and procedures to identify and remediate sites previously contaminated by the release of hazardous substances. CERCLA formalized the process for identification of sites and the prioritization for the clean-up of sites through the National Contingency Plan. It contains criteria for the evaluation of sites that provide the basis for the preliminary assessment and site inspection. The evaluation results in a priority ranking of the site that determines whether it should be placed on the National Priorities List (NPL). Facilities placed on the NPL are commonly referred to as "Superfund" sites. CERCLA was amended and strengthened by the Superfund Amendments and Reauthorization Act of 1986

(SARA). SARA retained the structure and objectives of CERCLA requirements, expanded the scope of hazardous waste cleanup and the size of the Superfund, and imposed stricter and more specific cleanup requirements. As noted previously, DODHF Novato is not on the NPL and the EPA has not recommended that the site be included on the NPL.

Community Environmental Response Facilitation Act

Congress amended CERCLA in 1992 through the passage of CERFA. The purpose of CERFA is to expedite the identification of uncontaminated real property within closing federal facilities that offer the greatest opportunity for reuse and redevelopment. Uncontaminated, or "CERFA-Clean," property is defined as any real property on which no hazardous substances and no petroleum products known to have been released, or were not disposed of. Federal property may be transferred if the property is suitable for the intended use, the intended use is consistent with the protection of health and the environment, adequate notice has been given, the transfer will not substantially delay necessary response action, and response action assurances are given.

Identification of uncontaminated properties at DODHF Novato is the responsibility of the Navy. EPA is the regulatory authority for enforcement of CERCLA, including the CERFA amendments. However, the EPA has joined with the California EPA (Cal EPA) in the implementation of CERFA for DOD facilities in California. Cal EPA serves as the lead agency for closures of military bases within California, including DODHF Novato, that are not listed on the NPL. Cal EPA generally follows EPA guidance for CERCLA sites.

The DOD, with regulatory participation, can develop a site-specific or supplemental environmental baseline survey, or in specific cases, use the basewide EBS and a Finding of Suitability to Lease (FOSL) or Finding of Suitability to Transfer (FOST) for properties that contain or potentially contain contamination. The FOSL may include specific land use restrictions to protect human health and the environment and to ensure government access for final investigations and remediation. A FOST may be issued for properties on which all remedial actions necessary to protect human health and the environment with respect to any such substance remaining on the property has been taken.

3.13.2 Hazardous Materials Management

Storage of hazardous materials and the generation, storage, and disposal of hazardous waste is regulated by federal, state, and local agencies. Storage of hazardous materials is primarily regulated by two state laws, the Waters Bill (AB 2185) and the La Follette Bill (AB 3777). These laws are administered by local agencies and are primarily intended to inform local emergency response teams of the presence, nature, and quantities of hazardous materials use and storage.

The land on which DODHF Novato is located was used for agricultural purposes prior to its development as a military residential facility. It had not been used for industrial purposes, and the use of hazardous materials and generation of hazardous waste was, therefore, limited. The EBS identifies 14 parcels where use or storage of hazardous materials may have occurred in the past. These are described more fully in Appendix H.

3.13.3 Hazardous Waste Management

The generation, storage, and treatment of hazardous wastes is regulated by RCRA and the California Code of Regulations, Title 22. These laws regulate all aspect of hazardous waste and are intended to minimize the possibility of releases to the environment. They are identical in their intent and are only slightly different in their approach to hazardous waste management.

DODHF Novato is listed as a small-quantity generator of hazardous waste. It is not listed in the March 1992 RCRA (EPA) database as a large quantity hazardous waste generator nor as a treatment, storage, and disposal facility. Hazardous waste generated at DODHF Novato formerly was collected and stored at a hazardous waste storage facility in Building 957. According to the BCP, this waste consisted of waste oil from shop activities. It was periodically removed for off-site disposal. Building 957 was located in the Exchange Triangle but has been demolished.

Following base closure, very limited quantities of hazardous wastes may be generated by maintenance operations. Such wastes would be handled and disposed of following current regulatory guidelines and industry standards.

3.13.4 Installation Restoration Program

In 1981, the Chief of Naval Operations (CNO) directed the Naval Energy and Environmental Support Activity (NEESA) and the Ordnance Environmental Support Office (OESO) to initiate a program to evaluate health and environmental hazards at those naval activities associated with past hazardous material operations and waste disposal activities. This direction resulted in the

Installation Restoration Program as defined currently by the Navy/Marine Installation Restoration Manual. The purpose of the Installation Restoration Program is to identify, assess, characterize, and clean up or control contamination from past hazardous waste disposal operations and hazardous material spills at Navy and Marine Corps activities.

No Installation Restoration Program sites were identified at DODHF Novato. Investigation and any required cleanup of DODHF Novato is being conducted in accordance with BRAC requirements. Because DODHF Novato is not included on the NPL, the state of California, through the Department of Toxic Substances Control, rather than the United States EPA, is overseeing the work.

3.13.5 Asbestos

Management and handling of asbestos-containing materials (ACM) are regulated by the EPA, the Occupational Safety and Health Administration (OSHA), and the state of California. Asbestos fiber emissions into the ambient air are regulated in accordance with Section 112 of the Clean Air Act, which established the National Emissions Standards for Hazardous Air Pollutants (NESHAP). The NESHAP regulations address the demolition or renovation of buildings with ACM. The Asbestos Hazard Emergency Response Act (AHERA) provides the regulatory basis for handling ACM in school, public, and commercial buildings. AHERA and OSHA regulations cover worker protection for employees who work around or remediate ACM.

Renovation or demolition of buildings with ACM has the potential to release asbestos fibers into the air. Asbestos fibers could be released due to disturbance or damage of various building materials, such as pipe and boiler insulation, acoustical ceilings, sprayed-on fireproofing, and other materials used for soundproofing or insulation. Only friable (crumbly) ACM, such as those listed above, is considered a health risk. Nonfriable ACM, such as transite piping, shingles, or floor tile, are not a health risk unless they are mechanically abraded in such a way as to produce dust.

Buildings in all areas of DODHF Novato have the potential to contain ACM because of their construction during a period when asbestos was commonly used in building materials. Previous abatement and control of asbestos has been conducted only during repairs or modifications. A survey of five PWCSFB buildings at DODHF Novato was conducted in 1990. The survey found friable ACM in four buildings, Buildings 965, 969, 972, and 1000; no friable asbestos was identified in Building 960. No other buildings at DODHF Novato were surveyed at that time. The Navy has reportedly conducted spot

checks for ACM at Rafael Village, and asbestos has been detected in the floor tile in the units there.

A comprehensive survey of all industrial buildings to identify damaged friable asbestos was completed by PWCSFB in September 1995. Based on the findings of the survey, abatement of damaged friable ACM was completed by PWCSFB in December 1996.

An asbestos survey of the housing units was conducted by PWC Norfolk Virginia in August 1995. Friable ACM was identified in the garages of 47 units inspected in Spanish Housing. No abatement of ACM has been done in Spanish Housing. Spanish Housing will be transferred to the Coast Guard in "as is" condition since this is a transfer to another Federal Agency.

3.13.6 Polychlorinated Biphenyls (PCBs)

PCBs occur in trace amounts in chlorinated hydrocarbon fluids used in electrical equipment, primarily in transformers and capacitors, because they are electrically nonconductive and stable at high temperatures. PCBs also have been identified in light fixtures, ballasts, certain machine shop equipment, and some solid materials.

The disposal of these compounds is regulated under TSCA, which banned the manufacture and distribution of PCBs except for PCBs used in enclosed systems. By definition, PCB equipment contains PCB concentrations of 500 ppm or more, whereas PCB-contaminated equipment contains PCB concentrations of greater than 50 ppm but less than 500 ppm. The EPA, under TSCA, regulates the removal and disposal of all sources of PCBs containing 50 ppm or more; the regulations are more stringent for PCB equipment than for PCB-contaminated equipment. Primary federal regulations for controlling existing PCBs are found at 40 CFR Part 761. California regulations are more stringent than their federal equivalents and are found at California Code of Regulations Title 22. Within California, a waste fluid containing 5 ppm PCBs or more is regulated as hazardous.

All Navy shore activities that generate, treat, store, or dispose of PCBs must inventory or validate all PCBs and PCB items annually in accordance with Navy procedures and applicable federal and state regulations. DTSC regulates PCBs as a non-RCRA hazardous waste. OPNAVINST 5090.1B specifies elimination by October 1998 of all transformers containing 500 ppm or more PCBs and elimination by October 2003 of all transformers containing 50 ppm or more PCBs. At the time of base closure, transformers known to have greater than 5 ppm of PCBs may still be present at DODHF Novato. The presence of PCB-contaminated transformers or other known electrical

equipment will be disclosed in FOSLs/FOSTs prior to property lease or transfer, as appropriate.

Sampling of oil-containing electrical equipment for PCBs was performed at the DODHF Novato Main Site in 1993 and 1994. Three of 183 pieces of equipment were found to contain PCBs at concentrations greater than 50 ppm. Twenty-four of the 183 pieces of equipment sampled contained between five and 49 ppm. None of the equipment contained more than 500 ppm.

Pole-mounted, oil-filled electrical transformers owned by PG&E are present throughout Rafael Village. PG&E has carried out a PCB removal program for all of its equipment over the last several years and now states that its equipment does not contain PCBs. No visual indications of impact from transformer fluid to the ground beneath the transformers were observed during preparation of the EBS.

3.13.7 Storage Tanks and Oil/Water Separators

Both underground storage tanks (UST) and aboveground storage tanks (AST) are used to store petroleum products at locations throughout DODHF Novato. Gasoline and other petroleum products are considered hazardous substances under California Law. Because oil/water separators (OWS) are often below ground and can create environmental issues similar to USTs, they are included in this discussion.

USTs are subject to federal regulations of RCRA (40 CFR 280), as mandated by the Hazardous and Solid Waste Amendments of 1984. California has adopted regulations under Title 23, Division 3, Chapter 16 of the CCR. These regulations are more stringent than the federal regulations and require secondary containment on both the tanks and piping systems installed after January 1, 1984. The Marin County Office of Waste Management administers the state regulations for USTs at DODHF Novato. This agency administers tank permit, installation, testing, and removal requirements (US Navy 1995b). The county requires that each existing UST be tracked by using an approved monitoring plan as specified by the county. The California Regional Water Quality Control Board (RWQCB), San Francisco Bay Region, administers investigation, remediation, and closure of USTs.

The EBS and BCP identified at least 14 locations of existing, former, or suspected USTs at DODHF Novato (US Navy 1995a, 1996a). The UST locations, size, and other data are shown in Table 3-23 and Figure 3-21. All tanks have since been removed.


Table 3-23
Underground Storage Tanks

| Planning Area | Tank ID Number | Adjacent Buildings | Tank Capacity (gallons) | Product Stored | Date Installed | Current Status | Comments | Future Actions Under BCP |
|----------------------|----------------|--------------------|-------------------------|----------------------|----------------|--|----------------------------|---|
| Commis-sary Triangle | 827-1 | 826/827 | 1,000 | gasoline/ unknown | unknown | Removed, further investigation underway | Contamination found | Remedial investigation/ corrective measure study |
| | 827-2 | | 1,000 | | | Removed, further investigation underway | Contamination found | Remedial investigation/ corrective measure study |
| | 827-3 | | 1,000 | | | Removed, further investigation underway | Contamination found | Remedial investigation/ corrective measure study |
| | 827-4 | | 1,000 | | | Removed, further investigation underway | Contamination found | Remedial investigation/ corrective measure study |
| Exchange Triangle | 1 | 970 | 10,000 | gasoline | unknown | Removed 5/96 | Passed 1990 tightness test | Investigation and corrective action |
| Exchange Triangle | 2 | 970 | 10,000 | gasoline | unknown | Removed 5/96 | Passed 1990 tightness test | Investigation and corrective action |
| Exchange Triangle | 3 | 970 | 10,000 | gasoline | unknown | Removed; further investigation underway | Contamination found | Investigation and corrective action |
| Exchange Triangle | Waste Oil | 970 | 1,000 | waste oil | unknown | Removed; further investigation underway | Contamination found | Investigation and corrective action |
| Exchange Triangle | 957 | 957 | 12,000 | gasoline | unknown | Removed; further investigation found soil and ground water contamination | Residual contamination | Corrective action, if necessary |

Table 3-23
Underground Storage Tanks (continued)

| Planning Area | Tank ID Number | Adjacent Buildings | Tank Capacity (gallons) | Product Stored | Date Installed | Current Status | Comments | Future Actions Under BCP | EBS Page Number |
|-------------------|----------------|--------------------|-------------------------|----------------|----------------|--|---|---------------------------------|-----------------|
| Exchange Triangle | 972 | 972 | 2,000 | fuel oil | unknown | Wooden tank removed; further investigation found soil but not ground water contamination | Site closed | No further action | 4-33 to 4-34 |
| Bowling Alley | 11A | None | 10,000 | fuel oil | unknown | Removed; further investigation found ground water contamination | Residual contamination; groundwater monitoring | Corrective action, if necessary | 4-53 to 4-55 |
| Bowling Alley | 11B | None | 10,000 | fuel oil | unknown | Removed; further investigation found ground water contamination | Residual contamination; groundwater monitoring | Corrective action, if necessary | 4-53 to 4-55 |
| Bowling Alley | 115 | 115 | 250 | fuel oil | unknown | Not found-presumed removed; no further action required by Marin County | Site closed | No further action | 4-56 |
| Officers' Club | None | 201 | unknown | fuel oil | unknown | No tank found | Number, size, and contents unknown | No further action | 4-71 |
| Officers' Club | None | 203 | unknown | fuel oil | unknown | Two tanks removed | Site closed | No further action | 4-71 |
| Building 522 | 522 | 522 | 8,500 | fuel oil | unknown | Removed | Removed during grading for housing construction | No further action | NA |

Source: US Navy 1995a; US Navy 1995b; US Navy 1996a



UST and AST Locations

DOD Housing Facility
Novato, California

Figure 3-21

LEGEND:

- ▲ Underground Storage Tank
- Aboveground Storage Tank
- DODHF Boundary

Note: All locations approximate



All USTs at DODHF Novato have been removed. No USTs or ASTs have been identified at Rafael Village.

Source: U.S. Navy 1995a

3.13 Hazardous Materials and Waste

Soil or ground water contamination has been identified at several UST removal sites. These areas and the results of soil and ground water sampling are described in full in Appendix H. All of the identified contamination sites are undergoing or are scheduled to undergo further investigation.

Aboveground storage tanks are regulated under California Health and Safety Code, Division 20, Section 6.7, the Uniform Fire Code, and the National Fire Protection Association regulations. The mechanism used for cleanup and prevention of spills is Senate Bill (SB) 1050 of January 1990. Regulatory control of any contamination from ASTs is by the State Water Quality Control Board. One AST, listed in Table 3-24 and shown on Figure 3-21, was identified at DODHF Novato by the BCP (US Navy 1996a).

OWSs are designed to separate oil, fuel, and grease from water by gravity. However, other contaminants, such as solvents, which are potentially present in water discharged to an OWS, cannot be removed by the OWS process. Water from an OWS is typically discharged to an industrial or sanitary sewer for further treatment. One two-chamber OWS was identified at the service station in the Exchange Triangle area (Building 970) (US Navy 1995a). The pavement drains in the service station are connected to this OWS. Other OWSs may be identified during the course of base closure activities.

Table 3-24
Aboveground Storage Tanks

| Planning Area Number | Adjacent Building | Tank Capacity (gallons) | Product Stored | Current Status | Comments |
|----------------------|-------------------|-------------------------|----------------|---------------------------------|---------------------------------|
| Exchange Triangle | 972 | 500 | empty | inactive; former diesel storage | portable AST; referenced in BCP |

Source: US Navy 1995a; US Navy 1995b; US Navy 1996a

3.13.8 Pesticides

The registration and use of pesticides are regulated under the Federal Insecticide Fungicide and Rodenticide Act (FIFRA) of 1972, as amended (7 USC 136 et seq). Pesticide management activities are subject to federal regulations contained in 40 CFR 162, 165, 166, 170, and 171, and California regulations contained in CCR Title 3, Chapter 4.

Pesticide records were examined at the DODHF Novato Environmental Department as part of the EBS. The housing and landscaped areas at DODHF Novato are likely to have received routine applications of pesticides, according to the EBS; however, the property was not used for commercial uses or for agricultural activities that would have required heavy pesticide use, such as

orchards or row crops. Pesticide issues were not addressed by the BCP because no pesticide issues were identified by the EBS.

3.13.9 Lead

Lead-based paint (LBP) and lead in drinking water are considered health threats, particularly to children. Lead was a major ingredient in the house paint used throughout the country and at DODHF Novato for many years. In 1978, federal regulations mandated that the maximum lead content be reduced to 0.06% of newly applied dry film of paint. LBP use was discontinued under federal law in 1980.

DOD policy is to manage LBP in a manner protective of human health and the environment and to comply with all applicable laws and regulations. BRAC residential property transferred after January 1, 1995, must comply with the Residential Lead-Based Paint Hazard Reduction Act of 1992 (42 USC Section 4822) (US Navy 1996a). For residential dwellings constructed prior to 1960, the property must be inspected for LBP, and any LBP hazards must be abated if the property is to be transferred out of federal ownership. For residential housing constructed between 1960 and 1978, the property must be inspected for LBP and the results of the inspection must be revealed to prospective purchasers or transferees, although abatement is not required.

Lead contamination from LBP is a potential concern at DODHF Novato. Rafael Village was constructed before 1960 when the use of lead in paints and in plumbing was common. Surveys and abatement for LBP would therefore be required for these housing areas if they are to be transferred out of federal ownership. Navy protocol also requires sampling for lead in dust and lead in soil. The Capehart Housing units were constructed from 1960 to 1963 and are therefore subject to the inspection and disclosure requirements for LBP, as well as sampling for lead in dust and lead in soil, but LBP abatement is not required. The Hillside Housing units were constructed after 1978 and are exempt from sampling and testing requirements for LBP, although they were subject to visual inspection and sampling for lead in dust and lead in soil.

Residential surveys for DODHF Novato housing were performed by the Navy in 1995. The surveys showed that LBP is present in the Rafael Village and Capehart Housing units. Rafael Village is planned to be demolished and LBP abatement will therefore not be performed. In accordance with recent DOD guidance, nonresidential structures will not be surveyed (US Navy 1995a). The full results of the LBP and soil assessment at the Capehart Housing units will be disclosed to potential purchasers.

Lead was detected in soil around the Capehart Housing units; lead concentrations in 4 of 110 soil samples taken in the Capehart Housing area

3.13 Hazardous Materials and Waste

were above the federal Department of Housing and Urban Development action level of 400 parts per million.

According to the BCP, no survey for lead in drinking water will be conducted because the drinking water distribution system pipes are not comprised of lead (US Navy 1996a).

3.13.10 Radiological

The EBS found no records of use of radioactive materials at DODHF Novato. The Naval Sea Systems Command Detachment, Radiological Affairs Support Office, stated in a letter to the Navy PWCSFB dated October 17, 1994, that no radioactive materials have been used at DODHF Novato (US Navy 1996a).

3.13.11 Medical And Biohazardous Waste

No medical or biohazardous waste is produced at DODHF Novato since the former Army-owned medical facility at Hospital Hill is no longer operational. Medical waste produced at the former medical facility in the past may have been disposed of at the former landfill located in the NHP Master Plan Area, outside the DODHF Novato area.

3.13.12 Ordnance

The EBS found that two areas, Buildings 191 and 193 in the Ballfields planning area, may have been used in the past for ordnance storage. Both buildings are described in the EBS as having been used formerly for storage of arms and ammunition. Neither building was found to contain arms or ammunition and no significant cracks or staining was observed during the walks (US Navy BCP, 1996). No other ordnance use or storage at DODHF Novato has been identified.

3.13.13 Radon

Radon is a naturally occurring gas that is produced by the natural radioactive decay of uranium to radium in soils. It is a colorless and odorless radioactive gas. Atmospheric radon is diluted to insignificant concentrations. Radon that is present in soil, however, can enter a building through small spaces and openings, accumulating in enclosed areas, such as basements. The cancer risk caused by exposure, through the inhalation of radon, is currently a topic of concern.

The amount of radon is measured in picocuries per liter of air (pCi/L). The average indoor level is estimated to be 1.3 pCi/l and about 0.4 pCi/L of radon is usually found in the outside air. There are no laws that require testing and

remediation for radon, but the EPA has made recommendations for both residential housing and schools.


The Application of Radon Reduction Methods (EPA 1988) summarizes the EPA-recommended action level of 4 pCi/L and guidance for action by recommending that:

- For radon concentrations greater than 200 pCi/L, action be initiated within a few weeks;
- For radon concentrations in the range of 20 to 200 pCi/L, action be initiated within several months;
- For radon concentrations in the range of 4 to 20 pCi/L, action be initiated within a few years (the higher the radon level the more urgent the need for action); and
- For radon concentrations less than 4 pCi/L, no action is specifically recommended. However, many individuals may elect to further reduce radon concentrations in the range of 1 to 4 pCi/L.

A radon facility screening survey was conducted at DODHF Novato in 1990 under a Navy-wide program known as the Navy Radon Assessment and Mitigation Program. The program was based on guidelines from US EPA for radon measurements. The screening survey entailed placing sampling detectors in 86 housing units at DODHF Novato (including 15 at Rafael Village). The maximum radon concentration detected was 3.7 pCi/L in Rafael Village. The maximum radon concentration detected on the Main Site was 3.0 pCi/L in the Knolls housing subarea of the adjacent USCG Spanish Housing. None of the readings from these sample locations showed radon levels above the 4 pCi/L guideline.

DOD policy regarding radon on BRAC properties is to ensure that any available and relevant radon assessment data pertaining to the BRAC property will be included in property transfer documents (US Navy 1995a). No further radon assessments are planned.

**DODHF
Novato**



4.0 ENVIRONMENTAL CONSEQUENCES

| | | |
|------|---------------------------------|------|
| 4.1 | LAND USE | 4-2 |
| 4.2 | AESTHETICS AND SCENIC RESOURCES | 4-10 |
| 4.3 | SOCIOECONOMICS | 4-14 |
| 4.4 | PUBLIC SERVICES | 4-27 |
| 4.5 | UTILITIES | 4-30 |
| 4.6 | CULTURAL RESOURCES | 4-36 |
| 4.7 | BIOLOGICAL RESOURCES | 4-42 |
| 4.8 | GEOLOGY AND SOILS | 4-48 |
| 4.9 | WATER RESOURCES | 4-53 |
| 4.10 | TRAFFIC AND CIRCULATION | 4-62 |
| 4.11 | AIR QUALITY | 4-77 |
| 4.12 | NOISE | 4-84 |
| 4.13 | HAZARDOUS MATERIALS AND WASTE | 4-90 |

4. ENVIRONMENTAL CONSEQUENCES

This chapter describes the potential environmental consequences associated with the disposal of surplus federal land and reuse of DODHF Novato. The disposal action would transfer the property out of Navy ownership. The reuse action would result in adaptive reuse of existing structures and facilities and potential new construction and would create public open space areas. The Reuse Plan identifies general categories and densities of land uses that would be allowed, but specific uses within each general category have not yet been determined. Impacts are therefore described at a relatively general level of detail, consistent with the level of detail in the Reuse Plan. Future specific projects and development proposals will be subject to the California Environmental Quality Act (CEQA) and environmental review requirements set forth by the City of Novato.

For purposes of the Navy NEPA analysis, direct environmental consequences or impacts are those associated with the No Action Alternative and Navy disposal of surplus property. Indirect impacts are associated with community reuse of Navy surplus property. The Navy's roles and responsibilities for disclosing indirect reuse-related environmental impacts is to address reasonably foreseeable impacts. However, property reuse will occur after it is conveyed from federal ownership and in support of local reuse actions. Implementation of mitigation measures for reuse environmental impacts is a local responsibility and not the responsibility of the Navy.

For each resource area evaluated in this EIS, impacts of disposal and of each alternative reuse action, including the No Action Alternative, are projected to 2010. (Due to the availability of regional projection data, traffic impacts are projected to 2015 and socioeconomic impacts are projected to 2020). Complete implementation of each reuse alternative is assumed in the determination of impacts. The Preferred Alternative is buildout of the revised Reuse Plan.

Consistent with the discussion of the affected environment, this chapter has been organized by resource to provide a comparative framework for evaluating the impacts of the reuse actions on the individual resources. The impacts discussion for each resource area includes an introduction indicating the criteria used to determine whether an impact would be significant, an impacts summary table, a description of planning issues associated with each resource area, and a description of the ROI applicable to the specific resource area. An ROI is a geographic area in which impacts for a particular resource likely would occur. The ROI for a resource having regional impacts would be different than the ROI for a resource with localized impacts. Where appropriate, analysis methodology and assumptions are described.

Each resource section identifies impacts of each of the reuse actions on the specific resources and also identifies whether the disposal action would result in impacts. For each impact a determination has been made whether it would constitute a significant or not significant impact. In addition, where beneficial impacts are identified, the nature of the beneficial impact is discussed in the text of the document. Impacts of the alternatives are evaluated for each of the eight Navy-owned planning areas at DODHF Novato, consistent with the reuse proposed for each area. The level of significance for each impact resulting from Navy disposal and community reuse actions for each resource is summarized in a table at the beginning of each section.

Mitigation measures are identified for any impact determined to be significant. Significant impacts and mitigation measures are numbered, while not significant impacts (including beneficial) are listed separately from the significant impacts and are not numbered. Unavoidable significant environmental impacts (i.e., impacts that cannot be mitigated to a less than significant level) also are identified. Processes that would be implemented through the local and regional planning processes and/or through implementation of the Reuse Plan that would concern other resources and issues are described wherever applicable. The mitigation measures described in this section are those the Navy has identified as available to future owners of DODHF property to reduce environmental impacts. The Navy would not be responsible for implementing or funding any mitigation measures related to reuse unless specifically identified in this EIS and the Record of Decision.

4.1 LAND USE

The disposal action, the proposed reuse alternatives, and the No Action Alternative are evaluated for their potential to cause substantial land use impacts. Impacts to on-site and surrounding land uses are evaluated for each alternative and are compared to current conditions. Demolition and construction impacts also are considered when evaluating the potential land use impacts of each alternative. The Reuse Plan provides a general picture of future land use at DODHF Novato and outlines a project specific planning process that will occur as part of the Reuse Plan implementation.

Region of Influence

The ROI for the land use analysis includes DODHF Novato and surrounding lands.

Significance Criteria

Land use impacts would occur through changes to land uses, construction of new buildings and infrastructure, and demolition activities. Impacts would be

significant if they would divide an established community or conflict with established uses. Table 4-1 summarizes the land use impacts of the Revised Reuse Plan Alternative and other alternatives.

Table 4-1
Summary of Land Use Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|--|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Demolition and Construction Impacts | ○ | ○ | ① | ① |
| Reuse of Capehart Housing | ○ | ○ | ○ | ○ |
| Change in Land Use in Commissary and Exchange Triangles | ○ | ○ | ① | ① |
| Change in Land Use in Town Center | ○ | ○ | ○ | ○ |
| Change in Land Use at Bowling Alley, Officers' Club and Ballfields | ○ | ○ | ○ | ① |

LEGEND:

- - Significant impact
- ① - Significant and mitigable impact
- ① - Not significant impact
- = No impact

Planning Issues

The process of implementing the Reuse Plan will occur under the jurisdiction of the City of Novato and, as required by CEQA, will include environmental review, public participation, and interagency coordination. The Reuse Plan discusses implementation and describes the City of Novato planning process. The implementation process would include designating DODHF Novato with the General Plan designation "Specific Plan." The purpose of this land use designation is to "permit flexibility in physical design and land use arrangements and encourage developments which are sensitive to, and respect, the unique character of the property in general accordance with the Reuse Plan policies" (Hamilton Reuse Planning Authority 1995b). DODHF Novato would be zoned Planned Community (P-C), a designation that requires preparation of a master plan. The master plan for DODHF Novato would include development regulations, land use designations, conditions of approval, public facilities, and physical features of the project area.

Final development of each planning area within the P-C district would require the completion of a precise development plan, which would provide criteria for all or a part of each of the planning areas within the approved master plan. Part of this process would be the preparation of subdivision maps to create

individual lots. Details required in a precise development plan include grading, architecture, landscaping, primary and accessory structures, infrastructure plans, and soils information prior to action by Novato. Only upon approval of precise development plans could the project proceed to the building permit stage.

4.1.1 Disposal

Because disposal would not entail any changes to the physical environment (it is a transfer of title), the disposal action would not result in land use impacts.

4.1.2 Revised Reuse Plan Alternative

Rafael Village

Not Significant Impacts

No significant impacts to adjacent lands uses are expected from the proposed residential land use designation for this planning area. The site is currently developed with military residential units, but the units are closed and being maintained under caretaker status. Previous residential uses were compatible with the surrounding residential and open space uses. The proposed residential use is consistent with previous use of Rafael Village as military family housing.

Demolition activities related to the removal of the existing residences would result in minor but not significant impacts from temporary incompatibility with the established residential uses in the surrounding area. Demolition activities would include tearing down existing structures, sorting recyclable materials, removing demolished materials, breaking and removing concrete foundations, and cleaning up the site. Impacts of demolition activities are further described in the aesthetics and scenic resources, cultural resources, air quality, noise, and utilities sections. The land use impact of demolition activities is not significant due to the short duration of the activities.

Construction activities related to the building of new residences to replace the demolished residences also would result in short-term but not significant impacts to the surrounding residential area. Construction impacts would include generation of dust and noise and visual disruption during the construction period. This impact would not be significant because construction would be of a short duration.

Main Site

No significant land use impacts from reuse of the Main Site would occur. Land use effects associated with each planning area are described under the individual planning sections below.

Capehart Housing

No Impacts

No impacts to surrounding land uses would occur from the proposed reuse under this alternative. Reuse of this planning area as a civilian residential neighborhood would be compatible with existing surrounding land uses including commercial land uses on Nave Drive, residential uses in Lanham Village, commercial and community uses in Exchange Triangle, and USCG use of Spanish Housing. It also is expected that there would be no conflict between residential uses and the adjacent agricultural operations in the non-Navy lands between Capehart Housing and Spanish Housing due to the lack of complaints under current operations.

Commissary Triangle

Not Significant Impacts

No significant impacts to adjacent lands uses are expected from the proposed reuse for this planning area. Demolition of the existing structures would result in residents of Lanham Village being subjected to short-term demolition-related impacts. Demolition activities would include tearing down existing structures, sorting recyclable materials, removing demolished materials, breaking and removing concrete foundations, and cleaning up the site. Impacts of demolition activities are further described in the aesthetics and scenic resources, cultural resources, air quality, noise, and utilities sections.

Construction activities related to the building of structures also would result in short-term impacts to the surrounding residential uses at Lanham Village. This impact would not be considered significant due to the short-term nature of the disruption.

The land uses designated in the Reuse Plan would result in a change from the current commissary/warehouse use to an area designated for community facilities and civic uses including special uses such as an 80-bed emergency shelter housing facility. No significant land use impacts are expected because the permitted uses under this designation would be compatible with the surrounding residential, open space, and commercial uses. Policies 3.6.2.4.1 through 3.6.2.4.6 in the Reuse Plan indicate that special attention would be given to the new uses in this area in order to achieve land uses that are

4.1 Land Use

compatible with Lanham Village and other adjacent areas. The Reuse Plan also states that community facilities and civic uses (CFCU) will be required to screen or buffer adequately uses that may impact adjacent uses.

Exchange Triangle

Not Significant Impacts

The not significant land use impacts due to demolition of existing structures, construction of new structures, and a change in land use would be similar to the impacts described for Commissary Triangle except that this planning area also could include neighborhood-serving commercial development. This development would be located somewhere along the north side of the Main Gate Road and would not exceed two acres. The impacts resulting from the proposed uses in this planning area would not be significant because of the short duration of demolition and construction activities and the lack of conflict between the proposed new land uses and existing surrounding land uses. The Reuse Plan addresses land use in this planning area and specifies land use policies 3.6.2.5.1 through 3.6.2.5.7 as measures to achieve compatible land use with Lanham Village and other adjacent uses.

Town Center

No Impacts

No land use impacts would result from proposed reuse under this alternative. Although land use would change through use of a portion of the existing civic area to be used for neighborhood commercial use, this use would be compatible with the other proposed uses and the existing uses. The proposed uses would not conflict with the surrounding uses. Use of the adjacent amphitheater site as a community facility also would be compatible with surrounding uses.

Bowling Alley

No Impacts

No land use impacts would result from proposed reuse under this alternative. Reuse of the existing structures as recreational facilities and designating the area as parkland is similar to the existing land use and would be compatible with surrounding uses.

Officers' Club

No Impacts

Proposed reuse of the existing structures as visitor-serving commercial, community facilities, and civic uses would not result in land use impacts.

Ballfields

Not Significant Impacts

No land use impacts to this planning area are expected under the Revised Reuse Plan Alternative.

4.1.3 Open Space Alternative

Reuse under the Open Space Alternative would be similar to the Revised Reuse Alternative with two primary exceptions. Structures at Rafael Village would be demolished and area would be converted to open space and parkland. On the Main Site, uses proposed for the Commissary and Exchange Triangle areas would be reversed and corporation yards would be allowed.

Rafael Village

Not Significant Impacts

No significant impacts to surrounding land uses would occur under this alternative. Existing Rafael Village structures would be demolished and the area designated for open space and parkland uses. Land use impacts resulting from demolition of the existing residences would not be significant due to the short-term duration of the activities. The change in land use from residential to open space would not be a significant impact because the open space area would be compatible with the surrounding land uses. Developments could include creek restoration, playing fields, jogging and bike paths, playgrounds, and sitting areas.

Main Site

No significant land use impacts from reuse of the Main Site would occur. Land use effects associated with each planning area are described under the individual planning sections below. Impacts for the Capehart Housing, Bowling Alley, and Officers' Club planning areas would be the same as under the Revised Reuse Plan Alternative because the proposed uses are the same as the Revised Reuse Plan Alternative.

Commissary Triangle

Not Significant Impacts

No significant land use impacts are expected under this alternative. The Open Space Alternative would include 13 acres for community facilities and civic uses similar to the Revised Reuse Plan Alternative, except the proposed homeless shelter would not be located in this planning area. Also unlike the Revised Reuse Plan Alternative, corporation yards would be permitted. Potential activities in the corporation yards include truck and bus storage, equipment cleaning and maintenance, storage of landscaping and construction materials, and equipment testing. These uses would be compatible with the surrounding land use, provided that appropriate landscaping was provided as discussed in Section 4.2.

Exchange Triangle

Not Significant Impacts

No significant land use impacts are expected under this alternative. The Open Space Alternative would include community facility and civic uses and two acres of neighborhood commercial use as described under the Revised Reuse Plan Alternative. The proposed homeless shelter would be located in this planning area and would be subject to the same policies described in the Revised Reuse Plan Alternative. As described above for Commissary Triangle, corporation yards would be permitted. These uses would be compatible with the surrounding land use, provided that appropriate landscaping was provided as discussed in Section 4.2..

Town Center

No Impacts

No land use impacts are expected under this alternative. The Open Space Alternative would use all nine acres of the site as community facilities and would not include commercial uses. The community facilities designation would be consistent with existing uses and compatible with the proposed surrounding land uses.

Ballfields

Not Significant Impacts

No land use impacts are expected under this alternative. The Open Space Alternative would designate 24 acres as open space and seven acres as parkland. The land use designation would be compatible with the proposed surrounding

uses. Four ballfields in current use would be converted to open space and would be unavailable under this alternative.

4.1.4 No Action Alternative

No Impacts

Under the No Action Alternative, the existing land uses at DODHF Novato would not change and no land use impacts would therefore occur. No demolition or construction activities would take place and no land use impacts would occur. Separate NEPA documentation would be completed prior to potential Navy approval of any proposed interim leases.

4.2 AESTHETICS AND SCENIC RESOURCES

The following section describes impacts to aesthetic and scenic resources that could occur under the reuse actions. The disposal action is a transfer of title and would not entail any changes to the physical environment or affect visual resources. Therefore, this section focuses on reuse impacts, which are compared to existing visual resources.

Region of Influence

The ROI for visual resources is DODHF Novato and the surrounding viewshed within five miles. A distance of five miles was selected because visual resources at a distance greater than five miles become indistinguishable from the general background of a viewshed.

Significance Criteria

For this analysis, impacts to visual resources were qualitatively evaluated by assessing the degree of visual contrast that proposed modifications under each of the alternatives would create with the existing landscape character, as seen from viewpoints on and surrounding the property. An impact was considered significant if it substantially reduced the scenic quality of a planning area as seen from any viewpoint with a high level of sensitivity. Table 4-2 summarizes the visual resource impacts.

Table 4-2
Summary of Aesthetics and Scenic Resource Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|--|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Aesthetic Impacts of Demolition and Construction | ○ | ○ | ○ | ① |
| Change in Visual Resources in the Rafael Village Planning Area | ○ | ① | ○ | ○ |
| Change in Visual Resources in the Main Site Planning Areas | ○ | ① | ○ | ○ |

LEGEND:

- - Significant impact
- ◐ - Significant and mitigable impact
- ① - Not significant impact
- - No impact

Planning Issues

The Novato City Council has authority over future development projects at DODHF Novato. During the approval process, the city council would act according to the goals and policies outlined in the General Plan and the Reuse

Plan. Projects also would undergo design review by the Novato Design Review Commission to consider the design attributes of specific projects. This multi-level community-based approval process would assure consistency between the visual characteristics of reuse projects and the Novato goals and policies found in the Reuse Plan and the General Plan.

The Reuse Plan addresses visual resource issues for all planning areas and has a specific chapter related to design guidelines for future development. These policies explain the planning process and call for a heightened awareness toward protecting visual resources during the implementation of the Reuse Plan. This approach would aid in reducing foreseeable visual resource impacts to a not significant level and eventually, through implementation of the Reuse Plan, would result in beneficial impacts for all of the planning areas.

4.2.1 Disposal

No impacts to visual resources would occur because disposal would not entail any changes to the physical environment (it is a transfer of title) and therefore, the disposal action would not affect visual resources.

4.2.2 Revised Reuse Plan Alternative

Rafael Village

Not Significant Impacts

Visual impacts associated with demolition and construction would be minimal and are not significant because they would be of a short duration. The eventual rebuilding of the Rafael Village planning area would result in beneficial impacts to visual resources because the new residential area would appear similar to the surrounding residential areas.

Main Site

Not Significant Impacts

No significant visual resource impacts would occur at the Main Site because the visual character of the site would not change substantially. Short-term impacts to visual resources during demolition and construction are possible. The Main Site housing would be reused, and any new construction would be consistent with local specific plans and design reviews. Long-term changes to the visual character of the nonhousing planning areas would be beneficial due to the increased emphasis on urban design guidelines found in the Reuse Plan.

4.2.3 Open Space Alternative

Rafael Village

Not Significant Impacts

Under this alternative, minimal but not significant impacts due to demolition activities would be similar to the Revised Reuse Plan Alternative. Few construction impacts would occur because the construction of new residential units would not take place. The eventual construction of an open space area would result in beneficial impacts to the visual resources in this planning area.

Main Site

Not Significant Impacts

Under the Open Space alternative, corporation yards would be permitted in the Commissary Triangle and the Exchange Triangle planning areas. Impacts to visual resources resulting from these uses would not be significant assuming that increased attention to buffering of uses and landscaping between adjacent uses in these planning areas is implemented, as called for under the Reuse Plan. Specific buffering features would be designed under specific use proposals, but would likely include construction of six-feet to eight-feet high buffer walls and landscaping to block views of the corporation yard from the Lanham Village housing area. It should be noted, however, that the Reuse Plan itself does not allow corporation yards.

4.2.4 No Action Alternative

Rafael Village

Not Significant Impacts

No significant aesthetic impacts would occur under the No Action Alternative. Structures in Rafael Village would continue to be maintained minimally. Navy minimal maintenance would not completely prevent deterioration of structures in Rafael Village. The structures are currently experiencing deterioration as described in Section 3.2.2 and this condition would continue in the future under the No Action Alternative. This impact would not be significant, however, because of the gradual rate of deterioration.

Main Site

Not Significant Impacts

No significant aesthetic impacts would occur under the No Action Alternative. Structures in the Main Site planning areas would continue to be maintained minimally. Although some deterioration of buildings would occur under this alternative, changes to the existing facilities and landscape would be minimal.

4.3 SOCIOECONOMICS

This socioeconomic analysis addresses the impacts on jobs, income, population, housing, schools, recreation, and environmental justice from the disposal and reuse of the DODHF Novato property.

Reuse of the DODHF Novato property under the community reuse alternatives would generate jobs and income and would lead to increases in recreational opportunities. Reuse also would lead to increases in affordable housing. As summarized in Table 4-3, no significant impacts on population, housing, and schools issues are anticipated under these alternatives.

Table 4-3
Summary of Socioeconomic Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|------------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Employment and Income | ○ | ○ | ○ | ○ |
| Population and Housing | ○ | ○ | ⊕ | ⊕ |
| Schools (K-12) | ○ | ○ | ⊕ | ⊕ |
| Recreation | ○ | ○ | ○ | ○ |
| Environmental Justice | ○ | ○ | ○ | ○ |

LEGEND:

- - Significant impact
- ⊕ - Significant and mitigable impact
- - Not significant impact
- - No impact

Region of Influence

The ROI for socioeconomic impacts varies depending on the type of impact being analyzed. For employment, impacts on the larger ROI (Marin County) as well as Novato are analyzed. For population, only the larger Marin County has been established as the relevant basis for analysis because most of the people employed at the DODHF Novato site likely would live beyond Novato and perhaps beyond Marin County. Choosing an ROI beyond Marin County, however, would not provide any pertinent insights since the impacts would be so small as to be irrelevant. For schools, the regional analysis focuses on the Novato Unified School District since the housing units proposed on the DODHF Novato site and other new housing construction that could result from the reuse of the DODHF Novato property would affect the local school district.

Significance Criteria

The significance of socioeconomic impacts is related to the social and economic characteristics of the region and the time period being evaluated. All of the alternatives result in beneficial employment impacts to the City of Novato and Marin County. The more jobs generated, the more beneficial are the economic impacts. Population and housing growth is the natural consequence of the employment level in the region and therefore is considered neither a beneficial nor an adverse impact of the disposal and reuse actions. Population and housing growth is considered in this way because growth can be perceived either positively or negatively, depending upon the point of view of the people being considered. For example, additional housing may be deemed positive by the children of long-time residents who would like to stay in the area but be seen as negative by landlords who would like to maximize rental prices. Population and housing increases can result in secondary effects such as traffic and the infrastructure cost improvements that growth may induce. Secondary impacts are discussed in the appropriate sections of Chapter 4 and Section 5.2, Growth-inducing Impacts.

With respect to recreation and schools, provision of additional physical facilities, such as additional parks and classroom facilities, would be considered beneficial. However, changes such as additional enrollments resulting in school overcrowding are considered adverse. Changes in annual operating budgets and cash flows (fiscal impacts) are not considered to be environmental impacts and are therefore not discussed in this section.

No significant adverse social or economic impacts have been identified for any of the analyzed alternatives. Table 4-3 summarizes socioeconomic impacts and their significance.

Methodology

To determine the impact of disposal and reuse on the regional economy, the increase in economic activity that could occur under each reuse alternative between 1995 and 2020 is evaluated. Year 2020 projections of future jobs, income, population, and households have been developed using the ABAG "Projections '94."

The effects of each alternative are evaluated first by the number of jobs generated, since the numbers and types of jobs generated strongly affect other socioeconomic conditions. Jobs create income for spending; spending supports local businesses, creates additional jobs, and generates more income. Jobs and income sustain families and households. When job opportunities exist, new residents generally move in, adding to the regional population. It is assumed that approximately 25 percent of the jobs generated by the Revised Reuse Plan Alternative would attract new residents to Marin County. New households

mean additional demand for housing construction and additional revenues and demand for local government services. The impact analysis quantifies those long-term jobs that would be directly generated by the reuse alternatives on site.

4.3.1 Disposal

No Impacts

No socioeconomic impacts would result from Navy disposal of DODHF Novato properties since no major construction or reuse of DODHF Novato facilities would occur and no population would be added as a result of the transfer of property title.

Regional Economy— Employment and Income

No Impacts

Federal disposal would create minimal additional employment in Marin County and therefore would have no effect on jobs and regional income levels.

Population and Housing

No Impacts

As disposal would not involve construction and/or reuse of housing, it would have no effect on housing demand or population levels.

Schools (K-12)

No Impacts

Federal disposal would have no impact on student enrollments since it would not involve construction and or reuse of housing that would increase student enrollments.

Recreation

No Impacts

Federal disposal would result in no change to existing recreational opportunities.

Environmental Justice

No Impacts

The Navy disposal is expected to result in no environmental impacts. As no impacts would occur, no one group would be disproportionately impacted, and no mitigations are required. Table 4-4 outlines elements of the Navy policy and the actions taken to address these elements.

Table 4-4
Environmental Justice

| OPNAVINST 5090.1B | Navy Disposal Action |
|---|--|
| Analyze the human health, economic, and social effects of Department of the Navy actions, including effects on minority communities and low-income communities. | Potential social and economic impacts have been assessed and determined not to disproportionately affect minority or low-income populations. |
| Ensure that whenever feasible, mitigation measures outlined or analyzed in the environmental impact statement, or record of decision, address significant and adverse environmental effects of proposed federal actions on minority communities and low-income communities. | It was determined that any beneficial or adverse impacts would affect all parts of the population equally. |
| Ensure that opportunities for community input in the National Environmental Policy Act process are provided, including identifying potential effects and mitigation measures in consultation with affected communities and improve the accessibility of meetings, crucial documents, and notices. | Scoping activities included publishing notices in local newspapers, meeting with government agencies, and holding public meetings. These activities are detailed in Appendix B of this document. |
| Ensure that the public, including minority communities and low-income communities, has adequate access to public information relating to human health or environmental planning, regulation, and enforcement. | The Draft and Final EIS will be made available to the public at all affected community public libraries. A copy also may be obtained from the Navy upon request. The Navy point-of-contact is listed on the cover sheet at the beginning of this document. |

Source: Developed by Tetra Tech 1995.

Pursuant to the Executive Order and DOD strategy, the following activities have been carried out in the process of EIS preparation:

- U.S. census demographic information (1990) has been reviewed to identify economic and racial groups in the area that might be adversely affected;
- Identified low-income and minority groups have been notified about the public meetings and document review process described in Chapter 1 of this document; and
- The Hamilton Homes Task Force (public agencies that represent the needs of homeless residents), the Hamilton Reuse Planning Authority, the New Hamilton Partnership (developer of the portion of Hamilton

adjacent to the Reuse Planning Area), and the Housing Council (affordable housing developers and advocates) developed an "Agreement to Principles for a Planning Agreement for Affordable Housing and Homeless Support Facilities" at Hamilton Army Air Field. This agreement calls for a total of 718 affordable units, with 324 ownership units and 393 rental units (Hamilton Reuse Planning Authority 1995a).

The Navy disposal and community reuse of the property is expected to result in mainly beneficial effects to the people and the communities in Novato and Marin County. Other than increasing the availability of affordable housing units, which would benefit low-income people, impacts resulting from federal disposal of the DODHF Novato property would affect all segments of the population in and around the site equally. No one group would be disproportionately impacted, and no mitigations are required.

4.3.2 Revised Reuse Plan Alternative

Regional Economy - Employment and Income

Beneficial Impacts

Under the Revised Reuse Plan Alternative, employment-generating land reuses at DODHF Novato property would include community facilities, civic uses, and neighborhood-serving commercial uses. Based upon employment estimates generated by applying standard factors to nonresidential and employment-generating land uses, the Revised Reuse Plan Alternative would generate a total of 938 net new jobs as shown in Tables 4-5 and 4-6.

The change in jobs under the Revised Reuse Plan Alternative would represent 1.9 percent of the projected job growth between 1995 and 2020 in Marin County and 10.1 percent in Novato. Regional personal income, which refers to the sum of all wages, salaries, and proprietors' income in the region, would be expected to increase proportionally with this regional employment increase.

Population and Housing

Not Significant Impacts

The Revised Reuse Plan Alternative would add to the population of Novato and Marin County due to increases in housing and employment, which would not be a significant impact. The Revised Reuse Plan Alternative would

Table 4-5
Direct Job Generation

| Employment-generating Land Uses | Alternatives | | | | | | | | |
|------------------------------------|-----------------------------------|----------------------------|------------------------------|------------------------|---------------|-----------------|--------------------------|---------------|-----------------|
| | Revised Reuse Plan Alternative | | | Open Space Alternative | | | No Action Alternative | | |
| | Acres | Built Area ¹ | Employ- ment ² | Acres | Built Area | Employ- ment | Acres | Built Area | Employ- ment |
| Community Facilities ³ | 44 | 383,000 | 767 | 50 | 436,000 | 871 | - | - | - |
| Neighborhood Commercial | 6 | 65,000 | 145 | 4 | 44,000 | 97 | - | - | - |
| Visitor Serving Commercial | 2 | 26,000 | 31 | 2 | 26,000 | 31 | - | - | - |
| Caretaker (Employees) ⁴ | | | | | | | | | 5 |
| Direct Employment | | | 943 | | | 999 | | | 5 |

¹ Total built area is determined by dividing the total area by the Floor Area Ratio (FAR). FAR is based on assumptions that reflect industry standards for the amount of a property that will be "built" under various land uses. FAR assumptions for nonresidential land uses are:

| <u>Nonresidential Uses</u> | <u>FAR</u> |
|----------------------------|------------|
| Community Facilities | 0.20 |
| Neighborhood Commercial | 0.25 |
| Visitor Serving Facilities | 0.30 |

Estimates are from the Association of Bay Area Government, 1991 as provided by Keyser Marston.

² Employment estimates are based on the following assumptions for each employment-generating land use:

| <u>Nonresidential Uses</u> | <u>Sq.Ft./Employee</u> |
|----------------------------|------------------------|
| Community Facilities | 500 |
| Neighborhood Commercial | 450 |
| Visitor Serving Facilities | 840 |

Estimates are from the Association of Bay Area Government, 1991 as provided by Keyser Marston.

³ Acreage for community facilities has been reduced by 10 acres to account for development of senior housing in the Exchange Triangle planning area (per Keyser Marston).

⁴ Under the No Action Alternative, total employment includes five jobs estimated to be required to maintain Navy property.

Source: Hamilton Reuse Planning Authority 1995b; Keyser Marston; Economics Research Associates

provide for reuse of 708 housing units and replacement of 503 deteriorated Rafael Village units with 500 new units, for a total of 1,208 housing units. Assuming an average household size of 2.38 persons these housing units would accommodate 2,875 residents. The addition of 938 new jobs due to reuse would add another 557 residents (see Table 4-7). Reuse of DODHF Novato would contribute to the total projected population growth anticipated in Novato and Marin County between 1995 and 2020 (Table 4-7); however, most of this growth would occur as a result of the reuse of existing housing units on the Main Site and replacement of Rafael Village housing units.

Population and housing growth is not considered a significant impact because growth is neither beneficial nor adverse in and of itself. For example, prospective home buyers and renters would benefit from additional housing units in the market while home owners and landlords might consider the additional housing detrimental to their property values.

However, population and housing growth could lead to secondary impacts that may be adverse, such as the potential traffic and the infrastructure cost

Table 4-6
Analysis of Job Impacts in Novato and Marin County

| Job Impact | Alternatives | | |
|---|--------------------------------|-------------------------------------|-----------------------|
| | Revised Reuse Plan Alternative | Open Space Alternative ³ | No Action Alternative |
| New Jobs Generated by Reuse | 943 | 999 | 0 |
| Net New Jobs Generated by Reuse/Alt. ¹ | 938 | 994 | 5 |
| Job Impact in Novato | | | |
| Projected Job Growth in Novato between 1995 & 2020 ² | 9,264 | 9,264 | 9,264 |
| Percentage Change in Jobs Due to Reuse As Percent of Job Growth in Novato | 10.1% | 10.7% | 0.1% |
| Job Impact in Marin County | | | |
| Projected Job Growth in Marin County between 1995 & 2020 ² | 50,187 | 50,187 | 50,187 |
| Percentage Change in Jobs Due to Reuse As Percent of Job Growth in Marin County | 1.9% | 2.0% | 0.0% |

¹ Five jobs associated with caretaker status under the No Action Alternative have been excluded in the net new jobs estimate for the reuse alternatives.

² Based on ABAG Projections '94.

³ The Open Space Alternative would have slightly more jobs than the Revised Reuse Plan Alternative because it includes more acreage for community facilities land uses.

Source: Association of Bay Area Governments, 1993; Economics Research Associates

improvements that growth may induce. These secondary impacts are discussed in the appropriate sections of Chapter 4 and Section 5.2, Growth-inducing Impacts.

The reuse plan calls for development of senior assisted-living housing units and an 80-bed emergency homeless shelter; these are considered to be community facilities that would serve the existing population of Marin County. Therefore, these units are not considered to increase the population within Marin County.

In estimating the growth attributable to job creation at the site, the analysis assumes that 25 percent of all future employees on the DODHF Novato property would move to Marin County, adding 557 new residents. The remaining jobs likely would be filled with people residing outside Marin County. (As the availability of housing in Novato and Marin County is limited, estimating that 25 percent of future employees at the former DODHF Novato site would move to Marin County to live is probably an overestimate, but is used for purposes of this analysis so that impacts will not be underestimated.)

Table 4-7
Analysis of Population Impacts in Novato and the ROI Resulting From Reuse Alternatives

| Population Impact | Alternatives | | |
|--|--------------------------------|------------------------|-----------------------|
| | Revised Reuse Plan Alternative | Open Space Alternative | No Action Alternative |
| Net New Jobs in the ROI due to Reuse | 938 | 994 | 5 |
| Reuse employees who may be new ROI residents ¹ | 234 | 248 | 1 |
| Total Gain in Population due to jobs (includes dependents) ² | 557 | 590 | 2 |
| Percent change due to jobs | 16.2% | 26.0% | 100.0% |
| Number of housing units | 1,208 | 708 | 0 |
| Gain in Population due to housing reuse/replacement ³ | 2,875 | 1,685 | 0 |
| Percent change due to housing reuse/replacement | 83.8% | 74.0% | 0.0% |
| Total Change in ROI Population due to Reuse | 3,432 | 2,275 | 2 |
| <u>Population Impact in Novato</u> | | | |
| Projected Population Growth in Novato between 1995 & 2020 ⁴ | 8,006 | 8,006 | 8,006 |
| Percentage Change in Population Due to Reuse as % of Population Growth in Novato | | | |
| Percent of change due to jobs | 7.0% | 7.4% | 0.0% |
| Percent of change due to housing reuse/replacement | <u>35.9%</u> | <u>21.0%</u> | <u>0.0%</u> |
| Total percent change | 42.9% | 28.4% | 0% |
| <u>Population Impact in Marin County</u> | | | |
| Projected Population Growth in Marin County between 1995 & 2020 ⁴ | 25,700 | 25,700 | 25,700 |
| Percentage Change in Population Due to Reuse As % of Population Growth in Marin County | | | |
| Percent of change due to jobs | 2.1% | 2.3% | 0.0% |
| Percent of change due to housing reuse/replacement | <u>11.2%</u> | <u>6.6%</u> | <u>0.0%</u> |
| Total percent change | 13.3% | 8.9% | 0.0% |

¹ Approximately a quarter of the jobs generated at DODHF Novato are assumed to attract new residents to Marin County. This estimate would be less if new residents reside in DODHF Novato housing.

² Average household size for the ROI in 1995 was 2.38 persons per household.

³ Excludes senior assisted housing and emergency shelter since these units are expected to service existing residents in the area.

⁴ Based on ABAG Projections '94.

Source: Association of Bay Area Governments, 1993; Economics Research Associates

Schools (K-12)

Not Significant Impacts

No significant impacts to schools would occur under this alternative. The Revised Reuse Plan Alternative would result in up to 201 additional students attending NUSD schools each year over the 25-year period. This increase would represent 2.9 percent of the total 1995 NUSD enrollment. Since most schools in the NUSD are below enrollment capacity, the Revised Reuse Plan Alternative would not result in an exceedance of capacity (see Table 4-8).

Under this alternative, the majority of the 201 additional students most likely would attend the three schools that serve the area: Hamilton Elementary School, San Jose Middle School, and Novato High School. Assuming that all of these students attended the area schools, the increase would represent 9.5 percent of the total 1995 enrollments in the area schools and would not be a significant impact since these schools are 19.1 percent below enrollment capacity (see Table 4-8).

Table 4-8
Impact on School District Enrollments

| | Alternatives | | |
|---|--------------------------------|------------------------|-----------------------|
| | Revised Reuse Plan Alternative | Open Space Alternative | No Action Alternative |
| Impacts on Novato Unified School District | | | |
| Total Increase in Student Enrollment due to Reuse ¹ | 201 | 132 | 0 |
| Students due to Reuse As % of Total 1995 NUSD Enrollment | 2.9% | 1.9% | 0% |
| Total 1995 NUSD Enrollment | 7,022 | 7,022 | 7,022 |
| 1995 NUSD Enrollment & Students due to Reuse | 7,223 | 7,154 | 7,022 |
| Total NUSD Enrollment Capacity | 7,821 | 7,821 | 7,821 |
| % Below Enrollment Capacity | 7.7% | 8.5% | 10.2% |
| Impacts on Area Schools² | | | |
| Total 1995 Area School Enrollment | 2,115 | 2,115 | 2,115 |
| Students due to Reuse As % of Total 1995 Area School Enrollment | 9.5% | 6.2% | 0% |
| 1995 Area School Enrollment & Increase due to Reuse | 2,316 | 2,247 | 2,115 |
| Area School Enrollment Capacity | 2,613 | 2,613 | 2,613 |
| % Below Enrollment Capacity | 11.4% | 14.0% | 19.0% |

¹ Estimates based on 0.139 students per household, based on a composite of grade range values as shown in Table 3-15. Excludes emergency shelter since these units are expected to service existing residents in the area.

² Students from the reuse planning area most likely would attend Hamilton Elementary, San Jose Middle School, and Novato High School, i.e., "the area schools."

Source: City of Novato 1995d; Economics Research Associates

Recreation

Beneficial Impacts

Implementation of the Revised Reuse Plan Alternative would add approximately 52 acres of neighborhood park facilities (Table 4-9) and 114 acres of open space. While some of the parks would be operated and maintained by the Novato Parks and Recreation Department, most of them would likely be maintained through non-city based financing. Since all neighborhoods within Novato are considered to be underprovided with parks, this expansion of recreational facilities would be a beneficial impact.

Environmental Justice

Beneficial Impacts

The increase in affordable housing in the city and county and the provision of emergency shelter housing and transitional housing would benefit the homeless and low-income residents in the area.

Table 4-9
Recreation Facilities Proposed for Reuse Planning Areas

| Planning Area | Facility Type | Revised Reuse Plan Alternative (acres) | Open Space Alternative (acres) |
|----------------------|--------------------|--|--------------------------------|
| Rafael Village | Neighborhood Park | 7 | 7 |
| Capehart Housing | Neighborhood Park | 9 | 9 |
| Commissary Triangle | None | - | - |
| Exchange Triangle | None | - | - |
| Town Center | Plaza/Passive Park | 2 | - |
| Bowling Alley | Neighborhood Park | 3 | 3 |
| Officers' Club | None | - | - |
| Ballfields | Neighborhood Park | 31 | 7 |
| Total (acres) | | 52 | 26 |

Source: Hamilton Reuse Planning Authority 1995b

4.3.3 Open Space Alternative

Regional Economy - Employment and Income

Beneficial Impacts

The Open Space Alternative would generate approximately the same number of net new jobs (994 jobs) in the community as the Revised Reuse Plan Alternative (938 jobs). It would have slightly more jobs because it includes

more acreage for community facilities land uses than the Revised Reuse Plan Alternative. Community facilities are one of the land use types that are expected to generate jobs. The Open Space Alternative therefore would have approximately the same beneficial impacts with regard to employment as the Revised Reuse Plan Alternative.

Population and Housing

Not Significant Impacts

The Open Space Alternative would add to the population of Novato and Marin County due to the addition of housing and employment, which would not result in significant impacts. The Open Space Alternative would provide for reuse of 708 housing units. The 503 Rafael Village units would not be replaced. These housing units would accommodate 1,685 residents. In addition, new employment due to reuse would add another 590 residents. Reuse of DODHF Novato would contribute to the total projected population growth anticipated in Novato and Marin County between 1995 and 2020 (Table 4-7); however, most of this growth would occur as a result of the reuse of existing housing units on the Main Site.

Population and housing growth is not considered a significant impact because growth is neither beneficial nor adverse in and of itself. For example, prospective home buyers and renters would benefit from additional housing units in the market while home owners and landlords might consider the additional housing detrimental to their property values.

However, population and housing growth could lead to secondary impacts that may be adverse, such as the potential traffic and the infrastructure cost improvements that growth may induce. These secondary impacts are discussed in the appropriate sections of Chapter 4 and Section 5.2, Growth-inducing Impacts.

The Reuse Plan calls for up to 210 senior assisted-living housing units and an 80-bed emergency homeless shelter; these are considered to be community facilities that would serve the existing population of Marin County. Therefore, these units are not considered to increase the population within Marin County.

In estimating the population growth attributable to job creation, the analysis assumes that 25 percent of all future employees on the DODHF Novato property would move to Marin County, adding 590 new residents. The remaining jobs likely would be filled with people residing outside Marin County. (As the availability of housing in Novato and Marin County is limited, estimating that 25 percent of future employees at the former DODHF Novato site would move to Marin County to live is probably an overestimate,

but is used for purposes of this analysis so that impacts will not be underestimated.)

Schools (K-12)

Not Significant Impacts

No significant impacts to schools would occur under this alternative. The Open Space Alternative would result in a total of up to 132 additional students attending NUSD schools each year over the 25-year period. This increase would represent 1.9 percent of the total 1995 NUSD enrollment. Since most schools in the NUSD are below enrollment capacity, the Open Space Alternative would not result in overcrowding (see Table 4-8).

Under this alternative, the majority of the 132 additional students most likely would attend the three schools that serve the area: Hamilton Elementary School, San Jose Middle School, and Novato High School. Assuming that all of these students attended the area schools, the increase would represent 6.2 percent of the total 1995 enrollments in the area schools and would not be a significant impact since these new students would not cause any of the schools to exceed capacity (see Table 4-8).

Recreation

Beneficial Impacts

Implementation of the Open Space Alternative would add 26 acres of neighborhood parks and 224 acres of open space. Like the Revised Reuse Plan Alternative, this would be a beneficial impact.

Environmental Justice

Beneficial Impacts

Under the Open Space Alternative, the addition of affordable housing in the city and county and the provision of emergency shelter housing and transitional housing would have the same beneficial impact as the Revised Reuse Plan Alternative.

4.3.4 No Action Alternative

Regional Economy— Employment and Income

The No Action Alternative would require only five caretaker employees and would therefore not significantly add to the job base in the Novato and Marin County area.

Population and Housing

No Impacts

Employment of five persons under the No Action Alternative would not add to the population or housing demand of Novato and Marin County (see Table 4-7).

Schools (K-12)

No Impacts

The No Action Alternative would not affect NUSD enrollment.

Recreation

Beneficial Impacts

Because the property would be in caretaker status, recreational opportunities would not increase or decrease.

Environmental Justice

No Impacts

The No Action Alternative would not have disproportionately high or adverse human health or environmental effects on minority and/or low-income populations.

4.4 PUBLIC SERVICES

This section presents the analysis of potential impacts to public services that could result from the disposal and reuse of DODHF Novato. Impacts occurring under the No Action Alternative also have been evaluated. The impact analysis evaluated future conditions against current conditions. Disposal-related impacts are differentiated from those resulting from reuse, as appropriate. Disposal impacts would be the same for all reuse alternatives. No disposal impacts would occur under the No Action Alternative. Public services include police, fire, and emergency medical services.

Region of Influence

The ROI for this section is the City of Novato including DODHF Novato. This ROI was selected because the city likely will assume jurisdiction over the property following disposal by the Navy.

Significance Criteria

A project may have a significant impact if it would result in a substantial increase in the level of police, fire, or emergency medical services required. Table 4-10 summarizes impacts to public services.

Table 4-10
Summary of Public Service Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|--|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Fire Protection and Emergency Medical Services | ○ | ○ | ⊕ | ⊕ |
| Police Protection | ○ | ⊕ | ⊕ | ⊕ |

LEGEND:

- - Significant impact
- ◐ - Significant and mitigable impact
- ⊕ - Not significant impact
- - No impact

Planning Issues

The Reuse Plan calls for the construction of a fire station as part of the NHP Master Plan. An agreement between the NHP and the Novato Fire Protection District (NFPD) dedicates a parcel of land within the development to a future fire station (Rentz, personal communication). Construction of the new fire station will begin when the volume of emergency calls requires expanded service. This would decrease the NFPD response time to emergency incidents at DODHF Novato.

4.4.1 Disposal

No Impacts

There would be no impact to public services under the disposal action. All Navy agreements and contracts with the city and the private security firm would be discontinued. City agencies would be solely responsible for providing security and preventing trespassing and vandalism of the property. Novato could meet these increased responsibilities by contracting with the security firm to continue its services or by more frequent patrols of the area by Novato police officers. The NFPD would continue to be responsible for fire suppression and the provision of emergency medical care.

4.4.2 Revised Reuse Plan Alternative

Fire Protection and Emergency Medical Services*Not Significant Impacts*

The Revised Reuse Plan Alternative would not result in significant impacts to fire protection and emergency medical services. As the population of DODHF Novato increases, the number of service calls received also can be expected to increase. As the volume of calls increases, the existing system will reach a point at which it will not be sufficient and a new fire station would be required. The Marin Countywide Plan recommends construction of a new station and the New Hamilton Partnership has dedicated a piece of property to the construction of a future station. The station would be constructed if and when the demand for fire protection and emergency medical service exceeds the capacity of the existing stations. Twelve additional fire fighters would be required for a single engine company at the new station. The NFPD also expressed the following concerns regarding DODHF Novato: bringing the Main Site water supply infrastructure up to district standards; upgrading residential structures to comply with the district's sprinkler ordinance; and possible damage or collapse of the Ignacio Boulevard overpass during an earthquake, which would isolate the Main Site from emergency service providers. The Ignacio Boulevard concern would be resolved by the construction of the new fire station. Needed improvements, additional fire personnel, and construction of the new fire station would be funded through taxes generated by the new development. The increase in demand for services would occur gradually during buildout and, therefore, is not identified as a significant impact. The infrastructure problem is in the process of being corrected through system replacement (Rentz, personal communication).

Police Protection

Not Significant Impacts

The Revised Reuse Plan Alternative would not result in significant impacts to police protection. Providing police service to DODHF Novato in the future would require additional personnel to deal with routine patrols, traffic control, and criminal investigations. Under the Revised Reuse Plan Alternative, the number of people living at DODHF Novato is expected to increase to approximately 3,432, requiring an additional five police officers, one vehicle, and two support staff members. The additional personnel and equipment could be paid for by taxes generated from the new development. The increase in demand for services would occur gradually during buildout and, therefore, is not identified as a significant impact.

4.4.3 Open Space Alternative

Not Significant Impacts

No significant impacts to public services would occur under the Open Space Alternative. Impacts are similar to those under the Revised Reuse Plan Alternative, with the exception that Rafael Village would require a lower level of public services than it currently demands. Under this alternative, the population of DODHF Novato would be approximately 2,275 persons and would require three additional police officers and one support staff member. If the new fire station is built, 12 additional fire fighters and an additional engine would be required.

4.4.4 No Action Alternative

Not Significant Impacts

Under the No Action Alternative, there would be no significant impacts to public services. The Navy would continue to be responsible for the provision of police, fire, and emergency medical services to all areas. The current staffing levels at the NFPD would be adequate, while the Novato Police Department would require an additional police officer and one support staff member.

4.5 UTILITIES

This section analyzes the effects of the EIS alternatives on the existing utilities, including the water distribution, sanitary sewer, storm drainage, electrical, natural gas, telephone, cable television, and solid waste management systems. Impacts are analyzed against existing conditions.

Region of Influence

The ROI for utility service is the service areas of the individual service providers, because analysis for each utility will be based on potential effects within the service area of each service provider.

Significance Criteria

An alternative may have significant effects on a public utility if it would increase demand in excess of utility system capacity to the point that substantial expansion would be necessary. Significant environmental impacts also could result from system deterioration due to improper maintenance or extension of service beyond its useful life. Effects would be identified as significant if federal, state, or local standards or requirements regulating a public utility system would be violated, such as a failure to monitor and sample stormwater discharges as may be required under a NPDES permit, resulting in fines or permit revocation. Table 4-11 summarizes impacts to utilities.

Table 4-11
Summary of Utilities Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|---|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Electric, Natural Gas, and Telephone Systems Capacity | ○ | ○ | ⊕ | ○ |
| Stormwater Drainage System Capacity | ○ | ○ | ⊕ | ⊕ |
| Water Supply and Sanitary Sewer System Capacity | ○ | ○ | ⊕ | ○ |
| Solid Waste Management (Demolition) | ○ | ○ | ● | ● |

LEGEND:

- - Significant impact
- ◐ - Significant and mitigable impact
- ⊕ - Not significant impact
- - No impact

4.5.1 Disposal

No Impacts

No utility impacts would be expected from Navy disposal of the DODHF Novato property.

4.5.2 Revised Reuse Plan Alternative

Electrical, Natural Gas, and Telephone Systems

Not Significant Impacts

The proposed upgrading of electrical, natural gas, and telephone systems to meet current PG&E and Pacific Bell standards would have no significant environmental impacts. Future upgrades to the Rafael Village power distribution system include additional primary points of connection to limit long power outages (the existing system has only a single feed). The Main Site power systems will need to be upgraded to meet current PG&E standards, including undergrounding utilities and constructing a new main substation to provide 12 kilovolts primary power. In Rafael Village and Capehart Housing, individual tenant natural gas meters would need to be installed for future individual customers. In the remaining Main Site areas, a new primary gas main and distribution system would need to be installed. In the event that the electrical system's overhead lines are relocated underground to meet future requirements, the telephone lines would also be included within a new "joint" trench, which would accommodate electrical, telephone, and cable television lines. The joint utility trench is expected to be located in public rights-of-way such as streets.

Each of the distribution companies has indicated that it has adequate capacity to serve potential future site users under this alternative.

Storm Drainage System

Not Significant Impacts

The proposed upgrading of the storm drainage system to meet current City of Novato criteria would have no significant environmental impacts. Construction of improvements to eliminate localized flooding areas and protect portions of the Ballfields from bay water inundation would have no significant environmental impacts. Future exact or specific quality of storm drainage runoff would depend on the type of future site users and the nature of the potential contaminants related to these operations. Although the

proposed development does not include industrial type uses, the construction of detention facilities, grease traps, or other facilities as required by current NPDES regulations would improve water quality prior to discharge into receiving waters.

Water Supply

Not Significant Impacts

The proposed upgrading of the distribution systems to meet current North Marin Water District and Marin Municipal Water District standards would have no significant environmental impacts. The Reuse Plan recommends upgrading the existing system at Rafael Village by completely replacing and relocating pipelines within public rights-of-way or public streets. These pipelines should be capable of providing fire flow of at least 1,000 to 1,500 gallons per minute (gpm) for two hours. The plan also recommends adding additional fire hydrants to satisfy the current fire hydrant spacing criteria of 350 feet, since the current maximum fire hydrant spacing is approximately 880 feet. Upgrades to Capehart Housing if the area is subdivided include replacing the existing system, relocating the facilities into public rights-of-way, and installing new individual service lines and meters at the subdivided parcels or dwelling units. The Reuse Plan recommends that additional fire hydrants be installed to satisfy the current fire hydrant spacing criteria in Capehart Housing of approximately 480 feet. In the Commissary and Exchange Triangles, pipelines should be abandoned in place, relocated into public rights-of-way, and upsized to be capable of providing the required fire flow.

The Revised Reuse Plan Alternative would result in levels of residential and commercial development nominally equivalent to existing conditions, so that a significant increase in water consumption would not be anticipated.

Sanitary Sewer System

Not Significant Impacts

The proposed upgrading of the sanitary sewer collection system to meet current Novato Sanitary District standards would have no significant environmental impacts. The Reuse Plan recommends replacement of the entire Rafael Village and Capehart Housing sewer systems. The Reuse Plan recommends that the pipelines in the Commissary and Exchange Triangles, Town Center, Bowling Alley, Officers' Club, and Ballfields be relocated to public rights-of-way, additional manholes be installed to satisfy the district's current spacing standards, and deteriorated pipelines be replaced. The Revised Reuse Plan Alternative results in levels of residential and commercial development nominally equivalent to existing conditions, so that a significant increase in wastewater generation would not be anticipated.

Solid Waste Management

Significant Impacts

Impact 1. A significant and mitigable impact would result if demolition of Rafael Village structures prevented Marin County from meeting the Cal EPA solid waste reduction standards of 50 percent by 2000. Though the demolition of structures at Rafael Village would not affect landfill life, as described below under Not Significant Impacts, the addition of this waste to the countywide waste stream would contribute to the nonattainment of solid waste reduction goals. The law provides for penalties of \$10,000 a day if the standards are not met. Currently, Marin County is exceeding its diversion goal of 25 percent. If the 50 percent goal is not met, Marin County may be able to obtain a waiver from the state to avoid paying the penalties; however, additional waste may result in higher landfill costs.

Mitigation 1. The California Integrated Waste Management Board (CIWMB) has been exploring ways to assist localities to divert construction and demolition debris from landfills through reuse, recycling, and other strategies. An informal base closure team has been organized with CIWMB staff and others to examine the issues and identify projects that could assist counties involved in base closures.

CIWMB has asked the Trade and Commerce Agency for funds to do several projects. The following are those proposed activities applicable to the demolition issue:

- Researching and producing guidebooks on suggested demolition practices to be used to minimize contamination and to maximize reuse;
- Developing a local materials exchange program adapted to base closures;
- Identifying reuse opportunities, processors, and markets for recovered materials;
- Developing local ordinances that require construction and demolition efforts to follow recovery and recycling guidelines; and
- Developing guidelines for handling potentially hazardous materials included in construction and demolition debris.

Taking the lead in addressing recycling associated with military base closures, the Secondary Materials and Technology Branch has been conferring with the Trade and Commerce Agency about the need for funding to support the CIWMB's base closure program. The CIWMB has requested funds from Trade and Commerce to implement technical assistance activities directed toward

communities impacted by base closure. The CIWMB has no direct funding for diversion efforts by affected jurisdictions.

The California Pollution Control Financing Agency does not provide direct funding to the public sector but to private sector operators and developers of waste management infrastructure. Waste disposal and resource recovery businesses would be eligible to apply for this financing, which is backed by tax-exempt bonds issued by the state.

Implementation of the above policies would reduce this impact to a not significant level.

Not Significant Impacts

For normal continuation of solid waste disposal at the DODHF Novato property, it is anticipated that disposal would be handled by the City of Novato through a private contractor. Once fully redeveloped, the facilities at the DODHF site can be expected to generate an amount of waste in proportion to other residential areas of the City of Novato. The Novato Sanitary District estimates that families occupying DODHF housing upon reuse will generate less waste destined for landfills than military families presently on-site, resulting in no significant impact (Hamilton Reuse Planning Authority 1995a).

The demolition of existing unwanted buildings and pavement at Rafael Village would create large quantities of construction and demolition debris. A local demolition contractor estimates that each structure might be expected to generate 13 to 14 tons of construction waste (Caldwell, personal communication). This would result in approximately 6,500 to 7,000 tons of construction and demolition debris from all of the structures, or 0.06 percent of the available capacity (10.9 million tons) in the Redwood Landfill (Frost, personal communication). Therefore, the addition of this amount of material would not measurably shorten the expected life of the Redwood Landfill, resulting in no significant impact. As Redwood Landfill is permitted for the disposal of asbestos- and lead-base paint-containing construction debris, buildings with these materials do not pose any impacts to the landfill.

4.5.3 Open Space Alternative

Solid Waste Management

Significant Impacts

Solid waste management impacts would be the same as under the Revised Reuse Plan Alternative.

Storm Drainage System

Not Significant Impacts

Impacts to the stormwater drainage system would be less under this alternative than under the Revised Reuse Plan Alternative due to less impervious cover with increased open space acreage. Impacts would be considered not significant.

Electrical, Natural Gas, and Telephone Systems

No Impacts

Compared to the Revised Reuse Plan Alternative, overall consumption of utilities would be reduced approximately 30 percent in the planned residential areas due to the elimination of the 503 Rafael Village units under this alternative. Such a reduction would have no impact on the local water supply and wastewater treatment facilities, nor on electricity, natural gas, and telephone service.

4.5.4 No Action Alternative

No Impacts

No utilities impacts would be expected under the No Action Alternative, especially with regard to solid waste since Rafael Village units would not be demolished. This alternative would place the DODHF Novato property in federal caretaker status. Overall utility consumption would be reduced significantly, resulting in beneficial effects to local water supply and energy sources.

4.6 CULTURAL RESOURCES

For purposes of this analysis, significant cultural resources are those properties listed in or eligible for inclusion on the National Register of Historic Places (NRHP). The California Register of Historical Resources also recognizes those properties as being significant. The NRHP is a list of properties that possess historic integrity and meet criteria established by the Secretary of the Interior, and therefore, are deemed worthy of preservation. As explained in Section 3.6.3, the Hamilton Army Air Field Discontiguous Historic District has been determined eligible for inclusion in the National Register by the Navy in consultation with the California State Historic Preservation Officer (SHPO).

The historic properties on DODHF Novato that contribute to the Hamilton Army Air Field Discontiguous Historic District that are being considered for disposal from federal ownership are the Bachelors Officers' Quarters (Building 201), the Swimming Pool (Building 205), the War Department Theater (Building 507), and the Amphitheater. As discussed in this section, it is anticipated that these properties will be conveyed under public benefit conveyance programs, which assure preservation of these facilities. The Navy action to dispose of surplus lands at the former DODHF Novato is subject to Federal preservation law and regulations and reuse of these lands is subject to state law.

Region of Influence

The ROI for cultural resources is the area defined by the boundaries of DODHF Novato.

Significance Criteria

This analysis uses the Criteria of Adverse Effect, as developed by the Advisory Council on Historic Preservation (ACHP) in its regulations for the "Protection of Historic Properties" (36 CFR Part 800) in identifying adverse effects. These regulations define an adverse effect as any action that would diminish the integrity of a historic property's location, setting, design, material, workmanship, feeling, or association. The regulations cite the following examples of effects that would be adverse.

- Destruction of or damage or alteration to all or part of the property;
- Isolation of the property or alteration of the character of the property's setting when that character contributes to the property's qualifications for the NRHP;

- Introduction of visual, audible, or atmospheric elements that are out of character with the property or changes that may alter its setting;
- Neglect of a property resulting in its deterioration or destruction; and
- Transfer, lease, or sale of a property, without adequate provisions to protect the property's integrity.

To ensure appropriate treatment of the cultural resources affected by the disposal and reuse of the historic properties on surplus lands at DODHF Novato, they will be transferred with adequate provisions to protect their integrity. For purposes of NEPA, implementation of these conditions reduces the significant impacts to cultural resources to a not significant level.

Eligible Historic Properties

The only historic properties eligible for listing on the NRHP as contributing elements of the Hamilton Army Air Field Discontiguous Historic District being considered for Navy disposal are the War Department Theater and Amphitheater (Town Center Planning Area) and the Swimming Pool and Bachelor Officers' Quarters (Officers' Club Planning Area). The California SHPO concurred with this conclusion of the Navy in May 1997.

Recent subsurface investigations of previously recorded archeological sites on DODHF Novato lands (Busby et al 1995) failed to identify any archeological features that would qualify for listing on the National Register. The results of these surveys and prior archeological study in this area are the basis for the Navy's conclusion that the disposal and reuse of DODHF Novato is not likely to affect significant prehistoric archeological resources. The California SHPO concurred with this finding in June 1997 (SHPO June 1997).

Nevertheless, it is possible for subsurface archeological resources to be encountered during grading or excavation activities associated with the redevelopment of the DODHF Novato property. If such resources are discovered their significance should be professionally evaluated and they should be afforded appropriate treatment under State law at that time.

The Navy has no role in the planning and the implementation of the local reuse plan, therefore, only the disposal action of the Navy is subject to Federal preservation law and regulations. The implementation of the proposed reuse plan for the site is subject to state law, and therefore, a distinction will be made between the Navy's disposal action and the community's reuse in the following discussion of impacts. Transferring jurisdiction and control of Spanish Housing area from the Department of the Navy to the Department of Transportation, USCG, is not considered an undertaking requiring review and

comment pursuant to Section 106 of the National Historic Preservation Act because the property remains in Federal ownership. That action is discussed in the Cumulative Impacts Section. Table 4-12 summarizes the potential impacts to cultural resources.

Table 4-12
Summary of Cultural Resources Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|---------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Rafael Village | ① | ○ | ① | ① |
| Capehart Housing | ① | ○ | ① | ① |
| Commissary Triangle | ① | ○ | ① | ① |
| Exchange Triangle | ① | ○ | ① | ① |
| Town Center | ① | ① | ① | ① |
| Bowling Alley | ① | ○ | ① | ① |
| Officers' Club | ① | ① | ① | ① |
| Ballfields | ① | ○ | ① | ① |

LEGEND:

- = Significant impact
- ① = Significant and mitigable impact
- = Not significant impact
- = No impact

4.6.1 Disposal

Pursuant to 36 CFR 800.9(b), the transfer, lease or sale of a historic property, eligible for or included on the NRHP, from Federal ownership without adequate restrictions or deed covenants to ensure preservation is an adverse effect and for purposes of NEPA would be a significant impact. The War Department Theater (Building 507), the Amphitheater, the Bachelor Officers' Quarters (Building 201), and the Swimming Pool (Building 205) are the only properties at DODHF Novato where this criteria would be applicable.

The Navy has advised the California SHPO and the Advisory Council on Historic Preservation (ACHP) that it anticipates that the War Department Theater and the Bachelor Officer's Quarters would be transferred to the City of Novato through the National Park Service administered program that permits properties listed on the NRHP to be transferred as Historic Monuments. These buildings may be adaptively reused for commercial purposes. This public benefit conveyance requires that all plans for the adaptive reuse of the property be reviewed and approved by the National Park Service, which assures preservation of the historic property after it is

transferred from Federal ownership. Similarly, the Navy has advised the California SHPO and the ACHP that it anticipates that the Amphitheater and the Swimming Pool would be transferred to the City of Novato through another public benefit conveyance program administered by National Park Service, Surplus Federal Land to Public Parks. The National Park Service will incorporate conditions into the conveyance documents for the Amphitheater and Swimming Pool to assure preservation of the historic characteristic of these facilities. Correspondence regarding these proposed transfers is included in Appendix E. Provided that these properties are transferred under the National Park Service programs, no significant impacts would occur. Should the historic properties not be transferred under the National Park Service programs, the Navy would further consult with the California SHPO and the ACHP pursuant to Section 106 of the National Historic Preservation Act. Provided that these properties are transferred under the National Park Service programs, no significant impacts would occur.

The disposal of DODHF Novato property would not have a significant impact on known prehistoric archeological resources or archeologically sensitive areas. Previously identified archeological sites appear ineligible for inclusion on the NRHP or no longer exist.

4.6.2 Revised Reuse Plan Alternative

Rafael Village

Not Significant Impacts

Two archeological sites had been previously recorded within Rafael Village. These sites have been professionally examined and determined to be no longer extant (Busby et al 1995). Therefore, implementation the Revised Reuse Plan Alternative should not impact any archeological resources included on or eligible for listing on the NRHP.

Nevertheless, the potential for finding previously unknown subsurface archeology may exist. Care should be taken when implementing ground disturbing activities in this area. Should such discoveries occur, work should cease in the vicinity of the discovery until appropriate professional archeologists have had an opportunity to evaluate the discovery and implement an appropriate treatment plan. Such sites are afforded a measure of protection under state law.

Main Site

Not Significant Impacts

Two surface scatters of shells within the Capehart Housing Area were subjected to archeological test excavations and were determined to be naturally-occurring deposits of shell material and not of archeological significance (Busby et al 1995). Implementation of the Revised Reuse Plan Alternative within the Capehart Housing area would not have a significant impact on known archeological resources eligible for or listed on the NRHP. Nevertheless, the potential for finding previously unknown subsurface archeology may exist. Care should be taken when implementing ground disturbing activities in this area. Should such discoveries occur, work should cease in the vicinity of the discovery until appropriate professional archeologists have had an opportunity to evaluate the discovery and implement an appropriate treatment plan. Such sites are afforded a measure of protection under state law.

The only historic properties within the Main Site that qualify for listing on the National Register of Historic Places are the War Department Theater (Building 507) and the Amphitheater in the Town Center planning area, and the Bachelors Officers' Quarters (Building 201) and the Swimming Pool (Building 205) in the Officers' Club planning area. These buildings are proposed for conveyance to the city for historic monument purposes or park and recreation purposes. In both instances the reuse of these properties would be restricted in a manner that assures the continued preservation of those characteristics that qualify them for inclusion on the National Register, thereby avoiding any significant impact.

4.6.3 Open Space Alternative

Under the Open Space Alternative the Rafael Village housing units would be demolished and the land would be reused for parkland instead of residential uses. Reuse of the Main Site planning areas would be similar to reuse activities under the Revised Reuse Plan Alternative.

Not Significant Impacts

Impacts to cultural resources at Rafael Village and the Main Site would be the same as under the Revised Reuse Plan Alternative.

4.6.4 No Action Alternative

The no action alternative would place the facility in caretaker, or inactive, status under federal ownership. On-site activities at buildings in caretaker status would be limited to security, minimal maintenance and those actions associated with caretaker status of surplus property. All buildings and housing units would be closed and secured, and the grounds would be maintained.

Not Significant Impacts

Minimal maintenance would be performed under caretaker conditions to prevent significant deterioration of historic properties. Security would be provided to prevent vandalism and the grounds would be maintained. No actions would be taken that might result in a significant impact to historic properties.

4.7 BIOLOGICAL RESOURCES

This section addresses potential impacts to biological resources that could result from the disposal and proposed reuse of DODHF Novato. Biological resources addressed in this analysis include nonsensitive vegetation and wildlife, sensitive species, and sensitive habitats on DODHF Novato and in surrounding areas.

The determination of significant impacts to biological resources includes direct and indirect impacts. Direct impacts are those in which activities reduce or remove a biological resource, such as the results of construction or grading. Indirect impacts could occur when the activity causes other actions that affect biological resources such as impacts from the introduction of runoff materials into sensitive habitats.

This section provides a description of the region of influence used for biological resources and the criteria for determining whether an action would significantly impact biological resources, followed by a summary of sensitive species and habitats specific to DODHF Novato. Under each alternative, impacts to nonsensitive species and habitats are described first, followed by a discussion of impacts to sensitive species and sensitive habitats.

Region of Influence

The ROI for biological resources includes DODHF Novato and surrounding areas within one-half mile to provide an area large enough to include any species that may use habitats on DODHF Novato but small enough to not include species that regularly use habitats not found within DODHF Novato.

Significance Criteria

Impacts to biological resources would be considered significant if they result in harassment or removal of any endangered or threatened species (including proposed species), their habitat, migration corridors, or breeding areas. Impacts to other sensitive species considered Species of Concern by USFWS, California species of special concern, or California Native Plant Society (CNPS) listed species would be considered significant if a substantial number of individuals or large areas of habitat could be affected. The loss of a substantial number of individuals of any native plant or animal species that could affect abundance or diversity of that species beyond normal variability also is considered significant. Any impacts to sensitive habitats may be considered significant. Table 4-13 summarizes impacts to biological resources from disposal and reuse alternatives.

Table 4-13
Summary of Biological Resource Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|-------------------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Nonsensitive Species/Habitats | ○ | ○ | ⊖ | ⊖ |
| Sensitive Species | ○ | ○ | ● | ● |
| Sensitive Habitats | ○ | ○ | ● | ● |

LEGEND:

- = Significant impact
- ◐ = Significant and mitigable impact
- ⊖ = Not significant impact
- = No impact

Sensitive Species/Sensitive Habitats

The sensitive species and sensitive habitats environmental consequences are combined because most the sensitive species indicated on Table 4-13 that may be affected by disposal or any of the alternatives inhabit riparian (streamside) and other sensitive habitats at DODHF Novato.

Sensitive species for which habitat is available at DODHF Novato and that inhabit the ROI are listed in Table 4-14 (as discussed in Section 3.7, Biological Resources). The tidewater goby, chinook salmon, longfin smelt, foothill yellow-legged frog, and Cooper's hawk could be supported by the creeks and riparian corridors within the ROI. The dwarf downingia, fragrant fritillary, Baker's navarettia, Mount Tamalpais jewelflower, burrowing owl, California horned lark, and loggerhead shrike could inhabit the grasslands and oak woodlands at DODHF Novato. The three sensitive bat species in the region, the pallid bat, Townsend's western big-eared bat, and California mastiff bat, could inhabit the vacant buildings within DODHF Novato.

Sensitive habitats at and adjacent to DODHF Novato include those protected by CDFG— riparian habitats, valley oak woodlands, freshwater marsh, and California bay forest. Riparian habitats and freshwater marsh are wetlands that could be under the jurisdiction of the US Army Corps of Engineers (COE) as discussed in Section 3.7. Of the sensitive habitats within the ROI, only riparian (streamside) habitats, other wetlands (drainage ditches), and valley oak woodlands exist on DODHF Novato while freshwater marsh and California bay woodlands exist in adjacent areas. Riparian habitats, other wetlands (drainage ditches), and valley oak woodlands also exist in adjacent areas.

Table 4-14
Sensitive Species that May Exist Within the ROI

| Common Name | Scientific Name | Federal/State/ CNPS Status |
|-----------------------------------|--|-------------------------------|
| Endangered and Threatened Species | | |
| tidewater goby | <i>Eucyclogobius newberryi</i> | E/CSC/none |
| winter-run chinook salmon | <i>Oncorhynchus tshawytscha</i> | E/E/none |
| California red-legged frog | <i>Rana aurora draytonii</i> | T/CSC/none |
| Other Sensitive Species | | |
| dwarf downingia | <i>Downingia pusilla</i> | C3c/none/2 |
| fragrant fritillary | <i>Fritillaria liliacea</i> | SC/none/1B |
| Baker's navarretia | <i>Navarretia leucocephala</i> ssp. <i>bakeri</i> | none/none/1B |
| Mount Tamalpais jewelflower | <i>Streptanthus glandulosus</i> var. <i>pulchellus</i> | C3c/none/1B |
| longfin smelt | <i>Spirinchus thaleichthys</i> | SC/CSC/none |
| foothill yellow-legged frog | <i>Rana boylei</i> | SC/CSC/none |
| Cooper's hawk | <i>Accipiter cooperi</i> | none/CSC/none |
| burrowing owl | <i>Athene cunicularia</i> | none/CSC/none |
| California horned lark | <i>Eremophila alpestris</i> | SC/CSC/none |
| loggerhead shrike | <i>Lanius ludovicianus</i> | SC/CSC/none |
| pallid bat | <i>Antrozous pallidus</i> | SC/CSC/none |
| Townsend's western big-eared bat | <i>Plecotus townsendii townsendii</i> | SC/CSC/none |
| California mastiff bat | <i>Eumops perotis californicus</i> | SC/CSC/none |

Source: CDFG 1994, 1995, 1996a, 1996b, 1996c; US Fish and Wildlife Service 1994a, 1994b, 1995a, 1995b, 1995c, 1996

E - Endangered

T - Threatened

SC - Species of Concern

C3c - Removed from the list

CSC - California Species of Special Concern

1B - Plants rare and endangered in California and elsewhere

2 - Plants rare and endangered in California but more common elsewhere

CNPS - California Native Plant Society

Areas of No Impact

Rafael Village, Capehart Housing, and adjacent areas are the only portions of DODHF Novato that contain native habitats. Commissary Triangle, Exchange Triangle, Town Center, Bowling Alley, Officers' Club, and the Ballfields contain only developed, paved, regularly mowed, or landscaped areas that sustain almost no native vegetation or wildlife and would not experience adverse effects from disposal or any of the alternatives.

4.7.1 Disposal

Nonsensitive Species/Nonsensitive Habitats*No Impacts*

No impacts to nonsensitive species or habitats would result from disposal. Federal property disposal would transfer DODHF Novato from federal ownership but would not result in significant impacts to nonsensitive species and habitats. The new property owner would be subject to federal, state, and local environmental regulations regarding these resources as discussed in Section 3.7.

Sensitive Species/Sensitive Habitats*No Impacts*

No impacts to sensitive species or habitats would result from disposal. The action of transferring DODHF Novato out of federal ownership would have no effect on the protection of the California red-legged frog, a threatened species that may be present in the ROI. This species was not observed at DODHF Novato during spring and summer surveys (US Navy 1996b). The US Fish and Wildlife Service and the National Marine Fisheries Service have concurred that this project is not likely to adversely impact endangered species (see Appendix F).

4.7.2 Revised Reuse Plan Alternative

Nonsensitive Species/Nonsensitive Habitats*Not Significant Impacts*

No significant impacts are expected to nonsensitive species or habitats from the Revised Reuse Plan Alternative. Any construction or demolition activities would occur in previously developed or landscaped areas and would not result in the substantial reduction of any nonsensitive species or habitats.

Sensitive Species/Sensitive Habitats*Significant Impacts*

Impact 1. Increased erosion could result in a significant and mitigable impact to sensitive wetland and riparian habitats in San Jose Creek adjacent to the southern boundary of Rafael Village and other wetlands habitats. Demolition and construction activities at DODHF Novato, particularly at Rafael Village, would increase the potential for erosion at the site. Sensitive species that may inhabit these areas include the tidewater goby, chinook salmon, longfin smelt,

foothill yellow-legged frog, and Cooper's hawk. No buffer area exists between Rafael Village and Capehart Housing and adjacent riparian habitats except a chainlink fence. Erosion could increase sedimentation in creeks and degrade the quality of riparian habitat. If this habitat is degraded, indirect impacts to sensitive species that could inhabit the creek and riparian habitat may occur. For example, the foothill yellow-legged frog requires slow-moving water with aquatic vegetation in which to lay egg masses. Increased sedimentation could affect the amount of aquatic vegetation in the creek and reduce the number of possible breeding locations for sensitive species.

Mitigation 1. Implementation of standard erosion control measures to minimize sedimentation into creeks and other wetlands during new construction as described in Section 4.9.2, Water Resources, would prevent significant impacts to sensitive species and habitats. Protect off-site areas (including streams and riparian areas) from potential erosion from adjacent bared areas by use of silt fences, staked straw bales, sedimentation basins, and other appropriate structural methods.

Sensitive Habitats

Not Significant Impacts

No significant impacts would be expected in the upland sensitive habitats (valley oak woodland and California bay forest) in and near DODHF Novato. Reuse activities would not occur within these areas and the existing uses of these areas would not change. Additionally, the number of people living near or using these habitats within the ROI is not expected to increase substantially.

4.7.3 Open Space Alternative

Nonsensitive Species/Nonsensitive Habitats

No Significant Impacts

As discussed under the Revised Reuse Plan Alternative, no significant impacts are expected to nonsensitive species or habitats from the Open Space Alternative. Beneficial impacts to nonsensitive species could occur from the addition of open space in the Rafael Village and Ballfields areas.

Sensitive Species/Sensitive Habitats

Significant Impacts

Impact 1. Increased erosion could result in a significant and mitigable impact to sensitive wetland and riparian habitats as discussed under the Revised Reuse Plan Alternative.

Mitigation 1. Implement erosion control procedures as discussed under the Revised Reuse Plan Alternative.

Sensitive Habitats

Not Significant Impacts

No significant impacts would be expected in the upland sensitive habitats in and near DODHF Novato as discussed under the Revised Reuse Plan Alternative. Beneficial impacts to sensitive species as well as nonsensitive native species could occur if active revegetation of native plant species in new open space areas provided more native habitat acreage within the ROI.

4.7.4 No Action Alternative

No Impacts

No impacts would be expected to occur to nonsensitive species, sensitive species, or sensitive habitats under the No Action Alternative with DODHF Novato in federal caretaker status.

4.8 GEOLOGY AND SOILS

The principal geologic concerns at the site are potential failure of some hillslopes on the northern boundary of Rafael Village, seismic hazards associated with ground shaking and lateral spreading, and potential erosion during construction.

Region of Influence

Potential geological effects from the proposed action would be localized; therefore the ROI for the geological impacts of the proposed action includes the land within the boundaries of DODHF Novato and immediately adjacent lands.

Significance Criteria

A project may result in a significant geologic impact if it exposes people or structures to major geologic hazards (such as slope failure, liquefaction, and ground shaking), limits the recovery of mineral resources, results in a loss of prime agricultural land, causes substantial soil erosion, or adversely affects unique geologic or topographic features. Table 4-15 summarizes the geology and soils impacts resulting from the Revised Reuse Plan Alternative and other alternatives.

Table 4-15
Summary of Geologic and Soils Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|-------------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Slope stability hazards | ○ | ○ | ◐ | ◑ |
| Soil erosion | ○ | ○ | ◑ | ◑ |
| Seismic hazards | ○ | ○ | ◐ | ◐ |

LEGEND:

- - Significant impact
- ◐ - Significant and mitigable impact
- ◑ - Not significant impact
- - No impact

4.8.1 Disposal

No Impacts

Disposal of DODHF Novato would not result in any geologic impacts. Disposal would involve the transfer of DODHF Novato out of Navy jurisdiction. In this analysis, geologic impacts would depend only on physical conditions, not on jurisdiction or legal context.

4.8.2 Revised Reuse Plan Alternative

Slope Stability Hazards

Significant Impacts

Impact 1. A potentially significant and mitigable impact could occur if demolition and new construction in Rafael Village undermines or weakens unstable slopes. Slope stability has not been identified as a concern in existing developed areas at the Main Site.

Mitigation 1. Prior to approval of detailed demolition and construction plans, site-specific geotechnical investigations would be conducted to identify potential geologic hazards that may affect new building sites. Geotechnical investigations are currently required in compliance with the City of Novato General Plan (Health and Safety Policy 16, HS-8) in areas showing landslide potential. Two such areas have been identified adjacent to Rafael Village. This policy should be extended to other areas at DODHF Novato covering or creating slopes in excess of 15 percent. A geotechnical engineer should review design plans and details and other improvement plans to determine whether they are compatible with the geotechnical conditions of the site. A geotechnical engineer and engineering geologist would inspect the site grading and document placement of engineered fills, stability of cut and fill slopes, and placement of subdrains. Application of site-specific recommendations of a geotechnical engineer and engineering geologist would reduce this potentially significant impact to a not significant level.

Seismic Hazards

Significant Impacts

Impact 2. A significant and mitigable impact could result if existing and proposed improvements in certain Main Site areas, particularly those on reclaimed land underlain by imported fill and bay mud, but also in areas underlain by alluvium, were exposed to potentially damaging levels of ground shaking during a large earthquake centered on one of the three nearest active

faults. Portions of some of the planning areas east of US 101, within the historical margin of San Francisco Bay, may be subject to lateral spreading in response to seismic shaking during a strong earthquake. In addition, areas underlain by sandy soils, where a shallow water table is present, or during periods of ground saturation due to rainfall or poor drainage, may undergo liquefaction during a strong earthquake. Areas of greatest concern include Town Center and the Bowling Alley, because they are underlain by imported fill and because they contain a number of existing or planned large public occupancy buildings.

Mitigation 2a. Existing Structures. An evaluation of the ability of existing structures to withstand site-specific seismic forces should be performed to identify structures that should be upgraded to reduce the potential for injury, loss of life, or economic damage. The evaluation should target all buildings intended for public occupancy, as well as other structures representative of the range of building types. The cost of upgrading the structures to meet existing building codes should be compared with the cost of replacement, and upgrade or replacement should be made a prerequisite of occupancy.

Mitigation 2b. Road and Utilities. Roads and utilities should be evaluated to determine if upgrades are needed to reduce safety hazards and to maintain emergency services after a strong earthquake.

Mitigation 2c. New Construction. All new construction should be designed to meet applicable building codes. A geotechnical engineer should review design plans and details and other improvement plans to determine whether they are compatible with the geotechnical conditions of the site.

Mitigation 2d. Zoning. Zoning to limit construction in areas subject to strong ground motion should be considered by the City of Novato. Implementation of the above recommendations of site-specific evaluations and applicable building codes would reduce this potential impact to a not significant level.

Soil Erosion

Not Significant Impacts

Under the Revised Reuse Plan Alternative there would be potential for soil erosion in the Rafael Village area during demolition, building removal, and the construction period, though this would not result in significant impacts. During this period land would be exposed to the erosional forces of wind and surface water runoff. While not significant, this could be reduced by implementing standard erosion control measures during demolition and construction, conducting demolition and construction activities during the dry

portion of the year, and reestablishing vegetation as quickly as possible following construction.

4.8.3 Open Space Alternative

This alternative proposes to convert Rafael Village to open space and parkland. This would eliminate the geologic impacts associated with Rafael Village structures that were identified for the Revised Reuse Plan Alternative. Converting the area to open space would require removal of structures and most paved areas. On the Main Site, uses proposed for the Exchanged Triangle and Commissary Triangle areas would be rearranged.

Seismic Hazards

Significant Impacts

Impact 1. Significant and mitigable seismic hazard impacts are expected to be generally the same for the Main Site under the Open Space Alternative as described for the Revised Reuse Plan Alternative.

Mitigation 1. The mitigation measures would be the same as under the Revised Reuse Plan Alternative.

Soil Erosion, Slope Stability, Seismic Hazards

Not Significant Impacts

The potential for soil erosion would be greater than under the Revised Reuse Plan Alternative in the Rafael Village area under this alternative, though still not significant. During demolition and building removal more land would be exposed to the erosional forces of wind and surface water runoff. Though not significant, this could be reduced by contouring the ground surface to reduce flow velocities and to promote percolation. After vegetation becomes established there would be less impervious cover, which would allow greater infiltration of surface water runoff.

Rafael Village slope stability and seismic hazard issues would not be significant impacts under the Open Space Alternative.

4.8.4 No Action Alternative

No Impacts

Under the No Action Alternative seismic impacts to structures or infrastructure at DODHF Novato from earthquakes could still occur.

4.8 Geology And Soils

However, no impacts would result because the potential for injuries or loss of life would be minimal since only a small caretaker population would be present at DODHF Novato at any given time.

Since no construction activity would occur under the No Action Alternative, slope stability would not be a concern.

4.9 WATER RESOURCES

This section presents an analysis of the impacts of the Revised Reuse Plan Alternative and of the other alternatives on water resources. Issues examined include stormwater runoff, surface water quality, and flooding potential. All impacts are analyzed against conditions existing at DODHF Novato in 1995.

Region of Influence

The ROI is limited to the immediate DODHF Novato environs and surrounding water bodies (Novato Creek, western San Pablo Bay, and adjacent wetlands areas).

Significance Criteria

A project may have a significant impact on water resources if it causes substantial flooding or erosion, if it adversely affects drainage patterns or any water body such as a stream, lake, or bay, if it exposes people to reasonably foreseeable hydrologic hazards such as flooding or tsunamis, or if it adversely affects surface or ground water quality or quantity. The 100-year recurrence interval for flood plains, tsunami runup, and tidal flood hazards is used as the significance criteria for those aspects of this study. Table 4-16 summarizes potential impacts to water resources and their significance.

Table 4-16
Summary of Water Resources Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|-------------------------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Ground Water Quality | ○ | ○ | ⊖ | ⊖ |
| Surface Water Quality | ○ | ○ | ● | ● |
| Effects to Drainage or Water Bodies | ○ | ○ | ⊖ | ⊖ |
| 100-year Flood Hazards | ○ | ○ | ● | ○ |
| Street Flood Hazards | ○ | ⊖ | ● | ⊖ |

LEGEND:

- = Significant impact
- ⊖ = Significant and mitigable impact
- ⊖ = Not significant impact
- = No impact

Planning Issues

Any new development resulting from reuse in the planning areas would be required to comply with the city's development requirements. As described in Section 4.5, deficient storm drainage systems would need to be upgraded to accommodate runoff from a storm with a 25-year recurrence interval as assumed in the Reuse Plan. Except where new construction is proposed, the project would not undertake this upgrade. Storm drainage upgrade issues are addressed in Section 4.5. In conformance with city policy, off-site flow characteristics would not be adversely altered as a result of project improvements. The project, with mitigation recommended in this section, would not adversely affect existing stream, wetland, or riparian areas, or water quality and would, therefore, comply with Novato General Plan policies promoting the protection of these areas and preserving water quality. The project would not exacerbate any existing on- or off-site flood hazards; however it would not limit existing flooding of project areas not subject to redevelopment. Therefore, it would only partially comply with the city policy of controlling flood hazards.

Development in mapped flood areas in the Commissary Triangle and Exchange Triangle would need to be raised or otherwise protected from flood hazards in order to comply with city and county policies and standards. The city would review the site for flood zone applicability after acquisition of the site from the Navy.

The Revised Reuse Plan Alternative and other alternatives would comply with all applicable state and federal policies identified in Section 3.9, Water Resources, assuming all required permits were obtained.

4.9.1 Disposal**Rafael Village***No Impacts*

Navy disposal would not result in any impacts to hydrologic or water quality conditions on the site. As noted above, under Planning Issues, the site would fall under the jurisdiction of the City of Novato and the Marin County Flood Control and Water Conservation District (MCFCWCD). Conformance with the City's policies is described above.

Main Site

No Impacts

Navy disposal would not result in any impacts to hydrologic or water quality conditions on the site. As noted above, under Planning Issues and Processes, the site would fall under the jurisdiction of the City of Novato and the MCFCWCD. Conformance with those local agencies' policies is described in that section above.

4.9.2 Revised Reuse Plan Alternative

Implementation of the Revised Reuse Plan Alternative would not result in substantial flooding, would not adversely affect any water body, nor would substantially affect ground water quality. Existing development on lower elevation areas of the Main Site would be subject to significant tidal flood hazards, which could become more severe with projected rise in sea level. This is mitigable through dikes, pumps, and other measures recommended in this section. Creekside and storm drain overtopping also could affect buildings and streets. These existing problems are assessed in Section 4.5, Utilities. Grading, demolition, and development could potentially increase erosion at those sites and are mitigable through erosion control measures.

Rafael Village

Significant Impacts

Impact 1. Significant and mitigable impacts could result from grading, demolition, and construction of new houses by disturbing the soil and increasing erosion/sedimentation into San Jose Creek, affecting surface water quality. These impacts would be mitigable below the level of significance by careful compliance with the National Pollutant Discharge Elimination System (NPDES) stormwater permit for the base, which includes requirements for a Storm Water Pollution Prevention Plan (SWPPP) that, in turn, is required to include erosion control plans.

Mitigation 1. Develop erosion control plans consistent with the SWPPP prior to any site clearing or grading. Protect off-site areas (including streams and riparian areas) from potential erosion from adjacent bared areas by use of silt fences, staked straw bales, sedimentation basins, and other appropriate structural methods. Where necessary, erosion control structures should be in place prior to the start of the rainy season (October 15) and should remain in place through the end of that season (April 15). The SWPPP should include a Best Management Practices (BMP) program for stormwater collection as part of the reuse project. The BMP program should focus on the following:

- Containing and controlling land use activities to prevent the generation of pollutants that might affect water quality;
- Preventing and controlling stormwater runoff; and
- Retaining and treating runoff on-site before it infiltrates the ground water or is released into the bay.

Where appropriate, nonstructural BMPs should be given preference over structural BMPs. The BMP program should use management measures and practices identified by the EPA in the Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters and the California Storm Water Best Management Practice Handbook. The BMP program should be consistent with the requirements of the State Water Resources Control Board and the RWQCB.

Impact 2. Significant and mitigable impacts could result if new Rafael Village area houses are developed in mapped 100-year floods from San Jose Creek, subjecting those houses to potential flood hazards. Currently, no Rafael Village housing units are sited in the mapped 100-year floodplain.

Mitigation 2. Limit development of new houses to outside the mapped 100-year flood plain of San Jose Creek.

Impact 3. Significant and mitigable impacts could result from the existing storm drain system, which was designed to handle a 10-year recurrence interval rainfall, being inconsistent with the City of Novato's 25-year recurrence interval standard. Localized street flooding could occur if the storm drain system were not upgraded to city standards.

Mitigation 3. During redevelopment of Rafael Village, the City of Novato shall require upgrading of all project area storm drains to meet the current city standard of a 25-year recurrence interval rainfall.

Not Significant Impacts

No significant impacts to ground water would result from this alternative. Implementation of the Revised Reuse Plan Alternative for Rafael Village would not substantially alter ground water quantity underlying the site. The Revised Reuse Plan Alternative would not increase the use of local ground water on the site. Infiltration of precipitation into the upper ground water layer would not be substantially affected by implementation of the Revised Reuse Plan Alternative. It also would not affect ground water flows underlying the site.

No significant erosion impacts would occur under this alternative. The Revised Reuse Plan Alternative would involve reuse of the existing developed area and would not increase impervious surfaces or surface runoff quantities at Rafael Village.

Construction equipment and operations may result in spills and other accidental emissions of pollutants that could enter and contaminate San Jose Creek and downstream receiving waters. This impact is not considered significant, as a spill control and countermeasure plan is required to be included in the SWPPP.

Main Site

Significant Impacts

Impact 4. Significant and mitigable impacts could result from grading, demolition, and construction of new buildings in any of the Main Site planning areas from soil disturbance and increased erosion/sedimentation into Pacheco Creek and downstream in Ignacio Reservoir, Novato Creek, and San Pablo Bay. Reuse of the Main Site would add urban pollutants such as oil, grease, fertilizers, and pesticides to the local runoff. Although some input of these contaminants currently is occurring, it could be increased upon reuse. These impacts would be mitigable below the level of significance by careful compliance with the NPDES stormwater permit for the base, which includes requirements for a SWPPP that, in turn, is required to include erosion control plans.

Mitigation 4. Develop erosion control plans consistent with the SWPPP prior to any site clearing or grading. Protect off-site areas (including streams and riparian areas) from potential erosion from adjacent bared areas by use of silt fences, staked straw bales, sedimentation basins, and other appropriate structural methods. Where necessary, erosion control structures should be in place prior to the start of the rainy season (October 15) and should remain in place through the end of that season (April 15). The SWPPP should include a BMP program for stormwater collection as part of the reuse project. The BMP program should focus on the following:

- Containing and controlling land use activities to prevent the generation of pollutants that might affect water quality;
- Preventing and controlling stormwater runoff; and
- Retaining and treating runoff on-site before it infiltrates the ground water or is released into the bay.

Where appropriate, nonstructural BMPs should be given preference over structural BMPs. BMPs should include grassy swales, detention ponds, and landscaping that will detain and treat water contaminated with urban pollutants. The BMP program should use management measures and practices identified by the EPA in the Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters and the California Storm Water Best Management Practice Handbook. The BMP program should be consistent with the requirements of the State Water Resources Control Board and the RWQCB.

Impact 5. Significant and mitigable impacts could result if development and reuse of Commissary Triangle and the Exchange Triangle subjected residents, workers, and other occupants of those areas to flood hazards in the event of a 100-year flood on Pacheco Creek. Development and reuse of portions of the Town Center, Bowling Alley, Officers' Club, and Ballfields areas could subject residents, workers, and other occupants of those areas to flood hazards in the event of pump failure coincident with the 100-year flood, 100-year high tide, or the combination of these events with storm surges. In addition, a sea level rise of approximately three inches is projected for the San Francisco Bay area by the year 2025 (based on historical trends) (ESA Associates, Inc. 1993). This rise in sea level could marginally increase the frequency of tidal and nontidal flooding on the site. This potentially significant impact is mitigable by implementation of the measures identified below.

Mitigation 5a. Reuse of planning areas subject to 100-year flood hazards shall not occur until after completion of the planned new levees west of the airfield. Development should be set back from those levees a sufficient distance, as determined by the City of Novato, to allow for levee maintenance and raising as required to account for projected rise in sea level and settlement of underlying muds.

Mitigation 5b. As an alternative to levee protection, any new development at sites below 10 feet (msl) should be protected from flooding by raising the base level of developed areas of the site to a minimum of 10 feet (msl). This elevation may be revised as appropriate, based on the refinements of estimates of the effects of sea level rise in combination with storm surges. In addition, any new development should comply fully with the city's Flood Damage Protection Ordinance. All 100-year floodplains on the site should be incorporated into the city's flood hazard zoning maps.

Mitigation 5c. As identified in the NHP project EIR, the levees shall be fitted with redundant pumping systems and an emergency power supply to assure that adjacent low-lying areas are not flooded in the 100-year storm in the event of a power interruption or pump failure. The Ballfields area is part of the emergency retention area for backed up storm water in the event of a pump

failure. This area should remain in open space or undeveloped recreational use to assure adequate emergency flood storage area.

Impact 6. Significant and mitigable flood hazard impacts could occur if constrictions in the drainage facilities downstream of Main Gate Road resulted in flooding of the Exchange Triangle area and adjacent lands along Pacheco Creek immediately upstream of that area during 100-year storm events.

Mitigation 6. The deficient drainage facilities downstream from the Exchange Triangle and Main Gate Road should be replaced and expanded as necessary to convey 100-year flood flows concurrent with the redevelopment of the Exchange Triangle area. Specific required drainage improvements should be determined by the city Public Works Department.

Not Significant Impacts

No significant impacts to ground water would result from this alternative. Implementation of the Revised Reuse Plan Alternative for the Main Site would not substantially alter ground water quantity underlying the site. The Revised Reuse Plan Alternative would not affect the use of local ground water on the site. Infiltration of precipitation into the ground water would not be affected substantially by implementation of the Revised Reuse Plan Alternative. It also would not affect ground water flows underlying the site.

No significant erosion impacts would result under this alternative. The Revised Reuse Plan Alternative would involve reuse of existing developed areas on the base and would not increase impervious surfaces, surface runoff, or flooding in any of the planning areas. It should be noted that the existing storm drain system is inadequate to handle existing runoff from the base in storm events exceeding the 10-year storm. The storm drain system is discussed in detail in Section 3.5 of this document. Downstream drainage and flooding would not be adversely affected by the project. Downstream areas would be protected by levees, pumps, and expanded drainage systems approved and under construction as part of the NHP and Hamilton Army Airfield reuse projects.

Construction equipment and operations may result in spills and other accidental emissions of pollutants that could enter and contaminate the surrounding water bodies. This impact is not considered significant, as a spill control and countermeasure plan is required to be included in the SWPPP.

The Revised Reuse Plan Alternative would not require culverting or clearing of streams, wetlands, or riparian areas or otherwise adversely affect any wetland or riparian areas.

4.9.3 Open Space Alternative

Rafael Village

Significant Impacts

Impact 1. Significant and mitigable surface water quality impacts from erosion could occur during the demolition of existing houses.

Mitigation 1. Same as identified for the Revised Reuse Plan Alternative, plus implementation of a revegetation/restoration program for the entire area reverting from residences to open space.

Not Significant Impacts

All of the impacts described as not significant under the Revised Reuse Plan Alternative also would be not significant under this alternative. In addition, the Open Space Alternative would involve demolition of the existing structures and conversion of the 107-acre residential area to open space. This reduction in impervious surfaces and resulting reduction in runoff would be a significant beneficial impact with respect to flooding on San Jose Creek and downstream, including helping to reduce flooding along San Jose Creek near Ignacio Pond. There would be no flood hazards to houses at Rafael Village under this alternative. The existing storm drain system at Rafael Village would not need to be upgraded.

Main Site

Reuses identified for the Main Site under the Open Space Alternative are generally similar to the Revised Reuse Plan Alternative. The primary differences in the land uses between this alternative and the Revised Reuse Plan Alternative are different permitted uses at the Commissary Triangle and Exchange Triangle areas, and the loss of two acres of parkland at the Town Center. None of these changes would materially affect hydrologic or water quality impacts. For this reason, all of the impacts and mitigations identified for the Main Site under the Revised Reuse Plan Alternative also would be applicable to the Open Space Alternative, as summarized below.

Significant Impacts

All of the significant and mitigable hydrologic, water quality, and storm drainage impacts described for the Main Site under the Revised Reuse Plan Alternative also would occur under this alternative. Mitigation measures for this alternative would be identical to those identified above for the Rafael Village portion of the Revised Reuse Plan Alternative.

Not Significant Impacts

All of the impacts described for the Main Site as not significant under the Revised Reuse Plan Alternative also would be not significant under this alternative.

4.9.4 No Action Alternative

Rafael Village

This alternative would not result in any significant impacts to hydrology or water quality on the Rafael Village site.

Not Significant Impacts

The existing storm drain system was designed to handle a 10-year recurrence interval rainfall, which is inconsistent with the City of Novato's 25-year recurrence interval standard. Localized street flooding would result if the storm drain system were not upgraded to city standards. This impact would be not significant because Rafael Village would remain vacant.

Main Site

This alternative would not result in any significant impacts to hydrology or water quality on the Main Site.

Not Significant Impacts

The No Action Alternative would not significantly impact hydrology or water quality at the Main Site. Intermittent flooding would continue to affect structures on low-lying areas of the site. These areas include portions of the Capehart Housing, Exchange Triangle, and Commissary Triangle planning areas, which would remain in federal caretaker status. Therefore, this would not be a significant impact. Periodic Ballfield flooding would continue but is not considered a significant impact. Removal of most vehicular traffic from the site under caretaker status would slightly decrease oil and grease in runoff from roads on the site and could result in slightly improved water quality.

4.10 TRAFFIC AND CIRCULATION

This section presents an analysis of the impacts of the Revised Reuse Plan Alternative and the other alternatives on local and regional traffic and circulation. The alternatives were analyzed in conjunction with assumed development in the City of Novato and the DODHF Novato planning areas through 2015. Impacts are evaluated based on effects to the Level of Service (LOS) on regional freeway segments and local intersections.

Consistent with the significance criteria, impacts have been identified whenever project traffic results in deterioration of LOS below acceptable levels or results in exacerbation of an existing unacceptable condition. In many cases, the traffic impacts are less significant under the Revised Reuse Plan Alternative and other alternatives than they would be for cumulative conditions under the presumed buildout of DODHF Novato under the city's Preferred General Plan. This is because the Revised Reuse Plan Alternative and other alternatives would generate fewer vehicle trips than projected vehicle trips for DODHF Novato under the Preferred General Plan.

Several areas of regional and local traffic currently are operating below acceptable levels or are projected to do so based on regional growth not associated with implementation of any of the alternatives. Section 5.1, Cumulative Impacts, presents an analysis of cumulative conditions and also describes improvements that would be required within the area in order to improve intersections to acceptable levels (LOS D or better). Because it would be speculative to assume that these improvements will be made, this analysis assumes that they will not be made and therefore identifies intersections operating below acceptable levels. If the improvements described in Section 5.1 were implemented, intersection service levels would be improved to acceptable levels under cumulative conditions (Preferred General Plan). Intersections also would operate at acceptable service LOS for the Revised Reuse Plan Alternative and other alternatives.

Previous traffic analyses performed in this area have shown that local traffic conditions generally can be mitigated through sometimes expensive, but still feasible, improvements, but regional impacts have been shown to be unmitigable. The primary reason for this finding has been that political and financial constraints make improving regional traffic facilities difficult.

Region of Influence

The ROI for this traffic analysis includes regional freeway (US 101 and State Route 37) and transit systems because regional access to the project site is provided primarily by these traffic links. The ROI also includes local access routes, as well as the City of Novato's street system, because of their potential

to be impacted by the project. The ROI for traffic and circulation analysis is shown in Figure 3-16.

Significance Criteria

Traffic Impacts - The City of Novato has established LOS D as the standard for the lowest (worst) acceptable service level. A significant impact would result if an LOS deteriorates below LOS D or if the Volume to Capacity (VC) ratio on a link or intersection currently experiencing LOS E or F conditions deteriorates as a result of the Revised Reuse Plan Alternative or other alternatives.

Transit Impacts - Transit impacts are identified if access to transit is not provided to all areas of the site. For the purposes of assessing accessibility, one-quarter of a mile is used as the distance that transit users will walk to a transit station/stop.

Pedestrian and Bicycle Impacts - These impacts are identified if safe, continuous, and connective nonmotorized facilities are not provided.

Table 4-17 summarizes the traffic impacts and their level of significance per implementation of each of the alternatives.

Table 4-17
Summary of Traffic and Circulation Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|------------------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Local Intersection Impacts | ○ | ○ | ⊖ | ⊖ |
| Regional Freeway Impacts | ○ | ○ | ⊖ | ⊖ |
| Transit Impacts | ○ | ○ | ● | ● |
| Pedestrian & Bicycle Impacts | ○ | ○ | ○ | ○ |

LEGEND:

- - Significant impact
- ⊖ - Significant and mitigable impact
- ⊖ - Not significant impact
- - No impact

Assumptions and Methodology

In order to assess the impacts of the Revised Reuse Plan Alternative and other alternatives on local and regional traffic conditions, it was necessary to make some assumptions about expected cumulative development within the City of Novato and the project vicinity in 2015. The City of Novato recently

completed a General Plan update, and the assumptions used in this analysis are consistent with the Preferred General Plan scenario in the updated General Plan. Future background traffic volume assumptions from the Novato General Plan Revision Transportation Background Report #3 (W-Trans, Inc. 1995) were used.

Future Transportation Network

For the purpose of this analysis, future background traffic conditions have been projected assuming implementation of local intersection and roadway improvements as identified in the NHP Master Plan. These improvements include the following:

- Adding a new loop on-ramp to intersect with Nave Drive at the existing US 101 northbound off-ramp just south of Ignacio Boulevard;
- Reconfiguring the intersection of Ignacio Boulevard at Nave Drive/US 101 on-ramp to eliminate the eastbound left turn and to add an exclusive eastbound right-turn lane to tie the intersection with the new loop on-ramp;
- Increasing the sight distance at the southbound off-ramp on Enfrente Boulevard;
- Extending the auxiliary lane on US 101 from the Enfrente Boulevard southbound off-ramp to the US 101 loop off-ramp to Ignacio Boulevard;
- Performing significant improvements to Nave Drive, including providing additional turns lanes at intersections, and providing continuous channelization, bicycle lanes, and bus turnout areas; and
- Signalizing the intersections of Nave Drive at New Loop Road, Nave Drive at State Access Road, Nave Drive at Main Gate Road, Nave Drive at Bolling Drive, and Alameda del Prado at Clay Court.

In addition to the above improvement assumptions, transportation improvements also have been identified in the Preferred General Plan scenario of the city's Updated General Plan. These improvements include widening US 101 north of Atherton Avenue (into Sonoma County) to six lanes providing and further improvements to the intersection of Ignacio Boulevard at Nave Drive/US 101 on-ramp (restripe one eastbound through-lane to a shared right/through-lane).

A traffic model of the DODHF Novato Main Site and the Ignacio Areas (Rafael Village) was constructed in 1995 to accurately assess future traffic conditions based on assumptions made in the Preferred General Plan scenario,

the New Hamilton Partnership Master Plan, USCG use of the Spanish Housing area, and the alternatives identified in the Reuse Plan. The model includes regional connections (US 101 and State Route 37) to DODHF Novato and contains about 50 traffic analysis zones (TAZs). Roughly half of the TAZs are used to subtract traffic generation associated with military uses from the traffic network, and the other half are used to introduce the new traffic generated by each of the alternatives to the network.

Trip Generation

DODHF Novato historically generates approximately 1,024 vehicle trips during the AM peak hour and 1,727 trips during the PM peak hour. These estimates were derived based on trip generation surveys taken at existing land uses and on standard industry trip rates for various uses. Adjustment factors were applied to standard trip rates for nonresidential land uses to reflect the fact that military nonresidential uses do not generate as many vehicle trips as civilian comparables. For example, the commissary, which is a grocery store for military personnel, generates about half the number of trips that a civilian grocery store of the same size would generate. AM and PM peak hour trip rates, sources, and reduction factors for both current military land uses and proposed uses under the Revised Reuse Plan Alternative are shown in Table G-5 in Appendix G. Trip generations associated with the Revised Reuse Plan Alternative and each of the other alternatives are summarized in Table 4-18 and discussed later in this section.


Table 4-18
Net New Trip Generation Summary for All Alternatives¹

| Alternative | Net New Trip Generation | |
|--------------------------------|-------------------------|--------------|
| | AM Peak Hour | PM Peak Hour |
| Revised Reuse Plan Alternative | 144 | (84) |
| Open Space Alternative | (55) | (269) |
| No Action Alternative | (805) | (1,448) |

¹Note: (xxx) - represents trips lost as a result of base conversion. Negative generations indicate that the previous military uses generated more vehicle trips than the proposed uses.

Trip Distribution

Assignment of trip distribution within the ROI is based on the same assumptions used by the Marin County Congestion Management Agency (CMA) Model for residential and nonresidential uses. This is consistent with the trip distribution assumptions used by the City of Novato in preparing its traffic analysis of the Preferred General Plan scenario. Trip distribution assumptions are shown in Figure 4-1 and Table G-6.



Trip distribution assumptions are based on assumptions used by the Marin County Congestion Management Agency Model for residential and nonresidential uses.

Trip Distribution Assumption

DOD Housing Facility
Novato, California

Figure 4-1

Traffic Assignment

Traffic assignment assumptions were derived based on the shortest path analysis. The inherent assumption in this type of assignment is that drivers will travel by the route that is the shortest distance from their origin to destination. In some cases, congestion on routes may play a role in the driver's travel route decision, and adjustments to traffic assignments were made to account for this where applicable. However, travel route options in the DODHF Novato area are limited, so most assignment assumptions are based strictly on shortest path.

Future Traffic Volumes

An estimate of future background traffic volumes in the ROI is important in determining which traffic impacts are attributable to the project. Estimated future background traffic volumes were obtained from the Preferred General Plan scenario (1995) of the updated General Plan for 20 key intersections in the ROI. These estimates of future background traffic are based on several assumptions. Within the ROI, but excluding DODHF Novato, growth assumptions include buildout of the remaining residential areas of Ignacio Boulevard, the New Hamilton Partnership Master Plan, as adopted, use of the Spanish Housing area for USCG housing, and other new commercial development.

For DODHF Novato, the Preferred General Plan scenario assumes that the level of traffic generated from DODHF Novato will be equivalent to the level of traffic from military uses prior to the disposal (1995) and reuse of DODHF Novato. It also assumes an additional increment of development beyond existing military uses consisting of 103 dwelling units and about 726,000 square feet of commercial space.

Level of Service Summary

LOS analysis is used to determine the impact of the Revised Reuse Plan Alternative and other alternatives on the local circulation system. LOS analyses were performed at 20 key intersections in the ROI and for four (bi-directional) freeway segments along US 101 and State Route 37 during the AM and PM peak hours. The analysis techniques are consistent with the 1994 Highway Capacity Manual (HCM) analysis techniques used to establish existing conditions, as described in Section 3.10, Traffic and Circulation. Appendix G, Tables G-7 and G-8 summarize the peak hour intersection operations for the AM and PM peak hours, respectively. Tables G-9 and G-10 summarize peak hour freeway operations for the AM and PM peak hours, respectively.

4.10.1 Disposal

No Impacts

Federal disposal of DODIIF Novato would not represent a development alternative in the sense that it does not stipulate a use for the land. As such, disposal would not affect traffic or circulation in the ROI and would therefore have no impacts.

4.10.2 Revised Reuse Plan Alternative

Under the Revised Reuse Plan Alternative, each of the DODHF Novato planning areas would be developed with the land uses designated in the revised Reuse Plan.

Trip Generation

The Revised Reuse Plan Alternative would generate approximately 12,065 average daily trips (ADT), slightly more than the 11,340 ADT associated with previous Navy use of DODHF Novato. This alternative would generate approximately 144 net new vehicle trips during the AM peak hour and a reduction of 84 trips during the PM peak hour compared to previous Navy activity. Table G-11 in Appendix G shows the trip generation characteristics (by planning area) for the various land uses that would be developed under the Revised Reuse Plan Alternative.

Intersection Operations

Not Significant Impacts

No significant impacts to intersection operations would result under the Revised Reuse Plan Alternative. Under this alternative, future intersection traffic volumes would increase slightly from the future Preferred General Plan scenario in the AM peak traffic hour and decrease in the PM peak traffic hour (see Figure 4-2). Seventeen of the 20 key intersections would operate at or above the city's acceptable criteria of average delay of under 30 seconds per vehicle for unsignalized intersections and under 40 seconds for signalized intersections (LOS D) during AM and PM peak traffic hour. Three intersections would operate below the city's acceptable criteria during the PM peak traffic hour. However, this is not considered a significant impact since the Revised Reuse Plan Alternative would result in better levels of service than under the city's approved Preferred General Plan.




Figure 4-2 allows for a comparison of intersection operations under existing conditions, the City of Novato's general plan scenario, and the alternatives evaluated in this EIS.

Intersection Operations

DOD Housing Facility
Novato, California

Figure 4-2

Source: Fehr & Peers Associates, 1996

Freeway Operations

Not Significant Impacts

No significant impacts to freeway operations would result under the Revised Reuse Plan Alternative. Traffic volumes on US 101 and State Route 37 would decrease under this alternative when compared to cumulative traffic volumes under the city's Preferred General Plan scenario, but would not decrease enough to eliminate the existing freeway congestion on these freeways. Three of four key freeway segments analyzed would exceed the freeway level of service criteria of no more than 1,824 passenger cars per hour per lane (LOS D) during peak periods. Figure 4-3 presents a summary of the freeway levels of service for the Revised Reuse Plan Alternative and other alternatives.


US 101 southbound between Ignacio Boulevard and State Route 37 would exceed 2,300 cars per hour per lane (LOS F) during the AM peak hour and would have between 1,824 and 2,300 cars per hour per lane (LOS E) during the PM peak hour. US 101 northbound between Ignacio Boulevard and State Route 37 would exceed 2,300 cars per hour per lane (LOS F) during the PM peak period. These are not considered significant impacts because implementation of the Revised Reuse Plan Alternative would result in better levels of service than provided under the city's Preferred General Plan.

US 101 southbound south of Ignacio Boulevard would have between 1,824 and 2,300 cars per hour per lane (LOS E) during the AM peak hour. US 101 northbound south of Ignacio Boulevard would exceed 2,300 cars per hour per lane (LOS F) during the PM peak hour. These are not considered significant impacts because implementation of the Revised Reuse Plan Alternative would result in better levels of service than provided under the city's Preferred General Plan.

State Route 37 eastbound between US 101 and Atherton Avenue would have between 1,824 and 2,300 cars per hour per lane (LOS E) in the PM peak hour. This is not considered a significant impact because implementation of the Revised Reuse Plan Alternative would result in better levels of service than provided under the city's Preferred General Plan.

Transit Service

The New Hamilton Partnership project includes substantial improvements to transit infrastructure, including the provision of turnouts on Nave Drive, construction of internal roadways to ultimately accommodate buses, and the identification of a transit station along the GGBHTD right-of-way. A shuttle also will be provided as part of that project, shuttling people from within the site to the bus stops on Nave Drive. For the purpose of assessing transit impacts under the Revised Reuse Plan Alternative, all improvements identified



Freeway Level of Service
DOD Housing Facility
Novato, California

Figure 4-3 provides a comparison of freeway levels of service between existing conditions, the City of Novato's General Plan Scenario, and the alternatives evaluated in the EIS.

Figure 4-3

Source: Fehr & Peers Associates, 1996

in the New Hamilton Partnership project are assumed to be in place under cumulative conditions.

A recently passed State Senate Bill, SB 437, overturns any mandatory employer-based trip reduction ordinances. Although this is not certain at this time, SB 437 also may have the authority to overturn any Transportation Demand Management (TDM) policies included as Conditions of Approval for new developments. Should the latter be true, TDM programs, including the NHP shuttle, required under the Conditions of Approvals for the New Hamilton Partnership project may be suspended.

Significant Impacts

Impact 1. A significant and mitigable impact would result from the increase in demand for transit services from reuse of DODHF Novato under the Revised Reuse Plan Alternative. The increase in demand would require convenient access for transit to all areas of the Main Site. GGBHTD has indicated that it will not add or expand its routes along Nave Drive into the Main Site area unless the costs of the additional service are provided through the Marin County Transit District (MCTD). MCTD, due to its own funding constraints, is not able to provide additional funds. This would be a significant and mitigable impact.

Mitigation 1. Internal collector roadways (Randolph Drive, Bolling Drive, and Escolta Avenue) at the Main Site could be constructed or improved to accommodate transit vehicles. In addition, a service could be provided to shuttle people from on-site locations to bus stops on Nave Drive. The most cost-effective means of providing this shuttle is likely to be an expansion of the NHP shuttle service.

Pedestrian and Bicycle Impacts

Beneficial Impacts

The Revised Reuse Plan Alternative calls for construction of continuous, connective, and safe pedestrian and bicycle facilities throughout the project area. If implemented, these facilities would represent a net beneficial impact to pedestrian and/or bicycle systems in the project area.

4.10.3 Open Space Alternative

Under the Open Space Alternative, the existing residential units at Rafael Village would be demolished. The site would be revegetated and would remain as undeveloped open space. Land uses at each of the Main Site planning areas would be the same as under the Revised Reuse Plan Alternative except for less

neighborhood commercial use in Town Center and more open space and less parkland in the Ballfields area.

Trip Generation

The Open Space Alternative would generate approximately 8,651 ADT, as compared to 11,340 ADT under previous Navy use of DODHF Novato. This alternative would result in a decrease of approximately 55 net vehicle trips during the AM peak hour and a decrease of 269 trips during the PM peak hour compared to previous Navy use. Table G-13 in Appendix G shows the trip generation characteristics (by planning area) for the various land uses that would be developed under the Open Space Alternative.

Intersection Operations

Not Significant Impacts

No significant impacts to intersection operations would result from the Open Space Alternative. Under this alternative, future intersection traffic volumes would increase slightly from the future Preferred General Plan scenario in the AM peak traffic hour and decrease in the PM peak traffic hour (see Figure 4-2). Seventeen of the 20 key intersections would operate at or above the city's acceptable criteria of average delay of under 30 seconds per vehicle for unsignalized intersections and under 40 seconds for signalized intersections (LOS D) during AM and PM peak traffic hour. Three intersections would operate below the city's acceptable criteria during the PM peak traffic hour. However, this is not considered a significant impact since the Open Space Alternative would result in better levels of service than under the city's approved Preferred General Plan.

Freeway Operations

Not Significant Impacts

No significant impacts to freeway operations would result from the Open Space Alternative. Traffic volumes on US 101 and State Route 37 would decrease under this alternative when compared to cumulative traffic volumes under the city's Preferred General Plan scenario, but would not decrease enough to eliminate the existing freeway congestion on these freeways. Three of four key freeway segments analyzed would exceed the freeway level of service criteria of no more than 1,824 passenger cars per hour per lane (LOS D) during peak periods. Figure 4-3 presents a summary of the freeway levels of service for the Open Space Alternative and other alternatives.

US 101 southbound between Ignacio Boulevard and State Route 37 would exceed 2,300 cars per hour per lane (LOS F) during the AM peak hour and

have between 1,824 and 2,300 cars per hour per lane (LOS E) during the PM peak hour. US 101 northbound between Ignacio Boulevard and State Route 37 would exceed 2,300 cars per hour per lane (LOS F) during the PM peak period. These are not considered significant impacts because implementation of the Open Space Alternative would result in better levels of service than provided under the city's Preferred General Plan.

US 101 southbound south of Ignacio Boulevard would have between 1,824 and 2,300 cars per hour per lane (LOS E) during the AM peak hour. US 101 northbound south of Ignacio Boulevard would exceed 2,300 cars per hour per lane (LOS F) during the PM peak hour. These are not considered significant impacts because implementation of the Open Space Alternative would result in better levels of service than provided under the city's Preferred General Plan.

State Route 37 eastbound between US 101 and Atherton Avenue would have between 1,824 and 2,300 cars per hour per lane (LOS E) in the PM peak hour. This is not considered a significant impact because implementation of the Open Space Alternative would result in better levels of service than provided under the city's Preferred General Plan.

Transit Service

Significant Impacts

The significant and mitigable transit impacts would be the same as described under the Revised Reuse Plan Alternative.

Pedestrian and Bicycle Impacts

Not Significant Impacts

Impacts would be the same as those described under the Revised Reuse Plan Alternative.

4.10.4 No Action Alternative

Under the No Action Alternative, DODHF Novato would remain under federal ownership in a caretaker, or inactive, status, with on-site activities limited to maintenance and remediation activities.

Trip Generation

This would result in a decrease of approximately 805 net vehicle trips during the AM peak hour and a decrease of 1,448 vehicle trips during the PM peak hour compared to previous Navy use. Table G-13 in Appendix G shows the trip generation characteristics by planning area for the various land uses that would be developed under the No Action Alternative.

Intersection Operations

No Impacts

No impacts to intersection operations would result from the No Action Alternative. Under this alternative, future intersection traffic volumes would increase slightly from the future Preferred General Plan scenario in the AM peak traffic hour and decrease in the PM peak traffic hour (see Figure 4-2). Eighteen of the 20 key intersections would operate at or above the city's acceptable criteria of average delay of under 30 seconds per vehicle for unsignalized intersections and under 40 seconds for signalized intersections (LOS D) during AM and PM peak traffic hour. Under the No Action Alternative the intersection of Ignacio Boulevard @ Nave Drive would improve compared to the other alternatives (from LOS E under the other alternatives to LOS D). Two intersections would continue to operate below the city's acceptable criteria during the PM peak traffic hour. However, this is not considered a significant impact related to the alternative since the No Action Alternative would result in better levels of service than under the city's approved Preferred General Plan.

Freeway Operations

No Impacts

No impacts to freeway operations would result from the No Action Alternative. Traffic volumes on US 101 and State Route 37 would decrease under this alternative when compared to cumulative traffic volumes under the city's Preferred General Plan scenario, but would not decrease enough to eliminate the existing freeway congestion on these freeways. Three of four key freeway segments analyzed would exceed the freeway level of service criteria of no more than 1,824 passenger cars per hour per lane (LOS D) during peak periods. Figure 4-3 presents a summary of the freeway levels of service for the No Action Alternative and other alternatives.

US 101 southbound between Ignacio Boulevard and State Route 37 would exceed 2,300 cars per hour per lane (LOS F) during the AM peak hour and have between 1,824 and 2,300 cars per hour per lane (LOS E) during the PM peak hour. US 101 northbound between Ignacio Boulevard and State Route

37 would exceed 2,300 cars per hour per lane (LOS F) during the PM peak period. These are not considered significant impacts because implementation of the No Action Alternative would result in better levels of service than provided under the city's Preferred General Plan.

US 101 southbound south of Ignacio Boulevard would have between 1,824 and 2,300 cars per hour per lane (LOS E) during the AM peak hour. US 101 northbound south of Ignacio Boulevard would exceed 2,300 cars per hour per lane (LOS F) during the PM peak hour. These are not considered significant impacts because implementation of the No Action Alternative would result in better levels of service than provided under the city's Preferred General Plan.

State Route 37 eastbound between US 101 and Atherton Avenue would have between 1,824 and 2,300 cars per hour per lane (LOS E) in the PM peak hour. This is not considered a significant impact because implementation of the No Action Alternative would result in better levels of service than provided under the city's Preferred General Plan.

Transit Service

The New Hamilton Partnership project includes substantial improvements to transit infrastructure including the provision of turnouts on Nave Drive, construction of internal roadways to ultimately accommodate buses, and the identification of a transit station along the GGBHTD right-of-way. A shuttle also will be provided as part of that project, shuttling people from within the site to the bus stops on Nave Drive. For the purpose of assessing transit impacts under the No Action Alternative, all improvements identified in the New Hamilton Partnership project are assumed to be in place under cumulative conditions.

No Impacts

For the No Action Alternative, no on-site transit would be required. There would be no transit impacts under this alternative.

Pedestrian and Bicycle Impacts

No Impacts

Under the No Action Alternative, the Navy would continue to maintain, police, and, where appropriate, provide lighting for all pedestrian and bicycle facilities. There would be no pedestrian or bicycle impacts under this alternative.

4.11 AIR QUALITY

The following section describes impacts to air quality resulting from disposal, no action, and community reuse of DODHF Novato.

Region of Influence

The ROI for air quality issues depends upon the type of air pollution being discussed. Primary pollutants such as carbon monoxide have localized regions of influence restricted to the immediate vicinity of the emission source. Secondary pollutants such as ozone have an ROI that encompasses the entire San Francisco Bay metropolitan area, including DODHF Novato.

Significance Criteria

Significance criteria for evaluating air quality impacts can be based on physical impacts, regulatory standards, or consistency with plans for meeting air quality standards. Air quality impacts are typically judged to be significant if the action would directly or indirectly:

- Cause or contribute to a violation of state or federal ambient air quality standards;
- Cause pollutant or pollutant precursor emissions in excess of BAAQMD impact significance thresholds (80 pounds per day for ozone precursors and PM₁₀ from project-related traffic);
- Conflict with specific air quality management plan policies or programs; or
- Foster or accommodate development in excess of the levels assumed by applicable air quality management plans.

The choice of significance criteria for physical air quality impact issues is dictated largely by the technical procedures used for the impact assessment. Dispersion modeling analyses have been performed to evaluate the potential for causing or contributing to violations of federal or state carbon monoxide air quality standards. The significance of ozone precursor emissions is evaluated in the context of Bay Area Air Quality Management District (BAAQMD) emission significance thresholds of 80 pounds of pollutant per day for reactive organic compounds (ROG), nitrogen oxides (NO_x), and inhalable particulate matter (PM₁₀).

Table 4-19 summarizes the impacts to air quality from disposal, the Revised Reuse Plan Alternative, the Open Space Alternative, and the No Action Alternative.

4.11.1 Disposal

No Impacts

Property disposal actions would have no air quality impacts as disposal is a transfer of property title. Property disposal actions generally qualify as de minimis actions under EPA's Clean Air Act conformity determination rule.

Table 4-19
Summary of Air Quality Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|--------------------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Construction and Demolition | ○ | ○ | ● | ● |
| Carbon monoxide concentrations | ○ | ○ | ⊕ | ⊕ |
| Ozone precursor emissions | ○ | ○ | ⊕ | ⊕ |
| Air quality plan consistency | ○ | ○ | ⊕ | ⊕ |

LEGEND:

- - Significant impact
- ⊕ - Significant and mitigable impact
- ⊕ - Not significant impact
- - No impact

4.11.2 Revised Reuse Plan Alternative

Construction and Demolition

Significant Impacts

Impact 1. A significant and mitigable impact could result from building demolition, renovation, and construction activities generating localized dust nuisance conditions. Construction, renovation, and demolition activities under the Revised Reuse Plan Alternative would occur incrementally over an extended buildout period. Demolition and construction would be a concern primarily in the Rafael Village planning area, where 503 existing residential structures would be replaced (with 500 new units). Buildout of the Commissary Triangle and Exchange Triangle areas also would involve demolition and construction. Construction-related dust would be a potentially

significant and mitigable impact that can be reduced to acceptable levels by proper dust control measures.

Mitigation 1. Implementation of the following dust control practices during demolition, construction, and renovation activities would reduce potential impacts to a not significant level.

- Minimize the area disturbed by clearing, earthmoving, or excavation activities.
- Prevent excessive dust generation by using water or dust control solutions on all unpaved areas subject to vehicle traffic, grading, or excavation.
- Ensure that any petroleum-based dust control products used on the site meet BAAQMD regulations for cutback asphalt paving materials.
- Halt all site clearing, grading, earthmoving, and excavation activities during periods of sustained strong winds (hourly average wind speeds of 20 mph or greater).
- Sweep streets adjacent to the construction site as necessary to remove accumulated dust and soil.
- Properly maintain all construction vehicles and avoid excessive idling of inactive equipment.

Traffic-related Ozone Precursor Emissions

Not Significant Impacts

No significant impacts from traffic-related ozone precursor emissions would result under the Revised Reuse Plan Alternative. Table 4-20 summarizes estimates of average weekday vehicle travel and resulting vehicle emissions for land use patterns under the reuse and no action alternatives. The 1994 Bay Area Clean Air Plan is based on land use and transportation patterns that existed in the early 1990s. Because most military installations are accounted for in the air quality plan as active facilities, the preclosure activity scenario provides a useful basis for judging the extent to which reuse alternative cause increases or decreases in traffic-related emissions.

As indicated in Table 4-20, the Reuse Plan Alternative would generate slightly more traffic-related emissions than would be associated with a continuation of preclosure activity levels. The net increase in traffic-related ozone precursor emissions would be about 11 pounds per day for organic compounds (ROG) and 20 pounds per day for nitrogen oxides. Net increases in PM₁₀ emissions would be about 28 pounds per day. These emission increases would not

exceed the BAAQMD impact significance threshold of 80 pounds per day. Consequently, this impact is not significant.

Table 4-20
Comparison of Vehicle Traffic Emissions for Reuse Alternatives

| Alternative | Daily Vehicle Trips | Daily VMT | Estimated Daily Vehicle Emissions (Pounds Per Day) | | | | |
|--------------------------------|---------------------|-----------|---|-----------------|----------------|----------------|------------------|
| | | | ROG | NO _x | CO (summer) | CO (winter) | PM ₁₀ |
| Preclosure Activity Level | 11,340 | 103,150 | 80 | 147 | 1,028 | 1,232 | 207 |
| No Action Alternative | 1,933 | 18,063 | 15 | 27 | 174 | 201 | 36 |
| Revised Reuse Plan Alternative | 12,065 | 117,372 | 91 | 167 | 1,117 | 1,303 | 235 |
| Open Space Alternative | 8,651 | 85,018 | 65 | 121 | 810 | 950 | 170 |

| Alternative | Net Change Compared to Preclosure Activity Scenario (Pounds Per Day) | | | | | | |
|--------------------------------|---|-----------|-----|-----------------|----------------|----------------|------------------|
| | Daily Vehicle Trips | Daily VMT | ROG | NO _x | CO (summer) | CO (winter) | PM ₁₀ |
| No Action Alternative | -9,407 | -85,087 | -65 | -120 | -854 | -1,031 | -171 |
| Revised Reuse Plan Alternative | 725 | 14,222 | 11 | 20 | 89 | 71 | 28 |
| Open Space Alternative | -2,689 | -18,132 | -15 | -26 | -218 | -282 | -37 |

Notes: VMT = vehicle miles traveled PM₁₀ = inhalable particulate matter
 ROG = reactive organic compounds NO_x = nitrogen oxides
 BAAQMD significance thresholds are 80 lbs/day for ROG, NO_x, and PM₁₀. Dispersion modeling was used to calculate CO emissions and is the best significance measure for CO.
 Daily reuse trip data based on traffic studies; these numbers take into account land use acreages, typical daily trip generation rates, and transit and ride sharing.
 Land uses for reuse plan alternatives are summarized in Table 2-1.
 Net daily trip estimates reflect adjustments for trips between study area land use categories.
 PM₁₀ emissions include a resuspended roadway dust component (0.69 g/VMT) as recommended by the BAAQMD.
 Emission estimates are based on EMFAC7F emission rates for 2010.

Source: Tetra Tech

Carbon Monoxide Concentrations

Not Significant Impacts

No significant carbon monoxide effects would result from implementation of the Revised Reuse Plan Alternative. As discussed in Section 4.10, Traffic and Circulation, buildout of the Reuse Plan would generate traffic that would contribute to traffic congestion problems at some locations in the Novato area. Air quality modeling was performed to determine whether vehicle emissions at congested intersections might cause localized violations of state or federal carbon monoxide standards. Table 4-21 summarizes the results of these dispersion modeling analyses. As indicated in Table 4-21, carbon monoxide levels would remain well below the applicable standards at all locations.

Table 4-21
Summary of Carbon Monoxide Dispersion Modeling Results

| Receptor Location | Peak 1-Hour Carbon Monoxide Concentration (ppm) | | | Peak 8-Hour Carbon Monoxide Concentration (ppm) | | |
|-----------------------------------|---|------------------------|-----------------------|---|------------------------|-----------------------|
| | Revised Reuse Plan Alternative | Open Space Alternative | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative | No Action Alternative |
| NE of Nave Dr. and Bel Marin Keys | 6.4 | 6.2 | 5.9 | 4.5 | 4.3 | 4.1 |
| SE of Nave Dr. and Bel Marin Keys | 7.7 | 7.3 | 6.9 | 5.4 | 5.1 | 4.8 |
| NW of Ignacio and Safeway access | 4.4 | 4.2 | 3.8 | 3.1 | 2.9 | 2.7 |
| SW of Ignacio and Safeway access | 4.7 | 4.5 | 4.2 | 3.3 | 3.2 | 2.9 |
| NE of Ignacio and Safeway access | 4.7 | 4.5 | 4.3 | 3.3 | 3.2 | 3.0 |
| SE of Ignacio and Safeway access | 5.0 | 4.8 | 4.5 | 3.5 | 3.4 | 3.2 |
| NW of Ignacio and Entrada Drive | 3.9 | 3.6 | 3.4 | 2.7 | 2.5 | 2.4 |
| SW of Ignacio and Entrada Drive | 4.2 | 3.8 | 3.5 | 2.9 | 2.7 | 2.5 |
| NE of Ignacio and Entrada Drive | 4.0 | 3.9 | 3.6 | 2.8 | 2.7 | 2.5 |
| SE of Ignacio and Entrada Drive | 4.8 | 4.3 | 4.0 | 3.4 | 3.0 | 2.8 |
| NW of Ignacio and Sunset Parkway | 8.5 | 8.1 | 3.3 | 6.0 | 5.7 | 2.3 |
| SW of Ignacio and Sunset Parkway | 6.6 | 6.4 | 2.9 | 4.6 | 4.5 | 2.0 |
| NE of Ignacio and Sunset Parkway | 7.2 | 6.9 | 2.9 | 5.0 | 4.8 | 2.0 |
| SE of Ignacio and Sunset Parkway | 6.3 | 6.0 | 2.8 | 4.4 | 4.2 | 2.0 |

Notes:

ppm = parts per million, by volume

All modeling results for carbon monoxide are within federal and state standards.

Federal carbon monoxide standards are 35 ppm for a 1-hour average and 9 ppm for an 8-hour average.

California carbon monoxide standards are 20 ppm for a 1-hour average and 9 ppm for an 8-hour average.

Modeling results were generated using the CALINE4 dispersion model and EMFAC7F emission rates for the year 2010.

Emissions from extended vehicle idling at congested intersections are included in the modeling analysis.

Modeling analyses assumed poor dispersion conditions (moderate temperature inversion [stability class F], 2.2 mph wind speed, 50-meter mixing height limit, and 10 degree wind direction fluctuation parameter), with wind directions varied in 10 degree increments.

A background carbon monoxide value of 2 ppm has been added to the peak 1-hour modeling results.

Peak 8-hour carbon monoxide concentrations are estimated as 70% of the peak 1-hour concentration.

Air Quality Plan Consistency

Not Significant Impacts

Administrative procedures established by the EPA general conformity rule apply to federally designated nonattainment and maintenance areas. Property transfers associated with reuse of DODHF Novato are excluded from the requirements of the EPA general conformity rule. Interim lease arrangements might be subject to the requirements of the general conformity rule only if the Navy retains authority to control the proposed use.

Regional air quality plans are periodically updated to reflect the current status of land use and transportation planning on a regional level. Thus, major development proposals that occur between updates are routinely incorporated into subsequent air quality plan revisions. Most new development associated with the reuse plan will happen outside the year 2000 time frame currently addressed by emission forecasts in the Bay Area Air Quality Plan. This precludes any quantitative analysis of plan consistency issues.

4.11.3 Open Space Alternative

Significant Impacts

Impact 1. Significant and mitigable demolition-related air quality impacts would be similar to those of the Revised Reuse Plan Alternative. Construction-related impacts would be less than under the Revised Reuse Plan Alternative because the 503 units in Rafael Village would not be replaced. Construction-related dust could be reduced to not significant levels by implementation of proper dust control measures.

Mitigation 1. See Mitigation 1 under the Revised Reuse Plan Alternative.

Not Significant Impacts

Traffic-related Ozone Precursor Emissions

The Open Space Alternative would not result in significant ozone precursor emission impacts. This alternative would generate less total vehicle travel than the preclosure activity scenario and as shown in Table 4-20, would result in net decreases in ROG, NO_x, and PM₁₀ emissions as compared to preclosure activity.

Carbon Monoxide Concentrations

No significant carbon monoxide impacts would result from the Open Space Alternative. This alternative has the potential to generate traffic that would contribute to traffic congestion problems at some locations in the Novato area. Air quality modeling was performed to determine whether vehicle emissions at congested intersections might cause localized violations of state or federal carbon monoxide standards. Table 4-21 summarizes the results of these dispersion modeling analyses. As indicated in Table 4-21, carbon monoxide levels would remain well below the applicable standards at all locations.

Compliance with the EPA general conformity rule would be similar to the Revised Reuse Plan Alternative and would not result in impacts.

4.11.4 No Action Alternative

No Impacts

Caretaker status under the No Action Alternative would not have any air quality impacts from construction or demolition activities or, as shown on Tables 4-20 and 4-21, from vehicle traffic. The No Action Alternative would not require a Clean Air Act conformity determination because resulting annual direct and indirect emissions would clearly be less than the applicable de minimis levels.

4.12 NOISE

The following section describes noise impacts resulting from disposal, no action, and community reuse of DODHF Novato.

Region of Influence

The ROI for noise is limited since noise levels decrease as the distance from the noise source increases. The overall noise ROI for this EIS is the City of Novato. A more localized ROI is appropriate for some discrete noise sources; such localized areas of influence are generally within one-half mile of the noise source.

Significance Criteria

Noise impacts associated with the reuse of DODHF Novato fall into three categories—temporary noise generation from demolition and construction activities, noise generation from added vehicle traffic, and exposure of proposed land uses to the combination of background and added noise levels.

Noise impact significance criteria are based partly on land use compatibility guidelines and partly on factors related to the duration and magnitude of noise level changes. Annoyance effects are the primary consideration for most noise impact assessments. Because the reaction to noise level changes involves both physiological and psychological factors, the magnitude of a noise level change can be as important as the resulting overall noise level. A readily noticeable increase in noise levels often would be considered a significant effect by local residents even if the overall noise level is still within land use compatibility guidelines. On the other hand, noise level increases that are not noticeable to most people generally are not considered a significant change, even if the overall noise level is somewhat above land use compatibility guidelines.

- An adverse impact would occur if an alternative exposed noise sensitive land uses (e.g., residential, educational, and health care uses) to ambient noise levels that are higher than the 60 dB land use compatibility criterion.
- An incremental noise level decrease would be considered a beneficial impact even if the overall noise level remains above land use compatibility criteria.
- A project-related noise level increase of 3 dB or more would be considered a significant impact if noise-sensitive land uses (residential, medical, or educational land uses) are affected and if the overall noise level is within 5 dB of the land use compatibility criteria.

- A project-related noise level increase of 1 dB or more would be considered a significant impact if noise-sensitive land uses (residential, medical, or educational land uses) are affected and if the overall noise level is 5 dB or more above the applicable land use compatibility criteria.
- Temporary noise sources that are restricted to daytime hours (such as most construction and demolition activities) would be considered a significant impact only if they result in noise levels 10 dB or more above the land use compatibility criteria.

Table 4-22 summarizes potential noise impacts of disposal and reuse.

Table 4-22
Summary of Noise Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|--------------------------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Construction and Demolition Noise | ○ | ○ | ◐ | ◐ |
| Added Traffic Noise | ○ | ○ | ⊕ | ⊕ |
| Noise Exposure of Proposed Land Uses | ○ | ○ | ● | ● |

LEGEND:

- - Significant impact
- ◐ - Significant and mitigable impact
- ⊕ - Not significant impact
- - No impact

4.12.1 Disposal

No Impacts

Property disposal actions would have no noise impacts.

4.12.2 Revised Reuse Plan Alternative

Noise modeling analyses were performed to assess the noise effects of the alternatives. Modeled receptor locations were arranged in transects north and south of Ignacio Drive between Entrada Drive and Palmer Drive, east and west of US 101 south of the SR 37 interchange, and east and west of US 101 between Main Gate Road and Bolling Drive. Table 4-23 summarizes the results of these noise modeling analyses.

Table 4-23
Summary of Traffic Noise Modeling Results

| General Location | Modeled Ldn Level (dB) by Reuse Alternative | | | |
|--|---|--------------------------------|------------------------|-----------------------|
| | Distance From Centerline (Feet) | Revised Reuse Plan Alternative | Open Space Alternative | No Action Alternative |
| N of Ignacio between Entrada and Palmer Drive | 100 | 69.4 | 69.3 | 69.0 |
| | 150 | 68.7 | 68.6 | 68.4 |
| | 200 | 68.5 | 68.4 | 68.2 |
| | 400 | 68.8 | 68.8 | 68.6 |
| | 750 | 68.0 | 67.9 | 67.8 |
| S of Ignacio between Entrada and Palmer Drive | 100 | 68.9 | 68.8 | 68.5 |
| | 150 | 67.7 | 67.7 | 67.4 |
| | 200 | 67.1 | 67.0 | 66.8 |
| | 400 | 65.5 | 65.5 | 65.3 |
| | 750 | 64.0 | 64.0 | 63.8 |
| | 1,500 | 62.0 | 61.9 | 61.8 |
| E of US 101, north of Rafael Village | 100 | 80.6 | 80.6 | 80.5 |
| | 200 | 75.6 | 75.6 | 75.4 |
| | 400 | 70.5 | 70.4 | 70.3 |
| | 750 | 65.6 | 65.5 | 65.4 |
| | 1,500 | 59.9 | 59.9 | 59.8 |
| | 2,500 | 55.4 | 55.4 | 55.3 |
| W of US 101 north of Rafael Village | 100 | 80.6 | 80.6 | 80.5 |
| | 200 | 75.6 | 75.6 | 75.5 |
| | 400 | 73.3 | 72.9 | 72.1 |
| | 750 | 74.1 | 74.0 | 73.5 |
| | 1,500 | 61.4 | 61.4 | 61.1 |
| | 2,500 | 56.2 | 56.2 | 56.1 |
| E of US 101 between Main Gate Road and Bolling Drive | 100 | 80.7 | 80.7 | 80.6 |
| | 150 | 77.8 | 77.8 | 77.7 |
| | 200 | 75.9 | 75.9 | 75.8 |
| | 400 | 71.0 | 71.0 | 70.9 |
| | 750 | 66.2 | 66.2 | 66.1 |
| | 1,500 | 60.4 | 60.4 | 60.3 |
| | 2,500 | 55.7 | 55.7 | 55.6 |
| W of US 101 between Main Gate Road and Bolling Drive | 100 | 80.8 | 80.8 | 80.7 |
| | 150 | 77.9 | 77.9 | 77.8 |
| | 200 | 76.0 | 76.0 | 75.9 |
| | 400 | 71.5 | 71.5 | 71.4 |
| | 750 | 67.3 | 67.3 | 67.2 |
| | 1,500 | 61.9 | 61.9 | 61.8 |
| | 2,500 | 57.2 | 57.2 | 57.1 |

Notes: Traffic noise was modeled using the Federal US Highway Administration traffic noise prediction model, California vehicle noise emission levels, and hourly distributions of car and truck traffic representative of freeways and arterial highways. Modeled traffic speeds were adjusted according to hourly volume:capacity ratios.

Acceptable noise levels as specified in the Novato General Plan are 60 dB for residential uses, hotels, motels, schools, libraries, hospitals, churches, museums, and meeting halls; 65 dB for outdoor sports and recreation, parks, and playgrounds; and 70 dB for office buildings, business commercial, professional, industrial, manufacturing, utilities, and agriculture land uses.

Significant Impacts

Impact 1. Significant and mitigable noise impacts from building demolition, renovation, and construction activities associated with reuse of the Rafael Village, Commissary Triangle, and Exchange Triangle planning areas would occur from causing temporary noise disturbances to adjacent land uses. Occupied residential locations around these planning areas, including Lanham Village and neighborhoods adjacent to Rafael Village, may experience temporary disturbance from construction noise. This would be a short-term significant and mitigable impact. The Reuse Plan anticipates little or no construction or demolition at the remaining Navy-owned planning areas.

Mitigation 1. Limit the use of heavy construction equipment and outdoor power tools to normal daytime hours (7 AM through 7 PM) during construction and demolition activities. Limiting construction and demolition activities to normal daytime hours would reduce potential noise impacts to a less than significant level.

Impact 2. A significant unmitigable noise impact would result from residential reuse in areas that would be exposed to existing ambient noise levels significantly above the land use compatibility guidelines provided in the Novato General Plan. The plan sets the acceptable noise level for residential housing at 60 dB. This level currently is exceeded due to noise from traffic along area roadways. As shown in Table 4-23, the 60 dB noise level is exceeded in Capehart Housing to a distance of 1,500 feet from the centerline of US 101, an area encompassing the western two-thirds and the most densely built portion of the planning area. As also shown on Table 4-23, this noise level is exceeded in Rafael Village north and south of Ignacio Boulevard to a distance exceeding 750 feet from the road, an area encompassing most of Rafael Village. The remaining planning areas would not be exposed to noise levels exceeding the standards for their specific type of land use.

Mitigation 2. The City of Novato and Caltrans should evaluate the feasibility of additional sound walls along US 101 in order to reduce traffic noise impacts on adjacent properties. During detailed planning for new housing units in Rafael Village, the City of Novato should consider site designs that provide for sound walls along Ignacio Boulevard. Although sound walls would reduce ambient noise levels by approximately 5 dB, the noise levels would still be significant in those areas nearest US 101 and Ignacio Boulevard.

Not Significant Impacts

No significant noise impacts would result from traffic generated by this alternative. As discussed in Section 4.10, Traffic and Circulation, buildout of the proposed reuse plan would generate traffic that would add marginally to background traffic volumes that are already high. Traffic noise modeling was

performed to determine whether the added traffic volumes would have a significant effect on ambient noise levels. Traffic noise modeling was performed for a simulated 24-hour pattern of auto and truck traffic on US 101, Ignacio Boulevard, and Nave Drive. The noise analysis takes into account a vehicle mix, including a percentage of heavy truck traffic. As indicated in Table 4-23, traffic added by the Revised Reuse Plan Alternative would not cause any significant change in ambient noise levels (represented by the No Action Alternative), including on surrounding land uses such as Lanham Village.

4.12.3 Open Space Alternative

Significant Impacts

Impact 1. Significant and mitigable noise impacts from demolition, renovation, and construction activities would be similar to those described for the Revised Reuse Plan Alternative. Construction-related noise would be less at Rafael Village, however, since the housing units demolished would not be replaced with new housing units.

Mitigation 1. Limit the use of heavy construction equipment and outdoor power tools to normal daytime hours (7 AM through 7 PM) during construction and demolition activities.

Impact 2. Significant unmitigable noise impacts would occur from reuse of noise-sensitive land uses in areas that would be exposed to existing high ambient noise levels. This alternative would, however, result in better land use compatibility conditions along Ignacio Boulevard than under the Revised Reuse Plan Alternative.

Mitigation 2. The sound wall evaluations discussed under the Revised Reuse Plan Alternative also should be considered for the Open Space Alternative.

Not Significant Impacts

As indicated in Table 4-23, traffic associated with the Open Space Alternative would not cause a significant change in ambient noise levels, including on surrounding land uses such as Lanham Village. The noise analysis presented in Table 4-23 takes into account a vehicle mix, including a percentage of heavy truck traffic. While not significant, noise levels from activities such as a corporation yard could be reduced through mitigations such as providing acoustical insulation when renovating buildings, providing adequate ventilation in buildings so activities can be conducted with the doors closed, and constructing masonry walls along property lines that border sensitive land uses.

4.12.4 No Action Alternative

No Impacts

Caretaker status under the No Action Alternative would have no noise impacts from construction or demolition activities or from added vehicle traffic. Since none of the residential units at DODHF Novato would be occupied, there would be no impacts from ambient noise levels from US 101.

4.13 HAZARDOUS MATERIALS AND WASTE

This section addresses the potential impacts of the disposal, no action, and reuse alternatives and the potential for environmental impacts caused by hazardous materials and hazardous waste-related activities associated with the reuse alternatives. Hazardous materials and wastes, asbestos, PCBs, storage tanks, pesticides, lead, medical wastes, and radon are discussed in this section.

Region of Influence

The region of influence for hazardous materials and waste issues is DODHF Novato, including the Rafael Village housing area, and any surrounding area that may have been affected by hazardous materials or hazardous wastes originating at DODHF Novato or from which hazardous materials or wastes could migrate onto DODHF Novato property.

Significance Criteria

A project may have a significant impact if it would result in a substantial increase in the use of hazardous materials or the generation of hazardous wastes or if it increases the risk of exposure to hazardous or toxic substances. The following criteria were used to identify potential impacts:

- Release of asbestos during the demolition or renovation of a building;
- Reuses that would require plans or programs under federal, state, or local law and for which no remediation plans or programs have been developed;
- New operational requirements or service for underground storage tanks and tank systems; and
- Releases that result in exposure of the public or the environment to hazardous substances.

Table 4-24 summarizes hazardous materials and waste impacts and significance.

Planning Issues

BRAC requirements call for the removal of all hazardous materials and wastes, investigation of potentially contaminated areas, and remediation of contamination prior to disposal of the property by the Navy. Some areas of soil or ground water contamination have been identified at DODHF Novato.

Table 4-24
Summary of Hazardous Material and Waste Impacts

| IMPACTS | NAVY | | COMMUNITY REUSE | |
|--------------------------------------|------------------|-----------------------|--------------------------------|------------------------|
| | Federal Disposal | No Action Alternative | Revised Reuse Plan Alternative | Open Space Alternative |
| Hazardous materials management | ○ | ○ | ⊖ | ⊖ |
| Hazardous waste management practices | ○ | ○ | ⊖ | ⊖ |
| Asbestos | ○ | ⊖ | ⊖ | ⊖ |
| PCBs | ○ | ○ | ⊖ | ⊖ |
| Hazards from existing storage tanks | ○ | ○ | ⊖ | ⊖ |
| Pesticides | ○ | ⊖ | ⊖ | ⊖ |
| Lead hazards | ○ | ○ | ⊖ | ⊖ |
| Medical materials and waste | ○ | ○ | ⊖ | ⊖ |
| Radon | ○ | ○ | ○ | ○ |

LEGEND:

- - Significant impact
- ⊖ - Significant and mitigable impact
- ⊖ - Not significant impact
- - No impact

The Navy is committed to all required contamination remediation at the former DODHF Novato resulting from Navy activities. Delays or restrictions in disposal and reuse of property are possible, depending upon the extent of contamination and the results of the risk assessment and remedial designs developed for contaminated sites. Examples of conditions resulting in possible land use restrictions would be the space required for operation of soil or ground water treatment systems and access to long-term monitoring wells. These conditions would have to be considered in the layout of future development. However, because the areas of potential contamination are relatively few and limited in size, any such restrictions are likely to be minor.

Properties that contain or that potentially contain contamination may be transferred prior to completion of environmental remediation only if conditions listed in the amended CERCLA regulation (CERCLA 120 as amended by Section 334 of the FY97 Defense Authorization Act) are met. These conditions include agreement by US EPA and the state that the property is suitable for the intended use and that the intended use will protect human health and the environment, that property use restrictions are implemented to ensure that human health and the environment are protected, that there are assurances from the Federal government that transfer of the property will not substantially delay response actions at the property, and that the Federal government will continue any necessary response actions after transfer.

4.13 Hazardous Materials and Waste

Section 3.13 details the Navy, regulatory, and public review processes to ensure property reuse is protective of human health and the environment. The BRAC Cleanup Plan (BCP) summarizes the status of the environmental restoration and compliance programs and presents a strategy for carrying out response actions necessary to protect human health and the environment.

Negligible quantities of hazardous materials and hazardous wastes are expected to be generated, handled, or disposed of by operations after base closure. In addition, maintenance operations associated with caretaker status are not expected to generate, handle, or dispose of significant quantities of such materials.

As reuse of DODHF Novato is implemented, hazardous waste management would be controlled by the property recipients. Once the responsibilities of hazardous waste management are allocated to individual organizations, proficiency with those materials and with spill response plans may be required by RCRA regulations. Business plans and risk management programs also may be required under state health and safety code requirements.

The presence of numerous independent operators/owners at DODHF Novato would change the existing regulatory requirements and may increase the regulatory burden relative to hazardous waste management.

4.13.1 Disposal

No Impacts

No direct hazardous material or hazardous waste impacts would result from disposal. Disposal involves the transfer of DODHF Novato out of federal jurisdiction. No hazardous material or waste-related impacts would occur from disposal of DODHF Novato. The Navy is required to remediate contamination prior to transfer. Base activities, including those involving hazardous materials and hazardous wastes, will cease. Hazardous materials will be collected from all designated storage areas and transferred off-site. Because only small quantities of hazardous materials presently are used or stored at DODHF Novato, the amount of these materials to be collected is expected to be minimal. Materials that are not redistributed or sold will be disposed of off-site in accordance with RCRA and state requirements.

4.13.2 Revised Reuse Plan Alternative

Hazardous Materials Management*Not Significant Impacts*

The quantity of hazardous materials used, stored, and disposed under the Revised Reuse Plan Alternative likely would decrease over current conditions, although specific chemicals and uses are not known. Future uses would be tightly controlled under current regulations. Hazardous materials likely to be used for activities in all of the proposed reuse alternatives are identified in Table 4-25.

Table 4-25
Hazardous Materials Usage By Land Use Category

| Land Use | Operation Process | Hazardous Materials |
|-----------------------|---|--|
| Commercial | Activities associated with offices, light industry, research and development, and higher value warehousing, retail, service industries, restaurants | Fuels, heating oils, pesticides, dry cleaning chemicals, solvents, corrosives, petroleum-based lubricants, ignitables |
| Residential | Utilization/maintenance of single-family and multi-family units, landscaping | Pesticides, fertilizers, fuels, oils, chlorine, and household chemicals |
| Recreation/open space | Maintenance of existing recreational facilities, including ball fields, swimming pools, and other recreational facilities | Pesticides, fertilizers, chlorine, heating oils, paints, thinners, cleaners, solvents, aerosols, petroleum-based lubricants |
| Institutional | Medical clinic, rehabilitation or elder care facilities, X-ray unit | Pharmaceuticals, medical biohazardous materials, chemotherapeutic drugs, nuclear medical sources, heavy metals |
| | Public education, higher education, research labs, training facilities, vocational schools | Laboratory chemicals, corrosives, ignitables, solvents, heating oils, solvents, lubricants, cleaners, pesticides, paints, thinners |

With implementation of any of the alternatives, separate organizations would be responsible for the management of hazardous materials according to applicable regulations. Depending on types and quantities of hazardous materials used, each organization would be subject to federal Superfund Amendments and Reauthorization Act (SARA) Title III requirements and state hazardous material business plans and risk management prevention programs for emergency planning review and community right-to-know inventory reporting. Mutual aid agreement with surrounding jurisdictions may require additional scrutiny and training of emergency staff. These impacts would therefore not be significant.

Hazardous Waste Management Practices

Not Significant Impacts

Under the Revised Reuse Plan Alternative, the total quantity of hazardous wastes generated and stored on the property would decrease substantially. Following base closure, operation of the hazardous waste accumulation area was discontinued. Very limited quantities of hazardous wastes may be generated by caretaker operations. Such wastes would be handled and disposed of according to regulatory guidelines and industry standards enforced at that time, resulting in no significant impact.

Asbestos

Not Significant Impacts

Under the Revised Reuse Plan Alternative, a number of buildings and residential structures on federal surplus land with asbestos-containing materials (ACM) would be demolished or renovated. This impact would not be significant. Such activities would be subject to all applicable federal, state, and local regulations. DOD policy is that "property with ACM will not be disposed through the BRAC process unless it is determined that the ACM does not pose a threat to human health at the time of transfer." Demolition activities would occur following transfer under the Revised Reuse Plan Alternative. Because any building demolition or renovation must comply with state and federal occupational health and safety and air emissions regulations for asbestos abatement, no significant environmental impact would result from these activities.

Polychlorinated Biphenyls

Not Significant Impacts

No polychlorinated biphenyls (PCB) release sites have been identified at DODHF Novato. Because any unidentified PCB release sites are likely to be relatively small, identifying, evaluating, and any necessary remediation of such sites would not be considered significant or be affected by the implementation of the Revised Reuse Plan Alternative.

The Navy plans to remove all PCB-containing electrical equipment prior to lease or transfer.

Storage Tanks and Oil/Water Separators

Not Significant Impacts

Reuse activities associated with the Revised Reuse Plan Alternative may require both aboveground storage tanks (ASTs) and underground storage tanks (USTs). The Navy plans to remove all USTs prior to lease or transfer. Any new USTs and ASTs required by the property recipients would be subject to all applicable federal, state, and local regulations. These regulations include acceptable leak detection methods, spill and overfill protection, cathodic protection, secondary containment for hazardous waste tank systems including the piping, and liability insurance. These measures would reduce potential impacts to a not significant level.

Pesticides

Not Significant Impacts

Minimal use of pesticides would be expected at DODHF Novato following base closure. The types of pesticides are likely to be consistent with those currently in use. This would not be a significant impact.

Lead

Not Significant Impacts

Lead-based paints have been used at DODHF Novato since its development. It is likely that all of the buildings at the facility built before 1980 have some amount of lead-based paint. In accordance with DOD policy and the Residential Lead-Based Paint Hazard Reduction Act of 1992, housing constructed prior to 1978 would be inspected for lead-based paint hazards. Lead-based paint hazards in housing constructed prior to 1960 would be abated if the housing is to be transferred out of federal ownership. The results of lead-based paint surveys and lead warning statements would be included in any contract for transfer or lease. This would not be a significant impact.

Medical Materials and Wastes

Not Significant Impacts

No medical wastes are now used or produced at DODHF Novato. Under the Revised Reuse Plan Alternative, a portion of the site may be used for assisted-care facilities for seniors. Small amounts of biohazardous waste may

4.13 Hazardous Materials and Waste

be generated and stored in the course of routine medical treatment for residents of these facilities. The new facilities would be required to comply with the requirements of the California Medical Waste Management Act for disposal of medical/biohazardous waste. This would not be a significant impact.

Radon

No Impacts

A radon survey of 86 buildings at DODHF Novato found no indication that radon levels are above the EPA-recommended action level for further assessment or remediation. In accordance with DOD policy, all available and relevant radon assessment data will be included in any contracts for transfer or lease. No impacts are expected.

4.13.3 Open Space Alternative

The impacts related to the Open Space Alternative would be essentially the same as for the Revised Reuse Plan Alternative. None of the impacts under this alternative would be significant.

Not Significant Impacts

Hazardous Materials and Waste Management Practices

Under this alternative, as under the Revised Reuse Plan Alternative, the total quantity of hazardous materials generated, used, and stored on the property could increase or decrease slightly compared to current conditions. Future uses would be tightly controlled under regulations enforced at the time of base closure and would not be considered significant.

Asbestos

Impacts would be similar to those under the Revised Reuse Plan Alternative.

Polychlorinated Biphenyls

Impacts would be similar to those under the Revised Reuse Plan Alternative.

Storage Tanks and Oil/Water Separators

Impacts would be similar to those under the Revised Reuse Plan Alternative.

4.13 Hazardous Materials and Waste

Pesticides

Impacts would be similar to those under the Revised Reuse Plan Alternative.

Lead

Impacts would be similar to those under the Revised Reuse Plan Alternative.

Medical Materials and Waste

Impacts would be similar to those under the Revised Reuse Plan Alternative.

No Impacts

Radon

Impacts would be similar to those under the Revised Reuse Plan Alternative.

4.13.4 No Action Alternative

The No Action Alternative would involve the storage and use of general maintenance-related hazardous materials, such as paint, thinners, and fuel. Any hazardous waste generated during the caretaker period would be managed under the appropriate hazardous waste regulations. Separate NEPA analysis and documentation, including hazardous materials impact evaluation, would be completed before Navy approval of any interim leases prior to final property transfers.

Not Significant Impacts

Asbestos

Any demolition or repair of existing buildings performed as part of caretaker activities under this alternative would be performed in accordance with applicable regulations controlling asbestos emissions and handling procedures. Asbestos materials will degrade over time and result in occasional abatement activities. No significant impacts are expected.

Pesticides

Under the No Action Alternative, caretaker activities may require application of pesticides. The amounts used are likely to be less than those used at present. No significant impacts are expected.

No Impacts

Hazardous Materials and Waste Management Practices

Under the No Action Alternative, the quantity of hazardous materials used, generated, stored, and disposed of would be minimal. Only limited quantities of hazardous materials, associated with facility caretaker activities, would be used. No impacts would be expected.

Polychlorinated Biphenyls

The Navy would continue to carry out its PCB removal program under the alternative. No impacts are expected.

Storage Tanks and Oil/Water Separators

Removal of inactive tanks and remediation of any residual contamination would be required at the time the facility was closed. These actions would preclude any impacts following closure of the facility.

Lead

The No Action Alternative would not impact lead or lead remediation activities at DODHF Novato.


Medical Materials and Waste

No medical materials or wastes would be used or produced during the caretaker period. There would be no impacts from this alternative.

Radon

No significant radon concentrations have been detected. There would be no uses under this alternative that would warrant further testing. No impacts are expected.

**DODHF
Novato**



5.0 OTHER CONSIDERATIONS REQUIRED BY NEPA

| | | |
|-----|---|------|
| 5.1 | CUMULATIVE IMPACTS | 5-1 |
| 5.2 | GROWTH-INDUCING IMPACTS | 5-15 |
| 5.3 | UNAVOIDABLE ADVERSE EFFECTS | 5-16 |
| 5.4 | SHORT-TERM USES AND LONG-TERM PRODUCTIVITY | 5-16 |
| 5.5 | IRREVERSIBLE/IRRETRIEVABLE COMMITMENT OF RESOURCES | 5-17 |
| 5.6 | ENVIRONMENTAL JUSTICE | 5-18 |

5. OTHER CONSIDERATIONS REQUIRED BY NEPA

This chapter addresses specific topics that NEPA requires in an EIS. These include an analysis of cumulative impacts, an analysis of growth-inducing impacts, the identification of any irreversible or irretrievable commitment of resources, the relationship between short-term uses and long-term productivity, and identification of any unavoidable adverse impacts from implementation of the alternatives. Issues related to environmental justice also are presented, in accordance with Executive Order 12898.

5.1 CUMULATIVE IMPACTS

An EIS must discuss cumulative impacts when they are significant, and when not significant, the document should explain the basis for that conclusion. Cumulative impacts are defined as two or more individual effects that, when considered together, are considerable or that compound or increase other environmental impacts. Individual effects may be changes resulting from a single project or a number of separate projects. Cumulative effects from several projects are the change in the environment that results from the incremental impact of the project when added to other closely related past, present, and reasonably foreseeable future projects. Cumulative effects can result from individually minor but collectively significant projects occurring over the lifetime of the project under consideration.

Analysis of cumulative impacts must include regional effects in addition to potentially cumulatively significant localized effects. The region considered in this analysis is Marin County except for air quality and biological resource issues, when the entire San Francisco Bay Area is considered. The alternatives would be implemented concurrently with other projects in the region of the project that could contribute to local and regionally cumulative impacts.

The methodology used to develop the cumulative analysis included reviewing the current general plans for the City of Novato and Marin County and compiling a list of ongoing and proposed specific projects near DODHF Novato that could reasonably contribute to cumulative impacts. Multiple sources were used to identify reasonably foreseeable projects because the general plans for the area do not include some of the most recent land use proposals in the DODHF Novato area. A list of cumulative projects is presented in Table 5-1, and their location is shown in Figure 5-1. The listed projects were considered with the disposal and reuse of DODHF Novato to prepare the following cumulative analysis.


**Table 5-1
Cumulative Projects**

| Project Name | Project Description | Status | Environmental Documentation |
|---|--|---|--|
| Bel Marin Keys Unit 5 | Construction of 796 houses, 2,500 square foot community center, yacht club, swim and tennis club, and golf course. | Original application deemed incomplete. | None |
| New Hamilton Partnership | Construction of 920 homes north of Hamilton Field. | Under construction. | Final EIR |
| Buck Center for Research In Aging | Construction of Biomedical research complex and 130 homes on 180 acres on the eastern slopes of Mount Burdell. | Annexation to City of Novato approved. Construction has started. | Final EIR |
| Hamilton Army Airfield Reuse | Return runway to wetlands. | New levee under construction by New Hamilton Partnership. | Final EIS |
| Transfer of Spanish Housing to US Coast Guard | USCG use of 282 housing units in the Spanish Housing area of DODHF Novato | Awaiting finalization of Federal property transfer | Final NEPA Categorical Exclusion |
| Novato Redevelopment Project | City land use control established to replan and reuse a previously underutilized area. Five areas are encompassed within the project area, including Vintage Oaks Shopping Center and Rowland Plaza. | Vintage Oaks Shopping Center area has been built out and Rowland Plaza area is partially built out. | Final EIR on Vintage Oaks Shopping Center. |

5.1.1 Major Cumulative Projects in the Vicinity of the Proposed Action

Six major projects located in the area immediately adjacent to DODHF Novato have the greatest potential for cumulative impacts with the reuse alternatives. These projects are the Bel Marin Keys Unit 5 development, the New Hamilton Partnership development, the Buck Center for Research in Aging, the disposal and reuse of the Hamilton Army Airfield property, transfer of the Spanish Housing area to the USCG, and a Novato shopping center redevelopment plan (see Figure 5-1).

Bel Marin Keys Unit 5. Plans for Bel Marin Keys Unit 5, which is located immediately northeast of the Hamilton Army Airfield, include 796 residential dwelling units, a neighborhood commercial center, an 18-hole golf course, a social center, a marina, a habitat enhancement program, and related roadway and other infrastructure facilities. The entire development would be situated around a 463-acre expansion to the existing lagoon that currently serves Bel Marin Keys Units 3 and 4. Area planners expect the revised development plan to include fewer residential units. The development application for this project was submitted in early 1996 but was deemed incomplete by the City of Novato.



In addition to these developments, the Buck Center for Research in Aging is proposed for development at the northern edge of the Novato City limits.

LEGEND:

- | | |
|---------------------------------------|---------------------------------------|
| 1 DODHF-Novato Reuse | 4 Bel Marin Keys Unit 5 |
| 2 Hamilton Army Airfield Reuse | 5 Novato Redevelopment Project |
| 3 New Hamilton Partnership | 6 USCG Spanish Housing |

Cumulative Project Location

DOD Housing Facility
Novato, California

Figure 5-1

5. Other Considerations Required by NEPA

New Hamilton Partnership (NHP) Master Plan. This master plan project involves development of a 415-acre parcel of land immediately adjacent to DODHF Novato. The parcel was also a part of the historic Hamilton Army Airfield but is now owned by private developers. Plans call for development of 920 dwelling units and approximately 600,000 to 800,000 square feet of commercial and office space. This project is approved and ground has been broken. The NHP Master Plan is incorporated into the Reuse Plan by reference.

Buck Center for Research in Aging. The Buck Center for Research in Aging is located adjacent to the City of Novato northern limits west of US 101. The project consists of a 220,000 square foot research facility and 135 housing units for research assistants and personnel. The facility was approved by the Marin County Board of Supervisors in 1995. Proposition B, passed by City of Novato voters in 1995, approved the project and the initiative to annex the area to the City of Novato. The Novato City Council approved the annexation in February 1996. Construction has begun on the facility.

Hamilton Army Airfield - Disposal and Reuse. This action by the US Army includes disposal and reuse of the 720-acre Hamilton Army Airfield immediately northeast of Spanish Housing, the Officers' Club, the Town Center, and the Ballfields. This parcel contains the historic airfield and a number of airplane hangars and other structures. Although the EIS for the site included a number of reuse alternatives, the City of Novato has requested that the majority of the site become salt marsh wetlands. This would be accomplished by breaching the existing levee system adjacent to San Pablo Bay and allowing bay tidal flows to inundate the airfield parcel. Over a period of 10 to 20 years, natural tidal action would create salt marsh wetlands.

Transfer of Spanish Housing to USCG. The Navy is transferring ownership of the land and facilities in the 142-acre Spanish Housing planning area of DODHF Novato to the USCG. The USCG will use the 282 residential units on this site to house personnel working in the San Francisco Bay area.

Novato Redevelopment Project. The Novato Redevelopment Project is a special land use control in place on 400 acres east of US 101 between SR 37 and Rowland Boulevard. The project was established to replan and reuse a previously underutilized area to increase employment opportunities and to provide public improvements. The redevelopment project includes five parcels of land. One parcel, Vintage Oaks, is built out as the Vintage Oaks Shopping Center, and another parcel, Rowland Plaza, is partially built out. The EIR for the shopping center evaluated cumulative impacts of project buildout.

5.1.2 Cumulative Effects of Reuse Alternatives

The reuse alternatives, in conjunction with other major military and nonmilitary projects in the region, would result in cumulative impacts to several resources. Some of these impacts, such as land use and socioeconomics, would be beneficial. Other impacts would be fully or potentially offset through the planning process or specific mitigation measures. Potentially significant unmitigable cumulative impacts have been identified for traffic and circulation. Cumulative impacts projected to occur are described below.

Land Use

Cumulative land use effects of the Bel Marin Keys, NHP developments, and Hamilton Army Airfield reuse are addressed in the Novato General Plan and the Marin Countywide Plan. These two planning documents have analyzed reasonably foreseeable growth and include the reuse of DODHF Novato as part of that expected growth. The planned reuse of DODHF Novato in combination with these projects is not expected to have significant land use effects because the proposed land uses are similar and none of the proposed uses would preclude other proposed or foreseeable uses. The most significant cumulative land use impact to the planning area is the conversion of land from open space uses to urban uses. Long-term attempts to control the rate of conversion indicate that development throughout the county should be focused in the eastern portion of the county near US 101. The proposed reuse under each of the alternatives primarily is adaptive reuse of existing developed areas and does not change current open space to urban uses. None of the alternatives, therefore, contribute to this cumulative impact.

The Marin Countywide Plan identifies a shortage of developed recreational facilities, and the Novato General Plan indicates an excess of undeveloped open space and shortage of developed recreational facilities. The Novato General Plan recommends five acres of developed recreation per 1,000 residents for each new residential development. Cumulative growth in the region should attempt to address this discrepancy by providing more developed recreational opportunities in the area. All reuse alternatives analyzed included a provision for developed recreation facilities consistent with the population growth. The Revised Reuse Plan Alternative would include an adequate amount of developed recreational facilities for its share of population growth. The Open Space Alternative would provide more recreational facilities than required for its share of population growth, and would therefore improve the recreational balance in the county.

Visual Resources

Under the Revised Reuse Plan Alternative, most structures would be adaptively reused, and Rafael Village would be rebuilt with residential housing consistent with local planning requirements. Under the Open Space Alternative, Rafael Village housing would be replaced with open space, and under the No Action Alternative, visual resources would not change. The reuse alternatives would not have significant visual impacts and when considered in combination with the cumulative projects identified in Figure 5-1, would not contribute to significant cumulative visual impacts in the region of influence (ROI). The projects identified in Figure 5-1 would result in increased public access and viewing opportunities of the former Hamilton Army Airfield. Projects involving construction of new structures would be subject to review and analysis of visual compatibility by the City of Novato. There would be no significant cumulative visual impacts from any alternative.

Socioeconomics

Reuse of DODHF Novato under all alternatives, in combination with other projects in the region, would generate substantial job opportunities in Marin County. These new jobs would indirectly create a need for additional support services that could generate additional jobs. This would be a cumulatively beneficial economic impact.

Public Services

Reuse of DODHF Novato under all alternatives, added to other planned public and private development in the City of Novato, would add to cumulative demands on Novato's police, fire, and emergency medical service departments. These impacts would be offset by added taxes and other revenues generated from such development. Additional revenues would fund increased services.

Utilities

The proposed development alternatives for DODHF Novato do not indicate the need for utilities capacities significantly different from existing or recent historical levels. However, the Ignacio Treatment Plant may need to be upgraded to handle the potential wastewater generated from Phase II of the NHP development.

Because several of the utility systems at DODHF Novato are connected to the utilities serving the Spanish Housing area that is being transferred to USCG, future developers would need to provide new metering facilities and may need to provide other system upgrades to effectively split the systems to serve both

5. Other Considerations Required by NEPA

areas. The USCG will maintain separate utility systems without metering for individual housing units.

Cultural Resources

The New Hamilton Partnership development and the disposal and reuse of the Army property have altered the character of the NRHP district at Hamilton Army Air Field, as evidenced by the reevaluation of the district (see Sections 3.6 and 4.6, Cultural Resources, and Appendix E). The EIS for the Army disposal of their property discussed cumulative impacts on the historical district. Impacts were mitigated for the entire historic district, including the DODHF Novato Main Site property, through extensive HABS recordation, public interpretation programs, museum displays, and permanent curation of historical documents. Since mitigation has been completed by the Army for the entire historic district and the City of Novato intends to preserve and reuse historic properties on DODHF Novato, no cumulative impacts from the DODHF Novato disposal would occur. USCG use of the Spanish Housing area would ensure continued government occupation and Federal protection for the historic and architecturally significant housing units in this area.

Biological Resources

The region of analysis for biological resources is the San Francisco Bay Area. Within the past century, nearly 98 percent of the wetlands in the Bay Area have been removed by fill or other development activities. The removal of additional wetlands habitat adjacent to the bay could constitute a significant impact. Development of the railroad right-of-way through Capehart Housing could result in the loss of a small area of wetlands. Such a loss, along with the potential removal of several acres of wetlands for the New Hamilton Partnership development as identified in the NHP Master Plan, could, if not mitigated, contribute to the cumulative loss of wetlands habitat in the ROI. However, the combined acreage for these potential impacts is relatively small, and the proposed restoration of salt marsh habitat over an area of approximately 700 acres at the Hamilton Army Airfield and an undetermined amount in the revised Bel Marin Keys Unit 5 project would be a net cumulative benefit to wetlands in the ROI.

Geology and Soils

The reuse alternatives would locate additional people in a seismically active area, but would not contribute to cumulative geologic hazards, soil erosion, or impacts in the ROI.

Water Resources

The reuse alternatives could add incrementally to the contribution of nonpoint source runoff contaminants to receiving bay waters. This would be offset by upgrading of the stormwater and sanitary sewer systems and implementation of required NPDES stormwater pollution prevention measures. Therefore, this impact would be mitigated at DODHF Novato and would not contribute to cumulative impacts on this resource.

Traffic and Circulation

This section presents the traffic analysis for cumulative conditions under the city's Preferred General Plan scenario and describes the improvements that would be required in order to improve transportation facility service levels. For the purpose of this analysis, future background traffic conditions have been projected assuming local intersection and roadway improvements as identified in the NHP Master Plan. These improvements include the following:

- A new loop on-ramp to intersect with Nave Drive at the existing US 101 northbound off-ramp just south of Ignacio Boulevard;
- Reconfiguration of the intersection of Ignacio Boulevard @ Nave Drive/US 101 on-ramp to eliminate the eastbound left-turn and to add an exclusive eastbound right-turn lane to tie the intersection with the new loop on-ramp;
- Increasing the sight distance at the southbound off-ramp to Enfrente Boulevard;
- An extension of the auxiliary lane on US 101 from the Enfrente Boulevard southbound off-ramp to the US 101 loop off-ramp to Ignacio Boulevard;
- Significant improvements to Nave Drive, including providing additional turn lanes at intersections and provision of continuous channelization, bicycle lanes, and bus turnout areas; and
- Signalization of the intersections of Nave Drive @ New Loop Road, Nave Drive @ State Access Road, Nave Drive @ Main Gate Road, Nave Drive @ Bolling Drive, and Alameda del Prado @ Clay Court.

In addition to these improvement assumptions, transportation improvements also have been identified in the Preferred General Plan scenario of the city's Updated General Plan. These improvements include widening US 101 north of Atherton Avenue (into Sonoma County) to six lanes and further

5. Other Considerations Required by NEPA

improvements to the intersection of Ignacio Boulevard @ Nave Drive/US 101 on-ramp (restripe one eastbound through-lane to a shared right/through-lane).

Although this analysis of cumulative conditions represents conditions under the city's Preferred General Plan scenario, the extension of Hamilton Drive from the Bel Marin Keys area to State Route 37 identified in the Preferred General Plan was not included. This roadway improvement was removed from the traffic analysis conducted for this EIS because it is extremely speculative whether the subject link could actually be built from engineering, environmental, and funding perspectives. Removal of this improvement results in the most realistic traffic analysis scenario. This results in a higher right turning volume on the westbound approach at the intersection of Ignacio Boulevard @ Nave Drive under this analysis than the Preferred General Plan.

Cumulative background traffic volumes were obtained from the Novato General Plan Transportation Revision Transportation Background Report #3 (W-Trans, Inc. 1995).

Intersection Operations

In order to assess the impacts of cumulative conditions on the local intersections, AM and PM peak hour operations analyses were performed at 20 key intersections. Tables 5-2 and 5-3 summarize the intersection operations under cumulative conditions. Sixteen of the 20 key intersections would operate at or above the city's acceptable criteria of average delay of under 30 seconds per vehicle for unsignalized intersections and under 40 seconds for signalized intersections (LOS D) during AM and PM peak traffic hour. Four intersections along Ignacio Boulevard (Ignacio Boulevard @ Sunset Parkway, Ignacio Boulevard @ Entrada Drive, Ignacio Boulevard @ Safeway Access, and Ignacio Boulevard @ Nave Drive) would function below the city's acceptable criteria during one or more peak hour as discussed below.

- The four-way stop controlled intersection of Ignacio Boulevard @ Sunset Parkway would have delays of over 45 seconds (LOS F) during both the AM and PM peak hours under future conditions with the Preferred General Plan. This intersection currently operates with delays of over 45 seconds (LOS F) during the AM peak hour and with delays of between 30 and 45 seconds (LOS E) during the PM peak hour. Motorists traveling through this intersection during peak periods would experience long delays at this intersection.

5. Other Considerations Required by NEPA

**Table 5-2
Cumulative Intersection Levels of Service
AM Peak Hour**

| Intersections | Control Type | Preferred General Plan ¹ | | |
|--|-----------------------------|-------------------------------------|-----------------|-----|
| | | V/C | Delay (seconds) | LOS |
| Ignacio Blvd @ Sunset Pkwy | Stop (T Intersection) | 2.53 | OVRFL | F |
| Ignacio Blvd @ Sunset Pkwy ² | Signal (T Intersection) | 0.57 | 9.60 | B |
| Ignacio Blvd @ San Jose Blvd W | Stop (T Intersection) | n/a | 0.30 | A |
| Ignacio Blvd @ San Jose Blvd E | Stop (T Intersection) | n/a | 2.50 | A |
| Ignacio Blvd @ Palmer Dr. | Signal (T Intersection) | 0.28 | 8.10 | B |
| Ignacio Blvd @ Entrada Dr. | Stop (T Intersection) | n/a | 9.50 | B |
| Ignacio Blvd @ Entrada Dr ² | Signal (T Intersection) | 0.31 | 3.80 | A |
| Ignacio Blvd @ Safeway Access | Stop (4-way Intersection) | n/a | 5.10 | B |
| Ignacio Blvd @ Safeway Access ² | Signal (4-way Intersection) | 0.49 | 13.60 | B |
| Ignacio Blvd @ Alameda Del Prado | Signal (4-way Intersection) | 0.58 | 19.10 | C |
| US 101 SB Off @ Enfrente Blvd | Stop (T Intersection) | n/a | 1.40 | A |
| Ignacio Blvd @ Enfrente Blvd | Signal (4-way Intersection) | 0.64 | 20.90 | C |
| Ignacio Blvd @ Nave Dr. | Signal (T Intersection) | 0.93 | 21.70 | C |
| Ignacio Blvd @ Nave Dr ² | Signal (T Intersection) | 0.93 | 20.40 | C |
| US 101 NB Off @ Nave Dr. | Signal (T Intersection) | 0.60 | 12.50 | B |
| Roblar Dr. @ Nave Dr. | Stop (T Intersection) | n/a | 0.60 | A |
| New Loop Rd @ Nave Dr. | Signal (T Intersection) | 0.51 | 7.60 | B |
| State Access Rd @ Nave Dr. | Signal (T Intersection) | 0.48 | 3.00 | A |
| Main Gate Rd @ Nave Dr. | Signal (T Intersection) | 0.68 | 16.80 | C |
| Bolling Dr. @ Nave Dr. | Signal (T Intersection) | 0.58 | 6.30 | B |
| US 101 Off-Ramp @ Nave Dr. | Yield (T Intersection) | n/a | 0.20 | A |
| Nave Dr. @ Alameda Del Prado | Signal (4-way Intersection) | 0.48 | 8.70 | B |
| US 101 SB Ramp @ Alameda Del Prado | Stop (T Intersection) | n/a | 10.70 | C |
| Main Gate Rd @ Randolph Dr. | Signal (T Intersection) | 0.45 | 0.30 | A |

NOTE:

¹ Represents cumulative conditions under the City of Novato's Preferred General Plan.

² Represents level of service conditions with improvements.

n/a - Volume to capacity ratio not applicable for unsignalized intersections.

OVRFL - Overflow

5. Other Considerations Required by NEPA

Table 5-3
Cumulative Intersection Levels of Service
PM Peak Hour

| Intersections | Control Type | Preferred General Plan ¹ | | |
|--|-----------------------------|-------------------------------------|-----------------|-----|
| | | V/C | Delay (seconds) | LOS |
| Ignacio Blvd @ Sunset Pkwy | Stop (T Intersection) | 1.93 | 521.40 | F |
| Ignacio Blvd @ Sunset Pkwy ² | Signal (T Intersection) | 0.51 | 8.20 | B |
| Ignacio Blvd @ San Jose Blvd W | Stop (T Intersection) | n/a | 0.70 | A |
| Ignacio Blvd @ San Jose Blvd E | Stop (T Intersection) | n/a | 34.50 | D |
| Ignacio Blvd @ Palmer Dr. | Signal (T Intersection) | 0.39 | 3.60 | A |
| Ignacio Blvd @ Entrada Dr. | Stop (T Intersection) | n/a | 168.30 | F |
| Ignacio Blvd @ Entrada Dr ² | Signal (T Intersection) | 0.51 | 4.20 | A |
| Ignacio Blvd @ Safeway Access | Stop (4-way Intersection) | n/a | 422.80 | F |
| Ignacio Blvd @ Safeway Access ² | Signal (4-way Intersection) | 0.86 | 22.10 | C |
| Ignacio Blvd @ Alameda Del Prado | Signal (4-way Intersection) | 0.69 | 10.00 | B |
| US 101 SB Off @ Enfrente Blvd | Stop (T Intersection) | n/a | 3.40 | A |
| Ignacio Blvd @ Enfrente Blvd | Signal (4-way Intersection) | 0.95 | 27.00 | D |
| Ignacio Blvd @ Nave Dr. | Signal (T Intersection) | 1.22 | 98.00 | F |
| Ignacio Blvd @ Nave Dr ² | Signal (T Intersection) | 1.02 | 32.10 | D |
| US 101 NB Off @ Nave Dr. | Signal (T Intersection) | 0.82 | 10.70 | B |
| Roblar Dr. @ Nave Dr. | Stop (T Intersection) | n/a | 3.80 | A |
| New Loop Rd @ Nave Dr. | Signal (T Intersection) | 0.74 | 8.80 | B |
| State Access Rd @ Nave Dr. | Signal (T Intersection) | 0.79 | 12.80 | B |
| Main Gate Rd @ Nave Dr. | Signal (T Intersection) | 0.85 | 20.80 | C |
| Bolling Dr. @ Nave Dr. | Signal (T Intersection) | 0.58 | 5.00 | B |
| US 101 NB Ramps @ Nave Dr. | Yield (T Intersection) | n/a | 0.50 | A |
| Nave Dr. @ Alameda Del Prado | Signal (4-way Intersection) | 0.49 | 6.70 | B |
| US 101 SB Ramp @ Alameda Del Prado | Stop (T Intersection) | n/a | 3.60 | A |
| Main Gate Rd @ Randolph Dr. | Signal (T Intersection) | 0.45 | 0.30 | A |

NOTE:

¹Represents cumulative conditions under the City of Novato's Preferred General Plan.²Represents level of service conditions with improvements.

n/a - Volume to capacity ratio not applicable for unsignalized intersections.

5. Other Considerations Required by NEPA

- The unsignalized T-intersection of Ignacio Boulevard @ Entrada Drive would have delays of over 45 seconds (LOS F) during the PM peak hour under the Preferred General Plan scenario. Side street traffic from Entrada Drive and left turns from Ignacio Boulevard to Entrada Drive would experience long delays when waiting for gaps in traffic on Ignacio Boulevard. Although this intersection operates poorly under conditions with the Preferred General Plan, it would operate acceptably with delays of under 30 seconds (LOS D) or better with the Revised Reuse Plan Alternative or any of the reuse alternatives.
- The unsignalized T-intersection of Ignacio Boulevard @ the Safeway store access would have delays of over 45 seconds (LOS F) during the PM peak hour under the Preferred General Plan scenario. Side street traffic from the Safeway access and left turns from Ignacio Boulevard to the driveway would experience long delays when waiting for gaps in traffic on Ignacio Boulevard. Operation of this intersection would improve under the reuse scenarios.
- The signalized intersection at Ignacio Boulevard @ Nave Drive/US 101 on-ramp would have delays of over 60 seconds (LOS F) during the PM peak hour under the Preferred General Plan scenario even with improvements (converting an eastbound through lane to a shared through/right-turn lane) described in the General Plan. Motorists would experience delays of a minute or more at this intersection in the future. This poor level of operation would result from cumulative development in the area. Operation of this intersection would improve to LOS E or better under the reuse alternatives.

Freeway Operations

As noted earlier, freeway analysis conducted for this EIS assumes that US 101 would be widened to six lanes north of Atherton Avenue and into Sonoma County within the next 20 years. This assumption has been included because it is included in the City of Novato's General Plan. No funding has been earmarked for this improvement, and there is likely to be considerable resistance to the widening. If this improvement cannot be constructed, the impacts of cumulative development on US 101 would be even more severe than those described below.

Freeway operations under cumulative conditions were performed on four segments along US 101 and State Route 37. Only one of the four freeway segments, US 101 north of Atherton Avenue, would function acceptably under cumulative conditions. Three of four key freeway segments analyzed (US 101 between State Route 37 and Ignacio Boulevard, US 101 south of Ignacio Boulevard, and State Route 37 between US 101 and Atherton Avenue) would exceed the city's freeway level of service criteria of no more than 1,824

5. Other Considerations Required by NEPA

passenger cars per hour per lane (LOS D) during peak periods. Table 5-4 presents a summary of the freeway levels of service for cumulative conditions. The operations of each freeway segments are discussed in more detail below.

US 101 southbound between Ignacio Boulevard and State Route 37 would exceed 2,300 cars per hour per lane (LOS F) during the AM peak hour and have between 1,824 and 2,300 cars per hour per lane (LOS E) during the PM peak hour. US 101 northbound between Ignacio Boulevard and State Route 37 would exceed 2,300 cars per hour per lane (LOS F) during the PM peak period.

US 101 southbound south of Ignacio Boulevard would have between 1,824 and 2,300 cars per hour per lane (LOS E) during the AM peak hour. US 101 northbound south of Ignacio Boulevard would exceed 2,300 cars per hour per lane (LOS F) during the PM peak hour.

State Route 37 eastbound between US 101 and Atherton Avenue would have between 1,824 and 2,300 cars per hour per lane (LOS E) in the PM peak hour.

Table 5-4
Cumulative Freeway Levels of Service

| Locations | AM Peak Hour | | PM Peak Hour | |
|-----------------------|--------------|-----|--------------|-----|
| | Volume | LOS | Volume | LOS |
| US Highway 101 | | | | |
| N/O Atherton - NB | 2,922 | C | 4,349 | D |
| N/O Atherton - SB | 4,713 | D | 3,796 | C |
| 37 to Ignacio - NB | 4,029 | C | 8,822 | F |
| 37 to Ignacio - SB | 7,499 | F | 6,089 | E |
| S/O Ignacio - NB | 3,799 | C | 8,512 | F |
| S/O Ignacio - SB | 6,847 | E | 5,326 | D |
| State Route 37 | | | | |
| 101 to Atherton - WB | 3,378 | D | 2,171 | C |
| 101 to Atherton - EB | 1,107 | B | 4,007 | E |

5. Other Considerations Required by NEPA

Transportation System Improvements

In order to improve traffic operations in the study area, several improvements to the local intersections and roadways would be necessary.

Intersection Improvements. Improvements are required to improve intersection operations at the four impacted intersections. Tables G-1 and G-2 in Appendix G present a summary of the intersection operations and control types with the proposed improvements. The following improvements are required to improve intersection operations:

- Signalize the intersections of Ignacio Boulevard @ Entrada Drive, Sunset Parkway, and Safeway access. Signalization of these three intersections would significantly improve their levels of service from LOS F to LOS A, B, and C, respectively, during the PM peak hour (see Table 5-3).
- Add a westbound right-turn lane at the intersection of Ignacio Boulevard @ Nave Drive. In order to provide this turn lane, it would be necessary to widen the Bel Marin Keys Boulevard bridge of the Northwest Pacific Railroad. This would improve the intersection's level of service from LOS F to LOS D during the PM peak hour.

Freeway Improvements. Under cumulative conditions, US 101 and State Route 37 would continue to function at LOS F. In order to improve these conditions it would be necessary to widen both facilities. However, given current funding levels for freeway projects and other political and environmental factors that would make widening difficult, it is unlikely that improvements would be made to these facilities within the 20-year time frame of this cumulative analysis.

Air Quality

For air quality, the cumulative ROI is the San Francisco Bay Area. The proposed reuse alternatives would contribute traffic to the local and regional transportation system. The reuse alternatives would thereby contribute to the cumulative air emissions in the project area. Additionally, cumulative traffic, and therefore air emission levels, under all reuse alternatives would be less than under the City of Novato Preferred General Plan scenario.

Noise

The proposed reuse alternatives would contribute traffic to the local and regional transportation system, thereby contributing to the cumulative noise level in the project area. However, cumulative traffic levels under all reuse alternatives would be less than under the Preferred General Plan scenario and would not contribute significantly to cumulative noise levels. The significant

5. Other Considerations Required by NEPA

noise impacts associated with the project result from residents of reuse housing being exposed to existing sources of noise on US 101. This is a project-specific impact that would not add to cumulative noise impacts.

Hazardous Materials and Waste

The cleanup of hazardous materials and waste between closure of DODHF Novato and buildout of the reuse alternatives, as well as cumulative base conversion projects throughout the Bay Area region, would have a beneficial impact on the regional environment and would occur under the Revised Reuse Plan Alternative, Open Space Alternative, and No Action Alternative. All contaminated areas would be remediated by the Navy to levels protective of human health and the environment.

5.2 GROWTH-INDUCING IMPACTS

An EIS must discuss the ways in which the proposed action and alternatives could foster economic or population growth or the construction of additional housing, either directly or indirectly, in the area surrounding the project. Analysis of growth-inducing effects includes those characteristics of the action that may encourage and facilitate activities that, either individually or cumulatively, would affect the environment. Population increases, for example, may impose new burdens on existing community service facilities. Similarly, improvement of access routes may encourage growth in previously undeveloped areas. Growth may be considered beneficial, adverse, or of no significance environmentally, depending on its actual impacts to the environmental resources present.

The reuse alternatives would create a substantial number of jobs due to development of community facilities and commercial land uses. The Revised Reuse Plan Alternative would directly create approximately 938 new jobs. Reuse of existing housing (and replacement of the Rafael Village units) would provide housing opportunities. The combination of new housing and job creation under the Revised Reuse Plan Alternative would result in a direct population increase within Marin County of approximately 3,432 people at buildout. The Open Space Alternative also would result in growth in population and employment, producing 994 jobs and 2,275 people. The No Action Alternative would have little effect on population and employment by creating five jobs and two additional ROI residents.

The increase in population and jobs under each alternative also would have the indirect effect of creating an undetermined number of additional jobs to provide support services for new residents and jobholders. These induced jobs would further induce new economic and population growth in the region. This increase in population cannot be considered completely new because the

5. Other Considerations Required by NEPA

housing units were occupied by military personnel prior to closure of DODHF Novato. Neither the direct or indirect growth under any of the reuse alternatives would be considered a significant adverse impact.

The reuse alternatives would reuse existing developed areas with existing infrastructure and would therefore not induce growth through extension of utilities or services.

5.3 UNAVOIDABLE ADVERSE EFFECTS

An EIS must describe any significant adverse environmental impacts for which either no mitigation or only partial mitigation is feasible, and may include imposing an alternative design on the alternatives if that is the only means of avoiding such impacts. For the majority of the identified significant impacts, feasible mitigations have been identified to reduce the impact to a not-significant level. Impacts for which no feasible mitigation measures have been identified are considered to be unavoidable adverse impacts. An unavoidable noise impact has been identified in the EIS. The Revised Reuse Plan Alternative would locate people in housing units in the Capehart Housing and Rafael Village areas. Both of these areas have existing ambient noise levels significantly above the land use compatibility guidelines (60 dB) provided in the Novato General Plan. The allowable level currently is exceeded to a distance of 1,500 feet from the centerline of US 101 due to noise from traffic. The allowable noise level is exceeded in Rafael Village north and south of Ignacio Boulevard to a distance exceeding 750 feet from the centerline of the road, an area encompassing most of Rafael Village. The remaining planning areas would not be exposed to noise levels exceeding the standards for their specific type of land use. Although sound walls would reduce ambient noise levels by approximately 5 dB, the noise levels would still be significant in those areas nearest US 101 and Ignacio Boulevard. The Open Space Alternative would have the same impact in the Capehart Housing area, but not in Rafael Village. No unavoidable adverse impacts would occur under the No Action Alternative.

5.4 SHORT-TERM USES AND LONG-TERM PRODUCTIVITY

NEPA requires that an EIS consider the relationship between short-term uses of the environment and the maintenance and enhancement of long-term productivity. The productivity of DODHF Novato historically has been related to its operation as a military housing support facility, and the resulting military jobs and services it has provided. Since the Revised Reuse Plan Alternative would make use of properties that could otherwise be left unused, it would improve both the short- and long-term economic productivity of the City of Novato and Marin County over conditions that would occur with a closed, inactive base facility. Interim leasing of properties during the period

that long-term tenants are being recruited also could add to the short-term productivity of DODHF Novato. Site remediation and cleanup activities will improve environmental conditions on the facility. The Revised Reuse Plan Alternative, with the mitigation measures identified in this report, would enhance the long-term productivity of the site. Long-term benefits include provision of housing, jobs, and opportunities for various recreational uses, maintenance of open space, and maintenance of various infrastructures on the site. The Open Space Alternative would have similar long-term benefits, but would provide less housing and slightly more jobs than the Revised Reuse Plan Alternative. Under this alternative, the Rafael Village planning area would provide additional open space and park land for recreational uses. The No Action Alternative would not provide housing, jobs, or recreational opportunities and would therefore not enhance the short- and long-term productivity of Novato and Marin.

5.5 IRREVERSIBLE /IRRETRIEVABLE COMMITMENT OF RESOURCES

NEPA requires that an EIS analyze the extent to which the alternatives' primary and secondary effects would commit nonrenewable resources to uses that future generations would be unable to reverse. Federal disposal of DODHF Novato property and structures would not involve irreversible or irretrievable commitments of resources.

Implementation of the Revised Reuse Plan Alternative would largely continue current types of land uses. Because the majority of the Revised Reuse Plan Alternative would be adaptive reuse of existing structures, the Revised Reuse Plan Alternative would generally not require significant commitments of renewable and nonrenewable energy and material resources. However, demolition and construction of the new residences in Rafael Village and of other structures in Commissary Triangle and Exchange Triangle would require an irreversible commitment of the land area of those sites for the foreseeable future and would require an irretrievable commitment of building materials.

The Open Space Alternative also would consist largely of adaptive reuse and would generally not require significant commitments of renewable and nonrenewable energy and material resources. However, compared to the Revised Reuse Plan Alternative, there would be no new structures in Rafael Village. Open space use of this planning area would preserve future land use options.

The No Action Alternative would not require long-term commitment of resources and the site would be available for future use options.

5.6 ENVIRONMENTAL JUSTICE

This section summarizes potential impacts from disposal and reuse of the DODHF Novato facilities on issues of Environmental Justice. As discussed in Section 3.3, the "Executive Order on Federal Actions to Address Environmental Justice in Minority and Low-Income Populations," issued on February 11, 1994, requires that "Each Federal agency shall analyze the environmental effects, including human health, economic and social effects, of Federal actions including effects on minority communities and low-income communities, when such analysis is required, by the National Environmental Policy Act of 1969 (NEPA), 42 U.S.C. section 4321 et.seq. Mitigation measures outlined or analyzed in an environmental assessment, environmental impact statement, or record of decision, whenever feasible, should address significant and adverse environmental effects of proposed Federal actions on minority communities and low-income communities." On April 21, 1995 the Secretary of Defense submitted a formal Environmental Justice strategy and implementation plan to the US EPA.

In order to comply with the Executive Order, this EIS included the following actions:

- Gathering of economic, racial, and demographic information generated from the 1990 census to identify areas of low-income and high minority populations in the vicinity of areas potentially exposed to project impacts;
- Assessment of the disposal and reuse actions for disproportionate impacts resulting from on-site activities associated with reuse of DODHF Novato facilities; and
- Encouragement of community participation and input through public hearings and meetings and extensive public notification, as described in Chapter 1 of this document.

Summary of Environmental Justice Impacts


Issues related to environmental justice are addressed in detail in Sections 3.3 and 4.3, Socioeconomics, of this document. The following discussion summarizes this analysis. The analysis established that the impacts from the proposed disposal and reuse actions would be the same under each reuse alternative and would be mainly beneficial.

None of the alternatives would have a disproportionately high and adverse effect on minority or low-income communities. The Navy disposal action was determined to have no impacts on minority and/or low-income communities as it is a transfer of title. The reuse alternatives would increase the availability of affordable housing units, which would benefit low-income people. All

5. Other Considerations Required by NEPA

other potential impacts of the action would affect all segments of the population in and around the site equally. No one group would be disproportionately impacted, and no mitigations would be required.

**DODHF
Novato**



6.0 CONSULTATION AND COORDINATION

| | | |
|-----|--------------------|-----|
| 6.1 | REPORT PREPARATION | 6-1 |
| 6.2 | SCOPING | 6-2 |

6. CONSULTATION AND COORDINATION

6.1 REPORT PREPARATION

The federal, state, and local agencies and private organizations that were contacted during the course of preparing this EIS are listed below.

City of Novato

T. Balestro, Community Development Department
Gary Barner, Police Department
Brian Brady, Police Department
Demitri Demushka, Engineering Division
Shirley Novak, Community Development Department
John Rentz, Fire Protection District
Al Arendell, Fire Protection District
Sonja Seeman, Community Development Director

County of Marin

Michael Frost, Office of Solid Waste
Tim Haddad, Planning Department

Department of Defense Housing Facility Novato

John Scales
Len Bastion
Diane Wachter

Engineering Field Activity, West

Patricia Duff
Larry Lind
Mike Mahoney
Lou Wall

US Fish and Wildlife Service

Kelly Geer

California Department of Fish and Game

John Brode
Kevin Schaffer

Basin Research Associates, Inc.

Colin Busby

Biosearch Wildlife Surveys

Mark Allaback
David Laabs

CSW Stuber-Stroeh Engineering Group, Inc.

Mike Meyer

Jones and Stokes Associates, Inc.

Dana McGowan

Robert Bein, William Frost, and Associates

Margit Allen
Ken Bell
Gary Miller

Trihey and Associates

Ramona Swenson

6.2 SCOPING

The project mailing list, including agencies, organizations, and individuals that received scoping letters, is provided in Chapter 10. The following parties responded to the scoping request.

Federal Agencies

US Environmental Protection Agency
US Department of Education
US Coast Guard

State Agencies

CA Environmental Protection Agency, Dept. of Toxic Substance Control

Local/Regional Agencies

Historical Resources Information System
Marin Municipal Water District


Organizations

Hamilton Field Preservation Association
Ignacio Neighborhood Committee
Lanham Village Homeowners Association
Marin Audubon Society
Marin Conservation League
Novato Little League
Sierra Club, Marin Group

Individuals

Mr. Donald Dunn
Ms. Diane Dito
Mr. Bill Long
Ms. Betty Pagett
Dr. Merton Shelton

**DODHF
Novato**



7.0 LIST OF PREPARERS

7. LIST OF PREPARERS

Navy

John H. Kennedy

M.A., Geography, University of California Los Angeles.

B.A., Spanish/Geography, University of California, Los Angeles..

Years of Experience: 17

(Navy Environmental Planning Branch Manager)

Douglas Pomeroy

M.S., Wildland Resource Science, University of California, Berkeley.

B.S., Wildlife Management, Humboldt State University.

Years of Experience: 9

(Supervisor, BRAC NEPA Section)

Gary J. Munekawa

B.S., Civil Engineering, University of California, Berkeley

Years of Experience: 20

(Navy NEPA Project Manager)

Patricia J. Duff

M.A., Anthropology, San Francisco State University.

B.A., Anthropology, San Francisco State University.

Years of Experience: 17

(Archaeological Resources)

Louis S. Wall

M.U.R.P., Urban and Regional Planning, George Washington University.

B.S., Urban Geography, University of Maryland.

Years of Experience: 26

(Historic Resources)

Tetra Tech

Project Management

Karen E. Frye

B.S., The Political Economy of Natural Resources, University of California, Berkeley.

Years of Experience: 8

(Project Director, QA/QC)

Thomas Leaf, AICP

M.S., Community and Regional Planning, University of Texas at Austin

B.S., Environmental Resource Management, Pennsylvania State University

B.S., Geology, Pennsylvania State University

Years of Experience: 9

(Project Manager)

Amy Cordle

B.S., Civil Engineering, Virginia Polytechnic Institute and State University

Years of Experience: 4

(Deputy Project Manager)

Technical Team

David Batts

M.S., Natural Resource Planning and Policy, Michigan State University

B.S., International Development, Lewis and Clark College, Portland, Oregon

Years of Experience: 6

(QA/QC)

John Bock

B.S., Environmental Toxicology, University of California, Davis

Years of Experience: 3

(Public Services)

Steve Burger

M.S., Land Resources, University of Wisconsin-Madison

B.A., Environmental Sciences, University of California, Berkeley

Years of Experience: 5

(Solid Waste Management)

Matt Dulcich

B.S., Environmental Policy Analysis and Planning, University of California,

Davis

Years of Experience: 3

(Land Use and Visual Resources)

Bradley S. Hall, R.G.

M.S., Geological Sciences, University of California, Riverside

B.S., Geology, Beloit College, Beloit, Wisconsin

Years of Experience: 7

(Hazardous Materials and Waste)

Fred Moseley, AICP

Ph.D., Political Science, Kent State University, Kent, Ohio

M.A., Political Science, University of Akron, Akron, Ohio

B.A., Philosophy, Phillips University, Enid, Oklahoma

Years of Experience: 20

(QA/QC)

Elizabeth Purl

M.S. Environmental Management, University of San Francisco

B.A., Political Science, Bryn Mawr College, Bryn Maer, Pennsylvania

Years of Experience: 7

(Hazardous Materials and Waste)

Robert Sculley

M.S., Ecology, University of California, Davis

B.S., Zoology, Michigan State University

Years of Experience: 22

(Air Quality, Noise)

Randolph Varney

B.A., Technical and Professional Writing, San Francisco State University

Years of Experience: 12

(Technical Edit)

Tom Whitehead, R.G.

M.S. Hydrology, University of Arizona.

B.S., Geology, California State University, Hayward

Years of Experience: 12

(Geology)

Subconsultants

Buescher Biological Consulting

Kathy Buescher

B.S., Biology, University of Redlands, Redlands

Years of Experience: 7

(Biology)

Fehr & Peers

Matthew Ridgway, AICP

B.A., Urban Studies, San Francisco State University.

Years of Experience: 6

(Traffic and Transportation)

Economics Research Associates

Eleanor Tiglao

M.C.P., City and Regional Planning, University of California, Berkeley

B.A., Economics, California State University, San Francisco

Years of Experience: 5

(Socioeconomics)

Steven Spickard

M.C.P., City and Regional Planning, University of California, Berkeley

B.A., Economics, California State University, San Francisco

Years of Experience: 4

(Socioeconomics)

Grassetti Environmental Consulting

Richard Grassetti

M.A., Geography (Emphasis - Water Resources), University of Oregon

B.A., Physical Geography, University of California, Berkeley

Years of Experience: 14

(Water Resources, QA/QC)

Greiner

Michael Polanski, P.E.

M.S., Civil Engineering, University of Michigan

B.S., Civil Engineering, University of Michigan

B.S., U.S. Naval Academy

Years of Experience: 22

(Utilities)

PAR Environmental

Mary L. Maniery

M.A., Anthropology, California State University, Chico


B.A., Anthropology, California State University, Chico

B.A., History, California State University, Chico

Years of Experience: 18

(Cultural Resources)

**DODHF
Novato**



8.0 REFERENCES

| | | |
|-----|-------------------------|-----|
| 8.1 | BIBLIOGRAPHY | 8-1 |
| 8.2 | PERSONAL COMMUNICATIONS | 8-9 |

8. REFERENCES

8.1 BIBLIOGRAPHY

- A-N West, Inc. 1989. *Special Report HR-12-86; Comprehensive Drainage Study, Navy Housing Facility, Hamilton Field Novato, California*. Prepared for WESTNAVFACENGCOM San Bruno, CA. January 1989.
- Association of Bay Area Governments. 1993. *Projections '94*.
- Association of Bay Area Governments. 1995. *City of Novato, On Shaky Ground City Map*. April, 1995.
- Barry, T. M. and J. A. Reagan. 1978. *FHWA highway traffic noise prediction model*. (FHWA-RD-77-108.) U.S. Federal Highway Administration. Washington, DC.
- Bay Area Air Quality Management District. 1985. *Air Quality and Urban Development Guidelines for Assessing Impacts of Projects and Plans*. San Francisco, CA.
- Beck, Warren A., and Ynez D. Haase. 1974. *Historical Atlas of California*. University of Oklahoma Press, Norman.
- Benson, P. E. 1989. *CALINE4 - A dispersion model for predicting air pollutant concentrations near roadways*. 1984 final report with 1986 and 1989 revisions. (FHWA/CA/TL-84/15.) California Department of Transportation. Sacramento, CA.
- Bickel, P. McW. 1978a. *Changing Sea Levels along the California Coast: Anthropological Implications*. *Journal of California Anthropology*. 5(1):6-20.
- Bickel, P. McW. 1978b. *Corrections to Sea Level Article*. *Journal of California Anthropology* 5(2):296-297.
- Biosystems Books. 1994. *Life on the Edge: A Guide to California's Endangered Natural Resources: Wildlife*. Santa Cruz, California.
- Blake, M.C., Jr., Bartow, J.A., Frizzell, V.A., Jr., Schlocker, J., Sorg, D., Wentworth, C.M., and R.H. Wright. 1974. *Preliminary Geologic Map of Marin and San Francisco Counties and Parts of Alameda, Contra Costa and Sonoma Counties, California*. US Geological Survey, Miscellaneous Field Studies Map 574. Scale 1:63,360.

8. References

- Busby, Colin I. and Donna M. Garaventa, Stuart A. Guedon and Melody E. Tannam. 1995. *Archeological Survey and Sites Evaluation: Disposal and Reuse, Department of Defense Family Housing, Novato, Marin County, California*. Prepared for the Department of the Navy, Engineering Field Activity, West, Naval Facilities Engineering Command, San Bruno, California.
- California Air Resources Board. 1984. *California Surface Wind Climatology*. June 1989.
- California Air Resources Board. 1991a. *Annual Summary of Air Quality Data*.
- California Air Resources Board. 1991b. *Methodology to Calculate Emission Factors for On-road Motor Vehicles*. Technical Support Division. Sacramento, CA.
- California Air Resources Board. 1992a. *Annual Summary of Air Quality Data*.
- California Air Resources Board. 1992b. BURDEN7C: *Methodology for Estimating Emissions from On-road Motor Vehicles*. Technical Support Division. Sacramento, CA.
- California Air Resources Board. 1993a. *Annual Summary of Air Quality Data*.
- California Air Resources Board. 1993b. *Methodology for Estimating Emissions from On-road Motor Vehicles*. Volume I: EMFAC7F. Draft. Technical Support Division. Sacramento, CA.
- California Air Resources Board. 1993c. *Methodology for Estimating Emissions from On-road Motor Vehicles*. Volume II: WEIGHT(E7FWT). Draft. Technical Support Division. Sacramento, CA.
- California Air Resources Board. 1993d. *Methodology for Estimating Emissions from On-road Motor Vehicles*. Volume III: BURDEN7F. Draft. Technical Support Division. Sacramento, CA.
- California Air Resources Board. 1994. *Annual Summary of Air Quality Data*.
- California Department of Finance. 1995. *Marin County Population and Housing Estimates*. Demographic Research Unit.
- California Department of Fish and Game (CDFG). 1989. *Fish Species of Special Concern in California*. October 1989.
- California Department of Fish and Game (CDFG). 1994. *Special Animals List*. National Heritage Division, National Diversity Data Base. August 1994.

8. References

- California Department of Fish and Game (CDFG). 1996a. *California Natural Diversity Data Base*. Natural Heritage Division.
- California Department of Fish and Game (CDFG). 1996b. *Endangered, Threatened, and Rare Plants of California*. Natural Heritage Division, Endangered Plant Program. January 1996.
- California Department of Fish and Game (CDFG). 1996c. *Endangered and Threatened Animals of California*. Natural Heritage Division. July 1996.
- California Department of Fish and Game (CDFG). 1996d. *Special Plants List*. Natural Heritage Division, National Diversity Data Base. January 1996.
- California Department of Health Services. 1987. *Guidelines for Preparation and Content of the Noise Element of the General Plan*. California Office of Planning and Research.
- California Employment Development Department. 1995. *Annual Planning Information for Marin County*. State of California, Employment Development Department.
- California Regional Water Quality Control Board. 1986. *San Francisco Bay Regional Basin Water Quality Control Plan*.
- Chavez, David. 1986. *Cultural Resources Evaluation for the Hamilton Field EIR, City of Novato, Marin County, California*. MS on file, S-8180, Northwest Information Center, Sonoma State University, Rohnert Park, CA.
- Christensen, M.N. 1966. *Quaternary of the California Coast Ranges*. in Bailey, E.H. ed., *Geology of Northern California*. California Division of Mines and Geology, Bulletin 190. pp. 305-313.
- Davenport, C.W. 1984. *An analysis of slope failures in eastern Marin County, California, resulting from the January 3rd and 4th, 1982 storm*. California Division of Mines and Geology, Open File Report 84-225F. 51 pp.
- EIP Associates, Inc. 1993. *Final Subsequent Environmental Impact Report, Hamilton Field Project. Prepared for the City of Novato*. March 1993.
- Environmental Laboratory. 1987. *Corps of Engineers Wetlands Delineation Manual, Technical Report Y-87-1*. US Army Engineers Waterways Experiment Station, Vicksburg, Mississippi.
- ERM-West, Inc. 1994. *Final Limited Baseline Survey for DODHF-Novato*. Prepared for EFA West, NAVFACENGCOM, San Bruno, California. November 30, 1994.

8. References

- ESA Associates, Inc. 1993. *Bel Marin Keys Unit 5 Final Environmental Impact Report/Environmental Impact Statement*. August 1993.
- Eschmeyer, William N. and Herald, Earl S. 1983. *A Field Guide to Pacific Coast Fishes*. Houghton Mifflin Company, Boston.
- Federal Emergency Management Agency (FEMA). 1989. *Flood Insurance Rate Map, City of Novato, California, Marin County*. Panels 4 and 5 of 7. Community-Panel Numbers 060178-0004C and 060178-0005C.
- Goerke, Elizabeth B., and Richard A. Cowan. 1983. *The Pacheco Site (Marin-152) and the Middle Horizon in Central California*. Journal of New World Archaeology. VI(1).
- Hamilton Reuse Planning Authority. 1995a. *Hamilton Army Airfield Reuse Plan Existing Conditions Report*. Prepared by: Robert Bein, William Frost & Associates, Keyser Marston Associates, Fehr & Peers, Edward J. Cass & Associates. May 1995.
- Hamilton Reuse Planning Authority. 1995b. *Hamilton Army Airfield Reuse Plan*. Prepared by: Robert Bein, William Frost & Associates, Keyser Marston Associates, Fehr & Peers, Edward J. Cass & Associates. October 1995.
- Hendriks, R. W. 1984. *California vehicle noise emission levels*. (FHWA/CA/TL-84/13.) California Department of Transportation, Office of Transportation Laboratory. Sacramento, CA.
- Hickman, James C. 1993. *The Jepson Manual: Higher Plants of California*. University of California Press, Berkeley.
- Holland, Robert F. 1986. *Preliminary Descriptions of the Terrestrial Natural Communities of California*. Prepared for State of California, The Resources Agency, Department of Fish and Game.
- Ingles, Lloyd G. 1965. *Mammals of the Pacific States*. Stanford University Press, Stanford, California.
- Kashiwagi, J.H. 1985. *Soil Survey of Marin County, California*. US Department of Agriculture, Soil Conservation Service.
- Kelly, Isabel. 1978. *Coast Miwok*. In *California*, edited by R. F. Heizer, Volume 8. Handbook of North American Indians, W. G. Sturtevant, general editor, pp. 414-425. Smithsonian Institution, Washington, D. C.
- Leonard Charles and Associates. 1995. *Draft Environmental Impact Report, Novato General Plan Revision*. July 1995.

8. References

- Maniery, Mary L., Leslie R. Fryman, and Fred Hrusa. 1993. *National Register of Historic Places Evaluation: Hamilton Army Air Field Historic District, Marin County, California*. Prepared for Jones & Stokes Associates, Inc., Sacramento, and U. S. Army Corps of Engineers, Sacramento, California.
- Maniery, Mary L. 1997. *National Register Eligibility Reevaluation Hamilton Army Airfield Historic District Department of Defense Housing District, Novato, California*. December 1996.
- Marin County. 1994. *Marin Countywide Plan*. Marin County Board of Supervisors.
- Marin County Office of Waste Management. 1996. Unpublished database report provided to Tetra Tech.
- McGinnis, Samuel. 1984. *Freshwater Fishes of California*. University of California Press, Berkeley.
- Melander, Ronald N., and Charles M. Slaymaker, III. 1969. *The Salvage Archaeology of 4-MRN-168: The Pacific Telephone Site, Ignacio, California*. San Francisco State College Archaeological Survey.
- Moratto, Michael J., Thomas F. King, and W. B. Woolfenden. 1978. *Archaeology and California's Climate*. *The Journal of California Anthropology*. 5(2):147-161.
- National Geographic Society. 1992. *Field Guide to the Birds of North America, Second Edition*.
- National Oceanic and Atmospheric Administration. 1985. *Climatology of the United States, Climatic Summaries for Selected Sites, 1951-1980, California*.
- National Wetlands Inventory. 1985. *National Wetlands Inventory Map of the Novato Quadrangle*. Scale 1:24,000. April 1985.
- Nokes, W. A. and P. E. Benson. 1985. *Development of worst case meteorology criteria*. (FHWA/CA/TL-85/14.) California Department of Transportation. Sacramento, CA.
- Novato Chamber of Commerce. 1995. *1994-1995 Novato Economic Profile, 1995 Edition*.
- Novato Fire Protection District. 1994. *1994 Annual Report*.
- Novato, City of. 1981. *1981 Novato General Plan*. City of Novato Planning Department: Novato, California.

8. References

- Novato, City of. 1989. *Trees and Shrubs Ordinance (Revised)*. City of Novato Planning Department.
- Novato, City of. 1990. *Sign Ordinance (Revised)*. City of Novato Planning Department.
- Novato, City of. 1994a. *Environmental Review Guidelines, Revised*. Prepared by: City of Novato Planning Department. September 1994.
- Novato, City of. 1994b. *Streets and Sidewalks (Revised)*. City of Novato Planning Department.
- Novato, City of. 1995a. *Zoning Ordinance*. City of Novato Planning Department.
- Novato, City of. 1995b. *Novato General Plan, Revised Draft*. Prepared by: City of Novato Planning Department. November 1995.
- Novato, City of. 1995c. *Draft Environmental Impact Report for the Novato General Plan Revision*. Prepared by: Leonard Charles and Associates. July 1995.
- Novato, City of. 1995d. *Existing Conditions Report. City of Novato General Plan Report*. Prepared by: City of Novato Planning Department. April 1995.
- Novato, City of. undated. *Design Review Guidelines, handout*. Community Development Department, City of Novato.
- Novato Unified School District (NUSD). *Application for Public Benefit Transfer of Surplus Federal Real Property for Educational Uses*. Novato Unified School District. May 31, 1996.
- Perkins, J.B., and J. Boatwright. 1995. *The San Francisco Bay Area -- On Shaky Ground*. Association of Bay Area Governments (ABAG) Publication No. P95001EQK. April, 1995.
- Petrides, George A. and Olivia. 1992. *Western Trees*. Peterson Field Guides.
- Rice, S.J. 1973. *Geology and Geologic Hazards of the Novato Area, Marin County, California*. California Division of Mines and Geology, Preliminary Report 21.
- San Rafael Independent. 1932. Title Unknown. July 15, 1932, San Rafael, CA.
- Section 334 of the Defense Authorization Act of 1997 (September 1996) amended title 42 U.S.C. 9620(h)(3)(CERCLA) and the authority to transfer contaminated federal property before completion of required response actions.

8. References

- Skinner, Mark W. And Bruce M. Pavlik. 1994. *Inventory of Rare and Endangered Vascular Plants of California*. California Native Plant Society, Sacramento.
- Stebbins, Robert C. 1985. *Western Reptiles and Amphibians, Second Edition*. Houghton Mifflin Company, New York.
- Transportation Research Board. 1994. *Special Report 209: Highway Capacity Manual, Third Addition*.
- US Army Corps of Engineers, Sacramento District, South Pacific Division. 1989. *Hamilton Army Airfield, Novato California, Final Report, Flood Control Study*. May 1989.
- US Army Corps of Engineers. 1993. *National Register of Historic Places Evaluation: Hamilton Army Airfield Historic District, Marin County, California*. Prepared by: Mary Maniery, Leslie R. Fryman, and Fred Hrusa.
- US Army. 1996. *Environmental Impact Statement Hamilton Army Airfield Disposal and Reuse*. Prepared by: US Army Corps of Engineers and Jones and Stokes Associates. February 1996.
- US Census. 1990. *Population and Housing, Summary Tape File 1A, Marin County, CA*.
- US Department of Agriculture. 1987. *Flood Control and Maintenance Plan for San Jose Creek and Pacheco Creek; Department of Defense Housing Facility, Novato, Marin County, California*. Prepared by the USDA River Basin Planning Staff. September 1987.
- US Environmental Policy Agency. 1988. *Application of Radon Reduction Methods*.
- US Environmental Protection Agency. 1995. *The Probability of Sea Level Rise*.
- US Fish and Wildlife Service. 1993. *Plant Taxa for Listing as Endangered or Threatened Species; Notice of Review*. 50 CFR Part 17. November 22, 1993.
- US Fish and Wildlife Service. 1994a. *Endangered and Threatened Wildlife and Plants; Animal Candidate Review for Listing as Endangered or Threatened Species; Proposed Rule*. 50 CFR Part 17. November 15, 1994.
- US Fish and Wildlife Service. 1994b. *Listed and Proposed Endangered and Threatened Species and Candidate Species that may Occur in the area of the Proposed Closure of the Department of Defense Housing Facility, Novato, Marin County, California*. March 5, 1994.
- US Fish and Wildlife Service. 1995a. *Endangered and Threatened Wildlife and Plants*. 50 CFR 17.11& 17.12. September 30, 1995.

8. References

- US Fish and Wildlife Service. 1995b. *Federally Listed Plants in California*. September 1, 1995.
- US Fish and Wildlife Service. 1995c. *Notice of Proposed Endangered Status for Suisun Thistle and Soft Bird's-Beak from Tidal Marshes in the San Francisco Bay Area of Northern California*. June 16, 1995.
- US Fish and Wildlife Service. 1996. *Endangered and Threatened Wildlife and Plants; Review of Plant and Animal Taxa that are Candidates for Listing as Endangered or Threatened Species*. 50 CFR Part 17. February 28, 1996.
- US Geological Survey. 1984. *Preliminary Geologic Map of Marin and San Francisco Counties, California*. Prepared by M.C. Blake Jr., J.A. Bartow, V.A. Frizzell, J. Schlocker, D. Sorg, C.M. Wentworth, and R.H. Wright.
- US Geological Survey. 1980. *Novato, California*. 7.5 Minute Series.
- US Navy. 1986. *Master Plan. DOD Housing Facility, Novato, California*. Prepared by: US Navy Western Division. September 1986.
- US Navy. 1987a. *Flood Control and Maintenance Plan for San Jose Creek and Pacheco Creek*. Prepared by USDA River Basin Planning Staff, Soil Conservation Service. September 1987.
- US Navy. 1987b. *Natural Resource Management Plan. DOD Housing Facility Novato, California*. Prepared by: USDA Soil Conservation Service in cooperation with Natural Resources Management Staff, US Navy Western Division. October 1987.
- US Navy. 1988. *Fish and Wildlife Management Plan for Department of Defense Housing Facility, Novato, California*. February 1988.
- US Navy. 1995a. *Basewide Environmental Baseline Survey/Community Environmental Response Facility Act Report for DOD-Novato*. Prepared by: ERM-West, Inc. October 19, 1995.
- US Navy. 1995b. *Base Closure and Realignment Cleanup Plan, DOD Housing Facility Novato, CA*. Prepared by: PRC Environmental Management, Inc. March 1995.
- US Navy. 1996a. *Base Closure and Realignment Cleanup Plan, Final, DOD Housing Facility Novato, CA*. Prepared by: PRC Environmental Management, Inc. March 1996.
- US Navy. 1996b. *Final California Red-legged Frog Spring and Summer Surveys for Department of Defense Housing Facility, Novato, California*. August 1996.

8. References

- US Navy 1996c. *Environmental Assessment and Initial Study for the Hamilton Service Center Relocation (Temporary Homeless Shelter)*. August 7, 1996.
- Wahrhaftig, C., and J. Wakabayashi. 1989. *The Franciscan Complex*. in Wahrhaftig, C., and D. Sloan, eds., *Geology of San Francisco and Vicinity, San Francisco Bay Region, California*. American Geophysical Union, Field Trip Guidebook T105, July 1-7, 1989.
- Wallace, R. E. 1990. *General Features*. in R.E. Wallace, ed. *The San Andreas Fault System, California*. US Geological Survey Professional Paper 1515. Pp. 3-12.
- Weinberger Transportation, Inc. 1995. *Novato General Plan Revision Transportation Background Report #3 (Draft Report)*. June 15, 1995.
- Working Group on California Earthquake Probabilities (WGCEP). 1990. *Probabilities of Large Earthquakes in the San Francisco Bay Region, California*. US Geological Survey Circular No. 1053.


8.2 PERSONAL COMMUNICATIONS

- Allaback, Mark and David Laabs. 1996. Personal communication with Biosearch Wildlife Surveys.
- Arendell, Al. March 12, 1996. Fax and telephone conversation with John Bock. Captain, Novato Fire Protection District.
- Barner, Gary. November 1995. Telephone conversation with John Bock. Captain, Novato Police Department.
- Balestro, T. August 29, 1995. Personal communication (telephone by Tom Whitehead of Tetra Tech). City of Novato, Community Development Department.
- Brady, Brian. March 7, 1996. Personal communication (Fax to John Bock of Tetra Tech). Chief, Novato Police Department.
- Brode, John. 1996. Personal communication with California Department of Fish and Game.
- Busby, Colin. November 1995. Telephone conversation with Mary Maniery. Basin Research Associates, Inc., San Leandro, CA.
- Caldwell, Bob. March 1996. Telephone conversation with Stephen Burger. Caldwell Building Wreckers, San Francisco, CA.

8. References

- Demushka, Demitri. November 1995. Telephone conversation with Richard Grasseti. Civil Engineer, Engineering Division, City of Novato Community Development Department, Novato, CA.
- Duff, Patricia. November 1995. Telephone conversation with Mary Maniery. US Navy, Engineering Facility Activity West, San Bruno, CA.
- Frost, Michael. February 1996. Telephone conversation with Stephen Burger. Waste Management Specialist, Marin County Office of Solid Waste Management, San Rafael, CA.
- Geer, Kelly. 1996. Personal communication with USFWS.
- Lavaggi, Chris. July 1997. Telephone conversation with Amy Cordle. Golden Gate Disposal Company, San Francisco, CA.
- Lind, Larry. 1996. Personal communication with Elizabeth Purl. US Navy, Engineering Field Activity West.
- McGowan, Dana. November 1995. Telephone conversation with Mary Maniery. Jones & Stokes Associates, Inc., Sacramento, CA.
- Miller, Gary. November 1995. Telephone conversation with Richard Grasseti. Vice President, Robert Bein, William Frost & Associates, Los Angeles, CA.
- Rentz, John. December 1995. Telephone conversation with John Bock. Fire Chief, Novato Fire Protection District, Novato, CA.
- Robbins, Edith. July 1997. Telephone conversation with Amy Cordle. Senior Civil Engineer, North Marin Water District.
- Shaffer, Kevin. 1994. Personal communication with California Department of Fish and Game.
- Swenson, Ramona. 1996. Personal communication with Trihey and Associates.

**DODHF
Novato**



9.0 INDEX AND GLOSSARY

| | | |
|-----|----------|-----|
| 9.1 | INDEX | 9-1 |
| 9.2 | GLOSSARY | 9-6 |

9 INDEX AND GLOSSARY

9.1 INDEX

A

Assembly Bill (AB) 3-48, 3-116
 Association of Bay Area Government (ABAG) 3-22, 3-23, 3-24, 3-25, 3-28, 3-74, 3-75, 4-15, 4-21, 4-23
 aboveground storage tank (AST) 3-119, 3-122, 3-123, 4-94
 asbestos-containing material (ACM) 3-113, 3-117, 3-118, 4-94
 Air Resources Board (ARB) 3-104, 3-105, 3-106
 Army Corps of Engineers (COE) 1-5, 3-49, 3-57, 4-43

B

Bay Area Air Quality Management District (BAAQMD) 3-107, 3-108, 4-77, 4-79, 4-80
 BRAC Cleanup Plan (BCP) ES-4, 1-11, 3-113, 3-114, 3-116, 3-119, 3-120, 3-121, 3-123, 3-124, 3-125, 4-92
 Base Realignment and Closure (BRAC) ES-1, ES-2, ES-3, ES-4, 1-1, 1-5, 1-9, 1-11, 3-113, 3-117, 3-124, 3-126,
 4-90, 4-92, 4-94

C

California Code of Regulations (CCR) 3-68, 3-119, 3-123
 California Department of Fish and Game (CDFG) 3-56, 3-57, 3-58, 3-60, 3-61, 3-62,
 3-63, 3-64, 3-65, 3-84, 4-43, 4-44
 California Environmental Protection Agency (Cal EPA) 3-114, 3-115, 4-33
 California Environmental Quality Act (CEQA) ES-3, 1-1, 4-1, 4-3
 California Native Plant Society (CNPS) 3-60, 3-61, 3-62, 4-42, 4-44
 California Natural Diversity Database (CNDD) 3-56
 California Species of Special Concern 4-44
 Chief of Naval Operations (CNO) 3-116
 Clean Air Act (CAA) ES-13, 3-106, 3-107, 3-108, 3-117, 4-78, 4-83
 Clean Water Act (CWA) 3-57, 3-65, 3-81
 coast live oak 3-58, 3-60, 3-64
 Code of Federal Regulations (CFR) 1-8, 2-26, 3-50, 3-57, 3-118, 3-119, 3-123, 4-36, 4-38
 Community Environmental Response Facilitation Act (CERFA) 1-11, 3-113, 3-115
 Comprehensive Environmental Response, Compensation, and Liability Act ES-3, 1-11, 3-113, 3-114, 3-115
 conformity determination ES-13, 3-108, 4-78, 4-83
 Corps of Engineers see Army Corps of Engineers
 Council on Environmental Quality (CEQ) 1-1, 2-18

D

dBA 3-109
 Defense Base Closure and Realignment Act (DBCRA) ES-1, ES-2, 1-1, 1-8
 Department of Defense (DOD) ES-1, ES-2, ES-3, ES-5, 1-1, 1-5, 1-9, 1-11, 3-43, 3-50, 3-54, 3-110
 3-113, 3-115, 3-124, 3-126, 4-17, 4-94, 4-95
 Department of Toxic Substances Control (DTSC) 1-12, 3-118
 drainage 2-12, 2-24, 3-38, 3-43, 3-44, 3-45, 3-46, 3-62, 3-63, 3-65, 3-80, 3-81, 3-82, 3-84,
 3-86, 4-30, 4-31, 4-35, 4-43, 4-50, 4-53, 4-54, 4-59, 4-60

E

| | |
|--|---|
| earthquake..... | ES-11, 2-21, 3-69, 3-74, 3-75, 4-28, 4-49, 4-50 |
| Endangered Species Act (ESA)..... | 3-56, 3-57, 3-58 |
| Environmental Baseline Survery (EBS)..... | ES-3, ES-4, 1-11, 3-113, 3-114, 3-115, 3-116, 3-119, 3-121, 3-123, 3-125 |
| EIS | ES-1, ES-2, ES-3, ES-4, ES-5, ES-7, |
| | ES-8, 1-1, 1-5, 1-11, 1-12, 1-13, 1-14, 1-15, 2-1, 2-2, 2-3, 2-5, 2-13, 2-26, |
| | 2-27, 3-10, 3-15, 3-57, 3-60, 3-89, 3-109, 4-1, 4-2, 4-17, 4-30, 4-84, |
| | 5-1, 5-2, 5-4, 5-7, 5-9, 5-12, 5-15, 5-16, 5-17, 5-18 |
| endangered species..... | 3-56, 3-57, 4-45 |
| environmental justice | ES-14, 1-12, 3-32, 4-14, 5-1, 5-18 |
| Environmental Protection Agency (EPA)..... | ES-11, 13, 20, 3-87, 3-108, 3-114, 3-115, 3-116, 3-117, |
| | 3-118, 3-126, 4-33, 4-56, 4-58, 4-78, 4-82, 4-83, 4-95, 5-18 |

F

| | |
|--|---|
| Federal Emergency Management Agency (FEMA)..... | 3-81, 3-84, 3-86 |
| flooding..... | 2-23, 2-24, 3-15, 3-44, 3-46, 3-75, 3-80, 3-81, 3-84, 3-86, 4-31, |
| | 4-53, 4-54, 4-55, 4-56, 4-58, 4-59, 4-60, 4-61 |
| Federal Property Management Regulations (FPMR) | 1-2, 1-8, 1-10 |
| Finding of Suitability to Lease (FOSL)..... | 1-8, 3-115 |
| Finding of Suitability to Transfer (FOST)..... | 3-115 |
| floodplain | 3-15, 3-45, 3-46, 3-81, 3-82, 3-84, 3-87, 4-53, 4-56 |

G

| | |
|--|---|
| General Services Administration (GSA) | ES-5, 3-49, 3-54 |
| Golden Gate Bridge Highway Transit District (GGBHTD) | ES-2, ES-5, 1-2, 1-5, 1-10, 3-100, 4-70, 4-72, 4-76 |
| green sturgeon | 3-61 |
| ground water | 3-57, 3-65, 3-80, 3-82, 3-87, 3-88, 3-120, 3-121, 3-123, 4-53, 3-55, 3-56, 3-57, 3-59, 3-90, 3-91 |

H

| | |
|--|---|
| Hamilton Advisory Commission (HAC)..... | ES-6, 2-1, 2-2 |
| Hamilton Army Airfield..... | ES-2, ES-5, ES-6, ES-7, 1-2, 1-5, 1-9, 3-7, 3-8, 3-14, 3-15, 3-16, 3-28, 3-38, 3-41 |
| | 3-54, 3-55, 3-56, 3-110, 4-59, 5-2, 5-4, 5-5, 5-7 |
| Hamilton Homes Task Force..... | 1-9, 2-26, 4-18 |
| Hamilton Reuse Planning Authority | ES-2, ES-3, ES-4, ES-9, 1-1, 1-26, 1-8, 3-10, 3-14, 3-15, 3-17, 3-28, |
| | 3-29, 3-31, 3-37, 3-38, 3-43, 3-56, 3-58, 3-64, 4-3, 4-18, 4-19, 4-26, 4-34 |
| Highway 37 | 3-36 |
| Hillside Housing | 1-9, 2-10, 3-25, 3-39, 3-40, 3-42, 3-124 |
| Historic District | 3-54, 3-55, 4-36, 4-37 |
| homeless shelter..... | 1-9, 2-10, 2-11, 2-12, 2-17, 2-19, 4-8, 4-22, 4-27 |
| Housing and Urban Development (HUD)..... | 1-9, 3-6, 3-125 |

K

| | |
|--------------------|-----------------------|
| Knoll Housing..... | 1-9, 3-25, 3-39, 3-54 |
|--------------------|-----------------------|

L

| | |
|---|---|
| landfill | 3-48, 3-125, 4-33, 4-34 |
| Lanham Village | ES-10, 1-14, 2-12, 3-16, 3-33, 3-44, 3-109, 3-110, 4-5, 4-6, 4-12, 4-87, 4-88 |
| lead-based paint (LBP) | 3-124 |
| lead 3-49, 3-81, 3-88, 3-113, 3-115, 3-124, 3-125, 4-14, 4-22, 4-27, 4-33, 4-34, 4-90, 4-95, 4-98 | |
| Level of Service (LOS) | 3-89, 3-91, 3-99, 3-102, 4-62, 4-63, 4-67, 4-68, 4-70, 4-73, |
| | 4-74, 4-75, 4-76, 5-9, 5-10, 5-11, 5-12, 5-13, 5-14 |

| | |
|---------------------|------------------------------|
| liquefaction..... | 3-72, 3-75, 4-48, 4-50 |
| longfin smelt | 3-61, 3-63, 4-43, 4-44, 4-45 |
| low-income..... | ES-4, ES-13, 3-32, 5-18 |
| LRA | 1-9, 1-11 |

M

| | |
|--|---|
| Multi-agency Board (MAB) | ES-6, ES-7, 2-1, 2-2 |
| Marin County Flood Control and Water Conservation District (MCFCWCD) | 3-81, 3-84, 4-54, 4-55 |
| Marin Countywide Plan | 3-6, 3-7, 3-31, 3-36, 3-41, 3-69, 4-28, 5-5 |
| Marin Municipal Water District | 1-10, 3-38, 3-39, 3-40, 4-32 |
| McKinney Act | 1-9, 1-10 |

N

| | |
|---|---|
| National Pollutant Discharge Elimination System (NPDES) | 3-81, 3-30, 4-32, 4-55, 4-57, 5-8 |
| National Environmental Policy Act (NEPA) | ES-1, ES-3, ES-8, ES-14, 1-1, 1-2, 1-8, 1-10, 1-12, 1-15, 1-17, 1-18, 2-26, 3-32, 3-108, 4-1, 4-9, 4-37, 4-38, 4-97, 5-1, 5-2, 5-16, 5-17, 5-18 |
| National Historic Preservation Act | 3-49, 3-50 |
| National Park Service | 3-49, 4-38 |
| National Register | 3-49, 3-50, 3-52, 3-54, 4-36, 4-37, 4-40 |
| National Register of Historic Places (NRHP) | ES-11, 3-50, 3-52, 3-54, 4-36, 4-37, 4-38, 4-39, 4-40, 5-7 |
| Native American Graves Protection and Repatriation Act (NAGPRA) | 3-51 |
| notice of availability | ES-15 |
| Notice of Intent (NOI) | ES-14 |
| Novato Fire Protection District | 1-10, 3-14, 3-35, 4-27 |
| Novato General Plan | ES-13, ES-14, 2-25, 3-2, 3-3, 3-4, 3-17, 3-29, 3-35, 3-41, 3-69, 3-78, 3-80, 3-110, 3-111, 4-49, 4-54, 4-64, 4-86, 4-87, 5-5, 5-9, 5-16 |
| Novato Police Department | 3-35, 3-37, 4-29 |
| Novato Sanitary District (NSD) | 3-14, 3-38, 3-40, 3-41, 3-42, 3-43, 3-48, 4-32, 4-34 |
| Novato Unified School District (NUSD) | 1-10, 3-29, 3-30, 3-31, 4-14, 4-24, 4-25, 4-28, 4-29 |

O

| | |
|------------|--|
| ozone..... | 3-104, 3-106, 3-107, 3-108, 4-77, 4-79, 4-82 |
|------------|--|

P

| | |
|--|---|
| Pacheco Creek | ES-12, 2-22, 2-23, 2-24, 3-10, 3-44, 3-45, 3-56, 3-63, 3-64, 3-65, 3-70, 3-80, 3-81, 3-82, 3-84, 3-87, 3-88, 4-57, 4-58, 4-59 |
| Pacheco Pond | 3-84, 3-88 |
| Pacific Bell | 3-38, 3-47, 4-31 |
| PG&E | 3-38, 3-46, 3-47, 3-119, 4-31 |
| Pryor Amendment | 1-8 |
| public involvement | ES-4, 1-12, 1-13, 2-2 |
| public scoping | ES-13, 2-26 |
| Public Works Center San Francisco Bay (PWCSFB) | ES-2, 1-1, 3-38, 3-117, 3-118, 3-125 |

R

| | |
|----------------------|---|
| Rafael Village | ES-1, ES-2, ES-7, ES-10, ES-11, ES-12, ES-13, ES-14, 1-1, 1-2, 1-5, 1-14, 2-3, 2-5, 2-7, 2-9, 2-17, 2-19, 2-20, 2-21, 2-22, 2-25, 2-26, 2-27, 3-1, 3-2, 3-3, 3-6, 3-8, 3-9, 3-10, 3-13, 3-14, 3-17, 3-18, 3-25, 3-31, 3-36, 3-37, 3-38, 3-39, 3-41, 3-42, 3-43, 3-46, 3-47, 3-48, 3-51, 3-52, 3-54, 3-56, 3-58, 3-62, 3-63, 3-64, 3-66, 3-70, 3-72, 3-75, 3-76, 3-78, 3-80, 3-82, 3-84, 3-86, 3-87, 3-88, |
|----------------------|---|

| | |
|---|---|
| | 3-89, 3-93, 3-97, 3-100, 3-104, 3-109, 3-110, 3-114, 3-118, 3-119, |
| | 3-124, 3-126, 4-4, 4-7, 4-10, 4-11, 4-12, 4-19, 4-26, 4-27, 4-29, |
| | 4-31, 4-32, 4-33, 4-34, 4-35, 4-38, 4-39, 4-40, 4-44, 4-45, 4-46, |
| | 4-48, 4-49, 4-50, 4-51, 4-54, 4-55, 4-56, 4-57, 4-60, 4-61, 4-64, |
| | 4-72, 4-78, 4-82, 4-86, 4-87, 4-88, 4-90, 5-15, 5-16, 5-17 |
| railroad..... | ES-2, 3-5, 3-10, 3-45, 3-64, 3-82, 3-96, 3-100, 3-110, 5-7 |
| Resource Conservation and Recovery Act (RCRA) | 3-114, 3-116, 3-118, 3-119, 4-92 |
| Record of Decision (ROD)..... | ES-3, 1-15, 4-2 |
| recycling..... | ES-11, 3-48, 3-33 |
| Regional Water Quality Control Board (RWQCB) | 3-41, 3-81, 3-82, 3-119, 3-121, 4-56, 4-58 |
| Reuse Plan..... | ES-2, ES-3, ES-4, ES-6, ES-7, ES-8, ES-9, ES-10, |
| | ES-14, 1-2, 1-9, 2-1, 2-2, 2-3, 2-5, 2-9, 2-10, 2-11, 2-12, 2-13, |
| | 2-14, 2-15, 2-16, 2-17, 2-19, 2-20, 2-26, 3-8, 3-10, 3-14, 3-15, |
| | 3-17, 3-28, 3-29, 3-31, 3-37, 3-38, 3-43, 3-45, 3-56, 3-58, |
| | 3-64, 3-114, 4-1, 4-2, 4-3, 4-4, 4-5, 4-6, 4-7, 4-8, 4-10, 4-11, |
| | 4-12, 4-15, 4-18, 4-19, 4-21, 4-23, 4-24, 4-25, 4-26, 4-27, |
| | 4-28, 4-29, 4-30, 4-31, 4-32, 4-34, 4-35, 4-38, 4-39, 4-40, |
| | 4-43, 4-45, 4-46, 4-47, 4-48, 4-49, 4-50, 4-51, 4-53, 4-54, |
| | 4-55, 4-56, 4-57, 4-59, 4-60, 4-61, 4-62, 4-63, 4-65, 4-67, |
| | 4-68, 4-70, 4-72, 4-74, 4-78, 4-79, 4-80, 4-81, 4-82, 4-83, |
| | 4-85, 4-86, 4-87, 4-88, 4-91, 4-92, 4-93, 4-94, 4-95, 4-96, |
| | 5-4, 5-5, 5-12, 5-15, 5-16, 5-17 |
| riparian corridor..... | 4-43 |
| Region of Influence (ROI)..... | ES-8, 2-1, 2-17, 2-21, 2-22, 2-23, 2-24, 2-32, 2-35, |
| | 2-38, 2-56, 2-60, 2-61, 2-62, 2-63, 2-68, 2-80, 2-89, 2-104, 2-109, |
| | 3-1, 3-2, 3-10, 3-14, 3-23, 3-27, 3-30, 3-36, 3-42, 3-43, 3-44, |
| | 3-45, 3-46, 3-47, 3-48, 3-53, 3-62, 3-65, 3-67, 3-68, 3-77, 3-84, |
| | 4-10, 4-14, 4-27, 4-30, 4-36, 4-42, 4-48, 4-53, 4-62, 4-77, |
| | 4-84, 4-90, 5-7, 5-14 |

S

| | |
|--|--|
| salt marsh harvest mouse..... | 3-61, 3-63 |
| San Jose Creek..... | ES-11, ES-12, 2-9, 3-20, 3-21, 4-3, 4-10, 4-14, 4-43, 4-51, 4-56, 4-62, 4-63, 4-65, 4-70, 4-72 |
| | 4-80, 4-81, 4-82, 4-84, 4-86, 4-87, 4-45, 4-55, 4-56, 4-57, 4-60 |
| San Pablo Bay.. | ES-2, ES-10, 2-16, 2-22, 3-19, 3-20, 3-50, 3-53, 3-80, 3-81, 3-82, 3-84, 3-86, 3-87, 3-88, 4-53, 3-57, 5-4 |
| Senate Bill (SB) | 3-123, 4-72, 5-10, 5-11, 5-13 |
| State Historic Preservation Officer (SHPO) | 3-49, 3-52, 3-54, 4-36, 4-37, 4-38 |

T

| | |
|--|------------------------------|
| Technical Advisory Committee (TAC) | ES-6, 2-1 |
| threatened species | 3-56, 4-42, 4-45 |
| tidewater goby..... | 3-61, 3-62, 4-43, 4-44, 4-45 |
| TSCA | 3-118 |
| tsunami..... | 4-53 |

U

| | |
|---|---|
| underground storage tank (UST)..... | 3-119, 3-122, 3-123, 4-90, 4-94 |
| US Army..... | ES-5, 1-1, 3-15, 3-48, 3-88, 3-110, 4-43, 5-4 |
| US Code (USC)..... | ES-2, ES-8, 3-115, 3-123, 3-124 |
| US Coast Guard (USCG) | ES-2, ES-5, ES-6, ES-7, 1-2, 1-5, 1-9, 2-1, 2-2, 3-14, 3-15, 3-19, 3-20, |
| | 3-25, 3-39, 3-43, 3-44, 3-53, 3-72, 3-75, 3-86, 3-109, 3-126, 4-5, 4-37, 4-64, 4-67, 5-2, 5-4, 5-6, 5-7 |
| United States Environmental Protection Agency (USEPA) | 3-87 |
| US Fish and Wildlife Service (USFWS) | 3-56, 3-57, 3-60, 3-61, 3-62, 3-65, 4-42, 4-44, 4-45 |

V

Veterans Affairs.....ES-6, 1-9, 2-2, 3-14

W

water qualityES-12, ES-14, 2-21, 3-57, 3-80, 3-82, 3-88, 4-32, 4-53, 4-54, 4-55, 4-56, 4-57, 4-60, 4-61

wetlandsES-11, 1-14, 2-20, 3-2, 3-7, 3-8, 3-31, 3-46, 3-56, 3-57, 3-58, 3-64, 3-65, 3-80, 3-81,
.....3-82, 3-84, 3-86, 4-43, 4-45, 4-46, 4-53, 4-59, 5-2, 5-4, 5-7

9.2 GLOSSARY

| | |
|-------------------------------|---|
| 100-Year Flood Zone | Land area having a one percent chance of being flooded during a given year. |
| A-Weighted Decibel (dBA) | A number representing the sound level which is frequency weighted according to a prescribed frequency response established by the American National Standards Institute (ANSI-S1.4-1971) and accounts for the response of the human ear. |
| Active Fault | A fault on which movement has occurred during the past 10,000 years and which may be subject to recurring movement, usually indicated by small periodic displacement or seismic activity. |
| Aesthetics | Referring to the perception of beauty. |
| Affected Environment | Existing biological, physical, social, and economic conditions of an area subject to change as a result of a proposed human action. Also, the chapter in an environmental impact statement describing current environmental conditions. |
| Air Quality | Measure of health related and visual characteristics of the air often derived from quantitative measurements of the concentrations of specific injurious or contaminating substances. |
| Alternatives | Courses of action which may meet the objectives of a proposal at varying levels of accomplishment, including the most likely future conditions without the project or action. |
| Ambient Air Quality Standards | Standards established on a state or federal level that define the limits for airborne concentrations of designated criteria pollutants (nitrogen dioxide, sulfur dioxide, carbon monoxide, ozone, lead), to protect public health with an adequate margin of safety (primary standards) and public welfare, including plant and animal life, visibility, and materials (secondary standards). |
| Arterial | Signalized street that serves primarily through traffic and provides access to abutting properties as a secondary function. |
| Asbestos | A carcinogenic substance formerly used widely as an insulation material by the construction industry; often found in older buildings. |
| Attainment Area | An area which meets the National Ambient Air Quality Standards for a criteria pollutant under the Clean Air Act or meets state air quality standards. |
| Burial | Human remains disposed of by interment. Burials may be <i>simple</i> (containing the remains of one person) or <i>complex</i> (containing the remains of two or more individuals), <i>primary</i> (including the remains as originally interred) or <i>secondary</i> (where a reinterment follows a temporary disposal elsewhere). |

| | |
|---|--|
| Capacity (Transportation) | The maximum rate of flow at which vehicles can be reasonably expected to traverse a point or uniform segment of a lane or roadway during a specified time period under prevailing roadway, traffic, and control conditions. |
| Capacity (Utilities) | The maximum load a system is capable of carrying under existing service conditions. |
| Clean Air Act (CAA) | The CAA legislates that air quality standards set by federal, state, and county regulatory agencies establish maximum allowable emission rates and pollutant concentrations for sources of air pollution on federal and private property. Also regulated under this law is proper removal and safe disposal of asbestos from buildings other than schools. |
| Clean Water Act (CWA) | The CWA is the major federal legislation concerning improvement of the nations water resources. It provides for development of municipal and industrial wastewater treatment standards and a permitting system to control wastewater discharges to surface waters. The act contains specific provisions for regulation of ships' wastewater and disposal of dredge spoils within navigable waters. Section 404 of the act regulates disposal into waters of the United States, including wetlands. |
| Climate | The prevalent or characteristic meteorological conditions (and their extremes) of any given location or region. |
| Community Noise Equivalent Level | Noise Compatibility level established by California Administrative Code, Title 21, Section 5000. The 24-hour average A-weighted sound level with a 5 dB weighting added to levels occurring between 10:00 p.m. and 7:00 a.m. |
| Community Environmental Response Facilitation Act (CERFA) | A 1992 amendment to CERCLA, CERFA expedites the identification of uncontaminated real property within closing facilities which offer the greatest opportunity for reuse and redevelopment. |
| Comprehensive Environmental Response, Compensation, And Liability Act (CERCLA) | CERCLA, also known as Superfund, was enacted in 1980 to ensure that a source of funds is available to clean up abandoned hazardous waste dumps, compensate victims, address releases of hazardous materials, and establish liability standards for responsible parties. The act also requires creation of a National Priorities List which sets forth the sites considered to have the highest priority for cleanup under Superfund. |
| Contamination | The degradation of naturally occurring water, air, or soil quality either directly or indirectly as a result of human activities. |
| Council On Environmental Quality (CEQ) | Established by NEPA, the CEQ consists of three members appointed by the President. CEQ regulations (40 CFR 1500-1508, as of July 1, 1986) describe the process for implementing NEPA, including preparation of environmental assessments and environmental impact statements, and timing and extent of public participation. |

| | |
|-------------------------------------|--|
| Criteria Pollutants | The Clean Air Act required the EPA to set air quality standards for common and widespread pollutants after preparing "criteria documents" summarizing scientific knowledge on their health effects. Today there are standards in effect for six criteria pollutants: sulfur dioxide, carbon monoxide, particulate matter, nitrogen dioxide, ozone, and lead. |
| Cultural | (1) The nonbiological and socially transmitted system of concepts, institutions, behavior, and materials by which a society adapts to its effective natural and human environment. (2) Similar or related assemblages of approximately the same age from a single locality or district, thought to represent the activities of one social group. |
| Cultural History | The archeological sequence of cultural activity through time, within a defined geographic space or relating to a particular group. |
| Cultural Resource | Prehistoric or historic districts, sites, buildings, objects, or any other physical evidence of human activity considered important to a culture, subculture, or community for scientific, traditional, religious, or any other reason. |
| Cumulative Impacts | The combined impacts resulting from all programs occurring concurrently at a given location. |
| Day-Night Average Sound Level (Ldn) | The 24-hour average-energy sound level expressed in decibels, with a 10 decibel penalty added to sound levels between 10:00 p.m. and 7:00 a.m. to account for increased annoyance due to noise during the night. |
| Decibel (dB) | A unit of measurement on a logarithmic scale which describes the magnitude of a particular quantity of sound pressure or power with respect to a standard reference value. |
| Developed | Said of land, a lot, a parcel, or an area that has been built upon, or where public services have been installed prior to residential or commercial construction. |
| Direct Impact | Effects resulting solely from the proposed program. |
| Disposal | Legal transfer of Navy property to other ownership. |
| Dredging | Removal of mud from the bottom of water bodies using a scooping machine. |
| Effluent | Waste material discharged into the environment. |
| Endangered Species | A species that is threatened with extinction throughout all or a significant portion of its range. |

| | |
|--------------------------------------|--|
| Endangered Species Act (ESA) | The ESA requires federal agencies to determine the effects of their actions on endangered species and their critical habitats. |
| Environmental Impact Statement (EIS) | A document required of federal agencies by NEPA for major projects or legislative proposals significantly affecting the environment. A tool for decision making, the EIS describes the positive and negative effects of the undertaking and lists alternative actions. |
| Equivalent Noise Levels (Leq) | Equivalent noise levels are used to develop single-value descriptions of average noise exposure over various periods of time. |
| Fault | Fracture in earth's crust accompanied by a displacement of one side of the fracture with respect to the other and in a direction parallel to the fracture. |
| Floodplain | The relatively flat land lying adjacent to a river channel that is covered by water when a river overflows its banks. |
| Flora | Plants; organisms of the plant kingdom taken collectively. |
| Ground Water | Water within the earth that supplies wells and springs. |
| Habitat | Area where a plant or animal lives. |
| Hazardous Material | A substance or mixture of substances that poses a substantial present or potential risk to human health or the environment. Any substance designated by the EPA to be reported if a designated quantity of the substance is spilled in the waters of the United States or if it is otherwise released into the environment. |
| Hazardous Waste | A waste or combination of wastes which, because of its quantity, concentration, or physical, chemical, or infectious characteristics, may either cause or significantly contribute to an increase in mortality or an increase in serious irreversible illness; or pose a substantial present or potential hazard to human health or the environment when improperly treated, stored, transported, disposed of, or otherwise managed. Regulated under RCRA. |
| Historic (Cultural Resources) | A period of time after the advent of written history dating to the time first Euro-American contact in an area. Also refers to items primarily of Euro-American manufacture. |
| Historic District | National Register of Historic Places designation of a geographically defined area (urban or rural) possessing a significant concentration, linkage, or continuity of sites, structures, or objects united by past events or aesthetically by plan of physical development. |
| Impact | An assessment of the meaning of changes in all attributes being studied for a given resource; an aggregation of all the adverse effects, usually measured using a qualitative and nominally subjective technique. |
| Indirect Impact | Program-related impact not directly attributable to the program itself. |


| | |
|---|---|
| Infrastructure | The basic installations and facilities on which the continuance and growth of a locale depend (roads, schools, power plants, transportation, and communication systems). |
| Land Use Plans And Policies | Guidelines adopted by governments to direct future land use within their jurisdictions. |
| Level Of Service (LOS) | In transportation analysis, a qualitative measure describing operational conditions within a traffic stream and how they are perceived by motorists and/or pedestrians. In public services, a measure describing the amount of public services available to community residents, generally expressed as the number of personnel providing service per 1,000 population. |
| Liquefaction | The transformation during an earthquake of unconsolidated, water-saturated sediment into a liquid form. |
| Long-term | Impacts that would occur over an extended period of time, whether they start during the construction or operations phase. Most impacts from the operations phase are expected to be long term since program operations essentially represent a steady-state condition (i.e., impacts resulting from actions that occur repeatedly over a long period of time). However, long-term impacts could also be caused by construction activities if a resource is destroyed or irreparably damaged or if the recovery rate of the resource is very slow. |
| McKinney Act | The McKinney Act gives recognized providers of assistance to the homeless a high priority in acquiring unneeded land and buildings on federal properties. The property can be used only for the homeless and only for two years. Homeless providers must be able to finance upgrades of facilities, pay a proportionate share of municipal service costs, and fund its program operations. |
| Mitigation | A method or action to reduce or eliminate program impacts. |
| Multi-Family Housing | Townhouse or apartment units that accommodate more than one family though each dwelling unit is only occupied by one household. |
| National Ambient Air Quality Standards | Section 109 of the Clean Air Act requires EPA to set nationwide standards for widespread air pollutants: carbon monoxide, lead, nitrogen dioxide, ozone, particulate matter, and sulfur dioxide. |
| National Environmental Policy Act (NEPA) | Public Law 91-190, passed by Congress in 1969, established a national policy designed to encourage consideration of the influence of human activities on the natural environment. NEPA also established the Council on Environmental Quality. NEPA procedures require that environmental information be made available to the public before decisions are made. |
| National Historic Preservation Act (NHPA) | The NHPA protects cultural resources. Section 106 of the act requires a federal agency to take into account the potential effect of a proposed action on properties listed on or eligible for listing on the National Register of Historic Places. |

| | |
|---|---|
| National Register of Historic Places | A federally maintained register of districts, sites, buildings, structures, architecture, archeology, and culture. |
| National Register Resources | Properties listed on the National Register of Historic Places, properties formally determined eligible for listing on the National Register, and those properties appearing to qualify for listing on the National Register. |
| Native American Graves Protection and Repatriation Act (NAGPRA) | NAGPRA defines the ownership and control of Native American human remains and associated funerary objects discovered or recovered from federal or tribal land. |
| Native Americans | Used in the collective sense to refer to individuals, bands, or tribes who trace their ancestry to indigenous populations of North America prior to European American contacts. |
| Native Vegetation | Plant life that occurs naturally in an area without agricultural or cultivation efforts. It does not include species that have been introduced from other geographical areas and have become naturalized. |
| Natural Gas | A natural fuel containing primarily methane and ethane that occurs in certain geologic formations. |
| Nitrogen Oxides (NO _x) | Gases formed primarily by fuel combustion, which contribute to the formation of acid rain. Hydrocarbons and nitrogen oxides combine in the presence of sunlight to form ozone, a major constituent of smog. |
| Noise | Any sound that is undesirable because it interferes with speech and hearing, or is intense enough to damage hearing, or is otherwise annoying. |
| Nonnative species | Species that have invaded or been introduced into an area. |
| Ozone | A major ingredient of smog. Ozone is produced from reactions of hydrocarbons and nitrogen oxides in the presence of sunlight and heat. |
| Particulate Matter (PM ₁₀) | PM ₁₀ is a fractional sampling of particle sizes that approximate the extent to which particles with aerodynamic equivalent diameters smaller than fifty (50) microns penetrate to the lower respiratory tract. The "10" in PM ₁₀ refers to a 50 percent collection efficiency size range, not an upper size limit. |
| Peak Hour | The hour of highest traffic volume on a given section of roadway between 7:00 a.m. and 9:00 a.m. or between 4:00 p.m. and 6:00 p.m. |
| Permit | An authorization, license, or equivalent control document to implement the requirements of an environmental regulation. |
| Polychlorinated Biphenyls (PCBs) | Any of a family of industrial compounds produced by chlorination of biphenyl. These compounds are noted chiefly as an environmental pollutant that accumulates in organisms and concentrates in the food chain with resultant pathogenic and teratogenic effects. They also decompose very slowly. |

| | |
|---|---|
| Potable Water | Water that is suitable for drinking. |
| Prehistory/Prehistoric | The archeological record of nonliterate cultures; the cultural past before the advent of written records. |
| Public Involvement | Process of obtaining citizen input into each stage of development of planning documents. Required as a major input into any environmental impact statement. |
| Record Of Decision (ROD) | The document prepared under the federal government that documents the reasoning behind the decision. |
| Recycling | The process of minimizing the generation of waste by recovering usable products that might otherwise become waste. |
| Region of Influence | For each resource, the region affected by the proposed action or alternatives and used for analysis in the affected environment and impact discussion. |
| Resource Conservation And Recovery Act (RCRA) | RCRA was enacted in 1976 as the first step in regulating the potential health and environmental problems associated with hazardous waste disposal. RCRA and the regulations developed by EPA to implement its provisions provide the general framework of the national hazardous waste management system, including the determination of whether hazardous wastes are being generated, techniques for tracking wastes to eventual disposal, and the design and permitting of hazardous waste management facilities. |
| Runoff | The noninfiltrating water entering a stream or other conveyance channel shortly after a rainfall event. |
| Seismicity | Relative frequency and distribution of earthquakes. |
| Short Term | Transitory effects of the proposed program that are of limited duration and are generally caused by construction activities or operations start-up. |
| Significance | The importance of a given impact on a specific resource as defined under the Council on Environmental Quality regulations. |
| Single-Family Housing | A conventionally built house consisting of a single dwelling unit occupied by one household. |
| Site | The location of past cultural activity; a defined space with more or less continuous archeological evidence. |
| Soil | A natural body consisting of layers or horizons of mineral and/or organic constituents of variable thickness and differing from the parent material in their morphological, physical, chemical, and mineralogical properties, and biological characteristics. |
| Soil Types | A category or detailed mapping unit used for soil surveys based on phases or changes within a series (e.g. slope, salinity). |

| | |
|---|--|
| Solid Waste Management | Supervised handling of waste materials from their source through recovery processes to disposal. |
| State Historic Preservation Officer (SHPO) | The official within each state, authorized by the state at the request of the Secretary of the Interior, to act as a liaison for purposes of implementing the National Historic Preservation Act. |
| Sulfur Dioxide | A toxic gas that is produced when fossil fuels, such as coal and oil, are burned. It is the main pollutant involved in the formation of acid rain. |
| Superfund Amendments And Reauthorization Act (SARA) | SARA was enacted in 1986 to increase the Superfund to \$8.5 billion, modify contaminated site cleanup criteria scheduling, and revise settlement procedures. It also provides a fund for leaking underground storage tank cleanups and a broad, new emergency planning and community right to know program. |
| Surface Water | All water naturally open to the atmosphere and all wells, springs, or other collectors which are directly influenced by surface water. |
| Threatened Species | Plant and wildlife species likely to become endangered in the foreseeable future. |
| Topography | Physical shape of the ground surface. |
| Toxic | Harmful to living organisms. |
| Toxic Substances Control Act (TSCA) | TSCA provides authority to test and regulate chemicals to protect human health. Substances regulated under TSCA include asbestos and PCBs. |
| Transfer | Deliver US government property accountability to another federal agency. |
| US Environmental Protection Agency | The independent federal agency established in 1970 to regulate federal environmental matters and oversees the implementation of federal environmental laws. |
| Wetlands | Areas that are inundated or saturated with surface or groundwater at a frequency and duration sufficient to support a prevalence of vegetation typically adapted for life in saturated soil. This classification includes swamps, marshes, bogs, and similar areas. Jurisdictional wetlands are those wetlands that meet the vegetation, soils, and hydrology criteria under normal circumstances (or meet the special circumstances as described in the US Army Corps of Engineers, 1987 wetland delineation manual where one or more of these criteria may be absent) and are a subset of "waters of the United States." |
| Zoning | The division of a municipality into districts for the purpose of regulating land use, types of buildings, required yards, necessary off-street parking, and other prerequisites to development. Zones are generally shown on a map and the text of the zoning ordinance specifies requirement for each zoning category. |

DODHF
Novato



10.0 DISTRIBUTION LIST

10. DISTRIBUTION LIST

| Title | First | Last | Organization | Branch | City | State |
|---------------------------------------|-------------|------------------|---|---|---------------|-------|
| Elected Officials | | | | | | |
| Mr. | John | Hass | Senator Boxer's Office | | San Francisco | CA |
| Mr. | Russell | Lowe | Senator Feinstein's Office | | San Francisco | CA |
| The Honorable | Mazzoni | Kerry | State Assembly Representative | | Sacramento | CA |
| The Honorable | Patricia | Ecklund | City of Novato | | Novato | CA |
| Mayor Pro Tem | Carole | Dillon-Knutsen | City of Novato | | Novato | CA |
| Councilmember | Michael | DiGiorgio | City of Novato | | Novato | CA |
| Councilmember | Ernest | Gray | City of Novato | | Novato | CA |
| Councilmember | Cynthia | Murray | City of Novato | | Novato | CA |
| Supervisor | John | Kress | Marin County | | San Rafael | CA |
| Supervisor | Annette | Rose | Marin County | | San Rafael | CA |
| | | | Marin County Board of Supervisors | | San Rafael | CA |
| Supervisor | Harry | Moore | Marin County | | San Rafael | CA |
| Supervisor | Harold | Brown | Marin County | | San Rafael | CA |
| The Honorable | Lynn | Woolsey | US Representative | | Washington | DC |
| Federal Agencies | | | | | | |
| | Lee | Keating | Advisory Council on Historic Preservation | Western Division, Project Review | Golden | CO |
| Executive Director | | | Advisory Council on Historic Preservation | | Washington | DC |
| Mr. | Richard | Brown | Dept of Housing and Urban Development | Office of Community Viability | Washington | DC |
| Director | Steven | Sachs | Dept of Housing and Urban Development | Community Planning and Development, 9ADE | San Francisco | CA |
| Mr. | Jimmy | Prater | Dept of Housing and Urban Development | | San Francisco | CA |
| | | | Federal Aviation Administration | Branch AWP530 | Los Angeles | CA |
| Regional Director | | | Federal Emergency Management Agency | Region IX | San Francisco | CA |
| Chief, Northern Branch | Dianne | Cah | General Services Administration | Office of Real Estate Sales (90R) | San Francisco | CA |
| Mr. | Dale M. Tom | Lanzone Doszkocs | General Services Administration | | Washington | DC |
| | | | General Services Administration | Interagency Real Estate Coordinator | San Francisco | CA |
| Regional Director | Helda | Diaz Soltero | National Marine Fisheries Service | SW Region | Long Beach | CA |
| Ms. | Diane | Windham | National Marine Fisheries Service | | Santa Rosa | CA |
| Ms. | Courtney | Damkroger | National Trust for Historic Preservation | | San Francisco | CA |
| | | | National Wildlife Federation | Public Affairs | Washington | DC |
| Ms. | Laurie | Sullivan | Dept. of Commerce | NOAA | San Francisco | CA |
| Mr. | George | Hoops | US Dept of Education | Federal Real Property Assistance Program | Seattle | WA |
| Director | David | Hakola | US Dept of Education | Real Property Group | Washington | DC |
| | | | US Dept of Energy | Office of EC&E, Env Program Division | Oakland | CA |
| | | | US Dept of State | Environmental Affairs Office | Washington | DC |
| Chief, Environmental Section | | | US Dept of the Interior | Bureau of Indian Affairs | Sacramento | CA |
| Director | | | US Dept of the Interior | | Washington | DC |
| Associate Regional Director | John | Cherry | US Dept of the Interior | Office of Environmental Policy and Compliance | San Francisco | CA |
| Chief of Planning Grants & Env. Qual. | Ray | Murray | US Dept of the Interior | National Park Service | San Francisco | CA |

| Title | First | Last | Organization | Branch | City | State |
|---|--------------------|--------------------|--|---|---------------|-------|
| Director's Representative Region IX Secretary | Pat | Port | US Dept of the Interior | Office of Environmental Policy and Compliance | San Francisco | CA |
| | | | US Dept of the Interior, USGS | | Menlo Park | CA |
| | Thomas | Patak | US Dept of Transportation | | San Francisco | CA |
| | | | US Dept of Transportation | Federal Highway Administration | San Francisco | CA |
| Mr. | Raymond | Seid | US Dept of Transportation | Office of the Federal Facilities Cleanup Code H-9-2 | Washington | DC |
| | | | US Environmental Protection Agency | | San Francisco | CA |
| Reuse Representative | Esther | Hill | US Environmental Protection Agency, Region IX | | San Francisco | CA |
| Mr. | David | Farrel | US Environmental Protection Agency, Region IX | Environmental Review Section (E-3-1) | San Francisco | CA |
| Mr. | David | Tomsovic | US Environmental Protection Agency, Region IX | Office of External Affairs | San Francisco | CA |
| Mr. | Wayne | White | US Fish & Wildlife Service | Ecological Services | Sacramento | CA |
| Department of Defense | | | | | | |
| Mr. Commander | District Robert | Engineer Koenig | US Army Corps of Engineers | Attn: CESPK-PM-M CESPK-PD-R CESPK-PM-M (ISS) (G-EVC-4) | Sacramento | CA |
| | Graham | Sharpe | US Army Corps of Engineers | | Sacramento | CA |
| | District | Engineer | US Army Corps of Engineers | | San Francisco | CA |
| | | | US Coast Guard | | Washington | DC |
| Ms. | Leo | Lozano | US Coast Guard | MLCP | Alameda | CA |
| | Sue | Boyle | US Coast Guard | Pacific Area | Alameda | CA |
| | Pat | O'Brien | US Dept of Defense | Office of Economic Adjustment | Arlington | VA |
| Mr. | Paul | Ryeff | US Dept of Defense | Office of Economic Adjustment | Sacramento | CA |
| Navy | | | | | | |
| Mr. Chief of Naval Operations CDR | John | Scales | Navy Public Works Center | Crystal Plaza 5, Room 680 | Novato | CA |
| | Tom | Peeling, N456 | Office of the Chief of Naval Operations | | Arlington | VA |
| | Steve | Daugherty | Navy CNO (N44) | | Reston | VA |
| Env Planning | Gary | Munekawa | COMNAVBASE EFA West | EFD Code 185 | San Diego | CA |
| | | | | | San Bruno | CA |
| State Agencies | | | | | | |
| Director Mr. | James | Boyd | CA Air Resources Board | Stationary Sources | Sacramento | CA |
| | Bob | Fletcher | CA Air Resources Board | | Sacramento | CA |
| | | | CA Archaeological Inventory | Sonoma State University, Foundation Center | Rohnert Park | CA |
| Mr. | Ken | Trott | CA Dept of Conservation | Div of Mines & Geology | San Francisco | CA |
| | | | CA Dept of Conservation | Office of Land Conservation | Sacramento | CA |
| Mr. | Pete | Phillips | CA Dept of Fish & Game | Environmental Services Div. | Sacramento | CA |
| Mr. | Brian | Hunter | CA Dept of Fish & Game | NW Region 3 | Yountville | CA |
| Mr. | Douglas | Wickizer | CA Dept of Forestry | | Sacramento | CA |
| | | | CA Dept of Health Service | Public Water Supply Branch | Sacramento | CA |
| Mr. | Steve | Hsu | CA Dept of Health Services | Office of Noise Control | Berkeley | CA |
| Mr. | Ken | Pierce | CA Dept of Parks & Recreation | Resource Management Division | Sacramento | CA |
| Chief | Edwin | Erwin | CA Dept of Transportation | Environmental Branch | Sacramento | CA |
| | | | CA Dept of Transportation | Transportation Planning, Branch A | Stockton | CA |
| Branch Chief | Ace | Forsen | CA Dept of Transportation, District 4 | Office of Transportation Planning, IGR/CEQA Branch | Oakland | CA |
| Mr. | Walt | Pettit | CA Dept of Water Resources | | Sacramento | CA |

| Title | First | Last | Organization | Branch | City | State |
|--|---|---|---|---|---|--|
| Ms. | Theresa | McGarry | CA Division of Water Quality CA Energy Commission CA Environmental Protection Agency | Dept of Toxic Substance Cntl, Office of Military Facilities | Sacramento Sacramento Sacramento | CA CA CA |
| Mr. Ms. | James M. Shirley | Strock Buford | CA Environmental Protection Agency CA Environmental Protection Agency | Dept of Toxic Substances Control | Sacramento Berkeley | CA CA |
| Ms. | Raymond | Leclerc | CA EPA, Dept of Toxic Substance Control CA Highway Patrol CA Highway Patrol, Long Range Planning Section CA Native American Heritage Community | Region 1, Base Closure Branch Planning and Analysis Division | Sacramento Corte Madera Sacramento | CA CA CA |
| Mr. | John | Walters | CA Native Plant Society CA Office of Emergency Services CA Office of Planning & Research | Marin Chapter | San Anselmo Pleasant Hill Sacramento | CA CA CA |
| Mr. Mr. | Mike Ben Ernie | Chiaritti Williams von Ibsch | CA Office of Planning and Research CA Public Utilities Commission | Safety and Enforcement Division | Sacramento San Francisco | CA CA |
| Mr. Mr. Mr. Project Manger CA State Historic Preservation Officer Chief Mr. Mr. | Tom John Jack Terri Cherilyn | Gansbury Adams Gregg Nevins Widell | CA Regional Water Quality Cntl Brd CA Regional Water Quality Cntl Brd CA Regional Water Quality Cntl Brd CA State Coastal Conservatory CA State Historic Preservation Office | Basic Planning Unit Land Disposal Section | Oakland Sacramento Oakland Oakland Sacramento | CA CA CA CA CA |
| Mr. Mr. Mr. | Jane Dave Robert | Sekelsky Plummer Berry | CA State Lands Commission CA State Lands Commission CA Trade and Commerce CA Water Resources Con. Board | Div of Land Management Div of Research and Plan | Sacramento Sacramento Sacramento Sacramento | CA CA CA CA |
| Mr. Transportation Planning | Earl Wade | Tucker Greene | Caltrans Caltrans District IV | Divisions of Aeronautics | Sacramento Oakland | CA CA |
| Mr. | Thomas | Nagle | Caltrans Planning Coastal Area Information Group | Employment Development Dept | Sacramento San Francisco | CA CA |
| Mr. | Marc F. | Roddin | Metropolitan Transportation Commission | | Oakland | CA |
| Mr. | Bill | Johnson | Native American Heritage Commission | | Sacramento | CA |
| Executive Director Mr. | William Douglas | Travis Wheeler | SF Bay Conservation & Dev Commission The Resources Agency | | San Francisco Sacramento | CA CA |
| Regional Agencies | | | | | | |
| Mr. Supervising Environmental Planner Mr. Director Mr. Mr. Mr. Director Chief City Engineer | Richard Pat Irwin Rolf Dennis Tom Ken Thomas Larry Tim | Arrow Perry Mussen Pendall Dorch Elliott Bell Selfridge Dito Nolan | Association of Bay Area Government American Indian Council Of Marin Bay Area Air Quality Management District Bay Area Council Bel Marin Keys City of Cotati City of Novato City of Novato City of Novato City of Novato City of Novato City of Novato | Controllers Office Community Services Dept Planning Dept Fire District Sanitary District Parks & Recreation Police Dept | San Rafael Oakland San Rafael San Francisco San Francisco Novato Cotati Novato Novato Novato Novato Novato Novato | CA CA CA CA CA CA CA CA CA CA CA CA CA |

| Title | First | Last | Organization | Branch | City | State |
|--------------------------------|------------|-------------|--|---|---------------|-------|
| Development Director | Sonja | Seeman | City of Novato | | Novato | CA |
| Director | Vi | Grinsteiner | City of Novato | Community Development Department | Novato | CA |
| Ms. | Carol | Hollander | City of Novato | Community Development Department | Novato | CA |
| Mr. | Mark | Westfall | City of Novato | Community Development Department | Novato | CA |
| Ms. | Annette | Conklin | City of Novato | Unified School District | Novato | CA |
| | | | City of Petaluma | Planning Department | Petaluma | CA |
| Director | Robert | Pendoley | City of San Rafael | Planning Department | San Rafael | CA |
| Mr. | Ron | Allen | City of Santa Rosa | Community Development | Santa Rosa | CA |
| Mr. | Harvey | Katz | Golden Gate Bridge Highway Transit Dist. | Planning Department | San Rafael | CA |
| General Manager | | | Golden Gate Bridge Highway Transit Dist. | | San Francisco | CA |
| | | | Las Gallinas Valley Sanitary District | | San Rafael | CA |
| Ms. | Dawn | Mittleman | Local Agency Formation Commission | | San Rafael | CA |
| | | | Marin Air Response Instant Network | | Tiburon | CA |
| Mr. | Lester | Roth | Marin Chamber of Commerce | | San Rafael | CA |
| | | | Marin County | Homeless Programs Office | San Rafael | CA |
| Mr. | Mark | Riesenfield | Marin County | Planning Department | San Rafael | CA |
| Mr. | Donald | Ward | Marin County | Planning Department | San Rafael | CA |
| | | | Marin County | Public Works Department | San Rafael | CA |
| | | | Marin County | Flood Control and Water Conservation District | San Rafael | CA |
| | Francis E. | Torr | Marin County Aviation Commission | | Novato | CA |
| | | | Marin County Counsel | | San Rafael | CA |
| | | | Marin County Open Space District | Department of Public Works | San Rafael | CA |
| | | | Marin County Open Space District | Marin County Parks and Recreation | San Rafael | CA |
| | | | Marin County Planning Department | Airport Land Use Committee | San Rafael | CA |
| Mr. | John | Law | Marin County Transit District | | San Rafael | CA |
| Mr. | Ronald | Johnson | Marin Municipal Water District | | Corte Madera | CA |
| Mr. | Eric | McGuire | Marin Municipal Water District | | Corte Madera | CA |
| | | | Marin-Sonoma | Mosquito Abatement District | Petaluma | CA |
| | | | North Bay Transit Committee | | San Rafael | CA |
| Ms. | Edith | Robbins | North Marin Recreation Center, Inc. | | Novato | CA |
| Ms. | Leigh | Jordan | North Marin Water District | | Novato | CA |
| | | | Northwest Information Center | Historical Resources | Rohnert Park | CA |
| | | | | Information Systems | | |
| Ms. | Maria | Davalos | Novato Chamber of Commerce | | Novato | CA |
| | | | Novato City Council | | Novato | CA |
| Mr. | Dennis | Scoles | Novato Task Force on Homelessness & Restoration Advisory Board | Novato | Novato | CA |
| | | | Public Works Department | | | |
| | | | | Marin County Aviation Commission | San Rafael | CA |
| Director | Paul | Skanchy | Rohnert Park | Planning Department | Rohnert Park | CA |
| Vice President | Janet | Jacob | San Marin Improvement Association | | Novato | CA |
| Hamilton Reuse Entities | | | | | | |
| Ms. | Shira | Wight | Hamilton Advisory Commission | | Novato | CA |
| | Nicki | McIntyre | Hamilton Advisory Commission | c/o Marin County Housing | San Rafael | CA |
| Ms. | Betty | Pagett | Hamilton Advisory Commission | Ecumenical Association for Housing | San Rafael | CA |
| Ms. | Gail | Wilhelm | Hamilton Advisory Commission | | Novato | CA |
| Mr. | Jeff | McAlpin | Hamilton Advisory Commission | | Novato | CA |
| Ms. | Nancy | Sangster | Hamilton Advisory Commission | | Novato | CA |
| Mr. | Harold J. | Leeds | Hamilton Advisory Commission | | Novato | CA |
| Ms. | Elizabeth | Moody | Hamilton Advisory Commission | | Novato | CA |

| Title | First | Last | Organization | Branch | City | State |
|--------------------|-------------|----------------|--|---|--------------|-------|
| Mr. | Robert | Gallimore | Hamilton Advisory Commission | | San Rafael | CA |
| Ms. | Susan | Stompe | Hamilton Advisory Commission | | Novato | CA |
| Mr. | Robert | Telder | Hamilton Advisory Commission | | Novato | CA |
| Ms. | Debbie | Rowland | Hamilton Advisory Commission | | Novato | CA |
| Ms. | Bobbi | Smith | Hamilton Advisory Commission | | Novato | CA |
| Mr. | Earl | Robertson | Hamilton Advisory Commission | | Novato | CA |
| Mr. | Ross | Millerick | Hamilton Advisory Commission | | Novato | CA |
| Ms. | Gloria | Maniscalco | Hamilton Advisory Commission | | Novato | CA |
| Mr. | Martin | Mackey | Hamilton Advisory Commission | | Belvedere | CA |
| Mr. | John | Bishop | Hamilton Advisory Commission & Los Robles Mobile Home Park | | Novato | CA |
| Mr. | Otis | Bruce, Jr. | Hamilton Advisory Commission | | Novato | CA |
| Mr. | Michael | Di Giorgio | Hamilton Advisory Commission | | Novato | CA |
| Mr. | David | Sowers | Hamilton Advisory Commission & Restoration Advisory Board | | Novato | CA |
| Ms. | Cheryl | Van Den Handel | Hamilton Air Field Action Association & Hamilton Advisory Commission | | Novato | CA |
| | Alix T. | Coutts | Hamilton Field Preservation Association | | Corte Madera | CA |
| | Vic | Canby | Hamilton Re-Use Committee | | San Rafael | CA |
| Mr. | William | Long | Multi-Use Agency Board | | Novato | CA |
| Ms. | Betsey | Cutler | Multi-Use Agency Board | | Mill Valley | CA |
| Mr. | Tom | Gram | Martin Group & Restoration Advisory Board | | Emeryville | CA |
| Ms. | Mauricia | Britto | Restoration Advisory Board | | Novato | CA |
| Mr. | Richard | Draeger | Restoration Advisory Board | | Novato | CA |
| Ms. | Patricia D. | Eklund | Restoration Advisory Board | | Novato | CA |
| Mr. | Tom | Gram | Restoration Advisory Board | | Emeryville | CA |
| Mr. | Thomas | Hinman | Restoration Advisory Board | | San Rafael | CA |
| Mr. | Harrison | Karr | Restoration Advisory Board | | Novato | CA |
| Mr. | Andre | Klein | Restoration Advisory Board | | Novato | CA |
| Ms. | Tunstall | Lang | Restoration Advisory Board | | Novato | CA |
| Mr. | Matthew | McCarron | Restoration Advisory Board | | Novato | CA |
| Ms. | Manuel | Mier | Restoration Advisory Board | | Mill Valley | CA |
| Ms. | Sabrina | Molinari | Restoration Advisory Board | | Novato | CA |
| | Karol | Raymer | Restoration Advisory Board | | Mill Valley | CA |
| Mr. | John | Sammons | Restoration Advisory Board | | Novato | CA |
| Ms. | Polly O. | Smith | Restoration Advisory Board | | Tiburon | CA |
| Mr. | Christopher | Valentino | Restoration Advisory Board | | Novato | CA |
| Mr. | Jack | Walton | Restoration Advisory Board | | Novato | CA |
| Mr. | James | Wilson | Restoration Advisory Board | | Novato | CA |
| Organizations | | | | | | |
| | Ceil | Scandone | ABAG Bay Trail | Metro Center Bel Marin Keys Development Association | Novato | CA |
| | | | Allen Larsen Venture Corp. | | Mill Valley | CA |
| | Wendy | Curtis | ARINC | | Alameda | CA |
| President | Harold | Bexton | Bahia Homeowners Association | | Novato | CA |
| Ms. | Ellen | Fusso | Bahia Homeowners Association | | Novato | CA |
| President | Bob | Jordon | Bahia Homeowners Association | | Novato | CA |
| Mr. | Gabriel | Murano | Bahia Homeowners Association | | Novato | CA |
| Corresponding Sec. | Diane | Thompson | Bahia Homeowners Association | | Novato | CA |
| Mr. | Ken | Bell | Robert Bein, Frost, & Associates | | Irvine | CA |
| Ms. | Margit | Allen | Robert Bein, Frost, & Associates | | Irvine | CA |
| Director | Ron | Simkins | Bel Marin Keys C.S.D. | | Novato | CA |
| | | | Bianchi, Paxton, Engel, Keegin | | San Rafael | CA |
| | | | Beryl Buck Inst for Education | | Novato | CA |
| Ms. | Rosalie | Webb | Black Point Environmental Association | | Novato | CA |
| | H. | Barner | Black Point Improvement Club | Liled's Candy Kitchen | Vallejo | CA |

| Title | First | Last | Organization | Branch | City | State |
|-----------|--------------|-----------|--|------------------------------------|---------------|-------|
| Ms. | Susan R. | Diamond | Brobeck, Phleger, & Harrison | | San Francisco | CA |
| | | | Buller Properties | Buller Family Partnership | San Francisco | CA |
| | | | Cheda Knolls HOA | Excel Management Association, Inc. | Novato | CA |
| | John E. | Gibbons | Consultant | | El Granada | CA |
| | | | CSW / Stuber-Stroch Assoc. | | | CA |
| | | | Del Monte HOA | Excel Management Association | Novato | CA |
| Mr. | Richard | Devereaux | Del Monte HOA | | Novato | CA |
| Mr. | Doug | Hale | Domingo Canyon HOA | | Novato | CA |
| Mr. | Joel | Jutovski | Domingo Canyon HOA | | Novato | Ca |
| Mr. | Luc | Vercamman | East Novato Neighborhood Association | | Novato | CA |
| Ms. | Mary | Murtagh | Ecumenical Association for Housing | | San Rafael | CA |
| Mr. | Tom | Graff | Environmental Defense Fund | | Oakland | CA |
| Mr. | Gene | Buvelot | Federated Coast Miwok | | Novato | CA |
| Mr. | Tim | Campbell | Federated Coast Miwok Crossroads HOA | Excel Management Association | Novato | CA |
| | | | GCX Corporation | | Novato | CA |
| | | | Ghilotti Brothers | | San Rafael | CA |
| | | | Gladish Interests Partnerships | | Kentfield | CA |
| Mr. | Ron | Frazier | Global Garden Projects, Inc. | | San Francisco | CA |
| Mr. | Ed | Stark | Griffiths Insurance | | Novato | CA |
| | | | Guild Mortgage Company | | Sacramento | CA |
| | | | Guzzardo Association | | San Francisco | CA |
| Mr. | Stan | Dennison | Hidden Valley HOA | | Novato | CA |
| Mr. | Vern | Dwelly | Hidden Valley HOA | | Novato | CA |
| Mr. | Jim | Parrett | Hidden Valley HOA | | Novato | CA |
| Mr. | Agnus | Gibson | Hill Neighborhood Association | | Novato | CA |
| Ms. | Patricia | Ecklund | Hillside Park East HOA | | Novato | CA |
| Ms. | Peggy | Hewett | Hillside Park HOA | | Novato | CA |
| | | | Horizon Cable Manittion Field | | Fairfax | CA |
| | Robert | Grice | Ignacio Neighborhood Committee | | Novato | CA |
| Ms. | Susan | Alexander | Indian Valley Association | | Novato | CA |
| Mr. | Ronald | Jorgensen | Jorgesen Properties | | San Rafael | CA |
| Mr. | Joseph | La Vigna | La Vigna & Co. | | San Francisco | CA |
| President | Debbie | Taylor | Lanham Village HOA | | Novato | CA |
| Mr. | Stuart | Flashman | Re: Lanham Village HOA | | Oakland | CA |
| President | Bob | Mohr | Laurel Creek HOA | | Novato | CA |
| Ms. | Andrea | Kiesel | Little Village School | | | |
| Mr. | Kevin | Patterson | Living History Centre | | Novato | CA |
| Mr. | Peter | Schunk | Loma Verde HOA | | Novato | CA |
| | Jack & Elsie | Taylor | Los Robles Mobile Home Park Association | | Novato | CA |
| | | | Lynwood Park Improvement Center | | Novato | CA |
| Mr. | Homer | Osgood | Marin Athletic Association | | San Rafael | CA |
| Ms. | Barbara | Salzman | Marin Audubon Society and Hamilton Advisory Commission | | Larkspur | CA |
| Mr. | George | Kozitza | Marin Community College | | Kentfield | CA |
| Mr. | Chip | Wray | Marin Conservation League | | San Rafael | CA |
| President | Priscilla | Bull | Marin Conservation League | | San Rafael | CA |
| Mr. | Hale | Knight | Marin Country Club HOA | | Novato | CA |
| Mr. | Robert | Resner | Marin County Dog Training Club | | San Rafael | CA |
| Ms. | Debora | Faust | Marin Family Action | | Novato | CA |
| Mr. | Michael | Lewis | Marin Horse Council | | Belvedere | CA |
| Mr. | Jim | McDermott | Marin Horse Council | | Kentfield | CA |
| | | | Marin Humane Society | | Novato | CA |
| President | Lew | Olds | Marin Valley Homeowners League | | Novato | CA |
| | | | Marin Valley Mobile Country Club HOA | | Novato | CA |
| Mr. | Todd | Wright | Martin Group | | San Francisco | CA |
| Mr. | Dennis | Foley | McClay Road HOA | | Novato | CA |

| Title | First | Last | Organization | Branch | City | State |
|--------------------|----------|--------------------|---|-----------------------------|---------------|-------|
| President | | | Millard Dubose Trust | | Novato | CA |
| Mr. | Larry | Myers | Mission Estates HOA | | Novato | CA |
| Ms. | Evelyn | Kelly | Native American Heritage Commission | Executive Secretary | Sacramento | CA |
| | | | Nave Gardens HOA | | Novato | CA |
| | | | North Marin Recreation Center | | Novato | CA |
| Mr. | Todd | Wright | New Hamilton Partnership | | Emeryville | CA |
| Mr. | Clark | Blasdell | Northbay Ecumenical Homes | | Novato | CA |
| Mr. | Michael | Malone | Northern California Rugby Football Union | | San Rafael | CA |
| Mr. | Charles | Badell | Northern California Rugby Union | | Petaluma | CA |
| | M. | Begley | Northwest Information Center | Department of Anthropology | Rohnert Park | CA |
| Mr. | Paul | Scheller | Novations for Sensible Growth | | Novato | CA |
| Ms. | Ms. | Kapranos | Novato Child Care Family Task Force | | Novato | CA |
| President | Marsha | Triplett | Novato Heights HOA | | Novato | CA |
| Mr. | Karen | Millikin | Novato Historical Guild | | Novato | CA |
| | Bill | Palmer | Novato Historical Guild | | Novato | CA |
| | Bruce E. | Johnson | Novato Little League | | Novato | CA |
| | Bosco | Wai-Choy Chiu | Novato Marie Callender Investors | | San Francisco | CA |
| | | | NWPRR | Southern Pacific Trans. Co. | Oakland | CA |
| Mr. | Bill | Gabbert | Old Town Merchants Association | | Novato | CA |
| Ms. | Lola | Gerhard | Pacheco Meadows HOA | | Novato | CA |
| Mr. | Frank | Bullentine | Pacheco Valle Hillside | | Novato | CA |
| President | Walter | Kettler | Pacheco Valle Masters Assoc. | | Novato | CA |
| Ms. | Louise | Sullivan | Pacheco Valle Masters Association | | Novato | CA |
| Mr. | Jerry | Evans | Pacheco Villas HOA | | San Francisco | CA |
| Mr. | Ron | Lake | Pacheco Villas HOA | | Corte Madera | CA |
| Staff Manager | | | Pacific Bell | Property Taxes | San Francisco | CA |
| Manager | | | Pacific Gas & Electric Company | | San Rafael | CA |
| | A. | Steinau | Pamaron Partners | | San Rafael | CA |
| President | Bob | Dreher | Parkridge Knolls HOA | | Novato | CA |
| Ms. | Cynthia | Clinton | Partridge Knolls Hoa | | Novato | CA |
| | | | Pioneer Park Neighborhood Association | | Novato | CA |
| Mr. | Jack | Slade | Poplar Terrace Neighborhood Association | | Novato | CA |
| | | | Prospect Place HOA | | Novato | CA |
| | | | Redwood Townhome Association | Excel Management Assoc. Inc | Novato | CA |
| Mr | B. Glen | Worthington Lajoie | River Vista HOA | | Novato | CA |
| | | | Robert Bein, William Frost and Associates | | Irvine | CA |
| Manager | K. Les | Symonds McDonald | Rolling Thunder | | Novato | CA |
| | | | Roman Catholic Archdiocese of San Francisco | Real Estate Department | San Francisco | CA |
| Ms. | Joyce T. | Lashbrook | San Geronimo Valley Horseman's | | Fairfax | CA |
| Mr. | Richard | Warren | San Marin HOA | | Novato | CA |
| | R. | Crutchfield | San Marin Valley HOA | | Santa Rosa | CA |
| Ms. | Patricia | Miller | Scottsdale Lake Homeowners Assoc. | | Novato | CA |
| Mr. | Phil | Petersen | Sierra Club, Marin Group | | Mill Valley | CA |
| Mr. | Stuart | Ludlow | Skylark Meadows HOA | | Novato | CA |
| Executive Director | Neil | Havlik | Solano County Farmlands and Open Space Foundation | | Fairfield | |
| President | Victor | Perella | South Novato HOA | | Novato | CA |
| | S.E. | Karson | Southern Pacific Transportation Co. | | San Francisco | CA |
| Mr. | Mike | Markovich | St. Vincents School for Boys | | San Rafael | CA |
| Ms. | Kathy | Lowrey | The Environmental Forum of Marin | | Larkspur | CA |
| | Colleen | | The Nature Conservancy | | San Francisco | CA |
| Ms. | Virginia | Brunini | The Prudential CA Realty | | Mill Valley | CA |
| Mr. | Roger | Will | Trust for Public Land | | San Francisco | CA |
| Mr. | Frank | Falzon | Verismo Valley HOA | | Novato | CA |
| Mr. | Ed | Dill | Village Marin Hillside | | Novato | CA |

| Title | First | Last | Organization | Branch | City | State |
|------------------|------------|------------|----------------------------------|-----------------------|------------|-------|
| Mr. | Jeffrey A. | Walter | Walter & Pistole | | Santa Rosa | CA |
| | P. | Midburst | Western Media | | Novato | CA |
| | Vic | Udaloff | Western Oaks Village Association | | Novato | CA |
| Mr. | Rich | Di Martini | Wild Horse Valley Association | | Novato | CA |
| Mr. | Palmer | Wilkins | Woodlands Homeowners Association | | Novato | CA |
| Libraries | | | | | | |
| | | | Novato Public Library | 1720 Novato Blvd. | Novato | CA |
| | | | Marin County Library | Marin Civic Center | San Rafael | CA |
| | | | Petaluma Regional Library | 100 Fairgrounds Drive | Petaluma | CA |
| | | | Sonoma County Central Library | 3rd and E Streets | Santa Rosa | CA |


Individuals (on distribution list)

| | | |
|------------------------|----------------------------|---------------------------|
| Amy L. A. | Lynda Edwards | Judith McClaren |
| Sarah Angulo-Curry | Deborah Emory | Reed and Susan McClintock |
| Anne Arena | Harry Flachs | Louis McDonald |
| John Arntz | Harry Forrest | Gail Meyers |
| Johanna Ashworth | Berwyn Forsythe | Louise Mills |
| Cindy Berinson | Rick Fraites | Earnest Molins |
| Ralph Bien | Charles Gallagher | Elizabeth Moody |
| Richard Breiner | John Garrett | Harry Moore |
| Susan Bricarelli | Patrice Garrett | C.O. and Alexa Morrison |
| Charles Buada | John and Cheryl Giles | Bob Morrow |
| Patti Bucy | John Gill | Catherine Morsehead |
| Thomas Buckle | Forrest Goff | Jeffory Morsehead |
| Bob Burke | Jean and Dorothy Goldstone | Dean Moser |
| Linda Buckley | Mike Gozashti | Martin Mueller |
| Ted Cain | Robert Griegg | Jack Nancarrow |
| Jack Campbell | John Groshak | Robbie Nancarrow |
| Tony Campodonico | Wayne Gurney | Karen Neilson |
| Marcia Carey | Thomas Haas | Terri Nevins |
| Alison Cauacaorch | Patricia Hadfield | Jeanine North |
| Irving Chapman | Karlos Halfhide | Don Nowacki |
| Erika Choy | Jim Henderson | Martin Peckins |
| Ruth Clark | Jim Hickey | Rita Pingatore |
| Braith and Jane Cleary | Steve Hoxie | Victor Pizarro |
| Lauren Cobb | M.C. Hungerford | Steven Podesta |
| Bill Collins | Jane D. Johnson | Charlotte Poole |
| James Coyle | Wendy Kallins | Bob Puett |
| Debra Craddock | Craig Kay | Sally Ready |
| William Craddock | Diane Kay | Carol Riklin |
| Rolfe and Julie Croker | Kristopher Kay | David Ripple |
| Geoffrey Currie | Alice Kelly | Bob Roberts |
| James Current | Dave Kenyon | Denny Rodown |
| Kathleen Curtis | Nancy and Mark Kubick | Herb Rowland |
| Elaine Dal Bon | Chris Lang | David Rubinger |
| John Daniels | Kim Lawrence | Jen Rusk |
| RJ DeRecat | Stuart Levin | William Rutledge |
| Daniel Donovan | Robert Levy | Paul and Eleanor Sade |
| Mark Donovan | Lora Logsdon | Kendall Sareth |
| Roy Dotto | Robert Luff | Marion Saunders |
| Loree Draeger | Betty Machado | Adrian and Jacqueline |
| Donald Dunn | Marjorie Macris | Scharlach |
| Guy and Mary Duryee | John Mani | Leonard Shaw |
| Heidi Eberly | Jerry Mayer | Merton Shelton |

10. Distribution List

Keith Shine
William Silva
Joseph and Mary Silveira
David and Anne Silverman
Cathy Sinclair
Grant Smith
Kathleen Smith
Lawrence Smith
T.F. Spink
Bjorn Stumer
Jennifer Surprise
Marc Tatarian
CJ Thelem
Kenneth and Teresa Toscanini
Bill Trumbo
Hugh Turner
Louis Vaccaro
Joyce Van Denburg
Bobbe Vargas
Augie Venezia
Loreene Volk
James Wallace
Jack Walton
Patsy White
Jennifer Wilkes
Kelly William
Cope Williams
Don Wilson
Fred Worth
Darlene Yochum
Ray Yochum
John Zamboli

**DODHF
Novato**



COMMENTS AND RESPONSES

**RESPONSE TO COMMENTS
ON THE
DRAFT ENVIRONMENTAL IMPACT STATEMENT
FOR THE
DISPOSAL AND REUSE OF DEPARTMENT OF DEFENSE HOUSING FACILITY
NOVATO, CALIFORNIA**

Introduction

The Draft Environmental Impact Statement (Draft EIS) for the Disposal and Reuse of the Department of Defense Housing Facility, Novato, California, was circulated for public and agency review from January 31, 1997 to March 17, 1997. During this period, the lead agencies, the US Navy and the City of Novato held a public hearing on February 27, 1997, to provide the public an opportunity to comment on the content and accuracy of the Draft EIS. In addition, written comments on the Draft EIS were accepted throughout the review period.

In accordance with National Environmental Policy Act (NEPA) Regulations, a final environmental impact statement shall provide responses to comments on the Draft EIS (40 CFR 1503.4). In compliance with those regulations, this response to comments appendix to the Final EIS presents all of the written and public hearing comments received during the review period, followed by responses to the substantive environmental issues raised in the comments.

This appendix presents a list of agencies, organizations, and individuals commenting on the Draft EIS. The list is followed by copies of all comment letters and the portion of the public hearing transcript containing public comments. Individual comments within each letter or portion of the transcript are identified by a letter and number and responses to each comment are presented on the facing page. If a comment does not relate to a substantive environmental issue, or expresses an opinion or fact, it is acknowledged by the words "comment noted."

List of Commenters

| Letter | Commenter | Letter or Comment Date |
|---------------|--|-------------------------------|
| A | David J. Farrel, Chief, Office of Federal Activities, US Environmental Protection Agency | March 14, 1997 |
| B | Patricia Sanderson Port, Regional Environmental Officer, Office of the Environmental Policy and Compliance, National Park Service, US Department of the Interior | March 17, 1997 |
| C | Theresa McGarry, Environmental Assessment and Reuse Specialist, Office of Military Facilities, California Department of Toxic Substances Control | March 17, 1997 |
| D | Glenn Lajoie, AICP, Senior Project Manager at Robert Bein, William Frost, and Associates, for the City of Novato | March 10, 1997 |

| | | |
|---|---|-------------------|
| E | Eric McGuire, Environmental Services Coordinator, Marin Municipal Water District | March 4, 1997 |
| F | Edith M.S. Robbins, Senior Civil Engineer, North Marin Water District | March 11, 1997 |
| G | Thomas S. Selfridge, Technical Services Manager, Novato Sanitary District | March 17, 1997 |
| H | Annette Conklin, Director of Community Relations, Novato Unified School District | March 21, 1997 |
| I | Historical Resources Information System, Northwest Information Center, Sonoma State University | February 20, 1997 |
| J | Nicky McIntyre, HHTF Coordinator, Marin Housing, Housing Authority of the County of Marin | March 17, 1997 |
| K | Phil Peterson, Sierra Club, Marin Group | March 17, 1997 |
| L | Barbara Salzman, Chair, Conservation Committee, Marin Audubon Society | February 21, 1997 |
| M | Priscilla Bull, President, Marin Conservation League | March 17, 1997 |
| N | Betty Pagett, Member, Hamilton Advisory Commission, Ecumenical Association for Housing | February 26, 1997 |
| O | Debora Faust, Leadership Group Member, Marin Family Action | March 11, 1997 |
| P | Mark Kubick, M.D., Nancy Kubick, M.D. | February 3, 1997 |
| Q | Stuart Flashman, Attorney, on behalf of Lanham Village Homeowners Association | March 17, 1997 |
| R | Andrea Kiesel, owner, Little Village School, Lanham Village | February 27, 1997 |
| S | William S. Craddock, Debra A. Craddock, Novato | February 27, 1996 |
| T | Susan Bricarelli, Novato | February 27, 1997 |
| U | Diane Kay, Kristopher Kay, Craig Kay, Jennifer Surprise, Novato | March 4, 1997 |
| V | Cathy Sinclair, Jack Nancarrow, Robbie Nancarrow, Novato | March 17, 1997 |
| W | Jen Rusk, Novato | March 17, 1997 |
| X | Marion Saunders, Johanna Ashworth, Amy L. A??, Jennifer Wilkes, Darlene Yochum, Ray Yochum, Kendall Sareth, Patti Bucy, Marcia Carey, Alison Cauacaourch, Jeanine North, Louise Mills | February 27, 1997 |
| Y | Linda Buckley, Novato | February 27, 1997 |

| | | |
|-------|----------------------------|-------------------|
| Z | Kathleen Curtis, Novato | February 27, 1997 |
| PH1 | Bill Long - MAB | February 27, 1997 |
| PH2 | Jim Henderson, Novato | February 27, 1997 |
| PH3- | Keith Shine, Novato | February 27, 1997 |
| PH13 | | |
| PH14 | Sally Ready, Novato | February 27, 1997 |
| PH15 | Heidi Eberly, Novato | February 27, 1997 |
| PH16 | Jane Davis Johnson, Novato | February 27, 1997 |
| PH17 | Mark Donovan, Novato | February 27, 1997 |
| PH18 | Andrea Kiesler, Novato | February 27, 1997 |
| PH19- | Judith McClaren, Novato | February 27, 1997 |
| PH23 | | |
| PH24- | Karlos Halfhide, Novato | February 27, 1997 |
| PH27 | | |
| PH28- | Jen Russ, Novato | February 27, 1997 |
| PH34 | | |
| PH35- | Elizabeth Moody, Novato | February 27, 1997 |
| PH38 | | |
| PH39- | Patrice Garrett, Novato | February 27, 1997 |
| PH41 | | |
| PH42 | Martin Peckins, Novato | February 27, 1997 |
| PH43- | Debra Foust, Novato | February 27, 1997 |
| PH44 | | |
| PH45 | Kim Laurance, Novato | February 27, 1997 |
| PH46- | Bob Roberts, Novato | February 27, 1997 |
| PH47 | | |
| PH48- | Bill Collins, Novato | February 27, 1997 |
| PH51 | | |
| PH52- | Debbie Taylor, Novato | February 27, 1997 |
| PH56 | | |
| PH57 | Bill Trombeau, Novato | February 27, 1997 |
| PH58- | Dean Moser, Novato | February 27, 1997 |
| PH60 | | |



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION IX

75 Hawthorne Street
San Francisco, CA 94105-3901

MAR 14 1997

Mr. Gary Munekawa
Code 1852GM
Engineering Field Activity West
900 Commodore Drive
San Bruno, California 94066-5006

Dear Mr. Munekawa:

The Environmental Protection Agency (EPA) has received the Environmental Impact Statement (EIS) for the proposed **Disposal and Reuse of the Department of Defense Housing Facility, Novato, California**. Our review is based on the National Environmental Policy Act (NEPA), the Council on Environmental Quality (CEQ) NEPA Implementation Regulations (40 CFR Parts 1500-1508), and Section 309 of the Clean Air Act (CAA).

Pursuant to the Defense Base Closure and Realignment Act (Public Law 101-510) and the base closure decisions approved by Congress in October 1993, the Department of Defense Housing Facility Novato (DODHF Novato) in Novato, California, has been closed. DODHF Novato includes two Navy-owned areas at the former Hamilton Air Force Base: the Main Site property and the off-site Rafael Village housing property. The EIS evaluates the proposed disposal of DODHF property and structures and the subsequent reuse of those facilities.

DODHF Novato is in the southeast portion of the City of Novato in eastern Marin County, California. The Rafael Village housing area of the DODHF Novato was closed in September 1995 while the DODHF Novato was closed completely in September 1996; it is currently under caretaker status. Remediation of site hazardous waste and contamination is on-going and is being conducted under the guidance of the California Department of Toxic Substances Control. The 411-acre site, which historically served as the housing and community services portion of the former Hamilton Air Force Base, includes military family housing, a commissary, a naval exchange, and community service and recreational areas. Other parts of the former air base adjacent to DODHF Novato but not part of this disposal and reuse action include a six-acre US Coast Guard parcel, a 105-foot railroad right-of-way, the 720-acre former Hamilton Army Airfield, and the 415-acre site being developed under the New Hamilton Partnership Master Plan.


The Preferred Alternative analyzed in the EIS is the disposal of DODHF property and subsequent reuse as described in the revised Hamilton Army Airfield Reuse Plan. The "Revised Plan" proposes demolishing existing housing and constructing new housing units at Rafael Village and reusing existing Main Site buildings and structures for uses similar to historic uses. Additional alternatives analyzed in the EIS include the Open Space Alternative and the No Action Alternative.

Based upon our review, we have rated the Draft EIS EC-2, Environmental Concerns - Insufficient Information (see attached *Summary of the EPA Rating System*). This rating reflects our conclusion that the Draft EIS should provide additional information on certain issues, including: project description, air quality, water and wetlands. Our detailed comments are enclosed.

We commend the Navy for preparing a generally well-written and organized report. We particularly appreciate the use of clear significance criteria and distinct and clearly enumerated impact and mitigation statements throughout the document. We appreciate the opportunity to comment on the proposed project and request that you provide this office (mail code CMD-2) with one copy of the Final EIS at the same time it is filed with our Washington, D.C. office. If you have any questions or wish to discuss any aspect of our comments, please contact me at (415) 744-1584 or Jeff Philliber of my staff at (415) 744-1574.

A-1

Sincerely,



David J. Farrel

David J. Farrel, Chief
Federal Activities Office

2569hnov.ds.jp
Enclosures: (2)

SUMMARY OF RATING DEFINITIONS AND FOLLOW-UP ACTION

Environmental Impact of the Action

LO-Lack of Objections

The EPA review has not identified any potential environmental impacts requiring substantive changes to the proposal. The review may have disclosed opportunities for application of mitigation measures that could be accomplished with no more than minor changes to the proposal.

EC-Environmental Concerns

The EPA review has identified environmental impacts that should be avoided in order to fully protect the environment. Corrective measures may require changes to the preferred alternative or application of mitigation measures that can reduce the environmental impact. EPA would like to work with the lead agency to reduce these impacts.

EO-Environmental Objections

The EPA review has identified significant environmental impacts that must be avoided in order to provide adequate protection for the environment. Corrective measures may require substantial changes to the preferred alternative or consideration of some other project alternative (including the no action alternative or a new alternative). EPA intends to work with the lead agency to reduce these impacts.

EU-Environmentally Unsatisfactory

The EPA review has identified adverse environmental impacts that are of sufficient magnitude that they are unsatisfactory from the standpoint of environmental quality, public health or welfare. EPA intends to work with the lead agency to reduce these impacts. If the potential unsatisfactory impacts are not corrected at the final EIS stage, this proposal will be recommend for referral to the Council on Environmental Quality (CEQ).

Adequacy of the Impact Statement

Category 1-Adequate

EPA believes the draft EIS adequately sets forth the environmental impact(s) of the preferred alternative and those of the alternatives reasonably available to the project or action. No further analysis or data collection is necessary, but the reviewer may suggest the addition of clarifying language or information.

Category 2-Insufficient Information

The draft EIS does not contain sufficient information for EPA to fully assess environmental impacts that should be avoided in order to fully protect the environment, or the EPA reviewer has identified new reasonably available alternatives that are within the spectrum of alternatives analyzed in the draft EIS, which could reduce the environmental impacts of the action. The identified additional information, data, analyses, or discussion should be included in the final EIS.

Category 3-Inadequate

EPA does not believe that the draft EIS adequately assesses potentially significant environmental impacts of the action, or the EPA reviewer has identified new, reasonably available alternatives that are outside of the spectrum of alternatives analyzed in the draft EIS, which should be analyzed in order to reduce the potentially significant environmental impacts. EPA believes that the identified additional information, data, analyses, or discussions are of such a magnitude that they should have full public review at a draft stage. EPA does not believe that the draft EIS is adequate for the purposes of the NEPA and/or Section 309 review, and thus should be formally revised and made available for public comment in a supplemental or revised draft EIS. On the basis of the potential significant impacts involved, this proposal could be a candidate for referral to the CEQ.

*From: EPA Manual 1640, "Policy and Procedures for the Review of Federal Actions Impacting the Environment."

NEPA and Planning Issues

1. The Draft EIS analysis should not assume that DODHF Novato activity levels prior to base closure can be used as an accurate baseline with which to compare projected impacts. The closure of DODHF Novato is a BRAC decision that is statutorily exempt from NEPA (Public Law 101-510, Section 2906). The closure action, then, is moot and separate from the disposal and reuse action; the analysis should generally use post-closure or No-Action activity levels as a proper baseline for analysis. A-2
2. Page ES-4: The Draft EIS identifies that "the primary objective of the planning process was to develop a community reuse plan for the entire former Hamilton Air Force Base complex" and that "in March 1994, the City of Novato and Marin County agreed to establish a procedure for joint participation in the reuse planning process for the former Hamilton Air Force Base to ensure the protection of local and regional interests." We concur with this approach. The Navy should explain in the Final EIS why the NEPA analysis of the proposed disposal and reuse of DODHF Novato is being conducted separately from other, similar actions being proposed for former Hamilton Army Air Force Base parcels, in accordance with 40 CFR Parts 1508.25(a)(1)(iii) and 1508.25(a)(3). A-3
3. Page 2-11: The portion of DODHF Novato identified as Planning Area 3, or the Spanish Housing site, is being transferred to the U.S. Coast Guard and is addressed only as a cumulative impact to the proposed action. Because the federal action analyzed in the Draft EIS is the disposal of DODHF Novato (Draft EIS page 1-1), however, we recommend that the disposal of the Spanish Housing site, be subject to full environmental analysis in the EIS. A-4
4. Page 4-4: The Draft EIS reports that no land use impacts would occur from the reuse of the Rafael Village area because "the site currently is used for residential uses and is compatible with the surrounding residential and open space uses." While the site was formerly used for residential purposes, it was closed in September 1995 and its houses are currently "boarded up" and in a state of disrepair (Draft EIS page 3-10). The Final EIS should reflect this. Please refer to NEPA comment #1, above. A-5

5. Page 5-4: In general, we commend the Navy on its Draft EIS approach to cumulative impacts analysis. The Final EIS, however, should provide additional information regarding its treatment of the Hamilton Army Airfield Disposal and Reuse project for that analysis. As stated in the Draft EIS, "although the EIS for the (Airfield) site included a number of reuse alternatives, the City of Novato has requested that the majority of the site become salt marsh wetlands." Apparently on the basis of that observation, the DODHF Novato Draft EIS cumulative impacts analysis assumes that the Airfield will be reused in that low-intensity manner. Under that assumption, potential cumulative impacts for the proposed action probably appear substantially less-severe than if a high-intensity reuse were to be chosen for the airfield (such as a civilian airport reuse). The Final EIS should provide additional information to ensure that its exclusive selection of the Hamilton Army Airfield wetlands reuse scenario is warranted, or it should expand its cumulative impacts analysis to account for different reuses of the Airfield.

A-6

Resource Issues

1. Page 4-29: The Draft EIS reports that the proposed project and its alternatives would not have a significant impact on water supply, as they "would result in levels of residential and commercial development nominally equivalent to existing conditions, so that a significant increase in water consumption would not be anticipated." As stated in NEPA comment #1, above, the EIS analysis should not assume historic, pre-closure DODHF Novato operational levels as the basis for measuring impact significance. The Navy should contact the North Marin Water District in determining whether or not a significant impact to water supply would be expected. This information should then be conveyed in the Final EIS.
2. Page 4-36: The Draft EIS identifies that the proposed action and alternatives would result in a significant, adverse impact to cultural resources because they would transfer several NRHP-eligible historic and potential archaeological sites to a nonfederal entity without restrictions on future uses. The EIS analysis bases its finding of significance on 36 CFR 800.9(b), which states that "the transfer, lease, or sale of a property from federal ownership without adequate restrictions or deed covenants to ensure preservation is an adverse effect and for purposes of NEPA would be a significant and mitigable

A-7

A-8

impact." Although the EIS finds that the impact is mitigable, it is not clear from the analysis why "adequate restrictions or deed covenants" would not be used by the Navy to prevent the significant impact from occurring (rather than rely on mitigation).

A-8

3. Pages 4-77, 5-14: The Draft EIS discloses that although the proposed action would create significant air quality impacts "in a NEPA context," (by exceeding the Bay Area Air Quality Management District's 80 pounds-per-day significance threshold for NO_x and 11 pounds-per-day for ROG), the added emissions would not measurably affect the Bay Area's attainment status for ozone and thus would not affect the Bay Area's ozone attainment status. However, under the EIS cumulative impacts analysis, the EIS reads that "although adding to cumulative air emissions in the ROI, these alternatives would not affect the Bay Area's attainment status for ozone." The Navy should explain in the Final EIS why the Bay Area's ozone attainment status would not be measurably affected by the cumulative effects of relatively small but significant additional emissions of NO_x and ROG elsewhere in the District. According to 40 CFR 1508.7, "(c)umulative impacts can result from individually minor but collectively significant actions taking place over a period of time."

A-9

4. Page 3-57: Under its discussion of wetlands-related policies, the Final EIS should identify Executive Order 11990--Protection of Wetlands and describe what actions the Navy will take in order to follow its directives. Executive Order 11990 requires that each federal agency, when proposing to dispose of federally-owned wetlands, to "(a) reference in the conveyance those uses that are restricted under the identified Federal, State or local wetlands regulations; and (b) attach other appropriate restrictions to the uses of properties by the grantee or purchaser and any successor, except where prohibited by law; or (c) withhold such property from disposal." Although the Draft EIS offers that DODHF Novato wetlands would be protected by existing provisions of Section 404 of the Clean Water Act, EPA believes that consistency with Executive Order 11990 requires additional action by the Navy.

A-10

Response to Comments

Response to Comment A-1. Comment noted, detailed responses to follow.

Response to Comment A-2. The Navy considers analysis compared to previously established environmental conditions appropriate. For many issues, pre- and post-closure conditions are the same [biology, water quality, visual, land use, hazardous material, cultural resources, geology]. For those issue topics that do change [socioeconomics, public services, utilities, traffic, air quality and noise], it is generally more informative to compare past use of the facilities and identify the conditions at that time than under post-closure conditions for which no data exist. The EIS discusses preclosure conditions plus a future no action (caretaker status) alternative.

Response to Comment A-3. As described in EIS Section 1.2.2, Hamilton Air Force Base has had a long history as a military base and has been owned by various entities within the Department of Defense (DOD). Various parcels at Hamilton have been owned by the Army, the Navy, the US Coast Guard (USCG), and the US Air Force. As the country's military needs have changed, various portions of the base have been closed through the years. In each case, environmental documentation has been prepared for the disposal and reuse planning effort of the individual federal action. In the case of the General Services Administration parcels sold to the New Hamilton Partnership, the disposal and planning for reuse has been ongoing for over 20 years. The 700-acre Army owned runway parcel was identified for closure under BRAC I in 1988. The Army completed its National Environmental Policy Act (NEPA) analysis with a Record of Decision in February 1997. The DODHF Novato parcels were recommended for closure in October 1993. Because these were nonconcurrent federal actions occurring under the jurisdiction of separate federal agencies, the actions are analyzed in separate NEPA documentation. The EIS does however address the relationship of the current planning effort in relation to the other projects occurring in the area in Section 5.1, Cumulative Impacts.

Response to Comment A-4. The Navy is transferring the Spanish Housing to the USCG for their continuing use. This action is a transfer of administrative responsibilities and has no environmental impact. The USCG is responsible for all future NEPA documentation for the Spanish Housing area. The Navy action in the EIS only involves property disposal and subsequent reuse of property leaving federal ownership. The EIS analyzes impacts from expected USCG uses of the property and other proposed nearby uses in Section 5.1, Cumulative Impacts.

Response to Comment A-5. Although the site is closed, it is developed as a residential area. Surrounding uses are residential and open space. Future use of the area for residential uses would not introduce a conflicting land use to the site. Continued residential use of the site would be expected to be compatible with surrounding uses. In addition, future specific development plans for the site would be subject to environmental review under California Environmental Quality Act (CEQA) and approval by the City of Novato. To more accurately reflect current conditions, the following sentence is added to EIS Section 4.1.2, Rafael Village:

"The site is currently developed with military residential units, but the units are closed and being maintained under caretaker status. Previous residential uses were compatible with the surrounding residential and open space uses."

Response to Comment A-6. Based on the Army's analysis of the runway site, as conducted in an EIS on reuse options for the site (Army 1996), the City of Novato has concluded that the Open Water/Natural Wetlands Formation Alternative is the most feasible and desirable alternative for the property. The Revised Reuse Plan identifies the entire 700-acre site as Open Space for wildlife habitat restoration and wetland restoration uses. The EIS therefore analyzes cumulative impacts based on open space use for the runway parcel.

Response to Comment A-7. Current water consumption under caretaker status is relatively low. As stated in the EIS, under the reuse alternatives, water consumption would be nominally similar to the prior use of the site as a military facility. The North Marin Water District did not comment on this issue in their comment letter (Letter F). The district, when contacted to further confirm this finding, concurred with the conclusion that adequate water supply exists to supply the new development proposed at the site (Edith Robbins, personal communication).

Response to Comment A-8. As a result of the reevaluation of the historic district (see Appendix E of the Final EIS), the only Navy properties remaining eligible for inclusion in the National Register are the Spanish Housing structures, Theater, Amphitheater, Bachelor Officers' Quarters (BOQ), and Swimming Pool. The Spanish Housing area will be transferred to the USCG and will continue to be protected by Federal historic preservation legislation. It is anticipated that the other four properties will be transferred to the City of Novato through National Park Service (NPS) administered programs for public benefit conveyance of surplus Federal property and the NPS will identify an appropriate treatment plan pursuant to the National Historic Preservation Act prior to disposal of these properties.

Response to Comment A-9. The Bay Area Air Quality Management District's (BAAQMD's) impact significance thresholds are based solely on the incremental addition of emissions from a proposed action. Nothing in those impact significance thresholds implies that the incremental addition of new emission sources would automatically translate into new or more frequent violations of federal or state ambient air quality standards.

The 1994 Bay Area Clean Air Plan is based on land use and transportation patterns that existed in the early 1990s. Because most military installations are accounted for in the air quality plan as active facilities, the preclosure activity scenario provides a useful basis for judging the extent to which reuse alternatives cause increases or decreases in traffic-related emissions. Compared to preclosure emission levels, the alternatives evaluated in the EIS would result in emission levels well below the BAAQMD impact significance thresholds (Revised Reuse Plan Alternative) as well as below preclosure emission levels (Open Space and No Action Alternatives).

Despite continual urban growth and the addition of new emission sources, there has been a clear downward trend in the magnitude and frequency of violations of the federal ozone standard over the last 20 years. The incremental addition of new emission sources has been more than offset by continuing improvements in emission controls for stationary, mobile, and area sources. In 1995 USEPA changed the ozone status designation for the San Francisco Bay Area from nonattainment to attainment. From a cumulative perspective, the long-term trend in the San Francisco Bay Area is clearly one of improving air quality conditions.

Response to Comment A-10. In accordance with Executive Order 11990, Protection of Wetlands, the Navy will reference in conveyance documents that the federal Clean Water Act regulates discharge of materials into wetlands and that streambank alterations require a permit under the California Fish and Game Code, Section 1603. As the wetlands at DODHF Novato are not proposed for development as part of the reuse plan, and do not support endangered or threatened species, no additional restrictions are required to protect these wetlands.



United States Department of the Interior

OFFICE OF THE SECRETARY
Office of Environmental Policy and Compliance
600 Harrison Street, Suite 515
San Francisco, California 94107-1376

ER 97/67

March 17, 1997

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
Attn: Mr. Gary J. Munekawa
Environmental Planning Branch
Code 1852GM
900 Commodore Drive
San Bruno, California 94066-5006

Dear Mr. Munekawa:


Thank you for the opportunity to comment on the Draft Environmental Impact Statement (DEIS) for the Disposal and Reuse of the Department of Defense Housing Facility, Novato, California.

The Affected Environment, Cultural Resources Section 3.6.3 indicates that structures within the Hamilton Army Airfield Historic District were recently being reevaluated for inclusion on the National Register of Historic Places. This section also stated that the reevaluation, conducted in consultation with the State Historic Preservation Office, was not completed prior to the DEIS release of January 1997. The National Park Service requests that this report be included in the Final Environmental Impact Statement.

B-1

Regarding these aspects of the proposed project, please contact Mr. Matt Wagers, Compliance Specialist, Pacific Great Basin System Support Office of the National Park Service at (415) 427-1442.

Sincerely,


Patricia Sanderson Port
Regional Environmental Officer

cc: Director, OEPC, w/original incoming
Field Director, Pacific West Area, NPS
Regional Director, FWS, Region.I

Response to Comments

Response to Comment B-1. The reevaluation report for the National Register of Historic Places (NRHP), "National Register Eligibility Reevaluation Hamilton Army Airfield Historic District Department of Defense Housing Facility Novato, California," was completed in February 1997 by PAR Environmental Services, Inc. The reevaluation of the historic district by the Navy was prompted by the New Hamilton Partnership's initiation of the redevelopment of the property it acquired from the General Services Administration and the Army. This has resulted in demolition of major portions of the historic district and the introduction of new construction. The reevaluation, concurred in by the State Historic Preservation Officer (SHPO), scales back the historic district to three discontinuous parts as shown in Figure 3-6. A copy of the SHPO's letter of concurrence is included in Appendix E of the Final EIS. A copy of this report was sent to Ms. Joan Chaplick of the Federal Lands to Parks Program, National Park Service, on March 13, 1997. The entire report has not been reproduced as an EIS appendix to shorten the document and reduce costs. Individual copies of the report are available from Mr. Gary Muneawa, the Navy point-of-contact for this EIS, whose address is listed in the front of this EIS.



Cal/EPA

Department of
Toxic Substances
Control

400 P Street,
4th Floor
P.O. Box 806
Sacramento, CA
95812-0806

Letter C



Pete Wilson
Governor

James M. Strock
Secretary for
Environmental
Protection

March 17, 1997

Mr. Gary Munekawa
Environmental Planning Branch, Code 185
U.S. Navy, Engineering Field Activity West
Naval Facilities Engineering Command
900 Commodore Drive
San Bruno, CA 94066-5006

REVIEW OF THE DRAFT ENVIRONMENT IMPACT STATEMENT FOR THE
DISPOSAL AND REUSE OF THE DEPARTMENT OF DEFENSE HOUSING
FACILITY NOVATO, CALIFORNIA DATED JANUARY 1997.

Dear Mr. Munekawa:

The Department of Toxic Substances Control (DTSC) is the lead state department within the California Environmental Protection Agency (EPA) for environmental cleanup of closing military bases. DTSC also has jurisdiction over all hazardous waste issues. DTSC has coordinated with the San Francisco Regional Water Quality Control Board (RWQCB) on the review of this document. Please find our comments below:

1. Page 3-114, Hazardous Materials and Waste. This section should reference the fact that as part of President Clinton's Five Point Program for restoration and reuse of closing military bases, a Base Realignment and Closure (BRAC) Cleanup Team (BCT) has been established for "fast track cleanup". The BCT members are made up of representatives from the Navy, United States EPA, DTSC and RWQCB. The BCT is responsible for developing and implementing the BRAC Cleanup Plan for Department of Defense Housing Facilities (DoDHF) Novato.

C-1



Printed on Recycled Paper

Mr. Gary Munekawa
March 17, 1997
Page 2

2. Page 3-115, Section 3.13.1, Hazardous Materials Regulations. Please include clarifying information regarding State jurisdiction. For example, environmental remediation at DoDHF is subject to State laws. The basis for DTSC's regulatory authority is found in California Health and Safety Code, Division 20, Chapters 6.5 (Hazardous Waste Control Law (HWCL)) and Chapter 6.8 (Hazardous Substances Account Act). The RWQCB has authority over the remediation of petroleum sites and the protection of the waters in the State of California. The RWQCB regulatory authority is found in the Porter-Cologne Water Quality Control Act, California Water Code and California Code of Regulations, Title 23.

C-2

3. Page 3-116, Community Environmental Response Facilitation Act (CERFA).

a. Second paragraph. Please include the statutory reference for CERFA, which is Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) Section 120(h)(4). CERCLA Section 120(h)(4) requires the U.S. EPA to concur with the identification of uncontaminated real property for those federal facilities on the National Priority List (NPL). For those federal facilities not listed on the NPL, in the case of DODHF Novato, CERCLA Section 120(h)(4) requires State concurrence. Properties determined to be "uncontaminated" pursuant to CERFA can be transferred under CERCLA Section 120(h)(4). Other properties which have had releases of hazardous substances can be transferred pursuant to CERCLA Section 120(h)(3) once remedial action is taken. Deferral of the CERCLA Section 120(h)(3) requirements is also possible under specified conditions. For example, property is suitable for the intended use and the transfer will not interfere or delay necessary response actions.

C-3

Mr. Gary Munekawa
March 17, 1997
Page 3


- b. Third paragraph. The text states that CERCLA Section 120(h)(3) was amended in 1996. This is correct. However, the discussion in the Environmental Impact Statement (EIS) should clarify that this amendment provides the authority to transfer federal property contaminated with CERCLA regulated hazardous substances before completion of required response actions. This type of transfer requires the concurrence by U.S. EPA and the State. C-4
- 4. Page 3-117, Hazardous Waste Management. The first sentence should state that the generation, storage, and treatment of hazardous waste is regulated by the Resource Conservation and Recovery Act and HWCL. C-5
- 5. Page 3-125, Section 3.13.9 Lead. DoD policy is to require inspection of lead-based paint (LBP) and LBP hazards for target housing constructed after 1960 and before 1978. For target housing constructed before 1960, DoD requires inspection of LBP and LBP hazards and abatement of any LBP hazards. Regardless of what the structures/facilities were used for, DTSC has statutory authority to require assessment, investigation, and remediation of hazardous substance releases. Paint chips from structures painted with LBP are potential sources of lead contamination for surrounding soils. Therefore, compliance with State laws is necessary before DTSC could conclude that all remedial actions have been taken for lead. C-6
- We strongly recommend that the Navy and the City of Novato coordinate closely with Federal and State environmental regulators in the base reuse planning process. Please send two copies of the Final EIS to me at the following address: C-7

Mr. Gary Munekawa
March 17, 1997
Page 4

Department of Toxic Substances Control
Office of Military Facilities
P.O. Box 806
400 P St
Sacramento CA 95812-0806

If you have any questions, please feel free to contact
me at (916) 323-3466.

Sincerely,

A handwritten signature in black ink, appearing to read "Theresa McGarry". The signature is fluid and cursive, with a large loop at the beginning and a long, sweeping tail.

Theresa McGarry
Environmental Assessment
and Reuse Specialist
Office of Military Facilities

cc: Mr. Larry Lind
BRAC Environmental Coordinator
Commanding Officer, Engineering Field Activity West
Naval Facilities Engineering Command
900 Commodore Drive
San Bruno, California 94066-2402

Jack Gregg , Ph.D
Regional Water Quality Control Board
San Francisco Bay Region
2101 Webster Street, Suite 500
Oakland, California 94612

Response to Comments

Response to Comment C-1. As referenced in the comment, one of the five points in the *President's Program to Revitalize Base Closure Communities* is fast-track environmental cleanup that removes delays while protecting human health and the environment. One of the mechanisms for implementing this goal is establishment of a BRAC Cleanup Team (BCT), which is responsible for developing and implementing the BRAC Cleanup Plan for the closing facility. The comment regarding the makeup of the BCT is noted.

Response to Comment C-2. As stated in Section 3.13.1 and the referenced comment, the California Department of Toxic Substance Control (DTSC) and Regional Water Quality Control Board (RWQCB) have regulatory authority over DODHF Novato's environmental remediation actions. DTSC's regulatory authority is based on the Hazardous Waste Control Law (HWCL) and the Hazardous Substances Account Act, Health and Safety Code Division 20, Chapters 6.5 and 6.8. The RWQCB has authority over petroleum contamination sites; its regulatory authority is based on the Porter-Cologne Water Quality Control Act, the California Water Code, and CCR Title 23.

Response to Comment C-3. As stated in the referenced comment, the statutory reference for the Community Environmental Response Facilitation Act (CERFA) is the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) Section 120 (h)(4). This regulation requires state concurrence with identification of uncontaminated real property at DODHF Novato and allows transfer of the identified properties. The requirements for transfer of properties that have been remediated are discussed in the last paragraph of Section 3.13.1. The text includes a reference to the CERCLA amendment allowing transfer of contaminated property under some conditions.

Response to Comment C-4. Section 4.13 of the EIS has been expanded to state, "Properties that contain or that potentially contain contamination may be transferred prior to completion of environmental remediation only if conditions listed in the amended CERCLA regulation (CERCLA 120 as amended by Section 334 of the FY97 Defense Authorization Act) are met. These conditions include agreement by US EPA and the state that the property is suitable for the intended use and that the intended use will protect human health and the environment, that property use restrictions are implemented to ensure that human health and the environment are protected, that there are assurances from the Federal government that transfer of the property will not substantially delay response actions

at the property, and that the Federal government will continue any necessary response actions after transfer."

Response to Comment C-5. Comment noted. The Resource Conservation and Recovery Act (RCRA) and HWCL are discussed in Section 3.13.1.

Response to Comment C-6. Comment noted. The Navy's policy is to comply with all applicable federal laws governing remediation. There are presently no regulatory requirements to survey or abate lead hazards in nonresidential facilities. In the case of housing constructed between 1960 and 1978, such as the Capehart Housing area, the Navy will not perform lead-based paint abatement unless required to do so by state or local lead-based paint law. No such requirements currently exist. The full results of lead-based paint and soil assessments will be disclosed to potential purchasers.

Response to Comment C-7. The comment recommending close coordination between the Navy, the City of Novato, and federal and state environmental regulators is noted. Two copies of the Final EIS will be sent to the commenter.



THE CITY OF
NOVATO
CALIFORNIA

900 Sherman Avenue
Novato, CA 94945
415/897-4311
FAX 415/897-4354

April 15, 1997

JN 32548

Mayor
Pat Eklund
Mayor Pro Tem
Carole Dillon-Knutson
Councilmembers
Michael Di Giorgio
Ernest J. Gray
Cynthia L. Murray

City Manager
Roderick J. Wood

Commanding Officer
Engineering Field Activity West
NAVAL FACILITIES ENGINEERING COMMAND
Attention: Mr. Gary J. Munekawa
Environmental Planning Branch, Code 1852GM
900 Commodore Drive
San Bruno, California 94066-5006

**Subject: Draft Environmental Impact Statement for the Disposal and
Reuse of the Department of Defense Housing Facility, Novato,
California**

Dear Mr. Munekawa,

On behalf of the City of Novato, we are pleased to offer the attached comments pertaining to the Draft Environmental Impact Statement (EIS) for the Disposal and Reuse of the Department of Defense Housing Facility (DODHF), Novato, California. The format of comments includes page number, paragraph and line citation.

This submittal is identical to the previous submittal by the City of Novato on March 17, 1997. Should you have any questions, please do not hesitate to call me at 714/855-3663.

Sincerely,

Glenn Lajoie, AICP
Senior Project Manager
City of Novato

Comments on the Draft Environmental Impact Statement for the Disposal and Reuse of the Department of Defense Housing Facility, Novato, California (March 1997):

General Comment - Environmental Consequences Section, Summary Table of Each Section, Legend

The "Significant and mitigable impact" statement should be changed to read "Significant, but mitigable impact."

D-1

Page 1-9, Paragraph 3 and Section 8.1, Bibliography

Page 1-9 provides a discussion of the 80-bed homeless shelter located within the Commissary Triangle area. The Draft EIS should include additional information and reference the prior environmental review for a temporary shelter situated on a 1.4 acre parcel within the Commissary Triangle. An Environmental Assessment was prepared in August, 1996 and a FONSI was issued in September, 1996.

D-2

Page 3-17, Paragraph 2, Line 4

This section indicates that the site visit and photographs occurred in November 1995. Given the elapsed time of over one year, we would suggest providing updated site photographs in the Final EIS.

D-3

Page 3-31, Table 3-16

Table 3-16 identifies the location and type of recreational facilities currently located on the DODHF. Although the Environmental Consequences analysis in Section 4.3 identifies a beneficial impact for recreation under the Preferred Alternative (an additional 52 acres of recreational uses), it would be helpful to provide the acreage of existing facilities in the table for comparison.

D-4

Page 3-38, Paragraph 4, "Rafael Village"

The contents of this paragraph which discuss plans related to the Reuse Plan should be moved to the Environmental Consequences section of this Draft EIS.

D-5

Page 3-39, Paragraph 5

The contents of this paragraph which identifies improvements related to the Reuse Plan should be moved to the Environmental Consequences section of this Draft EIS.

D-6

Section 3.11: Air Quality

The full names of pollutants are spelled out through page 3-108, paragraph 3, where the acronyms for the pollutants are first presented. From this point on, the section is inconsistent as to whether the full name or the acronym is used when referring to pollutants. For the sake of consistency, it would be beneficial to provide the acronym following the first time each pollutant is used, then only refer to the appropriate acronym for the remainder of the section.

D-14

Page 3-108, Paragraph 2, Lines 6 and 7

This sentence states that final action on the re-designation of the Bay Area to an attainment status for carbon monoxide is expected in 1996. Since this redesignation has not yet been approved by all parties and has not yet become final, the anticipated year of re-designation should be revised.

D-15

Page 3-117, Paragraphs 3 and 4

Paragraphs appear to be discussing the environmental consequences of the Disposal. Recommend that the Paragraph be moved to page 4.13.1, "Disposal."

D-16

Page 3-118, Lines 1 and 2

Did the EBS find the parcel which contained Building 957 (Demolished) to be "CERFA-clean?"

D-17

Page 3-119, Paragraph 4, Line 1

Did the asbestos survey of housing units by PWC Norfolk Virginia in August 1995 only include Spanish Housing? Please clarify that Capehart and Hillside housing were also inspected and were found to be free of asbestos.

D-18

Page 3-120, Paragraph 5, Line 6

Add the words "preparation of" following the word "during."

D-19

Page 3-124, Figure 3-21

Text adjacent to Commissary Triangle should be changed from "Possible UST (not confirmed)" to "USTs 827-1 through 827-4."

D-20

Page 3-126, Paragraph 4, Line 5

The sentence should be modified as follows; "Lead was detected in soil around all of the remaining housing areas at concentrations below the action level."

D-21

Page 4-2, Paragraph 5

The significance criteria for land use should define the policy sources in order to draw a nexus to the significance level determination.

D-22

Page 4-11, Paragraph 2, Line 1

Given the possible concerns for a corporation yard use which may impact nearby sensitive uses, the analysis should elaborate upon the buffering techniques, setbacks etc., which the discussion references in order to draw the conclusion of no significance for visual impacts. It should be clearly stated in this paragraph that an Open Space Alternative, which includes corporation yard uses, is not included in the Revised Reuse Plan.

D-23

Page 4-11, Paragraph 3, Line 1

The No Action Alternative discussion for Rafael Village concludes no significant impacts for visual resources. Although a No Action Alternative may imply that no impacts would occur, the discussion should reiterate the existing conditions analysis on page 3-18. Page 3-18, paragraph 3 provides a detailed account of the poor conditions, deterioration, damage, and vandalism and contrasts the setting with the surrounding well maintained neighborhoods. The analysis should clarify that these adverse conditions would continue under the No Action Alternative.

D-24

Page 4-12, Paragraph 4 (Significance Criteria), Sentences 2 through 4 and General Comment on Approach to Analysis

The purpose of the Significance Criteria Subsection is to identify the significance criteria used to evaluate potential impacts from disposal and reuse. These three sentences provide conclusions as to the overall significance of the reuse alternatives as they relate to employment, the economy, and population/housing growth. In order to assist the reader to understand the "significance criteria", it may be more appropriate to either delete or relocate these conclusions to elsewhere in the Section.

D-25

In addition, this Subsection should clearly provide the basis for the impact comparison (e.g., increases/decreases from alternatives are compared to existing DODHF, Novato conditions, or are compared to a closed condition). Although the baseline for existing conditions is explained elsewhere in the Draft EIS, it would assist the reader if the baseline condition was repeated here.

D-26

A detailed explanation of the Section 4.3 baseline is critical to the flow of the analysis. Since impacts from the Reuse Alternatives are compared to existing DODHF conditions (1996) when 546 dwelling units were occupied within the DODHF (page 3-25), the corresponding number of housing units, population and employment associated with the analyzed alternatives should be accounted for in a *net* impacts analysis (i.e., the Preferred Alternative would result in an additional population of 3,432 (Table 4-7) but the disposal would result in a population decrease of 1,299 persons (546 dwelling units multiplied by 2.38 persons per household); thus, the Preferred Alternative would result in a net population increase of 2,133 persons). It is presumed that this net impacts approach could be inappropriate or modified based on the response to the comment on Section 3.3 (Affected Environment: Socioeconomics) regarding whether the existing military population, housing and employment estimates were included in the existing conditions baseline.

D-26

Page 4-13, Paragraph 1, Line 1

This statement needs further clarification as to *why* physical changes to recreation and schools would be a beneficial impact; although the reader may be able to inherently understand the reason.

D-27

Page 4-13, Last Paragraph, Line 4

This paragraph states "When job opportunities exist, new residents move in, adding to the regional population. New households mean additional demand for housing construction and additional revenues and demand for local government services." These two sentences give the impression that whenever jobs are created, new residents will always move in, thus always increasing the population. It would be beneficial to repeat the information included in footnote #1 of Table 4-7 of the EIS here. The footnote states that approximately one-quarter of the jobs generated at DODHF are assumed to attract new residents to Marin County (this estimate would be less if new residents resided in DODHF housing).

D-28

Page 4-14, Population and Housing Subsection

This Subsection states that disposal would not have an effect on housing demand or population levels. In reference to the comment on Section 3.3 as to whether the existing population, housing and employment from the DODHF was accounted for in the local and regional estimates and the net impacts approach, it should be mentioned here that disposal would actually result in a local or regional population decrease of 1,299 persons (546 occupied residential units currently located on the DODHF, multiplied by 2.38 persons per household equals 1,299 persons). Any off-base housing units currently occupied by Navy personnel should also be accounted for in this net impacts analysis as disposal and reuse would potentially increase the number of existing units available in the City from relocated personnel.

D-29

Page 4-15, Last Paragraph, Line 1 and First Paragraph on Page 4-16

This paragraph states that "Navy disposal and community reuse of the property is expected to result in mainly beneficial effects to the people and the communities in Novato and Marin County. Other than increasing the availability of affordable housing units, which would benefit low-income people, impacts resulting from federal disposal of the DODHF Novato property..." This statement seems to contradict the "disposal" analysis which states that disposal would not affect housing or population levels. Although the conclusion drawn in this paragraph appears to be true, it should be consistent with the "disposal" analysis.

D-30

Pages 4-16 and 17, Regional Economy and Population/Housing Analyses

In accordance with previous comments on Section 4.3, the net impact analysis approach should be included here in the employment and population/housing discussions.

D-31

Page 4-18, Table 4-7

The reference to footnote #3 should be added to Table 4-7. Also, the net impact analysis approach may need to be included in this Table (i.e., net difference between existing population located on DODHF and the population generated by the respective reuse alternatives).

D-32

Page 4-20, Table 4-8

The net impacts analysis approach previously discussed may need to be added to Table 4-8.

D-33

Page 4-20, Paragraph 1, Line 1

This paragraph states that the Revised Reuse Plan Alternative would add approximately 52 acres of neighborhood park facilities and 114 acres of open space. It would be beneficial to expand this sentence to clarify the baseline for comparison, i.e., state that the additional recreational acreage would be either net additional acreage added into the City beyond existing conditions or only additional acreage that would be made available to the public upon closure of the military uses of the DODHF. This same clarification should be made on page 4-23, paragraph 3.

D-34

Page 4-27, Paragraph 3, Line 1

Since the No Action Alternative would require an additional police officer and one support staff member, it is recommended that the "No Impacts" statement be revised to "Not Significant Impacts."

D-35

Page 4-29, Paragraph 2, Line 1

There should be a discussion regarding short-term construction impacts associated with upgrading the facilities (i.e. undergrounding utilities within right-of-ways and the impacts it would have on circulation). Mitigation such as flagmen, detour signs, road closure signs, etc., should be identified in order to reduce short-term impacts to less than significant levels.

D-36

Page 4-29 through 4-30, "Storm Drainage System, Water Supply and Sanitary Sewer System," Line 1 under each heading

There should be a discussion regarding short-term construction impacts associated with upgrading the facilities (i.e. undergrounding utilities within right-of-ways and the impacts it would have on circulation). Mitigation such as flagmen, detour signs, road closure signs, etc., should be identified in order to reduce short-term impacts to less than significant levels.

D-37

Page 4-30, Paragraph 2, Line 7

Revise sentence to read as follows, "This would result in a significant, but mitigable impact."

D-38

Page 4-30, Paragraph 3, Line 1

The mitigation and conclusion of Not Significant Impact appears to be premature given the uncertainty of proposed activity by the California Integrated Waste Management Board (CIWMB), which requires funding by the Trade and Commerce Agency to implement the mitigation. The reviewer is left to assume that financing will occur, allowing mitigation. Since funding is subject to approval it seems inappropriate to assume this financial assistance. The discussion should conclude the likelihood of such assistance and identify appropriate alternative revenue sources.

D-39

Page 4-42, "Areas of No Impact" Discussion and Page 4-43, Section 4.7.2 Revised Reuse Plan Alternative

Each of the discussions should identify the fact that demolition of abandoned structures may impact any of the three bat species possibly found within DODHF, Novato. The Hamilton Field Project Final Subsequent EIR, dated March 1993 identified the loss of habitat for either of these (bat) species as a potentially significant impact.

D-40

Page 4-47, Paragraph 2, Line 1

There is no discussion identifying what impact the demolition and construction of structures in Rafael Village will have on slope stability in the area, particularly the northern area of Rafael Village. A statement should be incorporated, referencing Mitigation 1.

D-41

Page 4-48, Paragraph 2, Line 1

There appears to be several mitigation measures referenced in this paragraph. For clarity, each measure should be individually identified (i.e. 2a Existing Structures; 2b Roads and Utilities; 2c All New Construction; and 2d Zoning).

D-42

Page 4-48, Paragraph 3, Line 1

If soil erosion is not considered significant, why are measures identified to reduce this impact? The erosion impact should be identified as significant but with implementation of erosion control measures impacts would be reduced to less than significant levels.

D-43

Page 4-49, Paragraph 4, Line 1

The potential for soil erosion should be identified as significant, but with implementation of erosion control measures impacts would be reduced to less than significant levels.

D-44

Page 4-51, Paragraph 4, Line 2, and Paragraph 5

"... As noted above, under Planning Issues and Processes, the site would fail under the jurisdiction of the City of Novato and the (MCFCWCD)."

D-45

Comment: The section preceding this statement is referred to as "Planning Issues" and the MCFCWCD is not identified as having jurisdiction.

Page 4-53, Paragraph 5, Line 1

Recommended rewording is as follows: "During redevelopment of Rafael Village, the City of Novato shall require the upgrading of all project area storm drains to meet the current City standard of a 25-year recurrence interval rainfall."

D-46

Pages 4-76 and 77, Table 4-21, Table Notes and Paragraph 1, respectively

The acronym "ROG" is defined here as "reactive organic compounds." To be consistent with the Section text in the previous paragraph, the word "compounds" should be replaced with "gases." The term "compounds" in Paragraph 1 on page 4-77 should also be revised to read "gases."

D-47

Pages 4-77 and 79, Discussions on Air Quality Plan Consistency

Although mentioned in Section 3.11, a brief explanation as to why a Conformity Analysis is not required should be repeated here.

D-48

Page 4-84, Paragraph 1, Line 1

Reword the 3rd sentence as follows, "This would be a short-term significant, but mitigable impact."

D-49

Page 4-84, General Comment

The discussion is lacking a description of the potential impacts regarding the reuse of the Commissary and Exchange Triangles and the potential impact this may have on Lanham Village residents and Hamilton School. Mitigation and monitoring requirements should be identified (i.e., pre and post development monitoring to insure proposed uses due not exceed established noise guidelines).

D-50

Page 4-91, Heading "Lead", Paragraph 1

"The results of lead-based paint surveys and lead warning statements would be included in any contract for transfer or lease."

D-51

Comment: Is this statement referring to the soil sampling being conducted in the Capehart Housing area?

Page 5.1, Paragraph 2, Line 1

The land use analysis for Cumulative Impacts briefly discusses related policy documents with regard to growth and recreational facilities but fails to provide an analysis of land use compatibility and the relationship of DODHF-Novato Reuse to adjacent cumulative projects identified in Figure 5-1. The analysis should address the compatibility/relationship especially to the New Hamilton Partnership, Hamilton Army Airfield Reuse and USCG Spanish Housing, which are the adjacent planning areas.

D-52

Page 5.1, Paragraph 4, Line 1

Similar to the previous Land Use Section comment, the relationship to surrounding planning areas should be discussed in greater detail. The discussion pertaining to the main site and nearby planning areas should specifically be elaborated on.

D-53

Page 5-6, Paragraph 2, Line 1

As previously stated for land use and aesthetics, the level of detail in concluding the significance of impacts is in question. To assist the reviewer, the paragraph should provide a policy or projection reference to substantiate the conclusion.

D-54

Page 5-6, Paragraph 3, Line 1

Again, referencing the sources for the conclusions should be incorporated. For example, was police, fire and emergency medical entities contacted directly for input with regard to cumulative conditions or is the conclusion based on other reference materials?

D-55

Page 5-6, Paragraph 4, Line 1

Level of detail and sources of significance are in question. Also, although the Reuse Plan identifies potential upgrading requirements at the Ignacio Treatment Plant, rather than this EIS deferring to further analysis of capacities, this section should provide further analysis of the upgrade needs, given the extent of the cumulative projects provided.

D-56

Page 5-6, Paragraph 6, Line 1

The update to the architectural inventory the historical evaluation of Hamilton field should be incorporated into this section and updated, where appropriate.

D-57

Page 5-7, Paragraph 2, Line 1

Although the analysis addresses wetland habitat, the discussion should include other flora and fauna habitats, as appropriate, and provide a determination of impact significance.

D-58

Page 5-7, Paragraph 4, Line 1

This section tends to emphasize water quality. Further cumulative analysis should be provided for the effects to drainage or water bodies, 100 year flood hazards and street flood hazards.

D-59

Response to Comments

Response to Comment D-1. The commenter's proposed change of wording from "significant and mitigable" to "significant but mitigable" would result in no changes to the EIS analysis or conclusions. Therefore, the Navy has retained its existing language.

Response to Comment D-2. The following text has been added to EIS Section 1.3.1 describing the temporary homeless shelter and related National Environmental Policy Act (NEPA) documentation. The Environmental Assessment (EA) reference citation has been added to Section 8, References, of the EIS.

"The Hamilton Service Center, a temporary 80-bed homeless shelter, was located on property leased from New Hamilton Partnership. The Hamilton Service Center provided shelter, food, and clothing over a six-month winter period of October to April. The lease on the property expired and a relocation lease site on DODHF Novato has been identified to house a new temporary structure. The new site is a 1.4-acre parcel in the northern corner of the Commissary Triangle planning area with a proposed lease term of one year. An Environmental Assessment for the proposed shelter was prepared in August 1996 and a Finding of No Significant Impact was issued in September 1996 (US Navy 1996c)."

Response to Comment D-3. The suggestion for new photographs is noted. The site photos in Appendix A are included to provide a context for the text discussion. The photographs still satisfactorily serve this function. The main change between the time that the photographs were taken and the present is that the DODHF Novato facility has closed. New photographs would show fewer cars and some construction in the vicinity of the Town Center planning area related to the New Hamilton Partnership project.

Response to Comment D-4. Description of existing recreational facilities is consistent with the level of detail provided in the final Reuse Plan. As acreages were not available, no change was made to the text.

Response to Comment D-5. Section 3.5 utility discussions have been revised to reflect system deficiencies only. Discussions on upgrades to the utility systems as identified in the reuse plan have been moved to Section 4.5, environmental consequences, as suggested.

Response to Comment D-6. As stated in response to Comment D-5, discussion of upgrades to utilities identified in the reuse plan has been moved to Section 4.5.

Response to Comment D-7. As stated in response to Comment D-5, discussion of upgrades to utilities identified in the reuse plan has been moved to Section 4.5.

Response to Comment D-8. The missing flow rate of 330 cfs for Pacheco Creek at Main Gate Road is added to Section 3.5.

Response to Comment D-9. The reevaluation report for the National Register of Historic Places (NRHP), "National Register Eligibility Reevaluation Hamilton Army Airfield Historic District Department of Defense Housing Facility Novato, California," was completed in December 1996 by PAR Environmental Services, Inc. The reevaluation of the historic district by the Navy was prompted by the New Hamilton Partnership's initiation of the redevelopment of the property it acquired from the General Services Administration and the Army. This has resulted in demolition of major portions of the historic district and the introduction of new construction. The reevaluation, concurred in by the State Historic Preservation Officer, scales back the historic district to three discontinuous parts of the original 1930s Captain Nurse-designed Army Air Corps Base. A copy of the State Historic Preservation Officer's (SHPO's) concurrence is included in Appendix E of the Final EIS. All tables, Appendix E, and Figure 3-6 have been revised. Also, Manieri 1997 is added to references.

Response to Comment D-10. The suggested revision has been made to Figure 3-10.

Response to Comment D-11. The Federal Emergency Management Agency (FEMA) flood hazard map referenced in the excerpt noted by the comment does not indicate actual locations of structures in the flood plain. These structures are indicated on Navy maps at larger scales than the FEMA maps. A comparison of these two maps indicates that the 100-year flood plain on the incised portion of San Jose Creek adjacent to Rafael Village is contained within the larger stream channel. To the extent that yards extend down that channel, they would be subject to flooding in peak flow periods. The houses are located above the incised channel and are generally set back from the top of the channel by 30 to 50 feet. One wider area of 100-year flood hazards is mapped near the intersection of Shaffer Drive and Ignacio Blvd. This generally corresponds to the area where no houses are present on the south side of Ignacio Blvd. However, approximately four houses in that reach and some homes near the intersection of San Jose Blvd. and Ignacio Blvd. may be subject to 100-year flood hazards; the FEMA map detail is not adequate to confirm or negate this hazard to these houses. The remainder of the Rafael Village houses are outside of the 100-year flood plain and therefore not subject to that flood hazard. The lower

portion of San Jose Creek is shown on the westernmost edge of Figure 3-14. The upper portion of San Jose Creek adjacent to Rafael Village is not shown on that map.

Response to Comment D-12. The reference to Figure 3-14 has been removed and text has been expanded to describe ground water flows at the Main Site. Surface water features of Rafael Village are described in Section 3.9.2.

Response to Comment D-13. The commenter is correct that the term brackish is a description of ground water quality. However, this information is most appropriately discussed under an integrated discussion of ground water characteristics and therefore was not moved to Section 3.9.5, which discusses water quality primarily as it relates to surface water.

Response to Comment D-14. The suggestion that acronyms be defined the first time a term is used, and using the acronym thereafter, is the general style adopted for this document. The section has been reviewed for appropriate use of acronyms and revised where appropriate.

Response to Comment D-15. The comment that redesignation did not occur in 1996 is noted. It is unclear when redesignation will be finalized, but the text in Section 3.11.5, Air Quality, is revised to state that redesignation has not yet occurred.

Response to Comment D-16. Information contained in the paragraphs has been moved from Section 3.13.2, Affected Environment, to Section 4.13.1, Environmental Consequences.

Response to Comment D-17. Detailed information on specific parcels is included in the EBS and is beyond the scope of this programmatic document. Environmental cleanup of each parcel must be completed prior to conveyance of that parcel or the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) requirements allowing transfer of contaminated property must be met.

Response to Comment D-18. The asbestos survey included a random sampling from all housing areas at DODHF Novato. Asbestos-containing materials (ACM) were identified in all housing areas; however, asbestos that was friable was identified only in Spanish Housing. The Navy's policy is that property with ACM will not be disposed of through the BRAC process unless the ACM does not pose a threat to human health at the time of transfer. Asbestos-containing materials that are not damaged and friable are not considered to pose a health risk and will therefore not be abated. Only asbestos-

containing materials asbestos that is damaged, friable, and accessible would be repaired or removed prior to transfer. No friable ACM was found in the Capehart or Hillside housing so no abatement is required.

Response to Comment D-19. The suggested revision has been made to Section 3.13.6.

Response to Comment D-20. The text on Figure 3-21 has been changed from "Possible UST (not confirmed)" to "UST 827 (removed)".

Response to Comment D-21. Lead was detected at concentrations below the action level in soil samples from the Rafael Village housing area. Lead concentrations in 4 of the 110 soil samples taken in the Capehart Housing area were above the federal Department of Housing and Urban Development action level of 400 parts per million.

Response to Comment D-22. Because NEPA does not provide specific criteria for evaluation of impacts, the significance criteria for land use impacts are based on California Environmental Quality Act (CEQA) Appendix G. The criteria also incorporate the land use policies of the City of Novato General Plan for the definition of conflicting land uses. Land Use Policy 5 states that land use compatibility of specific development is to be determined by the appropriate City authority based on appearance, use characteristics, and proximity. Compatibility issues can arise from visual conflict, interference with established use, and negative physical impacts.

Response to Comment D-23. The referenced paragraph in Section 4.2.3 has been revised as follows:

"Under the Open Space alternative, corporation yards would be permitted in the Commissary Triangle and the Exchange Triangle planning areas. Impacts to visual resources resulting from these uses would not be significant assuming that increased attention to buffering of uses and landscaping between adjacent uses in these planning areas is implemented, as called for under the Reuse Plan. Specific buffering features would be designed under specific use proposals, but would likely include construction of six-feet to eight-feet high buffer walls and landscaping to block views of the corporation yard from the Lanham Village housing area. It should be noted, however, that the Reuse Plan itself does not allow corporation yards."

Response to Comment D-24. The following revised text addressing the continuation of site deterioration has been added to Section 4.2.4, Rafael Village:

"Structures in Rafael Village would continue to be maintained minimally. Navy minimal maintenance would not completely prevent deterioration of structures in Rafael Village. The

structures are currently experiencing deterioration as described in Section 3.2.2 and this condition would continue in the future under the No Action Alternative. This impact would not be significant, however, because of the gradual rate of deterioration.”

Response to Comment D-25. The existing text is provided to briefly summarize the analysis results of Section 4.3. As the results of each section are described in detail, no change is required.

Response to Comment D-26. As stated in Section 4.3, increases in population and housing are considered neither beneficial nor adverse impacts of the disposal action. Population and housing growth is considered in this way because growth can be perceived either positively or negatively depending upon the point of view of the reader. Data provided in Section 3.3 on population, housing, and employment prior to closure is included for informational purposes. Employment impacts of the reuse of the facility are compared to existing conditions, with minimal caretaker employment. A “net” impacts analysis would further reduce the estimated population and housing estimates and therefore would not change the conclusions reached in the EIS.

Response to Comment D-27. The referenced sentence is clarified in Section 4.3 to read as follows:

“With respect to recreation and schools, provision of additional physical facilities, such as additional parks and classroom facilities, would be considered beneficial.”

Response to Comment D-28. The referenced paragraph is revised in Section 4.3 to read as follows (new text is underlined):

“ . . . When job opportunities exist, new residents generally move in, adding to the regional population. It is assumed that approximately 25 percent of the jobs generated by the Revised Reuse Plan Alternative would attract new residents to Marin County. New households mean additional demand for housing construction and additional revenues and demand for local government services.”

Response to Comment D-29. Disposal is the transfer of title of the property from the Navy and would not result in changes in population. For the purposes of Navy NEPA analysis, direct environmental consequences or impacts are those associated with Navy property disposal and the No Action Alternative. Indirect impacts are associated with the proposed reuse alternatives. Population increases under the reuse alternatives would be indirect impacts of disposal.

Response to Comment D-30. In order to make the discussion under Disposal consistent, Section 4.3.1 is revised as follows:

“The Navy disposal is expected to result in no environmental impacts. As no impacts would occur, no one group would be disproportionately impacted, and no mitigations are required.”

Response to Comment D-31. As discussed in response to Comment D-26, reuse impacts are the indirect impacts of property disposal and are discussed under each reuse alternative.

Response to Comment D-32. As discussed in response to Comment D-26, reuse impacts are the indirect impacts of property disposal and are discussed under each reuse alternative.

Response to Comment D-33. As discussed in response to Comment D-26, reuse impacts are the indirect impacts of property disposal and are discussed under each reuse alternative.

Response to Comment D-34. The addition of 52 acres of park facilities and 114 acres of open space represents property and facilities that formerly belonged to the Navy. The property would become available for use by the general public. No text change is required.

Response to Comment D-35. The impact discussion has been revised from “No Impact” to “Not Significant Impact” in Section 4.4.4.

Response to Comment D-36. It is presumed that proposed upgrades to the electrical, natural gas, and telephone systems would occur prior to occupancy of the residences and facilities at DODHF Novato. Short-term construction effects would therefore have limited effects. The process of obtaining and complying with encroachment permits from the City of Novato would ensure that future specific utility projects would include proper planning for any possible disruptions to traffic. Upgrades would occur on the base and would not affect traffic on the regional roadway network.

Response to Comment D-37. As discussed in response to Comment D-36, it is presumed that proposed upgrades to the storm drainage, water supply, and sanitary sewer systems would occur prior to occupancy of the residences and facilities at DODHF Novato. Short-term construction effects would therefore have limited effects. The process of obtaining and complying with encroachment permits from the City of Novato would ensure that future specific utility projects would include proper planning for any possible disruptions to traffic. Upgrades would occur on the base and would not affect the regional roadway network.

Response to Comment D-38. See Response to Comment D-1.

Response to Comment D-39. It is anticipated that Marin will continue to meet or exceed its diversion goal, so the existence of the impact is, itself, speculative. Although it is anticipated that this program would be funded, it is beyond the scope of this document to speculate about the certainty of funding sources for public agencies or to identify alternate funding sources.

Response to Comment D-40. Several common bat species are found in the project area and sometimes roost in the attic and eaves structures of buildings. Although surveys were not conducted at the site, these bat species may be found in the buildings proposed for demolition. Demolition could affect roosting sites for these common bat species, primarily the Mexican free-tailed bat, but would not be considered a significant impact because the species likely to be found are not threatened or endangered, and such bats currently can be removed from any building to protect public health.

Response to Comment D-41. Impacts from demolition are considered to be part of the construction process. For clarity, the word "demolition" is added to both Impact 1 and Mitigation 1 in EIS Section 4.8.2.

Response to Comment D-42. For clarity, the mitigation actions included within Mitigation 2 have been individually identified.

Response to Comment D-43. The potential for soil erosion at the relatively flat Rafael Village site is not significant. The inclusion of standard erosion control procedures was to indicate standard measures typically taken on construction sites. No text change is required.

Response to Comment D-44. As discussed in Response to Comment D-43, the potential for soil erosion at the relatively flat Rafael Village site is not significant and no text change is required.

Response to Comment D-45. Section 4.9.1 is revised to read as follows:

"As noted above under Planning Issues, the site would fall under the jurisdiction of the City of Novato and the [Marin County Flood Control and Water Conservation District] MCFWD. Conformance with those local agencies' is described in that section above."

Response to Comment D-46. Section 4.9.2, Mitigation 3, is revised as suggested.

Response to Comment D-47. The term "reactive organic compounds" is the most accurate description of organic compounds that are precursors to the production of ozone. The most accurate terminology is "reactive organic compounds," but "ROC" is not a standard acronym. Therefore, ROG is used as the acronym for reactive organic compounds.

Response to Comment D-48. Federal Clean Air Act conformity requirements are discussed sufficiently in Section 3.11 and no text change is required. Additional text regarding Air Quality Plan consistency has been added to Section 4.11.2, as follows:

"Regional air quality plans are periodically updated to reflect the current status of land use and transportation planning on a regional level. Thus, major development proposals that occur between updates are routinely incorporated into subsequent air quality plan revisions. Most new development associated with the reuse plan will happen outside the year 2000 time frame currently addressed by emission forecasts in the Bay Area Air Quality Plan. This precludes any quantitative analysis of plan consistency issues."

For additional information, see also Response to Comment A-9.

Response to Comment D-49. See Response to Comment D-1.

Response to Comment D-50. This programmatic level EIS has addressed impact issues at a general plan level of detail. Impacts requiring analysis at a site design level of detail should be evaluated by the City of Novato or the school district in subsequent project-specific CEQA documents. Responsibility for the adoption, implementation, and monitoring of mitigation measures to reduce the impacts of reuse rests with local agencies, not the Navy. Additional discussion of suggested noise mitigation measures has been presented in Response to Comment Q-22.

Response to Comment D-51. This statement refers to all Navy investigations of lead-based paint (LBP) and LBP hazards, including lead in soil.

Response to Comment D-52. Section 5.1.2, Land Use, is revised as follows (new text has been underlined):

"Cumulative land use effects of the Bel Marin Keys, New Hamilton Partnership (NHP) developments, and Hamilton Army Airfield reuse are addressed in the Novato General Plan and the Marin Countywide Plan. These two planning documents have analyzed reasonably

foreseeable growth and include the reuse of DODHF Novato as part of that expected growth. The planned reuse of DODHF Novato in combination with these projects is not expected to have significant land use effects because the proposed land uses are similar and none of the proposed uses would preclude other proposed or foreseeable uses. The most significant cumulative land use impact to the planning area is the conversion of land from open space uses to urban uses. Long-term attempts to control the rate of conversion indicate that development throughout the county should be focused in the eastern portion of the county near US 101. The proposed reuse under each of the alternatives primarily is adaptive reuse of existing development areas and does not change current open space to urban uses. None of the alternatives, therefore, contribute to this cumulative impact."

Response to Comment D-53. Section 5.1.2, Visual Resources, is revised as follows (new text is underlined):

"Under the Revised Reuse Plan Alternative, most structures would be adaptively reused, and Rafael Village would be rebuilt with residential housing consistent with local planning requirements. Under the Open Space Alternative, Rafael Village housing would be replaced with open space, and under the No Action Alternative, visual resources would not change. The reuse alternatives would not have significant visual impacts and when considered in combination with the cumulative projects identified in Figure 5-1, would not contribute to significant cumulative visual impacts in the region of influence (ROI). The projects identified in Figure 5-1 would result in increased public access and viewing opportunities of the former Hamilton Army Airfield. Projects involving construction of new structures would be subject to review and analysis of visual compatibility by the City of Novato. There would be no significant cumulative visual impacts from any alternative."

Response to Comment D-54. As discussed in Section 4.3, Significance Criteria, creation of additional jobs is considered to be a beneficial impact. As the specific timing of reuse of DODHF Novato is speculative, a more detailed analysis of cumulative employment impacts is not warranted.

Response to Comment D-55. Conclusions regarding cumulative impacts for public services were developed through consultation with local public service providers. The sources for cumulative impacts are the same referenced in Sections 3.4 and 4.4 for the various service providers.

Response to Comment D-56. The analysis identifies the known utility conflicts and potential capacity deficits appropriate to cumulative analysis. Section 5.1, Utilities, is revised as follows:

"The proposed development alternatives for DODHF Novato do not indicate the need for utilities capacities significantly different from existing or recent historical levels. However, ~~when such requirements are combined with those of the NHP development, further analysis may be required to evaluate utilities capacities. For example, Section 5.3 of the Reuse Plan states that~~ the Ignacio Treatment Plant may need to be upgraded to handle the potential wastewater generated from Phase II of the NHP development."

Response to Comment D-57. Although the integrity of the NRHP district has been reevaluated, the discussion of cumulative cultural resources remains accurate as is.

Response to Comment D-58. As no sensitive plants or animals would be impacted by disposal or reuse of DODHF Novato, there would be no cumulative impacts on such species. Sedimentation associated with construction and demolition at DODHF Novato could contribute to regional sedimentation from other projects such as the New Hamilton Partnership Master Plan area and Bel Marin Keys construction. The extent of such sedimentation would be limited by implementation of standard erosion control procedures at construction sites, as required by National Pollutant Discharge Elimination System (NPDES) construction stormwater permits.

Response to Comment D-59. The drainage improvements proposed as part of the Reuse Plan, the NHP project, and the return of the runway area to tidal influence would not be expected to result in significant cumulative impacts to water bodies, 100-year flood areas, or street flooding in the cumulative project area.



**MARIN MUNICIPAL
WATER DISTRICT**

220 Nellen Avenue
Corte Madera, CA 94925-1169
415-924-4600
FAX 415-927-4953

March 4, 1997

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
Att: Mr. Gary J. Numekawa, Environmental Planning Branch
Code 1852GM
900 Commodore Drive
San Bruno, CA 94066-5006

Subject: Draft EIS for Disposal & Reuse of the Former DOD Housing Facility, Novato

Dear Mr. Numekawa;

Our staff has reviewed the above referenced EIS and find that overall it is a very good document. We have only a few specific comments;

Page 3-39 does not mention the new water piping in Main Gate Road installed by the new developer. While this piping does not serve most of the area being disposed of, it does serve some of it. In the interest of completeness, it should be mentioned. | E-1

Page 3-44 is missing a discharge figure for Pacheco Creek. | E-2

If you have any questions please call me at 924-4600 ext. 291.

Sincerely,

Eric McGuire,
Environmental Services Coordinator

Response to Comments

Response to Comment E-1. The following text has been added to Section 3.5.2, Water Distribution

System:

"New Hamilton Partnership recently installed new water piping along Main Gate Road to serve the New Hamilton Partnership development and a small portion of DODHF Novato."

Response to Comment E-2. The missing flow rate (330 cubic feet per second) has been added to the text.



NORTH MARIN WATER DISTRICT

999 RUSH CREEK PLACE • POST OFFICE BOX 146 • NOVATO, CALIFORNIA 94948 • (415) 897-4133 • FAX (415) 892-8043

March 11, 1997

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
Attention: Mr. Gary J. Munikawa, Environmental Planning Branch
Code 1852GM
900 Commodore Drive
San Bruno, CA 94066-5006

RE: Draft Environmental Impact Statement (DEIS) for the Disposal and Reuse of the Department of Defense Housing Facility, Novato, California
NMWD Job File 1 2356.00

Dear Mr. Munikawa:

Thank you for the opportunity to comment on the above referenced DEIS. The District has the following comments:

SECTION 3.5 UTILITIES, first paragraph, page 3-37

"Utilities diagrams are included in Appendix F."

District Comment:

Rewrite the sentence to read, "Utilities diagrams are included in Appendix D".

F-1

SECTION 3.5 UTILITIES, 3.5.2 Water Distribution System, Capehart Housing, Page 3-38

"..., Marin Municipal Water District's service area currently provides water service for the majority of the planning area located in North Marin's service area. The North Marin Water District has always protested such service."

F-2

DISTRICT COMMENT

The 434 units now served by Marin Municipal Water District are in the territory of North Marin Water District. This is the reason for the longest standing dispute.

SECTION 4.8. GEOLOGY AND SOILS, 4.8.2 Revised Reuse Plan Alternative, Slope Stability Hazards, Significant Impacts, first and second paragraphs, page 4-47

"Impact 1. ...A potentially significant and mitigable impact could occur if new construction in Rafael Village undermines or weakens unstable slopes."

F-3

"Mitigation 1. ...Geotechnical investigations are currently required in compliance with the City of Novato General Plan in areas showing landslide potential. Two such areas have been identified adjacent to Rafael Village"



Mr. Gary J. Munikawa
March 11, 1997
page 2

DISTRICT COMMENT

Regards the above referenced statements, the District has an existing tank site above Rafael Village. Proposed construction in Rafael Village shall not undermine or weaken slopes in the vicinity of the District tank site. In addition, the location of the two landslide potential areas referenced above are not shown in DEIS figures and should be shown.

F-3

SECTION 5.. OTHER CONSIDERATIONS REQUIRED BY NEPA. 5.1 CUMULATIVE IMPACTS.
5.1.1 Major Cumulative Projects In The Vicinity Of The Proposed Action, Buck Center for Research in Aging, page 5-4

"Construction has not yet begun on the facility."


F-4

DISTRICT COMMENT

Construction has commenced on this facility..

If you have further questions regards this response please do not hesitate to call me.

Sincerely,



Edith M. S. Robbins
Senior Civil Engineer

EMSR:edw

cc: File 1 2386.00
File 1 2446.00

Response to Comments

Response to Comment F-1. The correction to the appendix reference has been made as suggested.

Response to Comment F-2. The text referenced in Section 3.5.2 has been revised as follows:

"Most of the Capehart Housing area is within the North Marin Water District's service territory, though through a contract with DODHF Novato, water service is provided to the area by the Marin Municipal Water District. This arrangement has led to a long-standing dispute between the North Marin and Marin Municipal Water Districts. The two districts are working towards a settlement for this dispute."

Response to Comment F-3. Referenced areas with unstable slopes are shown in EIS Figure 3-13 (Section 3.8). The comment that the District has an existing tank site above Rafael Village is noted. The mitigation actions discussed under Mitigation 1 in EIS Section 4.8.2 would ensure that construction would not undermine or weaken slopes in the vicinity of the District tank site.

Response to Comment F-4. Text in EIS Section 5.1.1 is revised to indicate that construction on the Buck Center has begun.



NOVATO SANITARY DISTRICT

500 DAVIDSON STREET • NOVATO • CALIFORNIA 94945 • PHONE (415) 892-1694 • FAX (415) 898-2279

BOARD OF DIRECTORS

GEORGE C. QUESADA, President
ARTHUR T. KNUTSON
E.A. SAM RENATI
JOSEPH F. SILVEIRA
PHILIP J. YORK

CHARLES A. JOSEPH
Manager-Engineer-Secretary

KENTON L. ALM
Legal Counsel

March 17, 1997

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
900 Commodore Drive
San Bruno, California, 94066-5006

VIA FAX AND MAIL

Attn: Mr. Gary Munekawa, Environmental Planning Branch
Code 1852GM

Subject: Draft Environmental Impact Statement (DEIS) for the Disposal and Reuse of
the Department of Defense Housing Facility, Novato, California

Dear Mr. Munekawa:

This letter is in response to your "Notice Of Public Hearing" and request for comments on the above subject DEIS. The District's comments are as follows:

- Volume I, Section 3.5.3 Sanitary Sewer System

The second paragraph indicates that the District owns the 15" sewer in San Pablo Avenue.

The District does not own the 15" sewer in San Pablo Avenue. This sewer is owned by the U.S. Navy. The District does own a 6" sewer in San Pablo Avenue from Escolta Avenue easterly 150 feet, more or less.

G-1

The third paragraph indicates that the ultimate capacity of the Ignacio Treatment Plant (ITP) is 2.55 mgd and that the current flow treated at the ITP is 1.61 mgd.

The existing permitted dry weather flow capacity is 2.02 mgd. In response to the Novato General Plan and the Marin Countywide Plan, the District has projected a 2010 dry weather flow of 2.55 mgd. In order to treat those flows, the District must expand the Ignacio Treatment Plant and get an increase in the permitted discharge capacity from the Regional Water Quality Control Board.

G-2

Mr. Gary Munekawa
March 17, 1997
Page 2

The 1996 average dry weather flow being treated at the ITP is 1.41 mgd.

G-2

- Volume II, Appendix D, Figure D-2a


The legend designating sanitary sewer lines is misleading. It indicates that the District owns the sewers in the Capehart and Spanish Oaks housing areas.

The District owns the 15" sewer that parallels the railroad right-of-way through the commissary triangle; the 12" sewer that runs southerly between Lanham Village and the U.S. Navy property to the south side of Main Gate Road and an 8" sewer that runs westerly on State Access Road from the 15" sewer mentioned above.

G-3

Thank you for the opportunity to comment on the DEIS. Please contact this office if you have any questions or need additional information.

Sincerely,



Thomas S. Selfridge
Technical Services Manager

Response to Comments

Response to Comment G-1. The sentence in question in Section 3.5.3 was revised by deleting the reference to the 15-inch sewer in San Pablo and Escolta Avenues and adding a reference to the 6-inch sewer in San Pablo Avenue from Escolta Avenue.

Response to Comment G-2. The referenced paragraph in Section 3.5.3 has been replaced with the following:

“The District's Ignacio wastewater treatment plant has an existing design capacity of 2.02 million gallons per day (MGD). In response to the Novato General Plan and Marin Countywide Plan, the district has projected in year 2010 a dry weather flow of 2.55 MGD. To meet this projected demand, the district would have to expand the Ignacio treatment plant and obtain an increase in the permitted discharge capacity from the Regional Water Quality Control Board. The 1996 average dry weather flow treated at the Ignacio wastewater treatment plant was 1.41 MGD. The estimated flow contributed by DODHF Novato when fully operational was 0.80 MGD.”

Response to Comment G-3. The figure has been revised to clarify the ownership status of the sanitary sewer lines.



NOVATO UNIFIED SCHOOL DISTRICT

1015 SEVENTH STREET • NOVATO, CALIFORNIA 94945 • TEL: (415) 897-4201 • FAX: (415) 898-5790

Joel Montero
Superintendent

Annette Conklin
Director of
Community Relations
(415) 897-4259

March 21, 1997

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
900 Commodore Drive
San Bruno CA 94066

Attn: Mr. Gary J. Munekawa, Environmental Planning Branch Code 1852GM

Dear Mr. Munekawa:

Please accept the following comments on the draft environmental impact statement for the disposal and reuse of the Department of Defense Housing Facility, Novato, California dated January 1997.

General Comments

On May 31, 1996, the Novato Unified School District (NUSD) submitted its application for public benefit transfer of surplus federal real property for educational use to the Department of Education. The Department of Education forwarded its approval of the transfer to the Department of the Navy on August 28, 1996.

H-1

The EIS does not reflect any of the uses proposed by the Novato Unified School District in this transfer application. Nor did anyone contact us from the Environmental Planning Branch during the development of the EIS. Therefore, the EIS does not adequately assess the impact of the Novato Unified School District proposals since they are not addressed at all in the documents.

Open Space Alternative

The Open space Alternative primarily addresses Rafael Village. However, it also calls for corporation yards to be allowed in the Commissary and Exchange Triangles. The Novato Unified School District does not intend to operate a corporation yard in the Exchange Triangle planning area (the area which NUSD applied for.)

H-2

Socioeconomics - Schools p. 3-29 et seq.

The enrollment and capacity chart was developed in February 1995. While the overall enrollment has remained relatively stable, the chart used in the EIS only partially reflects the closure of the Navy housing. The capacity does not reflect the 1996 State law reducing class sizes at grades 1, 2, and 3 to a maximum of 20 students. Because of the districts participation, capacities at the

H-3

elementary schools will be reduced by a least 40 students. New proposals for capacities will be presented for school board review in late April.

H-3

The student generation factors need to be computed separately for each grade in calculating the number of students generated from each household.

H-4


All of the above affects the calculations in Table 4-8.

H-5

The replacement of military housing with civilian housing will have a permanent effect on the school district finances. The loss of federal impact aid, approximately \$1 million, will not be replaced with state funds since the financing formula for schools is not based on property coming back on the tax rolls.

H-6

Sincerely,

A handwritten signature in cursive script, appearing to read "Annette Conklin".

Annette Conklin
Director of Community Relations

AC/clm
hamreuse/envltr

Response to Comments

Response to Comment H-1. Although the specific request by Novato Unified School District (NUSD) is not described in the EIS, the uses proposed in the NUSD application fall within the general land use designation for the Exchange Triangle of community facilities and civic uses. The EIS addresses impacts from this general category of land uses throughout the document. This general level of detail is necessary should more than one user be interested in a portion of property being disposed from Navy ownership. The Navy acknowledges that the NUSD's public benefit conveyance request for portions of DODHF Novato has been approved by the US Department of Education. However, the Navy is also aware the Ecumenical Association for Housing (EAH) has submitted a public benefit conveyance request to the US Department of Housing and Urban Development (HUD) for some of the same portions of DODHF Novato requested by NUSD. As of the date of this EIS, HUD has not acted on the EAH request. For any property conveyed from Navy ownership, the future user would be responsible for preparing any additional required environmental documentation for their specific activities under the California Environmental Policy Act and other applicable federal and state regulations. Therefore, the EIS analyzes impacts at a level of detail consistent with the programmatic level of detail of the Reuse Plan.

Response to Comment H-2. The comment that the NUSD does not intend to operate a corporation yard in the Exchange Triangle planning area is noted. The EIS recognizes that the NUSD proposal, as currently proposed, would fall under the general land use designation of community facilities and civic uses and is analyzed in the Revised Reuse Plan Alternative. The corporation yard use analyzed in the Open Space Alternative is a theoretical analysis based on the types and levels of use that would be expected if a school district based and staged a fleet of school buses at the site. It is again emphasized that this theoretical use is not proposed by the NUSD in their current public benefit conveyance application.

Response to Comment H-3. It is recognized that any impact analysis is, by necessity, a snapshot in time and that the 1995 data reflect partial closure of the Navy housing. It is presumed that following complete closure of DODHF Novato the District's enrollment declined. The comment regarding the new law affecting school capacity and the District's forthcoming new capacity proposals is noted.


Response to Comment H-4. A composite student generation factor was used to determine the total number of students resulting from reuse. This was done to keep the analysis brief and understandable to the layman and is sufficient for the purpose of an environmental impact statement.

Response to Comment H-5. As stated in the comment, new laws that reduce class size have been enacted and an expansion of the class reduction program is currently proposed in the state legislature. The NUSD capacity is therefore decreasing, with capacity in each grade level currently unknown. If it is assumed that class size reduction programs would reduce capacity by 40 students at each of the NUSD's seven elementary schools, then current elementary enrollment would generate an increased district-wide enrollment/capacity ratio of approximately 96 percent, rather than the current 88 percent as stated in the EIS. As district-wide enrollment would still below capacity, conclusions in the EIS would not change. Consequently, the EIS analysis has not been revised.

Response to Comment H-6. The comment regarding the loss of school district funding through the conversion of military housing to civilian housing is noted. Lost funding due to loss of military housing is acknowledged in Section 3.3.3. This is a completely economic effect and therefore not considered an environmental impact under the National Environmental Policy Act (NEPA). Also, this economic impact is the result of the decision to close DODHF Novato, a decision that Congress has exempted from analysis under NEPA.

Letter I

Historical Resources Information System
Northwest Information Center
Sonoma State University
1801 East Cotati Avenue
Rohnert Park, CA 94928-3609



COMMANDING OFFICER
ENGINEERING FIELD ACTIVITY WEST
NAVAL FACILITIES ENGINEERING COMMAND
ATTN MR GARY MUNEKAWA
ENVIRONMENTAL PLANNING BRANCH
CODE 1852GM
900 COMMODORE DRIVE
SAN BRUNO CA 94066-5006



20 FEBRUARY 1997

File No.: 97-MA-8E


re: San Marin High School Student Center, 15 San Marin Drive
Novato, CA

Dear Staff:

Our office has no additional comment on the above
referenced document. However, thank you for your
continued concern for protecting historical resources.

I-1

Sincerely,


Leigh Jordan
Coordinator, NWIC

Response to Comments

Response to Comment I-1. The comment is noted; however, it is unclear, based on the heading on this letter, whether the commenter is providing comment on the DODHF Novato project or on a presumed project at San Marin High School Student Center, which was the location for the public hearing on the project.

March 17, 1997

Mr. Gary Munekawa
Code 1852GM
U.S. Navy
Engineering Field Activity West
900 Commodore Drive
San Bruno, CA 94066-5006



30 N. San Pedro Road
Suite 265
San Rafael California 94903

Executive Director
Janet Miller Schoder

Deputy Director
Michael D. Kelleher

Re: Draft Environmental Impact Statement ("EIS") for the Disposal and
Reuse of DODHF Novato, CA

Dear Mr. Munekawa:

I am writing on behalf of the Hamilton Homes Task Force (HHTF), the local coordinating body for those agencies approved for facilities serving homeless people at the Hamilton Army Air Field (HAAF) in Novato, California. This group has worked intensively for three years with the Hamilton Reuse Planning Authority to develop a plan for reasonable accommodation for facilities serving the homeless in the final reuse plan for the HAAF. The legally binding agreement for these facilities and land was approved by the Department of Housing and Urban Development in March of 1996.

J-1

Our team has reviewed the draft Environmental Impact Statement for the disposal and reuse of DODHF in Novato and has the following comments and questions:

1. Environmental Contamination Generally: The EIS repeatedly states that the Navy is responsible for cleaning up environmental contamination prior to lease or transfer. In all such instances, the EIS should also clearly state that (a) the Navy will provide evidence to the transferee or lessee that environmental contamination has been fully remediated to the satisfaction of all federal, state and local governmental authorities with jurisdiction, and (b) the Navy will indemnify and hold harmless the transferee or lessee from environmental contamination subsequently discovered and attributable to the Navy's period of ownership.
2. BRAC Cleanup Plan: The EIS states that the BRAC Cleanup Plan was completed in March 1995, updated in March 1996 and would be updated annually. All references in the EIS to the BRAC Cleanup Plan should identify when the 1997 update will be completed and available for review.
3. Permanent Service Center for Homeless People: In Section 2. Proposed Action and Alternatives under Planning Area 4, Commissary Triangle (p. 2-11), please clarify that the allowed uses include both the temporary and the permanent Hamilton Service Center, an 80-bed center for homeless adults.

J-2

J-3

J-4

Housing Authority of
the County of Marin

415/491-2525

(FAX) 415/472-2186
(TDD) 1-800-735-2929

- | | | |
|----|---|-----|
| 4. | Asbestos-Containing Materials: Section 3.13.5 of the EIS states that an asbestos survey was conducted in August 1995 and that friable asbestos was found in certain portions of Spanish Housing. This section should expressly state that no friable asbestos-containing material (ACM) was identified in any other housing units and that the Navy will be responsible for asbestos cleanup if any ACM is discovered during renovation at Capehart Housing. | J-5 |
| 5. | Underground Storage Tanks: Section 3.13.7 of the EIS should clearly identify the status of remediation of the underground storage tank or tanks located in the Commissary Triangle on the 3.9 acre parcel designated for use for the permanent Hamilton Service Center under the Revised Reuse Plan Alternative. | J-6 |
| 6. | Lead-Based Paint: Section 3.13.9 of the EIS provides that lead-based paint (LBP) is present and lead in the soil detected at Capehart Housing. This section further states that LBP abatement may be required if other renovation is performed. The latter provision must be revised either to require abatement by the Navy prior to transfer or to make the Navy responsible for abatement after the property transfer and during renovation by the subsequent property owner. Further, this section should identify the full extent of LBP in Capehart Housing and should summarize the results of the further assessment of lead in the soil at Capehart Housing. | J-7 |
| 7. | Lead in Soil: Section 3.13.9 of the EIS also provides that lead has been detected in the soil at Capehart Housing, that further assessment is planned and that further action by the Navy has not yet been determined. The current status of remediation of lead in the soil should be added to this section. | J-8 |

Thank you for addressing our concerns. Please feel free to call me with any questions you may have until March 28. My direct line is 491-2540. After March 28, you should address your responses to Elaine Reyff at 896-2300.

Sincerely,


Nicky McIntyre
HHTF Coordinator

Response to Comments

Response to Comment J-1. The comment is noted.

Response to Comment J-2. The regulatory requirements for cleanup and transfer of real property are discussed in Section 3.13.1. The Navy's leasing and disposal of DODHF Novato will be in compliance with these and other applicable requirements.

Response to Comment J-3. The EIS clearly states that the document will be updated annually. References to the BRAC Cleanup Plan (BCP) are to an existing document and repeated references to the update process are not added. The 1997 BCP update was completed in March 1997.

Response to Comment J-4. The EIS reference to "temporary" refers to the anticipated length of stay by the residents of the shelter. The allowed uses under this alternative would include both the temporary and the permanent Hamilton Service Center.

Response to Comment J-5. The asbestos survey included a random sampling from each housing area at DODHF Novato. Asbestos-containing materials (ACM) were identified in all housing areas; however, asbestos that was friable was identified only in Spanish Housing. The Navy's policy is that property with ACM will not be disposed of through the Base Realignment and Closure (BRAC) process unless the ACM does not pose a threat to human health at the time of transfer. Asbestos-containing materials that are not damaged and friable are not considered to pose a health risk and will therefore not be abated. No friable ACM was found in the Capehart housing so no abatement is required.

Response to Comment J-6. Updated information on the status of underground storage tank site investigations and remediation at this and other sites is available in the BCP update of March 1997.

Response to Comment J-7. The Navy's policy is to comply with all applicable state and federal laws governing remediation. In the case of housing constructed between 1960 and 1978, such as the Capehart Housing area, the Navy will not perform lead-based paint abatement unless required to do so by state or local lead-based paint law. No such requirements currently exist. The full results of lead-based paint and soil assessments will be disclosed to potential purchasers.

Response to Comment J-8. The Navy's policy is to comply with all applicable state and federal laws governing remediation. The Navy is working with the Department of Toxic Substance Control (DTSC)

Nicky McIntyre
Housing Authority of the County of Marin
Letter J

to determine the appropriate response action for lead in soils and will implement any remediation required by applicable federal or state laws prior to transfer.

SIERRA CLUB MARIN GROUP

Marjorie Macris, Chair
45 Wildomar St., Mill Valley, CA 94941
(415) 381-6667 fax: (415) 381-6668 email: mmacris@aol.com

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
900 Commodore Drive
San Bruno, Ca. 94066-5006
Attn: Mr. Gary Munekawa, Environmental Planning
Code 1852GM

Re: Draft EIS Hamilton Housing Facilities

Dear Mr. Munekawa:

The Marin Group of the Sierra Club has reviewed the Draft EIS and would like to take this opportunity to provide the following comments.

Despite the likelihood that Rafael Village housing units utilized significant amounts of asbestos containing materials as well as lead based paints in their construction and maintenance, there is very little discussion as to the impacts associated with their demolition. Indeed there is greater information on mitigation measures for dust control (4-75) than the aforementioned hazardous materials. Of particular concern would be contamination from flood erosion or surface runoff during demolition without proper containment measures. While the use of hay bales and silt fences may control soil erosion, they would presumably do little to assure containment of hazardous materials. References to "best management practices" could be of more value if specific techniques were outlined. Perhaps demolition should be restricted to historically dry months. Similarly, air-borne release of asbestos is of special concern given the proximity to existing school yards and residences. The EIS admits that only spot checks have been made at Rafael Village. More data is needed to gauge the extent of this potential problem.

K-1

Sedimentation in sensitive wetlands and riparian habitat due to demolition, site grading, and construction are of special concern and once again deserve more discussion than references to "best management practices" or "standard erosion control measures".

K-2

The EIS assumes reuse of Rafael Village area would not differ from existing conditions as pertains to surface runoff volumes and patterns. This opinion is premature without the benefit of a

K-3

page 2

specific Master Plan. It is more likely that new homes will result in a net increase of dwelling footprints and roadway surfaces. This would translate to mean less capacity to absorb surface runoff.

K-3

Traffic data appears to make like-for-like comparisons between reuse and military patterns. Although mention is made that civilian non-residential land use would be greater than military non-residential land use in terms of trip rates, no discussion is made for residential land use comparisons. Given the unique conditions to military life it is likely that unconventional traffic patterns would prevent standard comparisons. These variables might include composition of family members per household, absence of one adult for extended periods due to time at sea, vehicles per family, economic factors, and the self-contained nature of base life. These could all affect off-site vehicle trips.

K-4

The EIS should not downplay the significance of LOS F for intersections and freeway volumes simply because the Novato General Plan allows for even more build-out than the Reuse Plan Alternative (4-65). A significant impact is a significant impact and should be mitigated.

K-5

Sound walls as mitigation for noise (ES-12) along Ignacio Blvd. should be discussed as a potential conflict with goals for visual quality and scenic resources (3-17). Although solving one problem, sound walls may be the very source of another.

K-6

Even though NOx and Reactive Organic Compounds emissions would exceed BAAQMD thresholds (4-76), the EIS concludes that because the Region of Influence for these compounds is the entire Metropolitan Bay Area, the impact is somehow diminished. This may not be comforting to those residing and/or working within the immediate vicinity. ROI's for air quality should perhaps be held to the same standard as for water quality,

K-7

No mention is made as to potential impacts to newly restored wetland habitat on the 700 acre Army airfield runways. It could be assumed that residential and commercial development would impact this future restoration project. Possible mitigations might include buffer zones or setbacks.

K-8

Thank you for the opportunity to comment.

Yours Truly,
Phil Peterson
Ex. Com. Member
Sierra Club, Marin Group

Response to Comments

Response to Comment K-1. The comment appears to be based on misconceptions about the health threats posed by asbestos and lead. The primary threat to human health that could be created by demolition of a building containing asbestos would be the creation of airborne asbestos dust. The USEPA and the Bay Area Air Quality Management District have strict regulations regarding emissions of airborne asbestos. These regulations would generally require that asbestos be removed from buildings prior to large-scale demolition. Removal would be the responsibility of the site owner and the demolition contractor, as the Navy would not demolish Rafael Village prior to property transfer. An asbestos survey has been completed for all housing areas at DODHF Novato, including Rafael Village. Asbestos-containing materials were identified in all housing areas; however, asbestos that was both damaged and friable was not identified in Rafael Village.

With regard to lead, abatement of intact lead-based paint (LBP) on structures is not required prior to demolition. Dried LBP on building surfaces is not generally soluble in water and is therefore unlikely to create lead-contaminated runoff during demolition.

Regarding the specific mitigations that would be used during demolition and construction at the Rafael Village site, please see the following Response to Comment K-2, which provides a more detailed description of mitigations that would reduce the potential for sedimentation.

Response to Comment K-2. It is noted that sedimentation in biologically sensitive areas would be a significant impact if not mitigated. This issue is addressed in discussions of Impacts 1 and 4 in Section 4.9, Water Resources, and Impact 1 in Section 4.7, Biological Resources. The Clean Water Act requires standard mitigation measures and best management practices and the City of Novato has guidelines to lessen impacts. In order to assure that this impact would be mitigated to less than significant levels, the following additional mitigation is added to Section 4.9, Water Resources, Mitigations 1 and 4 and Section 4.7, Biological Resources, Mitigation 1:

“Protect off-site areas (including streams and riparian areas) from potential erosion from adjacent bared areas by use of silt fences, staked straw bales, sedimentation basins, and other appropriate structural methods.”

Response to Comment K-3. The commenter is correct in asserting that, at this time, it is not possible to determine the total impervious footprint of future residential development at Rafael Village. At this time it would be speculative to attempt to quantify any such increase. This issue will be addressed in

the California Environmental Quality Act (CEQA) documentation on specific reuse proposals. Potential mitigations that may be required under future analysis could include limiting the existing area of impervious coverage or incorporating detention basins or other structural or non-structural methods into redevelopment design to assure no increase in peak flows from that area into San Jose Creek.

Response to Comment K-4. Trip generation surveys of military residential uses in both Rafael Village and Spanish Housing showed that Rafael Village generated about 7.89 daily vehicle trips per occupied dwelling unit and Spanish Housing generated about 12.34 daily vehicle trips per occupied dwelling unit. The Rafael Village 7.89 daily vehicle trips per occupied dwelling unit is about 22 percent higher than the 6.47 trips per unit for a civilian apartment (Institute of Transportation Engineers, *Trip Generation Manual*, January, 1991, Page 311). The Spanish Housing 12.34 trips per day rate is about 29 percent higher than the 9.55 vehicle trips per day for a typical civilian single family residence (Institute of Transportation Engineers, *Trip Generation Manual*, January 1991, Page 257).

The pattern of higher traffic generation from military housing uses is attributed to larger household sizes within the military family housing stock than within the typical civilian housing stock. Vehicle trip generation per household increases as household size increases due to added trips associated with transporting children and/or older children owning cars and driving. One of the primary reasons that the Revised Reuse Plan would generate fewer vehicle trips than the occupied military use is that the civilian residential trip generation characteristics are lower than the military residential uses.

Response to Comment K-5. The EIS does not downplay projected poor operation (LOS E and F) conditions on local intersections or regional freeway links. Four intersections (Ignacio Boulevard @ Sunset Parkway, Ignacio Boulevard @ Entrada Drive, Ignacio Boulevard @ Safeway Access, and Ignacio Boulevard @ Nave Drive are projected to operate at LOS F during one or both peak hours) and three freeway segments (Highway 101 from SR 37 to Alameda del Prado and SR 37 from Highway 101 to Atherton Avenue) are projected to operate at LOS E/F under cumulative conditions. These are significant adverse impacts of cumulative development, but are not impacts resulting from implementation of the Revised Reuse Plan Alternative. Since the Revised Reuse Plan Alternative would result in a net negative number of new vehicle trips, it would not result in off-site impacts. Since these impacts are not a result of the project (Revised Reuse Plan Alternative), it would be inappropriate to identify any mitigation. However, the required improvements for the deficient intersections have been identified and may be required as mitigation for other cumulative developments. It is unlikely that improvements could be made to the freeway facilities within the next 20 years, so travelers on these facilities are likely to experience considerable delays under cumulative conditions.

Response to Comment K-6. The mitigation measure merely recommends future consideration of site designs that might allow for soundwalls along Ignacio Boulevard. Technical effectiveness, site access constraints, and aesthetic tradeoffs are normal components of soundwall feasibility evaluations.

Response to Comment K-7. It was not the intent of the EIS to imply that the significance of ozone precursor emissions is diminished because ozone is a regional air pollutant. The EIS does note, however, that the Bay Area Air Quality Management District (BAAQMD) emissions significance thresholds do not imply any change in the magnitude or frequency of violations of the state or federal ozone standards. Despite continual urban growth and the addition of new emission sources, there has been a clear downward trend in the magnitude and frequency of violation of the federal and state ozone standards over the last 20 years. The incremental addition of new emission sources has been more than offset by continuing improvements in emission controls for stationary, mobile, and area sources.

Response to Comment K-8. The EIS did not identify potential impacts to the wetland restoration project at the former Army runway site. The 700-acre Army Airfield site will already be separated from the DODHF Novato property by levees. No mitigations were proposed because no impacts were identified. Cumulative impacts analysis in Section 5.1 describes the wetland restoration project and its role in cumulative impact analysis.



Marin Audubon Society Box 599 Mill Valley, California 94942-0599
February 21, 1997

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
900 Commodore Drive
San Bruno, CA 94066-5006

ATT: GARY J. MUNEKAWA, CODE 1852GM

RE: DRAFT ENVIRONMENTAL IMPACT STATEMENT FOR THE DISPOSAL AND
REUSE OF THE DOD HOUSING FACILITY, NOVATO, CA

Dear Sirs/Madams:

The Marin Audubon Society appreciates the opportunity to comment on the Draft EIS for the Disposal and Reuse of Housing at Hamilton Field. The document reflects the plan arrived at by the community, however, there are a number of potential impacts and components that are not adequately addressed.

The following matters should be addressed in a future Draft:

Alternatives An alternative should be developed that retains existing houses at Rafael Village. This alternative would be avoid air quality, waste disposal, traffic, and other adverse impacts associated with demolition of the 503 houses and reconstruction of new housing.

L-1

Mitigations for Erosion and Sedimentation

We agree that demolition of existing houses and construction of new units at Rafael Village, Town Center, Exchange Triangle and other to-be-developed areas could result in erosion and sedimentation impacts to the creek and its resources. Benthic organisms would be covered, vegetation smothered, and water quality degraded by turbidity. Implementation of standard erosion control measures to minimize sedimentation is recommended on page 4-44. Reduced water quality in the creeks and downstream is also a potential adverse impact if erosion control measures are not effective. Again on page 4-48, the Soil Erosion impact is dismissed as not significant by "implementing standard erosion control measures during demolition and construction." Simply referencing these standard measures is insufficient to ensure that impacts to sensitive habitats and species would be reduced to a level of non-significance.

L-2

Measures that would be implemented as "standard erosion control" should be explained. Standard measures are not necessarily adequate in times of storm and heavy runoff in this area. There are a number of recent instances where so called "standard" methods have been ineffective and considerable erosion and sedimentation of adjacent creeks and wetlands have occurred. Simply placing haybales and hydromulching is not adequate because water flows around and under bales, and hydromulch placed before the rains begin does not have a long enough period to grow. The recommendation that vegetation be reestablished as quickly as possible following construction might work if construction were finished in spring. However, if construction goes into the summer and fall, there is insufficient growing time in this climate for this to be an effective mitigation.

A Chapter of National Audubon Society

Specific measures should be recommended that would be effective in this area. These should include prohibition of grading after October 15, silt fences that are maintained so as to avoid collapse, and covering of barren ground with layer of straw mulch.

L-2

Flooding Issues

As with erosion and sedimentation, simply following BMPs would not be sufficient to ensure that flooding would not occur. Specific measures to limit and prevent local flooding should be recommended, particularly removing houses from areas subject to flooding by reducing impervious surfaces so that runoff is not increased. Flood and erosion control practices must be suited to a specific area, not recommended as a generality.

L-3

The Reuse Plan would subject residents to flooding in several areas: Hillside Housing and Capehart Housing. Hillside Housing was constructed with the southern length of Valley Drive built over a creek. The creek was placed in a culvert under the road and it daylighted at the road. During times of heavy rainfall the water backs up and overflows onto Valley Drive, carrying and depositing sediment on the road. This occurs during many winters. This street should be removed and the riparian stream restored.

L-4

In addition, residents of Hamilton Airfield reported during the development of this plan that several houses that are part of Capehart Housing are also subject to regular flooding. These houses should be identified, the nature of the flooding addressed and a mitigation recommended that they be removed from the floodplain by raising, relocation or other means.

L-5

Restriction should be placed to preclude development of any Rafael Village housing in the floodplain or so as to impact the Creek in any way.

L-6

The ballfields are built on historic tidal marsh, are at a low elevation and flood during many winter seasons, they should be identified as part of the floodplain.

L-7

Creek Restoration

In addition, to restoration of the unnamed creek under Valley Drive in order to avoid subjecting residents to flooding, the creek should be restored because creeks are an important ecological resource that should not be filled. This creek provided wildlife habitat, water quality and aesthetic benefits and should be restored. California has only about 2% of its historic riparian resources remaining.

L-8

Water Quality

Reduced water quality is a potential adverse impact of the use of new development at Rafael Village, Town Center/exchange Triangle areas and other areas to be developed. Water quality degradation should be identified as an adverse impact of the development. Measurers should be recommended to avoid increased oil, greases and heavy metals flowing into streams. The discussion should address, as the most effective mitigation measure for this impact, retaining drainages above ground with natural vegetation remaining in place or planted. Natural vegetation traps and absorbs pollutants which otherwise would remain in the creek water and would flow into the Bay.

L-9

Any deficient drainage facilities (mitigation 6 page 4-55 or others) should be reconstructed to allow for the drainage to remain in or be restored to an above ground state. Significant adverse individual and cumulative impacts would result from undergrounding any creeks that are now above ground, so keeping all creeks and other drainageways flowing above ground should be identified as a mitigation measures for this impact.

Daylighting currently underground drainages should also be recommended to mitigate current adverse impacts.

L-10

Drainage systems should be designed to allow ponding flood plain along drainageway/channel. allowing sufficiently wide areas adjacent to creek banks would be a further mitigation for flooding.

L-11

Impacts of Demolishing Rafael Village

Contrary to the statement on page 4-53, the Revised Reuse Plan for Rafael Village would not "involve reuse of the existing developed area...." The existing Rafael development would be demolished and, consequently, impervious surfaces could be and surface runoff could be expanded.

L-12

Provisions should be included to ensure there will be no increase in impervious surfaces and that sufficient flood plain be retained to allow water to spread out in times of heavy flow.

Hazardous and Non-Hazardous Waste

The state and federal safety standards that will be followed in removing asbestos and other hazardous materials should be identified, so the public can evaluate whether or not they are adequate to reduce the potential impact to less than significant. How can it be assured that lead levels would be abated? How would lead based paint that undoubtedly exists in many buildings be abated?

L-13


Only hazardous waste is addressed in this document. The potential adverse impacts of removing and disposing of the waste generated by removal of Rafael Village Housing should be addressed. How much waste material would be generated? Where would it be dumped? How many truck trips would be generated to get it there? Describe the impacts of these trips on local traffic. What are the potential impacts to air quality from demolition and material being transported away from the site? How would noise levels be affected from the trucks and demolition activities?

L-14

The closest landfill is Redwood so presumably any suitable material would be deposited there. How would the disposal of the debris from this demolition affect the life span of the landfill? How much would the life span be shortened?

Thank you for responding to our comments.

Sincerely,



Barbara Salzman, Chair
Conservation Committee

Response to Comments

Response to Comment L-1. The commenter is directed to EIS Section 2.4, Alternatives Eliminated From Detailed Consideration. Section 2.4.1 describes an alternative that evaluated retaining the existing Rafael Village housing units. That alternative was eliminated from further consideration because the studies determined that it would be more costly to renovate the existing housing units to local code requirements than to demolish them and construct new houses.

Response to Comment L-2. As discussed in Response to Comment K-2, some of the suggested mitigation measures have been added to the EIS text. The Clean Water Act requires standard mitigation measures and best management practices and the City of Novato has guidelines to lessen impacts. In order to assure that this impact would be mitigated to less than significant levels, additional mitigation is added to Section 4.9, Water Resources, Mitigations 1 and 4 and Section 4.7, Biological Resources, Mitigation 1 to protect off-site areas (including streams and riparian areas) from potential erosion from adjacent bared areas by use of silt fences, staked straw bales, sedimentation basins, and other appropriate structural methods.

Response to Comment L-3. As discussed in Response to Comment D-11, most of the Rafael Village structures are located outside the boundary of the 100-year floodplain. However, some houses near the intersection of San Jose Blvd. and Ignacio Blvd. may be subject to 100-year flood hazards; the Federal Emergency Management Agency (FEMA) map detail is not sufficient to confirm or negate this hazard. The Response to Comment K-3 addresses the fact that it is not at this time possible to determine the total impervious footprint of future development. As such, it would be speculative to quantify any such increase or offer specific mitigations for different reuse areas. This issue will be addressed in the California Environmental Quality Act (CEQA) documentation on specific reuse proposals. As noted in Response to Comment K-3, mitigation under future analysis could include measures to not increase overall impervious areas or to incorporate structural or non-structural methods into redevelopment design to assure no increase in peak flows. It should be noted that in the main portion of Rafael Village, contributory flooding results primarily from flows generated outside of the project sites. Therefore, it is not possible for the project to mitigate this flooding at the source.

With respect to the Hillside and Capehart Housing areas, houses subject to the 100-year flood hazards are shown on Figure 3-15. The Navy studied flooding in this area as part of a comprehensive drainage study conducted in 1989 (A-N West January 1989). That study concluded that when the flow in Pacheco Creek reaches 220 cubic feet per second (cfs) at the Main Entrance Road, stormwater starts backing up into West Kelly Drive and floods some of the low lying houses along that street. If

the flow exceeds 330 cfs, the Main Entrance Road is overtopped. At the railroad crossing downstream of the Main Entrance Road, flows of 460 cfs for a 10-year event and 820 cfs for a 100-year event were calculated. Implementation of Section 4.9.2 Mitigation 6 for the Main Site would alleviate this flooding except for the Building 140 area. The Reuse Plan proposes elevating or regrading of the Building 140 area and providing secondary overflow paths for the sump basins on East and West Kelly Drives to alleviate this problem.

Response to Comment L-4. For a discussion of Capehart Housing area flood hazards, see Response to Comment L-3, above. The Hillside Housing area, including the Valley Drive area, is not indicated on the FEMA maps as subject to 100-year flood hazard. However, Valley Drive may be subject to occasional overland flows when the capacity of the underlying storm drain system is exceeded.

Response to Comment L-5. Existing flooding problems in Capehart Village are described in Section 3.9.3 of the EIS. The southern and southeastern portions of Capehart Housing, as well as its western fringe, are subject to flooding in a 100-year flood event. Response to Comment L-3, above, further describes this flooding.

Response to Comment L-6. Comment noted. The requested restriction on developing in the floodway is already included in Section 4.9.2, Mitigation 2, under Rafael Village for the Revised Reuse Plan Alternative.

Response to Comment L-7. The Ballfields described in the first paragraph of Section 3.9.3 of the EIS are subject to the 100-year flood.

Response to Comment L-8. Flood issues on Valley Drive are discussed in Response to Comment L-4. The commenter's concerns with respect to creek restoration are noted. Restoration could occur during reuse, but no environmental impacts have been identified in this EIS that require these activities as mitigation.

Response to Comment L-9. In response to this comment, the following additional impact and mitigation discussion is added to Impact 4, Section 4.9.2, Significant Impacts:

“Reuse of the Main Site would add urban pollutants such as oil, grease, fertilizers, and pesticides to the local runoff. Although some input of these contaminants currently is occurring, it could be increased upon reuse.”

Mitigation 4 includes retaining and treating runoff on site before it infiltrates the groundwater or enters the bay. The requested natural vegetation traps are part of the Best Management Practices (BMPs) recommended for this site. In order to clarify this, the following is added to Mitigation 4:

"BMPs should include grassy swales, detention ponds, and landscaping that will detain and treat water contaminated with urban pollutants."

Response to Comment L-10. Daylighting underground drainages is not required to mitigate for any environmental impact associated with disposal or subsequent reuse of DODHF Novato.

Response to Comment L-11. Given the current developed condition of much of the site, the comment's suggestion may not be feasible on much of the site. Future specific drainage designs would be subject to review and approval by the City of Novato, and would require site-specific analysis under CEQA.

Response to Comment L-12. As discussed in Response to Comment K-3, it is not possible to determine the total impervious footprint of future development. As such, it would be speculative to quantify any such increase or offer specific mitigations for different reuse areas. This issue will be addressed in CEQA documentation on specific reuse proposals. The Response to Comment K-3 includes possible mitigation measures that could be required under future analysis to not adversely affect downstream flooding.

Response to Comment L-13. The US Environmental Protection Agency (USEPA), California Environmental Protection Agency (Cal-EPA), and the Bay Area Air Quality Management District (BAAQMD) have strict regulation regarding emissions of airborne asbestos. The major federal regulations governing asbestos handling and removal are 40 CFR 61, Subpart M, National Emissions Standards for Hazardous Air Pollutants, and 29 CFR 1926.58, which deals with worker protection and procedures during asbestos removal. The state regulations for asbestos include CCR Title 8, Section 1529, Asbestos Regulations for the Construction Industry, and CCR Title 8, Section 5208.1, Asbestos Regulations for General Industry. These regulations would generally require that asbestos be removed from buildings prior to large-scale demolition. The Navy will abate LBP in accordance with applicable federal and state regulations as stated in Section 4.13.2. However, there is no requirement for the Navy to abate lead paint in structures planned for demolition. In these cases, federal and state regulations governing the handling and removal of lead-based paint would apply.

Response to Comment L-14. Demolition of the Rafael Village housing units is discussed in Section 4.5, Utilities. A local demolition contractor estimated that each unit would generate approximately 13 to 14 tons of construction debris. This would result in approximately 6,500 to 7,000 total tons of debris, or 0.06 percent of the available capacity (10.9 million tons) in the Redwood Landfill, where it would likely be disposed. Truck trips from hauling of the debris would not impact local traffic. While the number of truck trips can be estimated, the frequency of the trips is unknown since no demolition schedule exists. The number of trips generated by truck traffic during demolition would be far less than the number of trips generated when the Rafael Village housing units were occupied. The effects of demolition on air quality and noise are discussed in Sections 4.11 and 4.12, respectively. As discussed in Section 4.11, demolition would have a short-term effect on air quality from dust generation. Dust can be controlled to some degree using standard dust control measures. Construction equipment and trucks also would produce emissions during the time of their use. Use of this equipment would occur on a staggered schedule and for a short duration overall and would not have significant effects to local or regional air quality. As discussed in Section 4.12, demolition activities would produce temporary noise disturbances to adjacent land uses. During demolition, noise levels in the near vicinity of the activity could exceed local noise guidelines for residential land uses. However, noise associated with demolition would be of short duration and would produce no long-term noise effects. Limiting demolition to normal daytime hours would reduce noise effects associated with demolition.



MARIN CONSERVATION LEAGUE

55 Mitchell Blvd., Suite 21 • San Rafael, CA 94903
 Voice (415) 472-6170 • Fax (415) 472-1404
 e-mail: mcl@nbn.com • web site: www.nbn.com/mcl

3/17/97

Board of Directors

Priscilla Bull
President
 Jane Mills
Vice President
 Jean Berensmeier
Vice President
 Grant Davis
Secretary
 Lawrence Smith
Treasurer
 Bob Berner
 Carole d'Alessio
 Joy Dahlgren
 Ken Drexler
 Rick Fraites
 Harvey M. Freed
 Pegi Knopp
 Kathy Lowrey
 Marge Macris
 Frank Nelson
 Terri Nevins
 Karen Nygren
 Eliana Ponce de
 Leon Reeves
 Denis Rice
 Merritt Robinson
 George Sears
 Jean Starkweather
 Michael Straus
 Ann Thomas
 Periann Wood
 Peter H. Behr
Director Emeritus
 Jerry Edelbrock
Executive Director
 Marcy Roth
Public Education
 Bill Eichhorn
Financial Development
 Dee Welte
Office Manager

Commanding Officer
 Engineering Field Activity West
 Naval Facilities Engineering Command
 900 Commodore Drive
 San Bruno, CA 94066-5006
 Attn: Mr. Gary Munekawa, Environmental Planning
 Code 1852GM

Re: Draft EIS Hamilton Housing Facilities

Dear Mr. Munekawa:

The Draft EIS on the Department of Defense Housing Facility in Novato, CA has been reviewed by the Marin Conservation League. Some issues we raised during the scoping for the EIS do not appear to be adequately addressed, and some issues on which we would like to see some additional information.

M-1

The disposal and reuse appears to generate very few significant impacts, according to the EIS. However, we question the ROI (Region of Influence) for air quality and the deficiency of information on other issues.

M-2

The demolition of 503 housing units in Rafael Village and existing facilities on Commissary and Exchange Triangles particularly concerns us. The EIS had some information about the level of asbestos and PCB's in buildings to be demolished on the main base, but very little on Rafael Village. No mention was made of the demolition impact of lead paint acknowledged to be present in all the buildings to be demolished. Is the cumulative impact on the Redwood Landfill within the landfill's permit?

M-3

M-4

There are residential communities with young children within a very short distance of some of the demolition. The vague reference to the California Waste Management Board developing some guidelines for base demolition does not answer the current questions of how to protect neighboring homes and their occupants from airborne and runoff pollutants during and after demolition.

M-5

How many truckloads of debris would the 6500 - 7000 Tons to be generated by Rafael Village require? Are the pipes in Rafael Village wrapped with asbestos, as was commonly done in the 40's? What is the probability of asbestos becoming airborne during bulldozing? How much airborne asbestos is harmful to children under two years of age?

M-6

M-7

Table 3-14 on page 3-29 combines two elementary schools, but the numbers seem to reflect just one.

M-8



MARIN CONSERVATION LEAGUE

The Bay Plan has been amended by BCDC to remove Hamilton as an airport, so there is no conflict with the wetland restoration plan. This was not stated correctly in the EIS.

M-9

The water quality degradation from demolition and reconstruction seems under estimated because the creeks through both Rafael Village and the main base flow into the Pacheco wildlife ponds. These ponds store water, and accumulate sediments and toxics from the creeks. Because of this, extraordinary precaution should be exercised to prevent toxics from washing into streams. Perhaps demolition should be limited to certain months without rainfall, or a special runoff pond (or ponds) created to capture pollutants.

M-10

Page 4-53 states that reuse of the Rafael Village area would not increase impervious surfaces, and therefore would not impact surface runoff quantities. Observation of recent development in that area shows that houses are larger, driveways are larger and patios are larger than the existing Wherry housing. A comparison of the current paved footprint with adjacent new development would be more accurate in determining whether or not the increased runoff would be significant. The capacity of San Jose Creek to handle the added and cumulative runoff should be evaluated.

M-11

The discussion of traffic impacts states that military uses generated more trips than civilian uses. We question that assertion since under Naval use many of the residents were at sea for months at a time. We concur with the statement that military non-residential uses generate fewer trips than comparable non-military uses. Therefore, net new trip generation should be higher under the reuse. (Table 4-19, page 4-62). Three intersections operating at LOS F should require mitigation whether or not the city General Plan has a similar LOS. That is below the city's professed standard.

M-12

M-13

The Appendices should show 60 KV (and higher) power lines in the utility section figures.

M-14

The traffic data resources should be identified better. Page 3-98 states that local circulation data was collected "during March 1995". By whom, what days, what hours? This kind of information was provided in the appendix for the biological survey.

M-15

Thank you for the opportunity to comment.

Yours truly,

Priscilla Bull
Priscilla Bull
President

Response to Comments

Response to Comment M-1. The general comment regarding issues that the commenter considers as needing additional information is noted.

Response to Comment M-2. The region of influence for primary pollutants with localized emissions is generally restricted to Novato or to areas in the immediate vicinity of the source of emissions, while the ROI for secondary pollutants is the entire Bay Area Air Quality Management District (BAAQMD) air basin. The size of the region of influence has no bearing on whether or not air quality impacts are considered significant. Impact significance criteria are clearly defined at the beginning of the impact discussion as exceeding federal or state significance thresholds. The comment does not identify any specific "question" about the region of influence (ROI) for air quality.

Response to Comment M-3. As discussed in Section 3.13.6, the only polychlorinated biphenyls (PCBs) historically associated with the Rafael Village housing area were pole transformers owned by PG&E. PG&E has carried out a PCB removal program for all of its equipment over the past several years and now states that its equipment does not contain PCBs. As discussed in Section 3.13.5, spot checks for asbestos in Rafael Village units revealed asbestos only in floor tiles. Asbestos that was friable was not identified in Rafael Village. There are no requirements to abate lead-based paint (LBP) in structures that are being demolished. Intact LBP on structural members is generally not considered to be a hazardous waste; demolition would therefore not result in a release of hazardous waste.

Response to Comment M-4. The Redwood Landfill is capable of accepting demolition debris from the Rafael Village housing units. A local demolition contractor estimated that each unit would generate approximately 13 to 14 tons of construction debris. This would result in approximately 6,500 to 7,000 total tons of debris, or 0.06 percent of the available capacity (10.9 million tons) in the Redwood Landfill. Text has been added to indicate that the Redwood Landfill is permitted and has the capacity to receive asbestos- and lead-based paint-containing construction debris.

Response to Comment M-5. The US Environmental Protection Agency (USEPA) and California Environmental Protection Agency (Cal-EPA) have strict guidelines regarding run-off pollutants. These agencies and the BAAQMD have strict regulations regarding emissions of airborne pollutants. Regulations for handling materials are designed to avoid any significant releases. Normal procedures require removal of hazardous materials prior to any demolition of structures. Thus, there would be no significant health risk if demolition and waste handling activities comply with existing regulations.

Response to Comment M-6. Demolition activities at Rafael Village would generate 13 to 14 tons of debris per structure (approximately 6,500 to 7,000 tons total) and would require approximately 300 truck trips from Rafael Village to the Redwood Landfill (Lavaggi, personal communication). Due to the nature of demolition activities, the truck traffic would occur over a period of time and would not result in significant traffic congestion or related air quality and noise impacts. No specific demolition plan or demolition contractor has been identified to perform the work. When specific plans are identified, the proposal will undergo the appropriate local approval process.

Response to Comment M-7. An asbestos survey has been completed for a random sampling of each housing area at DODHF Novato, including Rafael Village. Asbestos-containing materials were identified in all housing areas; however, asbestos that was friable was not identified in Rafael Village. The USEPA and the BAAQMD have strict regulations regarding emissions of airborne asbestos. These regulations would generally require that asbestos be removed from buildings prior to large-scale demolition, in order to reduce the risk of airborne asbestos emissions. Removal would be the responsibility of the site owner and the demolition contractor. An assessment of asbestos health risks is outside the scope of this EIS.

Regulations for handling materials containing asbestos are designed to avoid any significant airborne releases of asbestos containing materials. Normal procedures require removal of asbestos containing materials prior to any demolition of structures. Thus, there will be no significant health risk if demolition and waste handling activities comply with existing regulations.

Response to Comment M-8. Table 3-14 lists all seven elementary schools in the Novato Unified School District system and gives capacity and enrollment figures for each of the seven individual schools. The table also provides totals for elementary school capacity and enrollment and total District capacity and enrollment.

Response to Comment M-9. Text in Section 3.1.2 regarding the San Francisco Bay Conservation and Development Commission (BCDC) designations has been revised to reflect BCDC's current designations for DODHF Novato and the Hamilton Army Airfield.

Response to Comment M-10. Demolition that occurs during reuse must be consistent with Best Management Practices and federal, state, and local regulations. See also the Responses to Comments K-2, K-3, and L-9.

Response to Comment M-11. As discussed in Response to Comment K-3, it is not at this time possible to determine the total impervious footprint of future development. As such, it would be speculative to quantify any such increase or offer specific mitigations for different reuse areas. This issue will be addressed in California Environmental Quality Act (CEQA) documentation on specific reuse proposals. As noted in Response to Comment K-3, mitigation under future analysis could include measures to not increase overall impervious areas or to incorporate structural or non-structural methods into redevelopment design to assure no increase in peak flows.

Response to Comment M-12. The statement that military residential uses generate more vehicle trips than comparable civilian uses is based on surveys conducted in the Rafael Village and Spanish Housing areas, just as the statement on non-residential uses is based on surveys conducted at the Commissary Site. This data is based on continuous week-long traffic counts on streets entering and exiting these areas. The practice of conducting field counts of existing uses is the most precise measure of a uses traffic generation characteristics, so this trip generation estimation technique is very reliable. The Response to Comment K-4 provides a more detailed description of the results of our trip generation analysis.

Response to Comment M-13. As stated in Response to Comment K-5, the EIS does not downplay projected poor operation (Level of Service [LOS] E and F) conditions on local intersections or regional freeway links. Four intersections and three freeway segments are projected to operate at LOS E/F under cumulative conditions. These are significant adverse impacts of cumulative development, but are not impacts resulting from implementation of the Revised Reuse Plan Alternative. Since the Revised Reuse Plan Alternative would result in a net negative number of new vehicle trips, it would not result in off-site impacts. Since these impacts are not a result of the project (Revised Reuse Plan Alternative), it would be inappropriate to identify any mitigation. However, the required improvements for the deficient intersections have been identified and may be required as mitigation for other cumulative developments. It is unlikely that improvements could be made to the freeway facilities within the next 20 years, so travelers on these facilities are likely to experience considerable delays under cumulative conditions.

Response to Comment M-14. The utility figures have been updated where possible to reflect in more detail the size and location of power lines within and coming onto DODHF Novato.

Priscilla Bull
Marin Conservation League
Letter M

Response to Comment M-15. Traffic data were collected by Fehr & Peers Associates, Inc. on February 27-28, and March 1 and 7, 1995 during the appropriate peak hour periods as defined in the EIS.



February 26, 1997

Commanding Officer
 Engineering Field Activity West
 Naval Facilities Engineering Command
 Attn.: Mr. Gary J. Munikawa, Environmental Planning Branch, Code 1852GM
 900 Commodore Drive
 San Bruno, CA 94066-5006

Re: Hamilton -- Draft Environmental Impact Statement; Hazardous Materials and Waste

Dear Mr. Munikawa,

I would like to request clarification on the issue of the Navy's responsibility for the discovery and disposal of hazardous materials, especially lead and asbestos. It has been my understanding that prior to disposal, the Navy must abate or clean up all hazardous materials and waste. In fact, on page 13 of the Executive Summary you state that the "Navy will... abate any lead-based paint or asbestos that pose a threat to human health, and clean up any contamination prior to transfer of DODHF Novato." However, information later in the report does not seem consistent with this statement. Please clarify the following:

N-1

1. **Asbestos** The Draft EIS (page 3-119) states that "An asbestos survey of the housing units was conducted ... in August 1995. The friable ACM was identified in the garages of 47 units inspected in Spanish Housing." Please clarify that Capehart and Hillside housing were also inspected and were found to be free of asbestos.

2. **Lead-based Paint** The Draft EIS (page 3-126) states that Lead-based paint (LBP) is present in the Capehart units. It also states that LBP abatement is not required. Because LBP poses a threat to human health and based on the Navy's policy to clean up contamination prior to transfer, it seems appropriate that the Navy would abate any LBP in the Capehart units.

N-2

3. **Other Sources of Lead** The Draft EIS (page 3-126) also states that lead has been detected in the soil around the Capehart units above the HUD action level. It indicates that further assessment is planned and that the response measures will be determined based on an assessment of the potential risk to human health and the environment. It also indicates that no survey for lead in the drinking water has been conducted. Please clarify

N-3

■ Creating community by developing, managing, and promoting affordable housing since 1968

2169 East Francisco Blvd.

Suite B

San Rafael, CA 94901-5531

415 / 258-1800 ■ Fax 415 / 453-4927

Response to Draft EIS, DODHF Novato
February 26, 1997
Page 2

that further testing for both sources of lead will be conducted and whether lead contamination above federal action levels will be abated.

N-3

These issues are essential to the utilization of the Capehart and Hillside housing units as envisioned in the Reuse Plan. If the parcels are not cleaned of contamination and hazardous materials before transfer, they may not be suitable for reuse or reuse may not be economically feasible. Thank you for your attention to this matter.

N-4

Sincerely,



Betty Pagett
Member, Hamilton Advisory Commission

c: Rod Wood, Novato City Manager

Response to Comments

Response to Comment N-1. The asbestos survey included a random sampling from each housing area at DODHF Novato. Asbestos-containing materials (ACM) were identified in all housing areas; however, asbestos that was friable was identified only in Spanish Housing. The Navy's policy is that property with ACM will not be disposed of through the Base Realignment and Closure (BRAC) process unless the ACM does not pose a threat to human health at the time of transfer. Asbestos-containing materials that are not damaged and friable are not considered to pose a health risk and will therefore not be abated. Only asbestos-containing materials that are both damaged and friable would be repaired or removed prior to transfer.

Response to Comment N-2. The Navy is not required by federal law to abate LBP hazards in housing constructed between 1960 and 1978. Consistent with Navy policy and federal law, the Navy will disclose the result of its lead-based paint (LBP) assessment to potential purchasers of housing constructed between 1960 and 1978. The Navy will abate LBP hazards in accordance with federal requirements in housing constructed prior to 1960. As the Capehart units were constructed after 1960, no LBP abatement is required.

Response to Comment N-3. The Navy does not plan any further action on the issue of lead in soils at Capehart. No drinking water surveys are required under federal law and none are anticipated prior to disposal.

Response to Comment N-4. The commenter's concerns regarding cleanup of contamination and hazardous materials prior to property transfer are noted.



MARIN FAMILY ACTION

1007 GREEN OAK DRIVE #35
NOVATO, CA 94949
PHONE/FAX: 415-883-1230
mfa@waonline.com

March 11, 1997

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
ATTN: Mr. Gary J. Munikawa, Environmental Planning Branch Code, 1852GM
900 Commodore Drive
San Bruno, CA 94066-5006

RE: Hamilton-Draft Environmental Impact Statement: Hazardous Materials and Waste

Dear Mr. Munikawa:

Marin Family Action supports the Navy's Preferred Alternative option for disposal and transfer of Hamilton Field.

The EIS does not state that an asbestos survey was done at Capehart and Hillside housing. Lead abatement is not being required in these units or the soil of the surrounding areas. It is the position of Marin Family Action that a thorough hazardous waste and materials investigation be complete at Hamilton Field prior to a final assessment of the property value.

We insist that a full disclosure be made of any and all known hazardous waste and materials that were ever stored at Hamilton Field not limited to asbestos, lead and DDT. Furthermore, it is our position that the Navy take responsibility for removing these toxins from this environment. A refusal to do so will impact the value of this property and have detrimental long term effects on the residents of Marin County.

O-1

Sincerely,

Debora Faust

Debora Faust
Leadership Group Member

Response to Comments

Response to Comment O-1. The asbestos survey included a random sampling from each housing area at DODHF Novato. Asbestos-containing materials (ACMs) were identified in all housing areas; however, asbestos that was friable was identified only in Spanish Housing. The Navy's policy is that property with ACM will not be disposed of through the BRAC process unless the ACM does not pose a threat to human health at the time of transfer. ACM that is not friable is not considered to pose a health risk and will therefore not be abated. Only ACM that is friable would be repaired or removed prior to transfer.

The Navy is not required by federal law to abate lead-based paint (LBP) hazards in housing constructed between 1960 and 1978. Consistent with Navy policy and federal law, the Navy will disclose the result of its LBP assessment to potential purchasers of housing constructed between 1960 and 1978. The Navy will abate LBP hazards in accordance with federal requirements in housing constructed prior to 1960. Impacts on property value are not considered environmental impacts under the National Environmental Policy Act (NEPA).

Extensive information on past use and storage of hazardous materials is available in the Environmental Baseline Survey (EBS).

Nancy Kubik M.D.
Mark Kubik M.D.
192 Caribe Isle
Novato, CA 94949
February 3, 1997


Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
Attn: Mr. Gary J. Munekawa, Environmental Planning Branch
Code 1852 GM
900 Commodore Drive
San Bruno, CA 94066-5006

Dear Mr. Munekawa:

In reference to 5090.0B, 1852GM/EP7-1190, 30 January 1997, we support the Open Space Alternative for Rafael Village. It is important to maintain and restore creek habitat, especially in California where creeks are often rare and /or seasonal. The creek is an environmental resource not available at Hamilton Field whereas housing and recreational areas can be at either site. Housing can be moved to the Hamilton area and the creekside restored.

P-1

Sincerely,


Mark Kubik M.D.


Nancy Kubik M.D.

Mark Kubik, M.D.
Nancy Kubik, M.D.
Letter P

Response to Comments

Response to Comment P-1. The commenters' preference for the Open Space Alternative is noted. The comment concerning the value of creek habitat and preference that housing and recreational areas not be developed at the Rafael Village site is noted.

Law Offices of
Stuart M. Flashman
5626 Ocean View Drive
Oakland, CA 94618-1533
(510) 652-5373 (voice & FAX)
E-mail - stuflash@aol.com

March 17, 1997

Commanding Officer
Engineering Field Activities West
Naval Facilities Engineering Command
Attn.: Mr. Gary J. Munekawa,
Environmental Planning Branch
Code 1852GM
900 Commodore Drive
San Bruno, CA 94066-5006

RE: DEIS for Disposal and Reuse of former DOD Housing
Facility, Novato, California.

Dear Mr. Munekawa,

These comments on the above-referenced Draft Environmental Impact Statement ("DEIS") are submitted on behalf of the Lanham Village Homeowners' Association, Inc. (LVHOA). They supplement earlier oral comments submitted at the February 27, 1997 public hearing on the DEIS.

As you may be aware, and as acknowledged in the DEIS, Lanham Village is a residential community located directly adjacent to the DOD property that is the subject of the DEIS. Consequently, the residents of Lanham Village, i.e., the members of LVHOA, are keenly concerned about the effects and impacts of the proposed disposal and reuse plan.

LVHOA's comments are primarily directed at the "Open Space Alternative" discussed in the DEIS. In overview, LVHOA believes that the potential impacts of this alternative, particularly in the areas closest to Lanham Village, have been underestimated. LVHOA believes that the open space alternative would result in significant impacts in the area surrounding Lanham Village, and consequently on Lanham Village and its residents.

The remainder of the letter will be devoted to identifying and discussing the potential deficiencies of the DEIS. For ease of reference to the DEIS, the comments will in general follow the order of presentation given in the DEIS.

2. PROPOSED ACTIONS AND ALTERNATIVES

REVISED REUSE PLAN ALTERNATIVE - PREFERRED ALTERNATIVE

Q-1

Exchange Triangle

One of the examples of a specific use under the proposed plan is a "transit center". The title of this use does not clearly indicate what would be entailed in the use. Potential impacts could vary widely, depending on what a "transit center" involved. If it was primarily a transfer point for busses and other public transit, impacts would likely be restricted to noise, traffic and air quality impacts related to vehicles accessing the site. nevertheless, these impacts cannot be assumed to be insignificant without discussion of level of use and analysis of impacts. The level of use should therefore be specified and impacts at that use level analyzed.

If the term "transit center" also includes storage and repair of vehicles, or even the use of the facility as a depot for vehicles, additional impacts could be expected. These include the noise from repair tools and from idling vehicles, air quality impacts from idling vehicles, and water pollution impacts from petroleum products released during idling, storage or repair of vehicles. Given the adjoining (and indeed co-mingled) uses by sensitive receptors (e.g., residential use at Lanham Village and homeless shelter, school children at charter school and childcare facility, elderly people at senior housing facility), special consideration should be given to the potential for significant impacts. Noise and air pollution impacts from idling busses can be expected to be significant and should be mitigated. Mitigation that should be considered includes moving all storage, repair, and bus idling areas off site to areas removed from residential and child use. Particular consideration should be given to the existing maintenance yard area at Rafael Village.

Q-2

OPEN SPACE ALTERNATIVE

The Open Space Alternative proposes to place several potentially incompatible uses in the Commissary and Exchange Triangle Planning Areas. In particular, it proposes to allow corporation yards in both areas. Both areas are adjacent to the Lanham Village residential area. In addition, the planning areas themselves are slated to include uses involving sensitive receptors (see preceding paragraph). Unless the term "corporation yard" is being given a meaning vastly different from its common meaning - i.e., a place where building supplies are stored and heavy equipment is stored and repaired - there would appear to be land use incompatibilities and significant impacts associated with this use. The term "corporation yard" therefore needs to be more clearly defined.

Q-3

3. AFFECTED ENVIRONMENT

Given the prior use of the area as a military facility (albeit a primarily residential one), there are several potentially significant issues that the DEIS fails to fully discuss. 1) pesticides - pesticide use was widespread in the military, particularly from World War II through the beginning of the Vietnam War. In particular, DDT was used extensively to control everything from head lice to cockroaches. It is not unlikely that DDT residues could be widespread throughout the area. The EIS should discuss, based on available records, the prior use history of DDT and other pesticides. In any area where the prior use history suggests possible presence of significant pesticide residue levels, samples should be collected and analyzed. 2) petroleum product residues could be present in the soil at any site where motor vehicles were stored or maintained. Appendix H presents partial data on past hazardous materials history of the project site. Even that partial history identifies several sites within the Commissary Triangle and Exchange Triangle areas with significant contamination. In addition, there appear to be large gaps in the history. Where gaps in the site history cannot be filled, or contamination appears possible based on available history, site sampling should be done to determine whether contamination is present. If contaminants are found, the Navy should commit to full site clean up as mitigation.

Q-4

Heading 3.3.3 - Socioeconomics

The discussion notes that the Novato Unified School District has "expressed interest" in acquiring additional land for school facilities. (Page 3-30.) It is LVHOA's understanding that NUSD has submitted a formal application for land, including the entire Exchange Triangle Parcel. It is LVHOA's understanding that the uses proposed by NUSD for the parcel include a school bus repair/training facility as well as corporation yards. Are these uses included in the uses analyzed in the "Open Space" alternative? If so, the analysis needs to include the noise, air pollution, and toxic waste production impacts that would be associated with such a facility. It should also discuss the compatibility of this use with adjoining residential and other sensitive receptor uses. This will be discussed further below.

Q-5

Heading 3.3.5 - Environmental Justice

The included discussion indicates there are no significant environmental justice issues associated with any of the proposed alternatives. This is incorrect. There is a currently-existing homeless shelter operated by Hamilton Service Center that is currently located on the Commissary Triangle Parcel. In the preferred alternative, this shelter would remain on this parcel. In the open space alternative,

Q-6

this shelter would be moved to the Exchange Triangle. It would be hard to think of a more disadvantaged and politically powerless group than the homeless people who use this shelter. The open space alternative proposes to place corporation yards in close proximity to the shelter. This will result in major impacts on a minority, low income, and politically powerless group. It would be hard to think of a more blatant example of environmental injustice!!

This section must be revised to disclose and discuss the environmental justice issues associated with deciding to locate corporation yards solely in the close proximity of the Hamilton Service Center's homeless shelter! In addition, the revised section should discuss the environmental justice issues associated with locating corporation yards in proximity to Lanham Village, one of the few affordable housing developments in the Novato area, and another group that is economically and politically disadvantaged compared with the average local population.

The discussion of the occurrence of Novato residents living in poverty should also discuss whether any such residents live in proximity to the project area.

4. ENVIRONMENTAL CON SEQUENCES

4.1 LAND USE

Significance Criteria:

The discussion of significance criteria identifies conflict of a proposed use with an established use as a significant impact. However, as becomes apparent when the DEIS considers the potential for conflict with proposed uses, the DEIS does not explain or define what would be considered a conflict. The DEIS should be revised to provide an explanation of what constitutes a land use conflict, including specific criteria by which the existence of a conflict can be objectively determined - e.g., if noise levels for a proposed use, considered cumulatively with other current and projected noise impacts, would result in a cumulative noise level for an existing low density residential area above 60 dB, or would result in an increase over existing and projected noise levels under the no project alternative of over 2 dB.

4.1.2 - Revised Reuse Plan Alternative

Commissary Triangle/Exchange Triangle

For both these areas, the DEIS states that potential land use incompatibility impacts would be insignificant because of

Q-7

Q-7

Q-8

the short duration of demolition/construction impacts. While this may be true if potentially significant impacts are mitigated, it is not automatically true - for example, if hours of demolition/construction are not limited, significant land use conflict impacts on the neighboring Lanham Village residential uses could result from night time demolition or construction activities.

Q-8

The DEIS does not address potential impacts associated with site clean up. Both areas have significant existing site contamination, which will require clean up. Absent adequate mitigation of potential impacts, site clean up could result in significant land use incompatibility impacts with Lanham Village.

Q-9

As to the permanent location of the homeless shelter (Hamilton Service Center) in the Commissary Triangle, the Hamilton Reuse Plan has identified numerous mitigation measures to mitigate potential impacts associated with the HSC. The EIS should commit to implementing these mitigation measures.

Q-10

4.1.3 - Open Space Alternative

Commissary/Exchange Triangle Areas:

The discussion of potential and use conflicts for these two areas demonstrates the inadequacy of the significance criteria used. The discussion asserts, without evidence or foundation, that placement of corporation yards would have no significant land use impacts because, "these uses would be compatible with the surrounding land use." This statement is false! The listed activities in a corporation yard have the potential to generate significant land use incompatibility impacts with uses involving sensitive receptors (e.g., residential use, schools, day care centers, elderly housing). In particular, the existing Lanham Village residential uses would be significantly impacted by having corporation yards located in their vicinities. Expected impacts include noise, air quality, visual, and safety impacts. These will be discussed more specifically below under the individual impacts. The DEIS provides no justification for its conclusory statement that there will be no incompatibility with existing surrounding uses. The evidence points to the contrary! **This section MUST be revised to identify the significant land use incompatibility impact that can be expected to result from locating corporation yards near a residential area!**

Q-11

4.2 - AESTHETIC/SCENIC IMPACTS

OPEN SPACE ALTERNATIVE - COMMISSARY/EXCHANGE TRIANGLE AREAS

Q-12

As above under land use impacts, the DEIS provides insufficient analysis of the potential visual/aesthetic/scenic impacts of allowing corporation yards in these two planning areas. Proposed mitigation is limited to, "increased attention to buffering of uses and landscaping." This will not necessarily fully mitigate significant impacts.

To begin with, landscaping generally takes a significant amount of time to become established. The EIS should discuss how long installed landscaping would take to become effective visual screening, and the significance of the visual impacts prior to that time. Alternatively, any corporation yard uses should only be allowed after the landscaping has been fully installed and grown up.

The Open Space alternative proposes to place a variety of uses in the Exchange Triangle area, including the HSC homeless shelter. In addition, both planning areas border on the Lanham Village residential area. The EIS should explain how buffering and landscaping will mitigate impacts on such potentially adjoining uses, especially when the alternative does not identify where in these planning areas corporation yards would be located.

Q-12

4.3 SOCIOECONOMICS

4.3.1 - Disposal - Environmental Justice

As noted earlier, the conclusory statements that impacts on minority and low-income population will be the same under all alternatives is unwarranted and false. Specifically, the Open Space Alternative, by proposing to place the HSC homeless shelter in the vicinity of corporation yard uses, raises a highly significant environmental justice issue. This is precisely the kind of undue impacts on a highly disadvantaged population that the term environmental justice was coined to identify and condemn! As discussed earlier, there is probably no group in our society less able to protect themselves from environmental abuse than the homeless. To place a homeless care facility in close proximity to the obnoxious industrial uses associated with a corporation yard is a proposal that is totally incompatible with the Navy's avowed policy on environmental justice. The EIS must address this inconsistent stance!

Q-13

Besides impacts on the homeless shelter, the corporation yard uses will also impact on the residents of Lanham Village. While Lanham Village is not as disadvantaged as the homeless community, it is one of the few affordable housing areas in Novato. Consequently, its residents are relatively disadvantaged and should be considered as covered by the Navy's environmental justice policy. Again, under that policy, there

is no justification for placing corporation yards in the vicinity of Lanham Village.

Q-13

4.9 - WATER RESOURCES - OPEN SPACE ALTERNATIVE - COMMISSARY/EXCHANGE TRIANGLE AREAS.

The DEIS fails to consider the potential impacts from the mobilization, in the event of flooding, of toxic or hazardous materials (e.g., pesticides, petroleum products, etc.) that would be stored at corporation yards under this alternative. The impacts should be discussed and mitigation identified.

Q-14

4.10 - TRAFFIC AND CIRCULATION

4.10.2 - Revised Reuse Plan Alternative

Transit Service

The Revised Reuse Plan includes as a proposed use in the Exchange Triangle a "transit center". No further definition is provided. The EIS should explain in more detail what such a transit center would consist of, and how it would operate. If it would involve additional bus use along State Access Road, that use should be factored into traffic counts, as well as noise and air quality analyses. If the results indicate that significant noise, traffic or air quality impacts could result, mitigation must be proposed or the significant impact disclosed and the EIS recirculated for additional comment.

Q-15

4.10.3 - Open Space Alternative

The traffic analysis for the Open Space Alternative does not appear to have included traffic impacts from corporation yard uses in the Exchange and Commissary Triangle Planning Areas. The type of trucks and heavy equipment associated with a corporation yard will have slower than average roadway speed and acceleration. They may therefore decrease calculated LOS for roadways and intersections. The analyses, including LOS calculations, should be revised to show the effects of this traffic. In addition, as for the transit center, noise and air quality impacts associated with the corporation yard vehicle/equipment traffic should be discussed.

Q-16

Q-17

4.11 - AIR QUALITY

4.11.3 - Open Space Alternative

As referenced above, the air quality analysis should include additional air quality impacts from truck and heavy equipment exhaust fumes. This should include not only impacts

Q-18

from vehicles traveling to/from corporation yards, but also during operation on the yard site. It should also include air quality impacts during engine operations associated with repair and testing of equipment.

The NUSD has proposed to operate a bus repair/training facility on the Exchange Triangle site. For any such facility, air quality impacts should be separately analyzed, including impacts from bus operations while being repaired and tested, as well as any expected impacts from busses left idling at the facility.

Q-18

Impacts should be measured at the site and at adjoining areas. This is particularly true for the Exchange Triangle site under the open space alternative because this one area is proposed to contain not only corporation yards, a transit center, and possibly a bus repair facility, but a number of uses with sensitive receptors, including the HSC homeless shelter, an elderly care assisted living facility, and child care facilities. Any specific special air quality requirements (e.g., needs of elderly people suffering from chronic obstructive pulmonary disease) should be considered in determining the significance of air quality impacts.

4.12 - NOISE IMPACTS

Significance Criteria:

The DEIS correctly notes that uses causing noise levels for noise sensitive land uses must be considered significant if the noise level exceeds 60 dB. It is worth noting that many cities consider the maximum acceptable noise level for sensitive uses to be 55 dB, not 60 dB. It should also be noted that sensitive uses, particularly residential uses, are much more sensitive to noise levels in the night time hours. The EIS should consider establishing an additional significance criterion of noise levels exceeding 50dB at a noise sensitive use site during the hours of 10 PM to 7 AM. Alternatively, the EIS should consider establishing a significance criterion for interior noise levels in residential units of 45 dB for those same hours.

Q-19

4.12.2 - Revised Reuse Plan Alternative

The impacts due to demolition/construction on sites adjoining Lanham Village may be insignificant, depending on the length of time involved and what additional litigation (e.g., use of temporary noise barriers) is provided. Merely limiting construction to daytime hours will not necessarily reduce impacts on sensitive residential uses to a level of insignificance. The LVHOA endorses the suggestion that

Q-20

Q-21

additional sound walls be constructed to reduce highway noise impacts in the area.

Q-21

4.12.3 - Open Space Alternative

The analysis of noise impacts is defective in failing to consider or analyze the potentially significant noise impacts associated with the operation of corporation yards, a transit center, or a bus repair facility in either the Exchange Triangle of Commissary Triangle planning areas. Any of these uses will generate significant amounts of noise due to the operation of diesel motors, generators, and other equipment creating excessively loud noises (e.g., pneumatic equipment associated with corporation yards or vehicle repair facilities.)

Q-22

The impact of these noise levels should also take into consideration nearby sensitive noise receptors, including the HSC, proposed elderly assisted living facility, and existing Lanham Village residential area. On its face, it would appear that the establishment of corporation yards or a bus repair facility would result in significant noise impacts on nearby noise sensitive uses. These impacts should be disclosed in the EIS and the document recirculated for comment. Alternatively, those uses generating significant noise impacts should be removed from the project.

4.13 - HAZARDOUS MATERIALS AND WASTE

As discussed earlier, the project site's history as a military base suggests that there may have been significant incidents of soil contamination with toxic materials. Some such instances have been documented in Appendix H. However, the inventory presented there is very incomplete. Sites for which the history is incomplete or where the history suggests the possibility of contamination need to be sampled, tested and, if necessary, decontaminated.

Q-23

While the DEIS acknowledges the presence of asbestos and lead paint residues, it does not discuss the risk that lead or asbestos residues present in the soil (e.g., due to prior demolition activity or paint removal for repainting) will be mobilized into the air or water during demolition or construction activities. This risk should be evaluated and appropriate mitigation (e.g., watering down site when dust could be produced and then collecting the water run-off from the site for disposal) should be proposed.

Q-24

SAFETY IMPACTS

Mr. Gary Munekawa
03/17/97 3:14 PM
Page 10

The DEIS fails to provide any discussion of potential adverse impacts of the project or alternatives on public safety. The LVHOA would like to note two areas of concern.


First is the issue of pedestrian safety. Both the Revised Reuse Plan Alternative and the Open Space Alternative will substantially increase vehicular traffic within the project area. There will be an additional cumulative traffic increase due to completion of the already approved new Hamilton Partnership project. As a result of the traffic increases, the hazard involved to pedestrians attempting to cross the major roadways in the project area will be substantially increased. The DEIS proposes to add several traffic signals. All traffic signals should have a pedestrian crossing button. In addition, the EIS should add as an additional mitigation measure placing pedestrian activated signals at major pedestrian crossing points across major arterials on the project site.

Secondly, the Open Space Alternative proposes to place corporation yards in the Exchange Triangle and/or Commissary Triangle Planning Areas. Such corporation yards are likely to be attractive nuisances for children living nearby. The EIS should discuss this safety impact and either propose feasible mitigation measures or identify it as a significant project impact.

CONCLUSION

The LVHOA generally supports the Revised Reuse Plan Alternative as the least environmentally damaging practicable alternative for disposal/reuse of the site. The LVHOA believes that the DEIS does not fully disclose the significant environmental and environmental justice impacts of the proposed open space alternative. Before any action is taken to consider approving this alternative, LVHOA believes the EIS needs to be extensively revised and recirculated. Thank you for allowing this comment on the DEIS. Please provide us with a copy of the final or revised EIS.

Most sincerely,


Stuart M. Flashman

Q-25

Q-26

Q-27

Response to Comments

Response to Comment Q-1. The comment that the Lanham Village Homeowners Association believes implementation of the Open Space Alternative would result in significant impacts that were underestimated in the EIS is noted. Responses to the following comments provide specific information in response to specific concerns of the commenter.

Response to Comment Q-2. One of the specific uses identified in the EIS for the Exchange Triangle planning area under the Revised Reuse Plan alternative is a transit center. "Transit center" refers to a park and ride lot proposed for future development on New Hamilton Partnership property. The transit center would provide parking and bus service. The effects of a potential transit center are included in the traffic analysis and in the resulting air quality and noise analyses performed for the cumulative impacts section of the EIS.

The only other transit-oriented use of the site would be the Novato Unified School District (NUSD) request for a public benefit transfer of Building 972 for use as a Vehicle Maintenance Shop (NUSD 1996). As described in the public benefit transfer application and through subsequent confirmation with NUSD, the old "Vehicle Maintenance Building" (Building 972) would be renovated to house the NUSD automotive training program, the Marin Conservation Corps construction training class, and the County Regional Occupational Program auto training class. As described by the NUSD, this new facility would be used for educational purposes only. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. It is envisioned that in addition to the district's fleet of 39 buses and 31 other vehicles, educational maintenance opportunities could be expanded to other districts and agencies. It is envisioned that a maximum of three to four buses would be located on the site at any given time. Repairs would occur inside the building. The NUSD vehicle maintenance would be a continuation of the previous Navy use of Building 972. The district estimates that \$1.5 million would be spent to renovate the facility, and although specific plans have not been developed, the facility would have to comply with all applicable health and safety regulations regarding reduction of noise and air contaminants. The impacts from these proposed uses are included in the analysis of noise and air quality impacts and are not expected to be significant, as described in the EIS. Because no significant impacts have been identified, no mitigations would be required.

Daily dispatch, operation, and routine maintenance such as oil changes, washing, fueling, and daily parking and staging of buses would continue to operate from the NUSD's 809 Olive Avenue location.

The Hamilton Army Airfield (HAAF) Revised Reuse Plan Alternative prohibits use of the Exchange Triangle area as a corporation yard or bus dispatch facility.

Response to Comment Q-3. As noted in the comment, the Open Space Alternative would allow development of a corporation yard in the Exchange Triangle or the Commissary Triangle planning areas. It is assumed in the EIS analysis that both sites would not be used simultaneously for corporation yards. Although no specific plans have been put forward by any entity for development of a corporation yard on either of these sites, the analysis of potential impacts from a corporation yard is based on the following theoretical description that incorporates the elements that would be expected if a bus fleet were to be based at the site. It should be emphasized that because no specific plans have been proposed for this theoretical corporation yard, no specific locations for the various facilities have been identified. For the theoretical analysis carried through the EIS, a corporation yard was defined as having the following elements:

- Parking space for 40 to 50 class I and II buses
- Parking space for 40 other vehicles, including pick-up trucks, vans, and tractors
- Parking for the personal vehicles of 75 employees
- Light maintenance facility for oil changes, tune ups, tire changes, etc.
- Facility for heavy maintenance, such as engine or transmission overhauls
- Vehicle fueling station
- Vehicle wash station
- Warehouse space for storage of materials and equipment
- Fencing for security, aesthetics, and sound buffering
- Office facilities

With regard to land use compatibility between surrounding uses and uses allowed under the Open Space Alternative, several factors should be noted. Land use incompatibility is not strictly defined. Land Use Policy 5 of Novato's General Plan states that land use compatibility of specific development is to be determined by the appropriate City authority based on appearance, use characteristics, and proximity. Compatibility issues can arise from visual conflict, interference with established use, and negative physical impacts. With regard to a corporation yard, physical impacts that were considered in determining land use compatibility were air quality, noise, traffic, visual conflict, and hazardous materials. The specific impacts from these potential physical impacts are addressed throughout the EIS analysis and in subsequent responses to comments.

Since only one of the planning area sites would include a corporation yard, other permitted community facilities that include sensitive receptors, such as a homeless shelter, schools, libraries, senior housing, and child care, would be assumed to be located away from the corporation yard, either at the other planning area or at the opposite end of the same planning area. For example, educational facilities or housing facilities housed in the former Navy Exchange building could easily be located over 400 feet from a corporation yard on the southeast portion of the Exchange Triangle or the northern part of the Commissary Triangle. Corporation yard facilities could be located in the northern portion of that planning area, approximately 250 feet from the nearest residence in Lanham Village.

In the Exchange Triangle, all or most of the facilities could be located east of C Street, which is over 300 feet from the nearest residence within Lanham Village. It is expected that all or most of the buildings in this part of the site would be demolished, which would provide an open site that could be designed to buffer and shield a corporation yard from surrounding land uses with appropriate sound walls and landscaping. Sound walls would likely be from six to eight feet tall and also would provide visual screening from adjacent land uses and roadways.

One additional factor should be considered when discussing compatibility of potential land uses in these planning areas. Although a number of uses are described in the Open Space Alternative as being allowed under the category of community facility and civic uses, it is highly unlikely that all of the potential uses would occur. These are merely the categories of land use that the City will consider for the site.

Response to Comment Q-4. As required under the Community Environmental Response Facilitation Act (CERFA), the Navy has developed extensive information on past hazardous materials use and storage, including any past use of pesticides and petroleum products, at DODHF Novato. This information is compiled in the Environmental Baseline Survey (EBS). An extensive archival search begins the EBS process and any potential areas of concerns are investigated further. Sampling has been conducted at potential areas of concern, and treatment of areas of concern require concurrence by regulatory agencies prior to transfer. For more detailed information regarding hazardous materials and waste, the commenter is referred to the EBS and BRAC Cleanup Plan. The Navy is committed to remediation of contamination at DODHF Novato consistent with applicable federal and state regulations prior to disposal and reuse of the property.

Because an EIS is intended to focus on analysis and not be encyclopedic, by necessity, the extensive information on hazardous materials is summarized in the EIS and its appendices, and the more detailed

information is referenced in the EBS. The EIS finds that there will be no significant hazardous material or waste impacts resulting from disposal and reuse of the DODHF Novato property.

Response to Comment Q-5. The Novato Unified School District submitted a request for public benefit transfer of surplus property on May 31, 1996. The property request included 21 of the 26 acres within the Exchange Triangle planning area. As noted in the comments, the request includes establishment of a vehicle repair/training facility to be housed in Building 972. The facility would be renovated to house the NUSD automotive training program, the Marin Conservation Corps construction training class, and the County Regional Occupational Program auto training class. As described by the NUSD, this new facility would be used for educational purposes only. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. See Response to Comment Q-2 for additional discussion. However, no corporation yard is proposed in the NUSD request and the HAAF Reuse Plan does not include a corporation yard in this area. Proposed uses included in the NUSD request are analyzed in the EIS under the Revised Reuse Plan Alternative. A hypothetical corporation yard is analyzed in the Open Space Alternative. It should be noted that this hypothetical corporation yard, although based on a school district bus operation, is not proposed by the NUSD. See Response to Comment Q-3 for more discussion of land use compatibility issues. Subsequent comments address specific potential impacts from noise, air pollution, and hazardous waste production.

Response to Comment Q-6. The discussion under the heading Environmental Justice in Section 3.3.5 discusses the intent of the Executive Order and describes the demographic characteristics of the City of Novato as a basis for analysis of environmental justice issues in Sections 4.3 and 5.6. Under Environmental Protection Agency (USEPA) guidelines for analysis of environmental justice issues, two factors must be present for significant environmental justice impacts to occur.

First, there must be a low-income or minority population as defined by the Bureau of Census. The residents of the proposed homeless shelter would qualify as a low-income population, which is defined as a majority of the population falling below the poverty threshold. For the residents of Lanham Village, an examination of data for Census Tract 1050 reveals that although Lanham Village residents have lower incomes than the Marin County average, they do not qualify as a low income or minority population. Even if individual residents of the Lanham Village neighborhood fall below the poverty line (which is not possible to determine from census data), the neighborhood's "population" does not qualify as a low-income or minority population.

The second factor to consider in determining any disproportionate environmental impacts is whether any unmitigable significant impacts would occur, as defined by the EIS significance criteria. In other words, for an impact to have a disproportionate effect, there has to be a significant project-related impact that cannot be mitigated to a not significant level. As discussed in the EIS, a corporation yard has not been found to have significant and unmitigable impacts. If a corporation yard were established in either of these two planning areas, it could be located within the parcel to be more than 200 feet away from either Lanham Village or other sensitive land uses, such as the Hamilton Service Center. No significant and unmitigable impacts are identified that would disproportionately impact Hamilton Service Center residents. It should be noted that ozone precursor emissions do not have a local air quality impact but affect regional air quality.

Response to Comment Q-7. As discussed in Response to Comment Q-3, land use compatibility is based on Land Use Policy 5 of Novato's General Plan, which states that land use compatibility of a specific development is to be determined by the appropriate City authority based on appearance, use characteristics, and proximity. Compatibility issues can arise from visual conflict, interference with established use, and negative physical impacts. Physical impacts that were considered in determining land use compatibility were noise, air quality, traffic, visual conflict, and hazardous materials. The specific impacts from these potential physical impacts are addressed throughout the EIS analysis and in subsequent responses to comments. A determination of land use compatibility considers each of the physical impacts listed above, but specific criteria for determination of physical impacts are included in each appropriate section of Chapter 4. For example, significance criteria for noise impacts are defined in Section 4.12 as exposing noise sensitive land uses to ambient noise levels higher than 60 dB. The commenter also is referenced to additional criteria on the same page that discuss impacts from project-related noise level increases.

Response to Comment Q-8. As discussed in Response to Comment Q-7, land use compatibility is based in part on specific analysis of physical impacts, which are analyzed in various sections of Chapter 4 of the EIS. The commenter is referred to Section 4.12.2, Mitigation 1, which proposes mitigation for noise-related impacts related to demolition and construction impacts in the Commissary Triangle and the Exchange Triangle by limiting the use of heavy equipment and power tools to the hours of 7 AM to 7 PM.

Response to Comment Q-9. As discussed in Response to Comment Q-7, land use compatibility is based in part on specific analysis of physical impacts, which are analyzed in various sections of Chapter 4 of the EIS. As discussed in Response to Comment Q-4, the Navy has identified areas of the base that

are contaminated or potentially contaminated with hazardous materials, including the Commissary Triangle and the Exchange Triangle. The Navy is committed to remediation of contamination at DODHF Novato consistent with applicable federal and state regulations prior to transfer and reuse of the property. Because all property will be remediated prior to transfer, there would be no hazardous material impacts that would result in land use incompatibility.

Response to Comment Q-10. The Hamilton Reuse Plan does not propose formal mitigation measures such as an environmental document would, but does contain various goals and guidelines regarding the establishment of the Hamilton Service Center. As these goals and guidelines are part of the Revised Reuse Plan, they also are included as part of the Revised Reuse Plan Alternative. The City of Novato or future site developer, and not the Navy, would be responsible for implementing mitigation measures associated with reuse impacts.

Response to Comment Q-11. As discussed in Response to Comment Q-3, land use compatibility is based on Land Use Policy 5 of Novato's General Plan that states that land use compatibility of specific development is to be determined by the appropriate City authority based on appearance, use characteristics, and proximity. Compatibility issues can arise from visual conflict, interference with established use, and negative physical impacts. With regard to a corporation yard, physical impacts that were considered in determining land use compatibility were air quality, noise, traffic, visual conflict, and hazardous materials. The specific impacts from these potential physical impacts are addressed throughout the EIS analysis and in subsequent responses to comments.

Response to Comment Q-12. As discussed in Response to Comment Q-3, no specific plan for a corporation yard has been proposed, so no specific location for a theoretical corporation yard within the two planning areas is identified. This would allow flexibility for the actual siting of a corporation yard within the 41 acres contained within the two sites, especially given that only one corporation yard would be allowed within the two sites. Flexibility in siting would allow buffering from adjacent land uses as called for in the EIS. Potential visual aspects associated with the theoretical corporation yard would be a large parking lot filled with up to 50 buses and 115 other vehicles. The largest visual features would be a vehicle maintenance building, which could be, but would not have to be, Building 972. Other visual features would be a vehicle wash station, office facilities, storage buildings, security fencing, sound walls, and landscaping.

As discussed in EIS Section 4.2, Planning Issues, subsequent design review by the City during the California Environmental Quality Act (CEQA) process for a specific development proposal would

provide specific mitigation measures related to design and staging of landscape installation. If the time to establish vegetation were an issue, mitigation measures for a specific development proposal could specify that landscaping consist of primarily mature landscape plants that would provide immediate screening benefits. It is likely that specific mitigations to screen a corporation yard from surrounding roadways or land uses would include a combination of landscaping and fences.

Response to Comment Q-13. The issue of environmental justice as it relates to the Open Space Alternative is discussed in Response to Comment Q-6.

Response to Comment Q-14. As stated in EIS Section 4.9, Planning Issues, development in mapped flood areas in the Commissary Triangle and Exchange Triangle would need to be raised or otherwise protected from flood hazards in order to comply with city and county policies and standards. Additionally, state and local hazardous materials regulations generally require that hazardous materials be stored within secondary containment and with other protection to reduce the risk of releases. If these regulations are followed, the potential impact of hazardous materials releases from corporation yards is not significantly greater than from other land uses.

Response to Comment Q-15. As described in Response to Comment Q-2, one of the specific uses identified in the EIS for the Exchange Triangle planning area under the Revised Reuse Plan alternative is a transit center. "Transit center" refers to a park and ride lot proposed at a future time on New Hamilton Partnership property. The transit center would provide parking and bus service. The effects of a potential transit center are included in the traffic analysis and in the resulting air quality and noise analyses performed for the cumulative impacts section of the EIS.

Response to Comment Q-16. The traffic analysis for the Open Space Alternative does include an analysis of the heavy vehicle trips that would be generated by a corporation yard as defined in Response to Comment Q-3. Since these vehicle trips are included in the traffic analysis, including LOS calculations, no revision of this analysis is needed.

Response to Comment Q-17. As discussed in Response to Comment Q-16, vehicle trip generation associated with operation of a corporation yard in the Commissary Triangle or Exchange Triangle is included in the traffic analysis and is therefore included in the analysis of traffic-related noise and air quality impacts.

Response to Comment Q-18. The air quality dispersion modeling analysis results presented in Section 4.11 of the Draft EIS already assume the vehicle volumes calculated to occur with operation of a corporation yard. It is assumed that 2.59 percent of the traffic on surface streets and 9.79 percent of the traffic on Highway 101 would be heavy duty vehicles. The modeling analysis shows no air quality problems at any of the modeled intersections. This includes Nave Drive at Bel Marin Keys Boulevard, where the surface street traffic was modeled as including 70 to 90 heavy duty vehicles during the afternoon per hour. In addition to the heavy duty vehicle traffic, there would be 2,000 to 3,000 passenger vehicles during the afternoon per hour on these roadways. The modeling analysis also assumed that idling delays at this intersection would average 40 to 50 seconds per vehicle.

The modeling analysis was conducted for locations 75 feet from roadway centerlines (about 50 feet from the closest traffic lane). If locations with these high traffic volumes have no air quality problems, then the much lower traffic volumes on State Access Road would not generate any air quality problems. Similarly, a few trucks or buses moving or idling on-site at any one time would have no potential for causing localized air quality problems.

With regard to the potential air quality impacts associated with operation of the NUSD's proposed vehicle training facility, as described in Response to Comment Q-3, the proposed facility would not serve as a routine maintenance facility. Only repairs that provide educational opportunities for student mechanics would be performed there. The NUSD estimates that approximately three to four vehicles would be at the facility at any given time. Since vehicles would be serviced inside the facility, all applicable regulations regarding ventilation and air filtration would be observed. The NUSD proposes \$1.5 million in renovation to the building, which would presumably include installation of appropriate ventilation and noise controls. Overall, the use of Building 972 would be similar to historic Navy use of the building as a vehicle maintenance shop.

As described in Response to Comment Q-3, it is unlikely that all of the permitted land uses would occur on the site, as the list of permitted uses under each alternative is merely the uses that the City could consider under specific development plans. Because no locations for specific development have been proposed within the 41 acres contained in the two subject planning areas, it is likely that any sensitive land uses would be strategically sited so as to be separated somewhat from a corporation yard.

Response to Comment Q-19. The City of Novato has adopted a community noise equivalent level (CNEL) value of 60 dB as the land use compatibility threshold for noise-sensitive land uses. This is consistent with common practice in urban areas throughout California.

The CNEL measure adds an additional 10 dB "penalty" for nighttime noises and a 5 dB "penalty" for evening period noise to the CNEL noise averages to reflect the increased intrusiveness of evening and nighttime noise. In other words, the standard is stricter during evening hours by 5 dB and during nighttime hours by 10 dB. Therefore, no special impact significance criteria are needed for nighttime noise from reasonably continuous noise sources (i.e., traffic) or from sources that operate primarily during daytime periods (construction activity, corporation yards, etc.).

Normal building construction will provide about 20-25 dB of attenuation for outside noise levels. Thus, an outdoor CNEL of 60 dB indicates an indoor increment of 40 dB or less.

Response to Comment Q-20. Available information does not indicate the need for an extended period of demolition and construction activity near Lanham Village. Most building demolition would occur at locations more than 400 feet from Lanham Village, but three small buildings near the property line are scheduled for demolition. Demolition activity for these buildings is unlikely to last much more than one week, with most of the time devoted to cleanup and removal of demolition debris. Actual building demolition would probably be accomplished by gutting the interior of structures and pushing them down with a bulldozer and would last about one day. Noise levels would be comparable to typical residential construction activity noise.

Response to Comment Q-21. The commenter's endorsement of additional sound walls to reduce highway noise is noted.

Response to Comment Q-22. As discussed in Response to Comment Q-3, the referenced transit center is a park and ride lot proposed at a future time on New Hamilton Partnership property. The transit center would provide parking and bus service. The effects of a potential transit center are included in the traffic analysis and in the resulting air quality and noise analyses performed for the cumulative impacts section of the EIS. Specific site proposals for the various permitted uses in these two planning areas have not been developed. It is also likely that not all of the allowed uses would be developed. Consequently, the EIS has addressed issues at a general plan level of detail. Impacts requiring analysis at a site design level of detail will be evaluated in subsequent, project-specific CEQA documents.

In general, however, it should be noted that vehicle repair activity associated with a corporation yard would take place inside a building rather than outdoors. This would substantially reduce noise levels at

adjacent properties. During subsequent project-specific analysis, the following mitigation measures should be considered when developing plans for corporation yard and bus repair facilities:

- Provide for acoustical insulation when renovating buildings that will be used for vehicle repair activities.
- Provide sufficient building ventilation when renovating buildings that will be used for vehicle repair activities so that repair activities can be conducted with doors closed.
- Consider providing a six- to eight-foot high masonry wall along property lines that border residential or other noise-sensitive land uses. Such a wall would serve both as a soundwall and as a site security measure, while also reducing aesthetic impacts on adjacent properties.

Response to Comment Q-23. As discussed in Response to Comment Q-4, extensive information on past hazardous materials use and storage is provided in the Environmental Baseline Survey (EBS). The BRAC Cleanup Plan (BCP) includes a plan for sampling in areas where the site history indicates a possibility of contamination. The Navy has developed extensive information on past hazardous materials use and storage at DODHF Novato. Because an EIS is intended to focus on analysis and not be encyclopedic, by necessity, the extensive information on hazardous materials is summarized in the EIS and its appendices, and the more detailed information is referenced. For more detailed information regarding hazardous materials and waste, the commenter is referred to the EBS and BCP. The Navy is committed to remediation of contamination at DODHF Novato consistent with applicable federal and state regulations prior to transfer and reuse of the property.

Response to Comment Q-24. The USEPA and the Bay Area Air Quality Management District (BAAQMD) have strict regulations regarding emissions of airborne asbestos. Regulations for handling materials containing asbestos and lead-based paint are designed to avoid any significant airborne releases of asbestos containing materials or lead dust. Normal procedures require removal of asbestos containing materials prior to any bulldozing of structures. Thus, there would be no significant health risk assuming demolition and waste handling activities are conducted in compliance with existing regulations. Dust control is discussed in Section 4.11.

Response to Comment Q-25. As discussed in Section 4.10.2, the Revised Reuse Plan Alternative calls for construction of continuous, connective, and safe pedestrian and bicycle facilities throughout the project area. Since few areas in the project site have well-developed pedestrian facilities, this would be considered a beneficial effect of the project. Specific development plans, when proposed, would need to

include pedestrian safety features such as pedestrian operable traffic crossing lights in order to be consistent with the Revised Reuse Plan.

Response to Comment Q-26. Although no specific proposal for a corporation yard has been proposed, the analysis in the EIS assumes that a corporation yard would be fenced for purposes of aesthetics, sound buffering, and security. Corporation yards are generally controlled access areas and standard security measures would be expected to prevent entry of the site by children and provide a reasonable level of safety to area residents, including children.

Response to Comment Q-27. The commenter's general support of the Revised Reuse Plan Alternative as the least environmentally damaging reuse for the site is noted. As discussed and demonstrated in the responses to specific comments within this comment letter, the EIS adequately discusses potential significant impacts that would occur from implementation of the Open Space Alternative. The responses to the comments in this letter serve to clarify and amplify the information contained in the Draft EIS, but no new impacts or mitigations are identified. There would be no significant unmitigable environmental impacts associated with the Open Space Alternative that were not disclosed in the Draft EIS. Additionally, there would be no significant environmental impacts that would disproportionately affect low-income or minority populations. Sufficient information on environmental impacts is provided in this EIS for the Navy to consider environmental impacts in its Record of Decision. Therefore, no extensive revision and recirculation of the EIS is required.

My name is Andrea Kiesel and I am owner of Little Village School. Little Village School is located in Lanham Village. We are a small preschool with the children of 50 families enrolled and we are open from 7am to 6pm.

We have serious concerns about what is happening to the area surrounding our school. We have obtained a copy of the proposed use of the 21 acres to the rear of Lanham Village. There are two parts of the proposal that are of concern to us.

1. Storage and Vehicle maintenance
2. Vocational, technical, trade schools

Building 972 is directly adjacent to the open space lawn area and the school playground that our children use. We feel that the use of this building as proposed would cause excessive noise and compromise the air quality of the area which is an area used daily by the children not only of the school but also of the community. The noise and fumes, the comings and goings of the number of vehicles housed there, not to mention noise and fumes from the repairs would be intrusive to a residential community. The waste from said maintenance would be detrimental to the children, the staff, the families and to the environment.

Having the ROP Program for automotive training also on that site increases the amount of noise, waste and fumes.

I have brought some photos for you to examine that demonstrate the close proximity of this facility to our school. We are opposed to the location of this facility and urge you to find another location for it.

Thank You For Your Time

R-1



Building 972 from the Playground of Little Village School





Andrea Kiesel
Little Village School
Letter R

Response to Comments

Response to Comment R-1. The commenter's concerns are addressed in Response to Comments Q-2 (proposed activities), Q-18, Q-22, and Q-14 (effects on air quality, noise, and hazardous materials and waste).

To Whom it May Concern,

We are opposed to the school bus maintenance facility being set up right behind Lanham Village. My husband and I did not buy a house here for you or anyone else to destroy our surroundings. We have three children who will grow up here and we want to keep it a peaceful and beautiful place for them. We love where we are and want to keep it as is. We don't want to have to worry about extra traffic coming through our streets. There are enough worries as is. We are opposed to some of the commercial building we hear that people want to build at Hamilton Field. Please reconsider where you want to put the school bus maintenance facility, like down by the hangers or some other unoccupied area.

S-1

Thank you for your attention on this matter.

William S. Graddock
Debra A. Graddock
37 Lovejoy Way
Novato, CA

Response to Comments

Response to Comment S-1. The commenters' objections to a school bus maintenance facility are noted.

February 27, 1997

To the U.S. Navy,

I am a resident of Lanham Village and am **STRONGLY OPPOSED** to development option #2: the Open Space Option. I do not want to be subjected to any further noise, pollution and traffic that this proposed commercial/industrial development would produce.

The back of my unit faces the Exchange Triangle. Just outside my patio is a beautiful field that is used by the families and guests of Lanham for picnics and parties. Also, it is an area for neighbors to socialize while running their dogs. **WE WILL NOT TOLERATE THE PROPOSED PLAN FOR A MECHANICS YARD FOR NOVATO'S SCHOOL BUSES IN OUR BACKYARD. THE DIESEL FUMES ALONE FROM THE BUSES ARE TOXIC. NOR DO WE WANT TO DRIVE INTO OUR COMMUNITY AND VIEW AN INDUSTRIAL YARD IN THE PROPOSED COMMISSARY LOCATION.**

WE AS A COMMUNITY HAVE SACRIFICED OUR STANDARD OF LIVING MORE THAN TWICE NOW WITH THE DEVELOPMENT OF A PERMANENT HOMELESS SHELTER AND THE DEVELOPMENT OF 1,000 HOMES THAT WILL BRING APPROXIMATELY 2,000-3,000 CARS DRIVING PAST OUR COMMUNITY DAILY. THESE DEVELOPMENTS ALONE WILL CREATE MORE NOISE, POLLUTION, TRAFFIC AND SECURITY ISSUES FOR ALL OF US. NOW YOU WANT US TO BE SUBJECTED TO MORE OF THE SAME. ENOUGH IS ENOUGH ... OUR PROPERTY VALUES WILL BE TAKING A HARD HIT WITH THE HOMELESS SHELTER AND WILL ONLY GET WORSE WITH BUS YARDS AND COMMERCIAL DEVELOPMENTS SURROUNDING US.

I ASK THAT YOU FIND A BETTER WAY TO USE THIS LAND, ONE THAT IS NOT HAZARDOUS OR NOISY TO IT'S SURROUNDING RESIDENTS. WOULD YOU TOLERATE THESE PROPOSED DEVELOPMENTS IN YOUR NEIGHBORHOOD ????????

Sincerely,



Susan Bricarelli
64 Martin Dr.
Novato, CA 94949

Response to Comments

Response to Comment T-1. The commenter's objection to development under the Open Space Alternative is noted. The commenter is referred to the Response to Comment Q-2 for clarification regarding activities proposed under the Novato Unified School District's (NUSD's) proposed vehicle repair training facility. Effects from traffic, noise, and air pollution are further clarified in Response to Comments Q-16 through Q-22. The existing traffic analysis, and subsequent air and noise analyses, take into consideration a level of heavy truck traffic that encompasses vehicular activity resulting from a corporation yard or a bus repair facility. In addition, as noted in Response to Comment Q-2 vehicles would be serviced inside Building 927, which would be renovated. Renovation presumably would include installation of appropriate ventilation and noise controls.

March 4, 1997

Engineering Field Activity West
Naval Facilities Engineering Command
900 Commodore Drive
San Bruno, Ca 94066-5006

Attn: Gary Munekawa (Code 1852GM)

Subject: Draft Environmental Impact Statement on Disposal and Reuse of Department of
Defence Housing Facility, Novato, Ca.

Gentleman:

We wish to register our family opposition to not allow the bus repair training facility or the corporation yard to be placed in the proposed area per the draft EIP. Every member of my family is of voting age and have affixed their signature below. We all reside at 104 Martin Drive.

Lanham Village is a COMMUNITY SPIRITED NEIGHBORHOOD comprised of 154 families. Where else in Novato does a community select a "homeowner of the year" award, put out a monthly newsletter and has annual events such as picnics, community yard sale, Halloween party, Easter Egg Hunt, Holiday Cookie Exchange, Holiday Lighting prizes, etc, etc. Our community is blessed with a Day Care Center and a Community Garden. Our family was one of the first residents at Lanham Village, donating time to dig post holes for the playgrounds and the par course before we moved here thirteen years ago. I, Diane Kay, was on the first Board of Directors for the both the Lanham Village Homeowners Association and the Lanham Village Day Care Center.


Both the Community Day Care Center and the Community Garden are located behind the fence of the proposed corporation yard/bus repair training area. What on earth are you thinking of? This is our children you are refusing to consider--- our greatest resource!!!! The food grown in the Community Garden will also suffer the consequences of having the proposed corporation yard/bus repair training area located behind the fence. This area is also therapy and social to our young families and seniors alike.

PLEASE REMOVE THE PROPOSED CORPORATION YARD/BUS REPAIR TRAINING CENTER FROM THIS AREA ON YOUR DRAFT REPORT.

We welcome you to visit our neighborhood to meet our neighbors and see for yourself what a unique community we are.

Your consideration would be appreciated.

Sincerely,


Diane Kay, Kristopher Kay, Craig Kay and Jennifer Surprise
104 Martin Drive
Novato, CA 9494
Day - 415-391-4321 - (Diane)
Evenings - 415-883-7827

Response to Comments

Response to Comment U-1. The commenters' objection to a school bus maintenance facility and corporation yard is noted. The corporation yard evaluated in the EIS is theoretical in nature. No specific proposals for such a use have been proposed, nor is such a use endorsed in the Reuse Plan. The commenter is referred to the Response to Comment Q-2 for a description of the Novato Unified School District (NUSD) proposed bus repair training facility.

The effects of a corporation yard or bus repair training facility on air quality are discussed in Response to Comment Q-18. As stated in this response, repair activities would occur indoors. Vehicle exhaust and other emissions would be vented out through the building and would include any required pollution control devices. The use of Building 972 would be similar to historic Navy use of the building as a vehicle maintenance shop.

CATHY SHINCLAIR
69 MARTIN DRIVE
NOVATO, CA 94949
TEL: (415) 382-1029
FAX: (415) 883-2831

Letter V

March 17, 1997

Mr. Gary Munekawa
Environmental Planning Branch
Naval Facilities Engineering Command

VIA FAX: 244-3737

RE: DoDHF, Novato Proposal

Dear Mr. Munekawa:


As a parent and resident of Lanham Village, I am quite distressed to learn of the possible implementation of the "Exchange Triangle" as a school bus maintenance yard.

I am more than happy to have the Novato School District take over this parcel, but the use as a school bus yard is, in my mind, quite out of the question as a suitable use. We live less than a block (as the crow flies) from the site, and it is very distressing to think that our quiet neighborhood will be impacted by bus engines at all hours. Even more distressing is the possibility that our children here in Lanham Village (of which there are many) will be breathing the unhealthy air being produced by the bus yard.

My son currently attends Novato Charter School. The Charter School is looking for a long-term, stable site for the school. I would be delighted to have the Exchange as their new home. This is a very reasonable, sensible use for the land. I am more than confident that the Novato School District would be able to find many, many uses for the parcel in question that did not involve the pollution (both noise and air quality) of the very wonderful, quiet, nurturing neighborhood where we are raising our children.

Thank you very much for your consideration of this letter.

Sincerely,


Cathy Sinclair
Jack Nancarrow
and Robbie Nancarrow, 5 years old

ROBBIE

Response to Comments

Response to Comment V-1. The commenters' objections to a school bus maintenance yard are noted. The Response to Comment Q-2 clarifies the activities that would be expected to occur under the Novato Unified School District (NUSD) proposal. The proposed facility would not serve as a routine maintenance facility; only repairs that provide educational opportunities for student mechanics would be performed there. Vehicles would be serviced inside the facility. The NUSD proposes \$1.5 million in renovation to the building, which would presumably include installation of appropriate ventilation and noise controls.

Letter W

March 17, 1997

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
Attn: Mr. Gary J. Munekawa, Environmental Planning Branch
Code 1852GM
900 Commodore Drive
San Bruno, CA 94066-5006

Dear Mr. Munekawa:

I am a resident of Lanham Village, the small condominium homeowners association situated at the periphery of DODHF Novato. I am writing to let you know that my neighbors and I do not want noise or pollution generating uses allowed in either the Commissary or Exchange Triangle parcels of the Hamilton Base. Both parcels are directly adjacent to our homes.

W-1

I read through the EIS. I noticed that Option 2, the open space plan, explicitly allows for corporation yards in either or both of these areas. I also noticed that while Option 1, the preferred reuse plan, did not include corporation yards per se, it made no reference to keeping noise and pollution generating uses out of these areas.

W-2

Additionally, I have a copy of the Novato Unified School District's application for Public Benefit Transfer of Surplus Federal Property. As a homeowner with a house 50 feet from the Exchange Triangle I can accept everything in their proposal, *except* their intention to create a massive automotive repair, maintenance, and training facility in Building 972. The application clearly states that this facility would be used to service 39 school buses and 31 vehicles, and will allow the district to expand its maintenance service to other districts and agencies due to its immense capacity. This is clearly a use which is incompatible with a daycare and homes literally on the other side of the fence.

Many have leveled the criticism that Lanham residents are nay-sayers. We are not. We have on numerous occasions given feedback on the types of uses we can live next to. A brief list of uses residents supported in our last community survey includes: senior care and senior housing facilities, childcare and preschool facilities, school district facilities that do not generate noise and pollution, office buildings, library facilities, quality retail businesses, a community park, community meeting facility, and residential homes.

W-3

You will notice that about the only thing we can't live with are any noise or pollution generating commercial or industrial uses such as corporation yards, vehicle maintenance facilities, machine shops, bus parking lots, transit centers, etc.

Many have also pointed out that this area currently houses commercial and industrial facilities. While that may be true, I point out that just because these were once placed here doesn't mean that it was ever appropriate. I also point out that the Military *has not used*

these facilities in any full capacity for many, many years. Who ever moves into this area in the future will occupy and use it.

W-3

The EIS states that there will be no significant long term environmental impacts of the development options proposed. The preferred reuse plan seems to best represent this conclusion, providing the City does not allow any noise or pollution generating uses that would negatively impact our neighborhood. The open space option would clearly allow noise, pollution, and traffic generating uses to be placed next to us that would have a permanent negative impact our community. As for the Public Benefit Transfer property, our community needs to know where we can direct our concerns, and whether the City has any control over the public benefit uses once they are approved? The massive vehicle maintenance facility the Novato Unified School District has planned is a direct threat to our health, the quality of life in our community, and the value of our homes.

W-4

W-5

Thank you for your time,

Jen Rusk
81 Martin Dr.
Novato, CA 94949

Response to Comments

Response to Comment W-1. The commenter's objections to noise or pollution generating uses are noted.

Response to Comment W-2. As described in Chapter 2 of the EIS, and in conformance to the reuse plan, community facility and civic uses would be permitted in the Exchange Triangle and Commissary Triangle planning areas. The EIS evaluates the effects of these types of uses at a general plan level of analysis. Water, air, and noise pollution issues associated with this alternative are addressed in Sections 4.9, 4.11, and 4.12, respectively.

Response to Comment W-3. The commenter's objection to a bus repair facility is noted. The activities that would occur at the Novato Unified School District (NUSD) bus repair training facility are clarified in Response to Comment Q-2. The proposed facility would not serve as a routine maintenance facility; only repairs that provide educational opportunities for student mechanics would be performed there. Regularly scheduled maintenance activities would continue to occur at the NUSD's existing site on Olive Avenue. The NUSD estimates that approximately three to four vehicles would be at the facility at any given time. Vehicles would be serviced inside the facility, which would be renovated. Renovation presumably would include installation of appropriate ventilation and noise controls.

Response to Comment W-4. The commenter's support for the Revised Reuse Plan Alternative is noted.

Response to Comment W-5. Public benefit conveyances could be approved following completion of the Navy's EIS process. The NUSD, as a public agency, is not subject to City of Novato zoning and planning requirements, however the District coordinates with the City in its planning efforts. All discretionary NUSD projects are subject to environmental review under the California Environmental Quality Act (CEQA).

To Whom it May Concern,

We the undersigned are opposed to the school bus maintenance facility being set up right behind Lanham Village. We did not buy our house here for you or anyone to destroy our surroundings. We have children who will grow up here and we want to keep it a peaceful and beautiful place for them. We love where we are and want to keep it as is. We don't want to have to look at an unattractive sight. Please reconsider where you want to put the school bus maintenance facility like down by the hangers or some other unoccupied area.

Thank you for your attention on this matter.

Marion Saunders
41 Lovejoy Way

Phanna Ashworth
45 Lovejoy Way

Amy L. Atch
24 Lovejoy Way.

Jennifer Wilkes
29 LOVEJOY WAY

Danlene Yoshimura
21 Lovejoy

Ed Yik
21 Lovejoy

Zena Jurek
25 Lovejoy way

Patti Buehly
12 Lovejoy Way

Marcia Carey
Marcia Carey
8 Lovejoy Way

Allison Casacand
65 Lovejoy way

Jimmie Neth
47 Lovejoy Way

Gaiose Mills
49 Lovejoy Way

Response to Comments

Response to Comment X-1. The commenters' objection to a school bus maintenance facility is noted. The Response to Comment Q-2 clarifies the activities that would be expected to occur under the Novato Unified School District (NUSD) proposal. The proposed facility would not serve as a routine maintenance facility; only repairs that provide educational opportunities for student mechanics would be performed there. Vehicles would be serviced inside the facility. The NUSD proposes \$1.5 million in renovation to the building, which would include installation of appropriate ventilation and noise controls. Development of the facility also could include fencing and/or landscaping to visually shield the facility from adjoining land uses.

As a resident of Lanham Village, I would like it noted that I oppose being surrounded by or even adjacent to any commercial and/or industrial areas, in particular one of the considered uses of the Navy Exchange triangle.

It has come to my attention that one of the suggested uses of this area is a bus repair yard. This is not a use I consider compatible with our residential neighborhood. I oppose the area being used for a bus repair yard and/or any similar use that would create the noise and air pollution that a bus repair yard would.

Thank you

Linda Buckley

129 Martin Dr
Norah, CA 94947

Response to Comments

Response to Comment Y-1. The commenters' objections to a school bus maintenance yard are noted. The Response to Comment Q-2 clarifies the activities that would be expected to occur under the Novato Unified School District (NUSD) proposal. The proposed facility would not serve as a routine maintenance facility; only repairs that provide educational opportunities for student mechanics would be performed there. Regularly scheduled maintenance activities would continue to occur at the NUSD's existing site on Olive Avenue. The NUSD estimates that approximately three to four vehicles would be at the facility at any given time. Vehicles would be serviced inside the facility, which would be renovated. Renovation presumably would include installation of appropriate ventilation and noise controls.

Letter Z

**DRAFT ENVIRONMENTAL IMPACT STATEMENT
ON DISPOSAL AND REUSE OF
DEPARTMENT OF DEFENSE HOUSING FACILITY, NOVATO, CA
FEBRUARY 27, 1997
SPEAKER REGISTRATION/COMMENT CARD**

Please check your affiliation below:

| | |
|-------------------------------------|-------------------------------------|
| <input checked="" type="checkbox"/> | Individual (no affiliation) |
| <input type="checkbox"/> | Private Organization |
| <input type="checkbox"/> | Federal, State, or Local Government |
| <input type="checkbox"/> | Citizen's Group |
| <input type="checkbox"/> | Elected Representative |
| <input type="checkbox"/> | Regulatory Agency |

Name:

Organization (if applicable):

Street Address (optional):

City/State/Zip (optional):

Phone # (optional):

Julian Carter
For Livingston St
Novato CA 94949
415-824-2171

Do you wish to speak this evening?

☐ Yes☒ No

If you wish to provide written comments only, please write your comments below and turn them in at this meeting. Thank you.

Comments:

I live at Larkin Village and I OPPOSE being surrounded by commercial & industrial use that are not compatible with our residential neighborhood.

We have said this before At it we will say AGAIN AND AGAIN WE WILL NOT LET YOU IGNORE US!

Comments also may be mailed by March 17, 1997 to: Engineering Field Activity West, Naval Facilities Engineering Command, 900 Commodore Drive, San Bruno, CA 94066-5106. Attn: Mr. Gary Munkawa (Code 1852GM).

Z-1

| | | | |
|-------------------|--------------|---------|------------|
| Post-It® Fax Note | 7671 | Date | # of pages |
| To | Gary Munkawa | From | Tom Leaf |
| Co./Dept. | EFA West | Co. | Tetra Tech |
| Phone # | | Phone # | |
| Fax # | | Fax # | |

Kathleen Curtis
Letter Z

Response to Comments

Response to Comment Z-1. The commenter's opposition to commercial and industrial use is noted.

SAN FRANCISCO BAY CONSERVATION AND DEVELOPMENT COMMISSION

THIRTY VAN NESS AVENUE, SUITE 2011
SAN FRANCISCO, CALIFORNIA 94102-6080
PHONE: (415) 557-3686

April 16, 1997

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
Attn: Mr. Gary J. Munekawa, Environmental Planning Branch, Code 1852GM
900 Commodore Drive
San Bruno, CA 94066-5006

SUBJECT: Draft Environmental Impact Statement (DEIS) for the Disposal and Reuse of the Former Department of Defense Housing Facility, Novato; BCDC Inquiry File MR.HM.7906.1

Dear Mr. Munekawa:

Thank you for the opportunity to comment on the Draft Environmental Impact Statement (DEIS) for the Disposal and Reuse of the former Department of Defense Housing Facility. While the Commission itself has not had the opportunity to comment on the DEIS, the following are staff comments based on the *Diked Historic Baylands of San Francisco Bay Findings, Policies, and Maps*, and the *Wetlands in the North Bay Planning Area* report for the North Bay Wetlands Protection Program. Because the Commission has no jurisdiction in this project, these comments should be considered advisory only.

AA-1

Our concerns relate to the riparian wetlands on San Jose and Ignacio Creeks, and other wetlands as shown in Figures 3-8 and 3-9. The *Diked Historic Baylands* report states that "projects should be designed and sited to buffer and protect any adjacent wildlife" (p. 4). The DEIS notes that increased erosion and sedimentation could result from construction activities at the site, and recommends standard erosion control measures. However, siting and buffering provisions are not specifically addressed in the DEIS. The DEIS should address additional siting and buffer measures that would help protect sensitive habitat from construction activities and development impacts.


AA-2

The *Wetlands in the North Bay Planning Area* report notes that wetlands and related habitats "should be maintained and enhanced wherever possible" (p. 63). However, in Figure 3-2 the DEIS depicts portions of the wetlands shown in Figures 3-8 and 3-9 as "residential use." Although the reuse plan itself may discuss siting and other protection measures, the DEIS does not explicitly describe how the wetlands will be treated by the reuse plan. Furthermore, the DEIS does not explicitly examine the impacts of the reuse on the wetlands beyond water quality (such as increased public access, potential for predation by domestic pets, etc.). An expanded discussion of these issues should be included in the DEIS.

AA-3

Thank you for the opportunity to comment on the DEIS. If you have any questions regarding this matter, please do not hesitate to contact me at (415) 557-3686.

Sincerely,



LEORA S. ELAZAR
Planner

LSE/bb

BCDC file - BCDC Inquiry File MR.HM.7906.1
North Bay General Correspondence File

Response to Comments

Response to Comment AA-1. The comment regarding the Bay Conservation and Development Commission's (BCDC's) lack of jurisdiction over this project and the advisory nature of the comments is noted.

Response to Comment AA-2. The comment requests that specific siting and buffer measures be identified as mitigation for potential impacts due to demolition and construction activities at the Rafael Village site. The commenter is referred to Responses to Comments K-2 and K-3, and Sections 4.7.2 and 4.9.2, which provide general programmatic mitigation measures for erosion and sedimentation.

Response to Comment AA-3. The commenter observes that some areas identified in the Land Use section as residential also are identified as wetland areas in the Biological Resources section. No development is proposed for these wetlands under either the Revised Reuse Plan Alternative or the Open Space Alternative. No other impacts on wetlands are described beyond water quality in this EIS as none were identified to have the potential for significant impacts. Additional public access and disturbance or predation by domestic pets are not potentially significant environmental issues at DODHF Novato as no endangered, threatened, or sensitive species have been identified at the facility.

1 you represent, if any.

2 Now we have nineteen.

3 I've mentioned we'll try to give a brief
4 reply if appropriate. We will not go into any long
5 debate tonight. I heard before we just got started
6 here a little debate going on, but we'll be happy to
7 hear those comments again, and if possible we'll
8 answer.

9 Are there any more cards? I've got
10 nineteen, twenty. Okay; the first speaker, and I'll
11 ask -- I'm actually going to mention two names so the
12 second speaker will know who is going to be next so you
13 can be standing by.

14 First speaker is Bill Long representing the
15 Multi-Agency Board, and the second person will be Jim
16 Henderson.

17 MR. POMEROY: Please go up to the
18 microphone.

19 MR. LONG: Thanks. My name is Bill Long.
20 I'm a member of the Multi-Agency Board, but I'm not
21 here representing them tonight. I live in Novato. I
22 have a thought I'd like you to consider in this Draft,
23 and it has to do with the caretaker alternative.

24 The Draft indicates that with respect to two
25 of the impacts, the socioeconomic impact, and the

PH-1

1 scenic and aesthetic impact, that the caretaker option,
2 the "No-Action" Option, has no significant impact or no
3 impact. I disagree with that. I think the option of
4 leaving the housing in caretaker's status for an
5 extended period has very significant adverse impacts
6 for the community, for the City of Novato, for the
7 school district, for the Federal government.

8 The image of the Federal government will
9 suffer if that situation exists for a long period of
10 time. Not only that, the economic impact on the
11 Federal government will be significant. Likewise,
12 there will be a significant economic impact on the
13 community and the school district. The city will
14 suffer because the lower-cost housing that would become
15 available won't be available. So I submit that that
16 "No-Action" option of that option ought to be
17 reconsidered in light of the adverse impacts on the
18 community, on the surrounding neighborhoods, and on our
19 Federal government. Thank you.

20 COMMANDER DOHERTY: Thank you, Bill. I will
21 insist that your comments be taken to heart as the
22 Draft is pushed on, and we'll compare that to some
23 other examples that have set precedent already. Thank
24 you.

25 Now, we have -- any other comments on that?

PH-1

1 MR. POMEROY: Yeah. I just have to mention
2 one thing here to help out my Commander. We're not
3 going to be able to respond to every comment like that
4 tonight. We're here, basically, to take your response
5 to the document. If there's a short factual question,
6 we would be able to answer that but beyond that, we are
7 here to listen to you tonight, and we won't be giving
8 detailed responses.

9 COMMANDER DOHERTY: Next we'll hear from Jim
10 Henderson, soon to be followed by Keith Shein.

11 MR. HENDERSON: My name is Jim Henderson. I
12 reside in Novato. My question is: If Rafael Village
13 is demolished, who will be responsible for disposing
14 of the hazardous materials if any are found in the
15 village?

16 MR. POMEROY: We'll answer that as part of
17 our final EIS. Thank you.

18 COMMANDER DOHERTY: Next will be Keith Shein
19 followed by Sally Ready.

20 MR. SHEIN: My name is Keith Shein, and I've
21 been chosen to speak for the Board of Directors of
22 Lanham Village where I've lived since opening and in
23 previous years served on before.

24 Before addressing the specifics of the EIS,
25 I would like to say that Lanham Village, through its

PH-2

1 directors and its community at large, has attempted to
2 participate in the planning process on all aspects of
3 the new Hamilton Partners.

4 Our posture has been to go hand-in-hand with
5 this development. Our concern is focussed exclusively
6 on ensuring that future developments be kept consistent
7 with the residential nature of our community. Our goal
8 is to continue that partnership with you, the Navy, the
9 City, and with the new Hamilton Partners.

10 Tonight we hope to identify concerns that we
11 fear might jeopardize our positive involvement. We
12 feel that we can unequivocally support the plans as
13 identified as the Preferred Alternative EIS. Every
14 objection that we have to the EIS as its written
15 focuses on the Open Space Alternative.

16 Our attorney, Stewart Flashman, will be
17 submitting to the Navy a detailed letter specifying our
18 concerns, but I would like this forum to introduce the
19 issues. They are.

20 1. EIS identifies in the Open Space
21 Alternative no land use conflict; however, the Open
22 Space Alternative would situate commercial and
23 industrial corporation yards and school bus yards in
24 the immediate vicinity of these residential areas,
25 Lanham Village, the Hamilton Service Center, Capehart

PH-3

1 Housing, and a possible elderly center. All of these
2 residential areas have been identified as sensitive
3 receptors. It's inconsistent with common sense and the
4 principles of planning to suggest that surrounding
5 residential areas with industrial use does not
6 constitute a land use conflict.

PH-3

7 In fact, we continue to propose that to
8 situate corporate yards and bus repair yards in the
9 Commissary and Exchange Triangle, is a direct and
10 serious threat to the residential neighborhood of our
11 community.

12 2. The EIS states that the Open Space
13 Alternative poses no aesthetic or scenic impacts. This
14 conclusion, again, violates common sense and basic
15 planning principles.

16 One of the reasons you don't mix industrial
17 and residential zones so the resident could care for
18 the neighborhood is not aesthetically adversely
19 effected. You cannot ask us to believe that they
20 would -- that there could be any mitigation through
21 landscaping or otherwise that would provide full
22 mitigation of the aesthetic threat of positioning
23 corporation yards and bus yards next to our homes.

PH-4

24 If the mitigation is to come from
25 landscaping, we must ask when? When will trees and

1 hedges mature adequately to provide actual mitigation
2 if any at all? We're going to look out of our houses
3 and see industrial yards under the Open Space
4 Alternative.

PH-4

5 3. As to Environmental Justice. The EIS
6 states that there are no serious environmental justice
7 issues under any of the alternatives.

8 We couldn't disagree more. The Open Space
9 Alternative puts corporation yards and bus yards right
10 on the front steps of the Hamilton Service Center. As
11 a disadvantage and distant franchise group, it's
12 difficult to imagine a more serious violation than
13 environmental justice.

PH-5

14 Further, Lanham Village is one of the few
15 affordable housing communities in Marin. Is it that
16 that makes us a likely target to being surrounded by
17 industrial use? Surely that, too, is in violation of
18 environmental justice.

19 4. As to Air Quality. The EIS offers no
20 discussion of impact to the air quality of idling buses
21 or the operation of commercial vehicles that would be
22 inevitable under the Open Space Alternative. Put
23 corporation yards and bus yards in the Commissary and
24 the Exchange Triangle, and there will surely be changes
25 to the quality of our air. We're talking about trucks,

PH-6

1 buses, and heavy equipment. Your EIS must reassess
2 this issue to talk about air quality.

PH-6

3 5. Noise impacts during construction. We
4 would also like the EIS to acknowledge that the current
5 construction schedule of 7:00 a.m. to 6:00 p.m., Monday
6 through Sunday, will have significant noise impacts on
7 our neighborhood. To mitigate this impact, the
8 construction schedule should be modified to 8:00 a.m.
9 to 6:00 p.m., Monday through Friday.

PH-7

10 6. Noise impacts after construction. The
11 EIS also ignores impacts after construction if the Open
12 Space Alternative is adopted. Again, put corporation
13 yards and bus yards in the Commissary and Exchange
14 Triangle and Lanham Village, Capehart, the Hamilton
15 Service Center, and a proposed elderly care center will
16 all suffer serious noise increase. We suggest that
17 there is no adequate mitigation to this threat.

PH-8

18 As it applies to hazardous materials, the
19 EIS again falls short when it considers hazardous
20 materials for the Open Space Alternative. We're
21 looking at corporation yards and bus yards. Are we to
22 believe that the storage of petroleum products and/or
23 insecticides and/or paint would not constitute a
24 hazardous material threat to residential communities if
25 such industrial entities are parked in the Exchange and

PH-9

PH-9

1 Commissary Triangles? No.

2 And during construction, the EIS does not
3 address the mobilization of lead in the soil and what
4 steps would be taken to mitigate it, nor is there
5 discussion of how asbestos release would be mitigated
6 during construction, nor is it stated if pesticides
7 were ever stored in construction areas, especially DDT
8 prior to 1965. Open space is an issue.

PH-10

9 We would also like to point out that the
10 Preferred Alternative, along with the plans of the new
11 Hamilton Partnership, afford a great deal of open
12 space. 250 of the 400 acres purchased by the Martin
13 Group is dedicated to open space. These adjoin an
14 additional 700 acres of additional open space under
15 Hamilton Wetlands. Planned are 5 acres of park and
16 recreational use, including baseball, football and
17 soccer field, plus tennis courts. The old Hamilton
18 pool is being refurbished. There will be miles of
19 walking, hiking and biking trails.

PH-11

20 The Preferred Alternative proposes buildings
21 with plenty concern for open space. When the entirety
22 of the Hamilton rebuilding is considered, there is more
23 than adequate provision for open space.

PH-12

24 Further, the open space alternative
25 eliminates 500 new and affordable homes to be built in

1 the Rafael Village area. That's approximately
2 one-third of the proposed development area. I'm an
3 individual who couldn't afford to live in Marin unless
4 affordable housing was provided for me. I find the
5 idea of eliminating one-third of those housings
6 ethically repugnant.

PH-12

7 In conclusion, the Board of Lanham Village
8 strongly advocates the adoption of the Preferred
9 Alternative. It deserves a residential carriage of our
10 neighborhood.

11 The Open Space Alternative is a direct and
12 serious threat to our community. We will have no
13 choice but to resist its adoption and implementation
14 with all our resources. Our choice would be to
15 continue going hand-in-hand with the development of
16 Hamilton. Thank you.

PH-13

17 COMMANDER DOHERTY: Thank you, Keith. Your
18 objections to the Alternative are noted.

19 Fourth is Sally Ready to be followed by
20 Heidi Eberle.

21 MS. READY: My name is Sally Ready. I live
22 at Lanham Village. I live at 12 Martin Drive. I'm
23 here to ask that you don't have corporation yards or
24 bus repair or other types of commercial industrial use
25 over my back fence.

PH-14

1 My condominium is up in the corner right
2 next to the Exchange Triangle back fence. It's very,
3 very close. We have children, we have a residential
4 situation, and we already get noise from the freeway.
5 We don't need any additional noise. We don't need that
6 stress. We don't need any additional traffic. We
7 don't need any additional air pollution. We don't need
8 any noxious smells. We don't need to hear engines
9 revving up. It's not compatible with residential use.
10 Having those things, anything of that type, including a
11 homeless shelter over our back fences would have a
12 significant adverse impact. Thank you.

13 COMMANDER DOHERTY: Thank you, Sally.

14 Fifth is Heidi Eberle followed by Jane
15 Johnson.

16 MS. EBERLE: Hi, my name is Heidi Eberle. I
17 just wanted to make some comments tonight on the
18 proposal.

19 Home. One of the definitions in the
20 dictionary states that, "A home is a place where one
21 likes to be. A restful, congenial place."

22 Lanham Village has been my home since
23 January of 1984. I was one of the original people that
24 moved in. One of the reasons I chose Lanham was for
25 the safe environment to raise my child. It was quiet

1 and unpretentious.

2 Over the years, we have been caught in what
3 I would describe as a Catch 22: Damned if you do, and
4 really damned if you spoke out about any consequences
5 surrounding the land.

6 I am certain many of you here tonight feel
7 that Lanham is just a small insignificant place that
8 doesn't matter. There are those that have monetary and
9 political gains to protect. Does this mean I have to
10 put up with industrial uses next to my home so someone
11 can make a couple bucks for a political coup?

12 Think about your homes. Did you have to
13 fight for several years to keep it a residential area?
14 Did you get knocked around just because you had a lower
15 property value? Just suppose you were in our position.
16 Now, think about it. Don't just pass us off. What if
17 a potential corporation yard or industrial use area was
18 being planned right next door to your home? Just
19 because you don't live next to a potential corporation
20 yard or industrial use area, doesn't mean you have to
21 dump them next door to mine.

22 We have many, many times over the last few
23 years asked to be heard. Yes, sometimes we are, but
24 concessions that have been promised to us did not come
25 to fruition. We have been kicked aside for too many

PH-15

1 political games. There has been little respect for the
2 people at Lanham Village.

3 I'm really angry at a system that states
4 that we are a viable entity and then stabs us in the
5 back. I believe you need to take a long hard look at
6 the consequences of putting any type of industrial
7 facility, such as a corporation yard, school bus repair
8 site, or the like, that would be detrimental to the
9 overall environment next door to my home, Lanham
10 Village.

11 Speaking for myself, I am sick and tired of
12 promises to my face and then having the opposite
13 happen. I'm appalled that a few people could ruin the
14 quality of life at my home. I'm appalled that a few
15 people can damage the equity of my home.

16 I live at Lanham Village, and I oppose being
17 surrounded by commercial industrial land uses that are
18 not compatible with a residential neighborhood.

19 We have said this before and we will say it
20 again. We will not let you ignore it. Thank you.

21 COMMANDER DOHERTY: Thank you, Ms. Eberle.

22 Six, as mentioned, is Jane Johnson followed
23 by Mark Donovan.

24 MS. JOHNSON: My name is Jane Johnson and I
25 live at 45 Martin in Lanham Village. I just moved

PH-15

1 there last year and it fulfilled a dream of mine -- I
2 get so emotional -- anyway, to own my own townhouse.

3 The reason I chose it wasn't just because it
4 was affordable, but there actually are things about
5 Lanham like the quality of life there. It's like a
6 neighborhood. It's like neighborhoods that you hear
7 about on Mr. Rogers T.V. show and stuff. It's really a
8 breathing, living entity, I mean, with all the life,
9 you know, all the really good things in life. Then I
10 move there and I get this letter, and I really haven't
11 been so involved in this whole process, and I find out
12 that, like the last previous neighbor said, that there
13 has been a lot of backstabbing, et cetera, et cetera,
14 and I just -- I'm just so appalled and so upset that a
15 corporation yard and a bus thing, that they're just
16 going to put it right in my dreamland and not even care
17 about how it impacts on a living, breathing
18 neighborhood. I just wanted to say that, and I'll be
19 back.

20 COMMANDER DOHERTY: Thank you.

21 Mark Donovan followed by Andrea Kiesel.

22 MR. DONOVAN: Hi, I'm another resident of
23 Lanham Village. I've been following this plan, and so
24 forth.

25 I've found that Lanham, as a whole, has been

PH-16

1 very cooperative in trying to work with the city on its
2 development, and all this cooperation has led to is
3 continued misuse of Lanham.

4 Currently, I find it very repugnant that you
5 want to use semantics to hide a bus maintenance yard by
6 calling it a learning facility. From my understanding,
7 there might be as many as seventy buses there.

8 I work at MUNI Railway. I'm very familiar
9 with the fumes that one diesel bus will give off and
10 the noise that it generates. So you have all these
11 statistics you want to throw at us, but the truth of
12 the matter is I've seen one diesel bus clear a whole
13 facility because of the fumes.

14 I think -- as I said, we have tried to be
15 good neighbors to Novato. At this point in time, my
16 personal recommendation to the Board, our Board, is now
17 to seek legal action. It's unfortunate because -- and
18 I think all the people at Lanham love Novato, and
19 that's not the type of thing that we would want or
20 desire.

21 The fact that you continue to just negate
22 Lanham Village and the people who live there, the
23 children who live there, who have participated in this
24 community who I personally have coached -- I know a
25 number of other people who have coached not only our

PH-17

1 children, but a number of children in Novato, and that
2 you just kind of like continually -- residents who
3 currently live there, okay, you're imposing this on us.
4 We just can't get up and move. We love this
5 neighborhood, and you want us to move. You're forcing
6 us to move.

7 I think this is an atrocity. You could put
8 these things elsewhere where it wouldn't have an impact
9 on us as neighbors. I would like to see the Board and
10 the politicians of Novato act as good neighbors to us
11 and act as the constituents we are, to treat us with
12 respect for once, just once respect our wishes. Thank
13 you.

14 COMMANDER DOHERTY: Thank you, Mark. Your
15 comments are so noted.

16 Andrea Kiesel, followed by Ms. Judith
17 McClarin.

18 MS. KEISEL: My name is Andrea Kiesel and I
19 am the owner of the Little Village School. The Little
20 Village School is located in Lanham Village. I am not
21 a resident of Lanham Village, but I may as well be
22 since I am there most of the hours of the day.

23 We are a small preschool with the children
24 of fifty families enrolled. We are open from 7:00 a.m.
25 to 6:00 p.m. More than half of our involvement, I

1 would say at this point, are from families in Lanham
2 Village, and we're getting more families every day.

3 We have serious concerns about what is
4 happening to the area surrounding our school. We have
5 obtained a copy of the proposed use of the 21 acres to
6 the rear of Lanham Village abiding by the unified
7 school district.

8 There are two parts of the proposal that are
9 of large concern to us: The storage and vehicle
10 maintenance, and the vocational and technical and trade
11 school sections.

12 Building 972 is directly adjacent to the
13 open space lawn area and school playground that our
14 children use. We feel that the use of this building,
15 as proposed, would cause excessive noise and compromise
16 the air quality of the area, which is an area used
17 daily by the children not only of the school, but also
18 of this community.

19 The noise and the fumes, the comings and
20 goings of a number of vehicles housed there, not to
21 mention the noise and fumes from the repairs, would
22 have an -- would be intrusive to a residential
23 community. The waste from said maintenance would be
24 detrimental to the children, the staff, the families of
25 the community, and to the environment.

PH-18

1 Having the ROP program for automotive
2 training also on that site increases the amount of
3 noise, waste and fumes.

4 I have brought some photos for you to
5 examine that demonstrate the close proximity of this
6 facility to our school. Would you like your children
7 to play here with seventy buses emitting diesel fumes
8 being housed right there? I don't think so.

9 We are opposed to the location of the
10 facility and urge that another location be found for
11 it. The proposed use raises two questions in my mind:
12 To whom will these agencies be accountable, and how is
13 this being allowed to happen. Thank you for your time.

14 COMMANDER DOHERTY: Next is Ms. Judith
15 McClarin followed by Karlos Halfhide. Did I pronounce
16 that correctly?

17 MS. McCLARIN: My name is Judith McClarin,
18 and I am here today to -- really, representing myself,
19 although I should point out that I am the Chair of the
20 North Marin County Land Conservation League, and the
21 secretary of the Sierra Club Marin Group.

22 There are really three points that I'd like
23 to make this evening, and they have to do with your
24 impact on water quality, air quality, and traffic.

25 First, I would like to -- well, perhaps

1 first I'd like to ask, or ask you to find out, is there
2 asbestos, as I am led to believe, in the homes at
3 Rafael Village; and if so, why are there not any
4 mention of this asbestos in the impact on air quality
5 or water quality, and how do you propose to dispose of
6 this asbestos?

PH-19

7 It was my understanding that the homes were
8 declared unlivable because of this material, and,
9 therefore, when you demolish the homes, the material
10 will go into the air and into the streams.

11 Also, under Water Quality on page 452 and
12 453, it talks about -- let me see. I need to find it.
13 -- a best management practices program for storm water
14 collection as part of the reuse project; however, this
15 best management practices program is not outlined
16 and/or detailed in any way; and, therefore, it is
17 extremely difficult to determine whether or not it will
18 adequately protect the streams from pollutants during
19 the demolition, and so we would request, or I would
20 request, that you outline the best management practices
21 and what they would entail so that we can determine
22 whether or not they are adequate.

PH-20

23 On page 462, this is in the Traffic and
24 Circulation section, the claim is made that there will
25 be no significance on traffic. Well, or that there

PH-21

1 would be an impact but not a significant impact on
2 traffic and circulation.

3 The analysis which is on page 462 discusses
4 the fact that Novato historically generates
5 approximately 1,024 vehicle trips. Unfortunately, it
6 doesn't tell us what year you're taking this data from;
7 and, of course, we need to know exactly where the data
8 is coming from because Hamilton has gone up and down in
9 usage over the years. At some times it was very
10 heavily used, and right now it's not used very heavily
11 at all; and so it would be important to know what dates
12 you're using for your comparisons.

PH-21

13 Also, there is a statement here that says
14 the fact that military and nonresidential uses do not
15 generate as many vehicle trips as civilian comparables.
16 Now, I'll give you an example here of a commissary
17 which does not generate or which only generates half
18 the number of trips that a similar-sized grocery store
19 was; but, unfortunately we're discussing in this area a
20 very large residential neighborhood or neighborhoods,
21 and it seems to me that that assumption does not hold
22 water because you have military people going to their
23 job, and you have homemakers often at home taking the
24 children to school and back again, and to the grocery
25 store, and to gymnastics, and to soccer and to

PH-22

1 baseball, just like all of the rest of us do; and so I
2 would ask that you either substantiate or revise that
3 assumption and see what effect it would have.

PH-22

4 In the Air Quality, again, I wish to bring
5 up the matter of the asbestos and the effect of the
6 asbestos on the air quality during demolition and the
7 disposal of that material.

8 Also, and this is more in line of a
9 question, although when I read the EIR it appeared to
10 me that for -- if we take, for example, air quality, it
11 appeared to me that it was saying that the Open Space
12 Alternative would have no impact, and yet in your
13 summary of impacts, it has significant impact for both
14 the Reuse Plan and the Open Space Alternative. I was
15 wondering perhaps I could have an explanation of that,
16 and I can have it some other time. Okay; thank you
17 very much.

PH-23

18 COMMANDER DOHERTY: Thank you, Judy; that
19 was exactly 5 minutes, and you had more than one
20 question so there's no generic possibility of giving
21 you more than one answer.

22 MS. McCLARIN: No, there are no answers to
23 the ones I made.

24 COMMANDER DOHERTY: Thank you very much.

25 Next is Mr. Halfhide followed by Jen Rusk.

1 MR. HALFHIDE: Good evening, my name is
2 Karlos Halfhide. I'm a co-chair of the Marin For
3 Family Action. I have three questions that I have to
4 ask. The first one, of course, is what she just
5 previously mentioned about the asbestos. There's a
6 question in my mind as to on your Draft of the EIS that
7 says, "An asbestos survey of the housing units was
8 conducted in August 1995." The ACM, that's the
9 asbestos, "was identified in the garages of 47 units
10 inspected in the Spanish Housing."

PH-24

11 Now, I'd like you to clarify, if it's
12 possible, why the Capehart on the hillside housing were
13 inspected not to be free of asbestos.

14 2. Lead-based paint. You probably know
15 that lead is poison and it's very toxic. It
16 contains -- well, it causes brain damage and it's very
17 susceptible to young kids. They put it in their mouths
18 and whatever, so we are concerned about that.

19 We want to know that -- according to your
20 statement of the EIS, it states that, "lead-based paint
21 is present in the Capehart units." It also states that
22 lead-based paint -- the abatement is not required. I
23 don't understand that. Why do you designate between
24 one and the other? If it's lead, it's lead; it's got
25 to go. All right; so much for that.

PH-25

1 Well, since it poses an effect to human
2 health, and it's based on Navy policy to clean up the
3 contamination prior to the transfer, it seems
4 appropriate that the Navy would abate almost any LBP in
5 the Capehart units. I don't understand why there's
6 such a dissemination between that, but that's something
7 that we'll work on, I guess.

PH-25

8 The third one, and my last point is that are
9 there other sources of lead? I think the last lady
10 touched on it. What she said was in the Draft EIS,
11 lead has been found in the soil around the Capehart
12 units above HUD level reactions.

13 It also indicates that further assessment is
14 planned and that the response measures will be
15 determined based on the assessment of the potential
16 risk to human health and the environment.

PH-26

17 It also indicates that no survey for the
18 lead in the drinking water has been conducted. Well,
19 if you're going to have a place, you got to make sure
20 that it's clean. I'd like you to clarify that if it's
21 possible, and that further testing for lead will be
22 conducted and whether lead contamination above the
23 Federal levels will be abated.

24 In closing, I'd like to say that if the
25 parcels are not clean of contamination and hazardous

PH-27

1 material before the transfer, they may not be suitable
2 for reuse or might be economically feasible. Thank you
3 for your attention to this matter.

4 COMMANDER DOHERTY: Mr. Halfhide, thank you
5 very much. I'm not going to give you any specific
6 answer, but I believe they're all being looked at very,
7 very carefully as we move forward.

8 Ms. Jen Rusk, number eleven, followed by
9 Betty Pagett.

10 MS. RUSK: Hi, my name is Jen Rusk, and I
11 live at 81 Martin Drive in Lanham Village. I'm here
12 tonight to make clear once again that my neighbors and
13 I do not want a corporation yard in the Commissary or
14 Exchange Triangle of the Hamilton property.

15 I read through the EIS, and I noticed that
16 option 2, the Open Space Option, explicitly allows for
17 corporation yards in either or both of these parcels.

18 Additionally, I have a copy of the Novato
19 Unified School District's application for Public
20 Benefit Transportation of Surplus Federal Properties.

21 As a homeowner with a house fifty feet from
22 the Exchange Triangle, I can accept everything that the
23 school district is proposing except their intention to
24 create a massive automotive repair, and maintenance and
25 training facility in building 972.

PH-27

PH-28

1 The application clearly states that this
2 facility would be used to service 39 school buses and
3 31 vehicles, and will allow the district to expand its
4 maintenance service to other district and agencies to
5 an immense capacity. This clearly is a use which is
6 incompatible with the daycare and homes literally on
7 the other side of the fence.

PH-28

8 Many people have criticized and said that
9 Lanham residents -- that we are naysayers, and we are
10 not. We have, on numerous occasions, given feedback on
11 the types of uses that we can live next to. A brief
12 list of the uses residents supported in our last
13 meeting survey include: senior care and senior housing
14 facilities, child care and preschool facilities, school
15 district facilities that do not generate noise and
16 pollution, office buildings, library facilities,
17 quality retail businesses, community parks, community
18 meeting facility, residential homes.

PH-29

19 You'll notice that about the only thing we
20 can't live with are noise and pollution generated by
21 commercial or industrial uses, such as corporation
22 yards, vehicle maintenance facilities, machine shops,
23 bus parking lots, transit center, et cetera.

24 Many have also pointed out that this area
25 currently houses, the Exchange Triangle and Commissary

PH-30

1 Triangle, currently houses commercial and industrial
2 facilities. While this may be true, I point out that
3 just because these uses were one placed here doesn't
4 mean it was ever appropriate next to a residential
5 community.

PH-30

6 I also point out that the military has not
7 used this facility in a full capacity for many, many
8 years. Whoever moves into this area in the future will
9 occupy it and will use it.

10 I've brought some pictures that I will
11 submit for the public record, and they document just
12 how close the Exchange Triangle and Commissary Triangle
13 are to our homes. They include a picture of a few of
14 the 25 Lanham homes directly adjacent to the Commissary
15 Triangle, the daycare building that is located adjacent
16 Triangle fence where the maintenance facility is
17 proposed, and 2 of the 21 homes that will be directly
18 affected by the Exchange Triangle development.

PH-31

19 The EIS states there will be no significant
20 long-term environmental impacts in the development
21 options proposed. Preferred Reuse Plans seem to best
22 represent this conclusion, providing the city does not
23 allow any noise or pollution-generating uses that would
24 negatively impact our neighborhood.

PH-32

25 The Open Space option would clearly allow

PH-33

1 noise pollution, and placed next to us, they would have
2 a permanent and negative impact on our community.

PH-33

3 As for the public benefit transfer property,
4 our community needs to know where we can direct our
5 concerns and whether this city has any control of the
6 possible beneficial uses once they are approved.

PH-34

7 The massive vehicle maintenance facility
8 that Novato Unified School District has planned is a
9 direct threat to our health, the quality of life in our
10 community, and the value of our homes. Thank you.

11 COMMANDER DOHERTY: Thank you, Ms. Rusk.

12 Number 12 is Betty Pagett, followed by
13 Patrice Garrett.

14 MS. MOODY: I'm Elizabeth Moody, speaking
15 for Betty Pagett. Betty had to leave for another
16 county meeting in conflict.

17 Ethnic Association for Housing asks about
18 the asbestos, as the previous speaker has. The
19 asbestos has been identified in the Spanish Housing
20 inspected, and the EAH would like to have it clarified.

21 If Capehart and hillside housing have been
22 inspected, and if they've been found free of asbestos
23 and the lead-based paint that is present in Capehart
24 units, as well as in the soil around, they're asking
25 that if they pose as a threat to human health, and

PH-35

1 based on the Navy's policy to clean up contamination,
2 then isn't it appropriate that this be cleaned up by
3 the Navy?

PH-35

4 They also ask that there seems to be no
5 survey for the lead in the drinking water, and along
6 with looking at the lead in the soil around, could this
7 be checked?

PH-36

8 On my own part, I would like to note that on
9 page 319 on the aesthetic and scenic resources which
10 describe the existing conditions that I think there
11 should be some note that it is a poor aesthetic
12 appearance across from Lanham Village, and I do
13 question why the corporation yards were placed in the
14 Open Space Alternative.

PH-37

15 This community needs to be protected
16 sound-wise, aesthetic-wise, and it's health and
17 viability, not only because it is a very fine
18 affordable housing community that deserves that type of
19 protection, but also because of the importance of it
20 being right at the entrance to all of our Hamilton
21 Village base. Thank you.

PH-38

22 COMMANDER DOHERTY: Thank you, Ms. Moody.

23 Next is Patrice Garrett, followed by Martin
24 Peckins.

25 MS. GARRETT: Hi, my name is Patrice

1 Garrett. .

2 As a homeowner living in Lanham Village, I
3 am here tonight to tell you that I oppose the Open
4 Space Alternative. I'm here tonight to tell you that I
5 strongly oppose placing a school district, bus repair
6 facilities, corporation yards, and automotive training
7 facilities alongside our homes and playgrounds.

8 We already suffer from air pollution and
9 noise pollution with the endless racket generated by
10 freeway traffic 24 hours a day, and Nave traffic which
11 is growing, including Golden Gate Transit buses.

12 We're going to be further impacted by the
13 expanded traffic from the Commercial Center that's
14 planned, the hundreds of new homes currently being
15 built, and all of the traffic generated by public
16 facilities and offices already planned further inside
17 Hamilton.

18 To additionally place an activity that
19 generates noise from the facility and the buses
20 themselves, including routine use of the hazardous
21 cancer-causing chemicals, and additional traffic and
22 air pollution adjacent to a small well-cared-for
23 community with three hundred small children and
24 residents, and others going to school in the area all
25 week long, is outrageous and unconscionable. You don't

PH-39

PH-40

PH-41

1 find Sears Automotive Centers built next to homes.

2 We are taxpayers and voters, too, please
3 don't put this sort of project next to our homes.
4 Don't turn our lovely, affordable community into a
5 slum. Don't destroy the value of our homes by caving
6 into political ambition and whatever greed may be
7 involved. Thank you

8 COMMANDER DOHERTY: Thank you.

9 Number fourteen, Mr. Peckins, followed by
10 Debura Faust.

11 MR. PECKINS: Good evening. My name is
12 Martin Peckins, and I'm a homeowner and a resident of
13 Lanham Village.

14 I strongly oppose being surrounded by
15 commercial and/or industrial uses that are not
16 compatible with our quiet residential neighborhood.

17 We have said this before and we'll say it
18 again and again, we will not let you ignore us. Thank
19 you.

20 COMMANDER DOHERTY: Thank you, Martin.

21 Ms. Faust followed by Kim Lawrence.

22 MS. FAUST: My name is Debura Faust. I am a
23 Marin County resident, and I am representing Marin
24 Family Action. I'm a renter in Marin County. I have a
25 nine and-a-half year-old daughter. I do a lot of

PH-41

PH-42

1 volunteer work in this community, and I would like to
2 have the opportunity to be able to have an affordable
3 home that I could own some day.

PH-43

4 Marin Family Action supports the -- let's
5 see -- revised Reuse Plan Alternative, the Preferred
6 Alternative Plan.

7 I was a girl scout for many years as a teen.
8 A policy that we had that I've adopted throughout my
9 life is that I take my trash and a little bit more
10 whenever I go someplace; and, personally, and as a
11 representative of Marin Family Action, I encourage, and
12 if I may be so bold, demand that the Army or Navy take
13 a full accounting and a thorough investigation of any
14 toxic -- toxins, hazardous waste, asbestos, lead-based
15 paint, and take full responsibility to check and see
16 just what is there so this land will be safe for any
17 future use. Thank you.

PH-44

18 COMMANDER DOHERTY: Thank you, Ms. Faust.

19 As mentioned, Kim Lawrence followed by Bob
20 Roberts.

21 MS. LAWRENCE: Hi, my name is Kim Lawrence
22 and I'm very thankful that we live in America and have
23 a democracy, and that we're allowed to vote and to say,
24 "No, we don't like this," or, "Yes, we like this."

25 I remember being passed out a survey saying,

1 "What would you like next to your home, your family?"
2 Because that's exactly what Lanham Village is to me.

3 I'm a homeowner, and I'm also a family
4 member of this village because that's what we are.
5 We're not a bunch of separate identities. We have
6 molded into one, and our children play together, and we
7 pass sugar and milk from one door to another, which you
8 don't find in many neighborhoods anymore.

9 This survey asked me, "Do you want a bus,"
10 or what you had mentioned, you know, previously, "or do
11 you want a library or a park or an elderly center, a
12 senior housing?"

13 You know, you said that we're naysayers.
14 We're not. Our Board has worked so hard with everyone
15 to accommodate everything that you guys have done, and
16 we've tried to support everything that you are, you
17 know, saying, but you guys haven't given us anything.
18 You haven't given us any good news, per se.

19 When I said, "Yes, I wouldn't mind," I know
20 progress is going to happen. I can't stop that. I
21 wouldn't mind to have an elderly home, you know, placed
22 over there. I mean, they need, you know, our help, and
23 of course I think a nice park or a library, something
24 that would further the growth of our children, I think
25 that would be great on the other side.

1 I don't know who voted for this bus, this
2 automotive stuff that's going to go adjacent to our
3 daycare center or this, you know, diesel bus station.
4 I didn't vote for it, and I don't think anyone in my
5 village voted for it. I'd like to see the results of
6 those, you know, voters because I know for a fact that
7 we did not vote for the bus station or the automotive.

8 I just want to say that right now we are now
9 horse-shoed in, basically. We are having to put fences
10 up on all sides, and we're basically jailed in our own
11 community because of the things that are happening that
12 we did not vote on. I'd like for you guys to
13 reconsider everything that you are proposing today.

14 You also mentioned environmental impact. I
15 don't know if you guys took into account that there are
16 probably over a hundred children living in Lanham
17 Village, and this is going to impact them, their
18 breathing, their playing, their livelihood, their
19 growth, your future congressmen, your future senators,
20 your future president. You're affecting them, not only
21 us, so I'd like for you to please consider the
22 children. Thank you.

23 COMMANDER DOHERTY: Kim, Thank you. I'd
24 like to say two things. No one on this Board has made
25 the statement regarding naysayers.

PH-45

1 . Secondly, I'd like Ken Bell to make a twenty
2 second comment about our policy on voting on the bus
3 depot or the rehab facilities. Ken.

4 MR. BELL: Yeah, that facility that's being
5 talked about was mentioned in the Novato Unified School
6 District Application for Public Benefit Discount. It
7 was indicated to be a vehicle maintenance training
8 facility, and it was described by the Novato Unified
9 School District. It was forwarded to the Department of
10 Education, and they're the ones that validate its
11 propriety as an educational facility. The Multi-Agency
12 Board of the Novato City Council did not come up with
13 that idea or finally have the final say and approval of
14 that public benefit discount transfer.

15 COMMANDER DOHERTY: So noted.

16 Number seventeen, Bob Roberts, followed by
17 Bill Collins.

18 MR. ROBERTS: Hello, I'm a homeowner at
19 Lanham Village, and I want to echo everything everybody
20 else has said.

21 To speed it up, I do want to say that I
22 think it's disingenuous what the school district is
23 doing by not calling it what it is. It is not an
24 educational facility, it's going to be a bus repair
25 center, and we're going to be impacted heavily by it.

PH-46

1 I think calling it anything else but what it
2 is, is lying to the people of Lanham Village. It's a
3 smokescreen, and the impact is going to be the same,
4 which is we're going to have seventy busses being
5 worked on, diesel fuel and noises, and all the problems
6 that come with it.

PH-46

7 I know that if this was a country club area,
8 it would not happen there. If this was Bell Marin
9 Keys, it would not happen there. It's happening here
10 because what you have is school teachers, what you have
11 is people who are -- who repair buses professionally,
12 what you have is homemakers, what you have is people
13 that are on the lower economic stream in Marin County.

PH-47

14 The feeling is that we are people that can
15 be stepped on and impacted with no retaliation, and you
16 think we have no recourse. We do have recourses. We
17 do have an attorney, and although none of us are
18 wealthy, combined, we have enough money to hire the
19 attorneys to have a physical impact on the people who
20 are assaulting us. Thank you.

21 COMMANDER DOHERTY: Thank you.

22 Mr. Collins, followed by Elizabeth Moody.

23 Elizabeth, do you have another one?

24 MS. MOODY: No.

25 COMMANDER DOHERTY: Okay; so I will go

1 through that one.

2 Followed by Debbie Taylor.

3 MS. TAYLOR: I want to be last.

4 COMMANDER DOHERTY: You want to be last?

5 Well, there are three more after you that just came up.
6 I'll make you last if you want.

7 MR. COLLINS: Debbie, would you like to be
8 last?

9 Hi, my name is Bill Collins. I'm a brand
10 new resident to Lanham Village. I have not had a
11 chance to look at the details, but I will say that just
12 in my cursory review of the Executive Summary tonight,
13 there seems to be some flaws and omissions, all of
14 which have been pointed out tonight. One of those is
15 on the issue of traffic. It seems absurd to me to, in
16 the Executive Summary, that there's no impact on the
17 intersection traffic. How much traffic do you think is
18 going to be generated by all these new commercial uses
19 and residential activity? You might say a substantial
20 amount, and not addressing that to me, that's an
21 omission at best and a flaw at worse.

22 Air quality. I can hold the best of them
23 with numbers. I'm a statistician and an accountant.
24 I'm also a graduate of the School of Status^{istics}. I know
25 you can make a lot of lies with status.

PH-48

PH-49

1 . There's something that you said that really
2 kind of annoyed me. You pointed out very succinctly
3 that there's an air -- that the amount of pollution
4 misses the mark. Well, you're right.

5 The thing that really irritates me is that
6 when you said that on a regional bases that the
7 pollution doesn't -- isn't a drop in the bucket. Well,
8 sir, I don't live in a region. I live in a place. I
9 think all these people here, we don't live in a region;
10 so the, you know, the drop in the bucket doesn't mean
11 anything to us. We're interested in where the drop is.

12 Noise. Where on the impact study does it
13 discuss the commercial use and the noise that the bus
14 zone poses? You said there's no impact. That is a
15 lie, and it's a flaw, and it's an omission.

16 Your report says there's no noise. Now, I'm
17 not aware of the Navy, the Army, or my old Alma Mater,
18 the Air Force, has developed a new stealth bus. Buses
19 make noise.

20 Finally, a rose is a rose is a rose. I
21 don't care what you call it by any name, if you want to
22 call it an education center or whatever, an Air Force
23 base is an Air Force base, a bus depot is a bus depot.
24 Thank you.

25 COMMANDER DOHERTY: Debbie Taylor, followed

PH-49

PH-50

PH-51

1 by Bill Trumbo.

2 MS. TAYLOR: Hello, my name is Debbie
3 Taylor. I am a Lanham Village homeowner, and I am the
4 former president of my association, and have worked
5 closely for many years on this Hamilton Reuse Plan.

6 I'm very upset about how this process was
7 handled, how the Environmental Impact Statement will
8 affect my community.

9 The School district was over represented on
10 the Hamilton Advisory Committee. They had two Board
11 members and one PTA member to our one representative
12 from Lanham.

13 When we found out that they wanted to put a
14 corporation yard near Lanham, we went to the school
15 district meeting and told them that this was not an
16 acceptable use near our community. They said that they
17 agreed and would not pursue this type of use.

18 Now they are applying for a storage yard
19 that will not only be for the school district's use,
20 but for schools countywide, and that there will be a
21 maintenance yard that will service 39 school buses and
22 31 county vehicles. This sounds a lot like a
23 corporation yard to me.

24 I feel that the school district is trying to
25 get as much property as they can so that they can sell

PH-52

PH-53

1 or lease out their other properties for a profit.

2 Corporation yards do not fit in with a
3 residential neighborhood. We do not need any more
4 noise or pollution in our neighborhood. We already
5 deal with pollution and noise from the freeway and on
6 Nave Drive. We won't accept this type of use. I don't
7 think that the EIS addresses these issues.

PH-54

8 There are other groups applying for the
9 land, and the school district is trying to absorb all
10 of the available land.

11 What we would like to see around our homes
12 is more residential-type uses and uses that don't
13 generate noise or pollution, such as senior housing or
14 a library.

PH-55

15 It is my hope that this will get further
16 environmental studies and will go back before the
17 Multi-Agency Board for a closer look at what the Reuse
18 Plan would do to its already existing neighborhoods.

19 Based on all the people that were here
20 tonight, I'd say probably three quarters of the people
21 here are Lanham residents. If we didn't care about our
22 community, we wouldn't be here tonight, and everything
23 that everybody in this room from Lanham has said
24 tonight has been expressed over and over and over
25 again.

PH-56

1 It says right here in the revised Reuse
2 Plan, Alternative Plan, that in both the Commissary and
3 Exchange Triangle, there will be no corporation yards
4 permitted. Like someone else had said, corporation
5 yard, maintenance yard, they're all one in the same.

6 It's my hope that if we approve this Reuse
7 Plan, the Preferred Alternative, that somebody from the
8 city will finally get up and stand up to the school
9 district and say, this is not allowed in this plan that
10 we have worked so hard at. I hope that the city will
11 back us and say that this is a form of a corporation
12 yard. Thank you.

13 COMMANDER DOHERTY: Thank you, Ms. Taylor.

14 Bill Trumbo, followed by the last card I
15 have, Dean Moser.

16 MR. TRUMBO: Hi, I'm Bill Trumbo. I live at
17 40 Hickox Road in Novato. I don't live at Lanham.

18 I do have a couple comments about the
19 Summary here because it said on the page of the
20 Executive Summary, ES-10, "Disposal and reuse of the
21 Hamilton project base would have no significant impact
22 on the utilities, including electric and natural gas,
23 telephone, water, and sanitary," and then it goes on to
24 explain the solid waste stream impacts, and so forth.

25 I'd have to see the details on that to

PH-56

PH-57

1 understand how they came up with that conclusion, but
2 just from a very superficial look, from a
3 nonprofessional, I would have to wonder about that.
4 I'd have to say there is going to be some significant
5 impacts on utilities. In particular, what I'm thinking
6 of is the electricity and the gas use which are used to
7 light homes and heat homes and run the motors in homes,
8 the air conditioners, and so forth.

9 I think it's going to be crucial to address
10 the issue of how the energy is going to be used in the
11 homes and the buildings that are retrofitted, how the
12 energy could be saved or conserved or used more
13 efficiently, and there are means to do that.

14 I would propose that if the city has a say
15 in this, which of course they do, that the plan
16 followed by the City of San Jose, which is called
17 IDEAS -- it's an acronym for Innovative Design for
18 Energy Alternative Solutions; it's conducted by their
19 building department -- and any plans that come to the
20 building department get reviewed under these
21 guidelines, which are not mandatory, but it's a
22 suggestion. You can save ten percent more electricity
23 if you would install energy-efficient refrigerators.
24 You could install skylights and save thirty percent of
25 electricity for lighting during the daytime. You can

PH-57

1 save natural gas by increasing installation.

2 I know there's Title 24 requirements for
3 building, but I'm talking about beyond that level of
4 compliance; so I think that would make a significant
5 difference, and it would reduce the energy impacts of
6 Hamilton Reuse.

7 As a case in point, if you look at this
8 building and look up at these lights, these lights are,
9 I don't know how many watts but quite a few, and of
10 course we need them at night. There's not enough light
11 outside to come inside.

12 Think of the use of this building. Ninety
13 percent of the time this is used in the daytime. In
14 the daytime they have these lights on all day. If they
15 had enough forethought in the planning of this building
16 to put in skylights throughout that would be
17 triple-glazed energy-efficient for not letting in too
18 much heat, they could turn off all these lights and
19 save all that juice all day long. It's something that
20 doesn't occur to people after the building is there.
21 It's just a fact that they've got fluorescent lights or
22 incandescent lights and you just pay the energy bills.

23 I would suggest look at the City of Novato's
24 new gymnasium, which has skylights. Compare their
25 energy bills now with what they used to pay before and

PH-57

1 see what the actual difference is in the savings only
2 on electricity. That's how you determine the impact of
3 utilities. Thank you.

4 COMMANDER DOHERTY: Thank you.

5 Mr. Moser.

6 MR. MOSER: Yes, my name is Dean Moser. I
7 live at 17 Germane Place in Domingo Canyon, Novato. I
8 don't live in Lanham Village like most of these people
9 here.

10 I would like to reiterate what I think even
11 the first speaker said, I think Mr. Bill Long, relative
12 to the alternatives of the use as proposed. One is
13 open space, and the other is "do nothing", and both of
14 those are not appropriate alternatives in my mind.

15 Novato only has three percent of its base
16 left for any kind of development. We all know what
17 kind of economic help the Vintage Oak Shopping Center
18 has been to the City of Novato, and, likewise, could
19 the same kind of help be achieved with the development
20 of Hamilton; not only that, but the housing, low-income
21 housing, as well as moderate-priced housing and
22 high-priced housing would be good alternatives for the
23 base itself.

24 I pass by Rafael Village and have for the
25 last thirty years. Right now with it all boarded up

PH-57

PH-58

PH-59

PH-60

1 and things not being maintained like they had to be
2 when they were under the Air Force control in
3 particular, it's getting pretty sloppy out there.

4 I think that the no -- the caretaker
5 alternative is just not feasible. The homes, the
6 buildings out there should be torn down as soon as
7 possible and then rebuilt with some design plan for
8 housing in that whole area. Thank you.

9 COMMANDER DOHERTY: Thank you. I think Dean
10 was the last speaker. Did we miss anybody else?

11 That was 21 speakers, and we've taken all
12 the comments seriously. I thank all the comments
13 tonight, and they will be taken seriously, and you were
14 heard loud and clear, and we've got them recorded.

15 As we move quickly through this process --
16 and let me say the Navy is supporting the quick
17 transition of this property and not the alternative of
18 the "do nothing". We're proceeding as best we can.
19 There were many players involved in this process.

20 Tonight we were here primarily to talk about
21 the so-called NEPA process. We continue to work on the
22 separate track, as mentioned by Doug, the clean-up
23 process and the sale of the land process, all are very
24 complicated.

25 I agree with Mr. Moser that we need to do

PH-60

1 this in conjunction with everyone's consideration as
2 quickly as possible so we can get places torn down.


3 So without any further questions, again,
4 thank you very much.

5
6
7 (WHEREIN, AT 9:15 P.M. THE
8 HEARING WAS CONCLUDED.)
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

REPORTER'S CERTIFICATE

I, THE UNDERSIGNED COURT REPORTER, DO HEREBY
CERTIFY THAT THE FOREGOING IS A FULL, TRUE AND CORRECT
TRANSCRIPT OF PROCEEDINGS HAD IN THE WITHIN-ENTITLED
CAUSE ON THE DATE HEREINBEFORE SET FORTH; AND I DO
FURTHER CERTIFY THAT THE FOREGOING TRANSCRIPT HAS BEEN
PREPARED BY ME.


RHONDA L. AQUILINA

Response to Comments

Response to Comment PH-1. The commenter's opinion that the No Action Alternative would have opportunity costs where the facilities would not be available to the citizens of Novato is noted.

Response to Comment PH-2. Removal and disposal of nonfriable asbestos-containing material in the housing areas will be the responsibility of the future owner of the housing.

Response to Comment PH-3. The significance criteria used for land use impacts is based on the California Environmental Quality Act (CEQA) Appendix G and the land use policies of the City of Novato General Plan for the definition of conflicting land uses. Land Use Policy 5 states that land use compatibility of specific development is to be determined by the appropriate City authority based on appearance, use characteristics, and proximity. Compatibility issues can arise from visual conflict, interference with established use, and negative physical impacts. Physical impacts that were considered in determining land use compatibility were air quality, noise, traffic, visual conflict, and hazardous materials. The specific impacts from these potential physical impacts are addressed throughout the EIS analysis and in Response to Comments Q-7 through Q-24.

Response to Comment PH-4. As discussed in Response to Comment Q-3, no specific plan for a corporation yard has been proposed, so no specific location for a theoretical corporation yard within the two planning areas is identified. This would allow flexibility for the actual siting of a corporation yard within the 41 acres contained within the two sites, especially given that only one corporation yard would be allowed within the two sites. The two planning areas where corporation yards would be allowed would be visible primarily from State Access Road for the Commissary Triangle and C Street for the Exchange Triangle. There is well-developed vegetation along the border between Lanham Village and the Exchange Triangle. Existing development on the Exchange Triangle site includes a large vehicle maintenance building, miscellaneous storage buildings, the Exchange building, and associated parking lots and fences. Proposed uses of this area would maintain the current visual character.

As discussed in Section 4.2, Planning Issues, subsequent design review by the City during the CEQA process for a specific development proposal would provide specific mitigation measures related to design and staging of landscape installation. If the time to establish vegetation were an issue, mitigation measures for a specific development proposal could specify that landscaping consist of primarily mature landscape plants that would provide immediate screening benefits. It is likely that specific mitigations to screen a corporation yard or repair facility from surrounding roadways or land uses would include a combination of landscaping and fences.

Response to Comment PH-5. See Response to Comment Q-6 regarding the Navy's determination as to whether this project would have disproportionate significant and adverse impacts on minority and low-income populations.

Response to Comment PH-6. As discussed in Response to Comment Q-18, air quality dispersion modeling analysis results presented in the Draft EIS already assumes the vehicle volumes calculated to occur with operation of a corporation yard. With regard to the potential air quality impacts associated with operation of the Novato Unified School District's (NUSD's) proposed vehicle training facility, as described in Response to Comment Q-3, the proposed facility would not serve as a routine maintenance facility. Only repairs that provide educational opportunities for student mechanics would be performed there. The NUSD estimates that approximately three to four vehicles would be at the facility at any given time. Since vehicles would be serviced inside the facility, all applicable regulations regarding ventilation and air filtration would be observed. The NUSD proposes \$1.5 million in renovation to the building, which would presumably include installation of appropriate ventilation and noise controls. Overall, the use of Building 972 would be similar to historic Navy use of the building as a vehicle maintenance shop.

Response to Comment PH-7. Section 4.12 of the EIS identifies a construction schedule of 7 AM to 7 PM as mitigation for construction noise. This mitigation is consistent with the general plan level of impact analysis conducted in the EIS. Once specific proposals are submitted to the City for review and approval, definitive plans such as construction schedules will be developed. In addition, available information does not indicate the need for an extended period of demolition and construction activity near Lanham Village.

Response to Comment PH-8. As discussed in Response to Comment Q-3, specific site proposals for a corporation yard have not been proposed. No designs or detailed use proposals were provided for use in the EIS impact analysis. Consequently, the EIS has addressed issues at a general plan level of detail. Impacts requiring analysis at a site design level of detail should be evaluated by the City of Novato or the school district in subsequent project-specific CEQA documents. However, the noise analysis presented in the EIS does incorporate a level of heavy truck traffic that encompasses the traffic that would be generated by a corporation yard.

As described in Response to Comment Q-2, the NUSD bus repair facility would be used for educational purposes only. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. Daily operation and routine

maintenance such as oil changes, washing, fueling, and daily parking and staging of buses would continue to operate from the NUSD's 809 Olive Avenue location. Vehicle repair activity would take place inside a building rather than outdoors, substantially reducing noise levels at adjacent properties.

In addition, the city and school district should consider the mitigation measures outlined in Response to Comment Q-22 when developing plans for a corporation yard and bus repair facilities.

Response to Comment PH-9. Hazardous material use and waste generated would be subject to appropriate local, state, and federal regulations to prevent impacts to the human and natural environment. As such, no significant impacts from hazardous materials and waste would result from corporation yards or a bus repair facility.

Response to Comment PH-10. The base closure and reuse process includes an exhaustive characterization of the condition of property to be transferred. Extensive information on past hazardous materials use and storage is provided in the EBS. See Response to Comment Q-4 for a discussion of sampling. See also Response to Comments N-1 and N-2 regarding asbestos and lead-based paint hazards and remediation. Where contamination is identified, the federal entity is required to clean up the site to a level protective of human health and the environment. The Navy is committed to remediation of contamination at DODHF Novato consistent with applicable federal and state regulations prior to transfer and reuse of the property. All cleanup activities follow strict procedures to avoid the release of contaminants during cleanup.

Response to Comment PH-11. The comments regarding provision of open space in the area are noted.

Response to Comment PH-12. The comment opposing the reduction of affordable housing in the Open Space Alternative is noted.

Response to Comment PH-13. The commenter's opposition to the Open Space Alternative is noted.

Response to Comment PH-14. The commenter's objection to corporation yards and a bus repair facility is noted. The land use compatibility analysis in the EIS is based on Land Use Policy 5 of Novato's General Plan that states that land use compatibility of specific development is to be determined by the appropriate City authority based on appearance, use characteristics, and proximity. Compatibility issues can arise from visual conflict, interference with established use, and negative physical impacts. With regard to a corporation yard, physical impacts that were considered in determining land use compatibility were air quality, noise, traffic, visual conflict, and hazardous

materials. The specific impacts from these potential physical impacts are addressed throughout the EIS analysis. Effects from traffic, noise, and air pollution are further clarified in Response to Comments Q-16 through Q-22. The traffic analysis, and subsequent air and noise analyses, take into consideration a level of heavy truck traffic that encompasses vehicular activity resulting from a corporation yard or a bus repair facility. These analyses were found to have nonsignificant or mitigable traffic, air, and noise impacts on existing land uses.

Response to Comment PH-15. The commenter's opinions are noted. The EIS evaluates the potential effects of a theoretical corporation yard. No specific proposal for such a facility has been made, nor does the Reuse Plan recommend such a use. Responses to comments Q-2 and Q-3 detail the NUSD bus repair facility proposal and describe a theoretical corporation yard used in the EIS analysis. The land use compatibility analysis in the EIS is based on Land Use Policy 5 of Novato's General Plan that states that land use compatibility of specific development is to be determined by the appropriate City authority based on appearance, use characteristics, and proximity.

Response to Comment PH-16. The commenter's objections to a corporation yard and bus repair facility are noted.

Response to Comment PH-17. The commenter's objections to a corporation yard and bus repair facility are noted. The Response to Comment Q-2 clarifies the NUSD bus repair training facility proposal. As stated in this response, the facility would be used for educational purposes only. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. It is envisioned that in addition to the district's bus and vehicle fleet of 39 and 31 vehicles, respectively, educational maintenance opportunities could be expanded to other districts and agencies. Daily operation and routine maintenance such as oil changes, washing, fueling, and daily parking and staging of buses would continue to operate from the NUSD's 809 Olive Avenue location. It is envisioned that a maximum of three to four buses would be located on the site at any given time, and repairs would occur inside of Building 972.

Response to Comment PH-18. The Response to Comment Q-2 clarifies the NUSD proposal for activities on its requested public benefit conveyance. As stated in this response, the facility would be used for educational purposes only. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. It is envisioned that in addition to the district's bus and vehicle fleet of 39 and 31 vehicles, respectively, educational maintenance opportunities could be expanded to other districts and agencies. Daily operation and routine maintenance such as oil changes, washing, fueling, and daily parking and staging

of buses would continue to operate from the NUSD's 809 Olive Avenue location. It is envisioned that a maximum of three to four buses would be located on the site at any given time, and repairs would occur inside of Building 972. As described in Response to Comment Q-18 and Q-22, noise would be substantially dampened and fumes controlled since the repairs would occur inside a facility rather than outside. Hazardous material use and waste generated would be subject to appropriate local, state, and federal regulations to prevent impacts to the human and natural environment. As such, no significant impacts from hazardous materials and waste would result from a bus repair facility.

Response to Comment PH-19. An asbestos survey has been completed for all housing areas at DODHF Novato, including Rafael Village. Asbestos-containing materials (ACM) were identified in all housing areas; however, asbestos that was both damaged and friable was not identified in Rafael Village. The Navy's policy is that property with ACM will not be disposed of through the Base Realignment and Closure (BRAC) process unless the ACM does not pose a threat to human health at the time of transfer. Asbestos-containing materials that are not damaged and friable are not considered to pose a health risk and will therefore not be abated. The US Environmental Protection Agency (USEPA) and the Bay Area Air Quality Management District (BAAQMD) have strict regulations regarding emissions of airborne asbestos. These regulations would generally require that asbestos be removed from buildings prior to large-scale demolition, in order to reduce the risk of airborne asbestos emissions. Removal would reduce the potential for impacts from asbestos releases. Removal would be the responsibility of the site owner and the demolition contractor. Rafael Village does not meet current building codes for many reasons; the houses have not been condemned because of the presence of asbestos, as implied in the comment.

Response to Comment PH-20. The Best Management Practices (BMPs) have been clarified and expanded in Response to Comments K-2 and L-9. BMPs include detaining and treating runoff on site, placement of erosion-control measures including straw bales and silt fences, and the use of other soil stabilization techniques to be specified in specific erosion-control plans to be developed in compliance with Storm Water Pollution Prevention Plans required as part of the National Pollutant Discharge Elimination System (NPDES) construction stormwater permits.

Response to Comment PH-21. The historical traffic generation for the DODHF Novato is identified as 1,024 vehicle trips during the AM peak hour and 1,727 trips during the PM peak hour. This is based on full occupancy of the Reuse Plan area, which would be reflective of about year 1990 conditions. This total reflects occupancy of the portions of the Hamilton Army Airfield (HAAF) area currently under study in the Reuse Plan. It does not include Lanham Village or the New Hamilton Partnership areas. Lanham Village, which was converted to civilian use in 1983, is not included in this total because

it was no longer a part of the HAAF area. The New Hamilton Partnership portion of the Main Site has been inactive for a number of years so was not included in this total.

Response to Comment PH-22. The issue of the civilian versus noncivilian residential trip generation estimates is addressed in Response to Comment K-4.

The commenter indicates that the trip purposes of the military residential uses are likely to be no different from those of the civilian use. The types of trips described for the military residential uses are dropping children off at school, trips to the grocery store, gymnastics, soccer, or baseball. These types of trips are common to all residential areas with families. The primary difference is that the HAAF housing areas are designated as "family housing" so nearly every military person living on the base has children. The average household size is larger than a typical residential area occupied by a wider mix of families, single people, and retired people. As a result, the military family housing areas generate more vehicle trips per day for precisely the types of trips referenced in the comment.

Response to Comment PH-23. The USEPA and the BAAQMD have strict regulation regarding emissions of airborne asbestos. These regulations would generally require that asbestos be removed from buildings prior to large-scale demolition. Removal would be the responsibility of the site owner and the demolition contractor.

The air quality analysis has been revised based on Navy guidance to evaluate the effects of air quality against preclosure conditions (an operational base) when preclosure conditions are accounted for in the State Implementation Plan (SIP). The SIP, submitted to and approved by the USEPA, is the plan for achieving attainment of the federal ambient air quality standards. A different SIP is prepared for each nonattainment pollutant. The 1994 Bay Area Clean Air Plan, the portion of the SIP that covers the Bay Area, is based on land use and transportation patterns that existed in the early 1990s (preclosure conditions). Because most military installations are accounted for in the air quality plan as active facilities, the preclosure activity scenario provides a useful basis for judging the extent to which reuse alternative cause increases or decreases in traffic-related emissions. Compared to preclosure emission levels, the alternatives evaluated in the EIS would result in emission levels well below the BAAQMD impact significance thresholds (Revised Reuse Plan Alternative) as well as below preclosure emission levels (Open Space and No Action Alternatives). The text in Section 4.11 has been revised to reflect this new analysis and Table 4-20 revised to show that no significant ozone precursor, carbon monoxide, or air quality plan consistency impacts will occur under any of the alternatives. As also discussed in Section 4.11.2 and 4.11.3, significant but mitigable construction and demolition impacts would occur under the Revised Reuse Plan and Open Space Alternatives.

Response to Comment PH-24. The asbestos survey included a random sampling from each housing area at DODHF Novato. Asbestos-containing materials were identified in all housing areas; however, asbestos that was friable was identified only in Spanish Housing. The Navy's policy is that property with ACM will not be disposed of through the BRAC process unless the ACM does not pose a threat to human health at the time of transfer. Asbestos-containing materials that are not damaged and friable are not considered to pose a health risk and will therefore not be abated. Only asbestos-containing material that is damaged, friable, and accessible would be repaired or removed prior to transfer.

Response to Comment PH-25. The Navy is not required by federal law to abate lead-based paint (LBP) hazards in housing constructed between 1960 and 1978. Consistent with Navy policy and federal law, the Navy will disclose the result of its LBP assessment to potential purchasers of housing constructed between 1960 and 1978. The Navy will abate LBP hazards in accordance with federal requirements in housing constructed prior to 1960. As the Capehart units were constructed after 1960, no LBP abatement is required.

Response to Comment PH-26. The Navy does not plan any further action on the issue of lead in soils at Capehart. No drinking water surveys are required under federal regulations and none are anticipated prior to disposal.

Response to Comment PH-27. The commenter's opinions regarding suitability of sites for transfer are noted.

Response to Comment PH-28. The commenter's objection to a corporation yard or bus repair facility is noted. The NUSD proposal for a bus repair training facility is clarified in Response to Comment Q-2. As stated in this response, the facility would be used for educational purposes only. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. It is envisioned that in addition to the district's bus and vehicle fleet of 39 and 31 vehicles, respectively, educational maintenance opportunities could be expanded to other districts and agencies. Daily operation and routine maintenance such as oil changes, washing, fueling, and daily parking and staging of buses would continue to operate from the NUSD's 809 Olive Avenue location. It is envisioned that a maximum of three to four buses would be located on the site at any given time, and repairs would occur inside of Building 972.

Response to Comment PH-29. The commenter's support of certain uses is noted. The effects of a theoretical corporation yard and a bus repair training facility on air quality and noise are amplified in

Response to Comments Q-18 and Q-22, respectively. As indicated by these responses, the analysis in the EIS takes into the account the traffic and associated air emissions and noise that would be generated by such activities. These responses further clarify the effects of the NUSD facility based on the level of projected activity and the fact that repairs would take place indoors, lessening the effects of noise and air pollution.

Response to Comment PH-30. The commenter's statement of existing use compatibility is noted. The analysis in the EIS evaluates the potential environmental and socioeconomic effects based on buildout of the Reuse Plan and alternatives. The level of activity under reuse would be slightly less than the level of activity under a fully active base.

Response to Comment PH-31. The commenter's submittal of photos taken in the vicinity of the Exchange Triangle and Commissary Triangle is noted.

Response to Comment PH-32. The commenter's support of the Revised Reuse Plan Alternative analysis is noted.

Response to Comment PH-33. The traffic noise effects of a theoretical corporation yard and the NUSD bus repair training facility are presented in Section 4.12. The resulting noise, as stated in Section 4.12, was found to be within the City noise and land use compatibility standards for residential uses. The noise effects of these activities are further clarified in Response to Comment Q-22. As stated in this response, vehicular repair activity would take place indoors, which would dampen noise generated by repair activity. This response also offers additional mitigation measures that could be implemented by the City once specific proposals were submitted for formal City review and approval.

Response to Comment PH-34. Public benefit conveyances would only be approved following completion of the Navy's EIS process. As described in Response to Comment Q-2, the NUSD bus repair training facility would be used for educational purposes. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. Daily operation and routine maintenance such as oil changes, washing, fueling, and daily parking and staging of buses would continue to operate from the NUSD's 809 Olive Avenue location. It is envisioned that a maximum of three to four buses would be located on the site at any given time, and repairs would occur inside of Building 972.

Response to Comment PH-35. The asbestos survey included a random sampling from each housing area at DODHF Novato. Asbestos-containing materials were identified in all housing areas; however,

asbestos that was friable was identified only in Spanish Housing. The Navy's policy is that property with ACM will not be disposed of through the BRAC process unless the ACM does not pose a threat to human health at the time of transfer. Asbestos-containing materials that are not damaged and friable are not considered to pose a health risk and will therefore not be abated. Only asbestos-containing material that is damaged, friable, and accessible would be repaired or removed prior to transfer.

LBP hazards and abatement responsibilities are addressed in Response to Comment PH-25.

Response to Comment PH-36. Lead in the soil and drinking water testing responsibilities are addressed in response to comment PH-26.

Response to Comment PH-37. The commenter's statement of existing scenic quality is noted. The Open Space Alternative evaluates a less developed DODHF Novato site overall, though some specific areas may project more development than under the Revised Reuse Plan Alternative. Corporation yards were evaluated in the EIS based on comments received during scoping specifically requesting that this use be analyzed. Because corporation yards were not endorsed by the Reuse Plan, they were analyzed under the Open Space Alternative at a general plan level of detail to determine the potential effects of such a reuse.

Response to Comment PH-38. The commenter's statement of the value of Lanham Village's location at the entrance to the former base is noted. The scenic, air quality, and noise effects on Lanham Village have been evaluated in the EIS and have been further clarified in the Response to Comments Q-12, Q-18, and Q-22, respectively.

As discussed in Response to Comment Q-12, no specific plan for a corporation yard has been proposed, so no specific location for a theoretical corporation yard within the two planning areas is identified. This would allow flexibility for the actual siting of a corporation yard to reduce visual impacts. As discussed in Section 4.2, Planning Issues, subsequent design review by the City during the CEQA process for a specific development proposal would provide specific mitigation measures related to design and staging of landscape installation. It is likely that specific mitigations to screen a corporation yard or repair facility from surrounding roadways or land uses would include a combination of landscaping and fences.

Air quality and noise effects of a theoretical corporation yard and a bus repair facility have been incorporated into the air quality and noise analyses included in the EIS. The proposed NUSD bus repair facility is detailed in Response to Comment Q-2, and the Response to Comments Q-18 and Q-22

further clarify the potential effects of the NUSD bus repair facility. Repairs would occur inside of Building 972, which would provide shielding from noise and would control and direct air emissions in compliance with local and state regulations.

Response to Comment PH-39. The commenter's objection to a corporation yard and bus repair facility is noted.

Response to Comment PH-40. The commenter's concerns about cumulative traffic, air quality, and noise effects is noted. The commenter is referred to Section 5.1.2 of the EIS for a discussion of the cumulative effects of reuse and other projects within the area. A cumulative traffic analysis and subsequent cumulative air quality and noise analyses indicate that cumulative effects would be less under the reuse alternatives than under the City's preferred general plan scenario.

Response to Comment PH-41. The commenter's objection to the location of a corporation yard in the vicinity of Lanham Village is noted. No specific proposal for a corporation yard exists at this time. The NUSD's proposal for a bus repair training facility has been clarified in Response to Comment Q-2. As discussed in this response, the facility would be used for educational purposes. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. Daily operation and routine maintenance such as oil changes, washing, fueling, and daily parking and staging of buses would continue to operate from the NUSD's 809 Olive Avenue location. It is envisioned that a maximum of three to four buses would be located on the site at any given time. Repairs would occur inside of Building 972, which would undergo renovation. Although specific plans have not been developed for the renovation, the facility would have to comply with all applicable health and safety regulations regarding reduction of noise and air contaminants. In addition, the facility would have to comply with all local, state, and federal regulations regarding the use of hazardous materials and generation of hazardous waste products.

Response to Comment PH-42. The commenter's objection to commercial and industrial uses around Lanham Village is noted.

Response to Comment PH-43. Comment noted.

Response to Comment PH-44. Comment noted. Navy policy is that hazardous materials and wastes will be removed from the site prior to disposal of the property, and that contaminated areas will be remediated to the full extent required by applicable laws and regulations prior to transfer.

Response to Comment PH-45. The EIS evaluates the environmental impacts to all segments of the population.

Response to Comment PH-46. The response to Comment Q-2 clarifies the NUSD proposal for a bus repair training facility. As stated in this response, the facility would be used for educational purposes only. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. It is envisioned that in addition to the district's bus and vehicle fleet of 39 and 31 vehicles, respectively, educational maintenance opportunities could be expanded to other districts and agencies. Daily operation and routine maintenance such as oil changes, washing, fueling, and daily parking and staging of buses would continue to operate from the NUSD's 809 Olive Avenue location. It is envisioned that a maximum of three to four buses would be located on the site at any given time, and repairs would occur inside of Building 972.

Response to Comment PH-47. The commenter's opinions are noted.

Response to Comment PH-48. The effects of traffic are addressed in Section 4.10 of the EIS and details of the traffic analysis are included in Appendix G of the EIS. As stated in these sections, the traffic analysis included an evaluation of the effects of project-related traffic on existing intersection operations. This analysis determined that the traffic generated by reuse would result in levels of service that are better than those projected under cumulative traffic conditions under the City of Novato's preferred General Plan.

Response to Comment PH-49. The air quality impact assessment addresses the potential for both localized air quality problems and regional air quality problems. Emissions from vehicle traffic will occur over the entire route of vehicle travel, and will then be spread over an even larger geographic area by atmospheric dispersion processes. The analysis notes that no localized carbon monoxide problems are expected. As discussed in Response to Comment PH-23, air quality analysis comparing the two reuse alternatives against preclosure conditions found that emissions from the Revised Reuse Alternative would be below BAAQMD significance thresholds and emissions from the Open Space Alternative would be below preclosure conditions.

Response to Comment PH-50. Table 4-23 summarizes anticipated noise levels at various distances from roadways with significant traffic volumes. Roadways with high traffic volumes and high vehicle speeds are the dominant source of traffic noise. Roadways with low traffic volumes and low speeds will not generate traffic noise levels that exceed land use compatibility criteria for noise-sensitive land uses.

For roadways with vehicle speeds of about 35 mph, it takes a daily traffic volume of close to 4,000 vehicles (including about 130 heavy vehicles) to generate CNEL levels above 60 dB at a distance of 50 feet from the roadway centerline.

Response to Comment PH-51. The commenter's opinion is noted. The NUSD proposal for a bus repair training facility is clarified in Response to Comment Q-2.

Response to Comment PH-52. The commenter's opinion that the school district was over-represented on the Hamilton Advisory Committee is noted.

Response to Comment PH-53. The NUSD proposal for a bus repair training facility is clarified in Response to Comment Q-2. As stated in this response, the facility would be used for educational purposes only. Only those vehicles whose repair would provide educational opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. It is envisioned that in addition to the district's bus and vehicle fleet of 39 and 31 vehicles, respectively, educational maintenance opportunities could be expanded to other districts and agencies. Daily operation and routine maintenance such as oil changes, washing, fueling, and daily parking and staging of buses would continue to operate from the NUSD's 809 Olive Avenue location. It is envisioned that a maximum of three to four buses would be located on the site at any given time, and repairs would occur inside of Building 972.

Response to Comment PH-54. The commenter's objection to a corporation yard is noted. Corporation yards have been evaluated in the EIS on a theoretical basis. No specific plan for a corporate yard has been submitted, nor does the Reuse Plan endorse corporation yards. Air pollution and noise from such a use has been evaluated in the EIS and further clarified in Response to Comments Q-18 and Q-22. Any specific proposals for a corporation yard would have to undergo City review and approval processes, including additional environmental review.

Response to Comment PH-55. The commenter's support of stated land uses is noted.

Response to Comment PH-56. The commenter's opinions are noted. As stated in response to previous comments, the EIS evaluates the effects of a theoretical corporation yard. No specific plans for such a use have been proposed, nor does the Reuse Plan endorse such a use. Any such proposal made in the future would be subject to City review and additional environmental documentation. The proposed NUSD bus repair training facility is described more clearly in Response to Comment Q-2. The facility would be used for educational purposes; only those vehicles whose repair would provide educational

opportunities for the listed programs, such as an engine overhaul, would be brought to this facility. It is envisioned that in addition to the district's bus and vehicle fleet of 39 and 31 vehicles, respectively, educational maintenance opportunities could be expanded to other districts and agencies. Daily operation and routine maintenance such as oil changes, washing, fueling, and daily parking and staging of buses would continue to operate from the NUSD's 809 Olive Avenue location. It is envisioned that a maximum of three to four buses would be located on the site at any given time, and repairs would occur inside of Building 972.


Response to Comment PH-57. Analysis of impacts on utilities are discussed in Section 4.5. Most of the buildings at DODHF Novato would be reused in their existing capacity and condition. In addition, buildout densities of areas of new construction (Rafael Village) would be similar to densities under historic conditions. As such, utility demands would not exceed historic levels and no additional burden on infrastructure or utility capacities would result. Any new construction would be subject to local building codes and will undergo appropriate review procedures at that time. No specific building plans exist at this time and therefore impacts are assessed at a general program level rather than a specific level.

Response to Comment PH-58. The commenter's opinions regarding appropriateness of alternatives is noted.

Response to Comment PH-59. The commenter's opinions regarding additional alternatives are noted.

Response to Comment PH-60. The commenters opinions regarding the caretaker status for Rafael Village are noted.

**DODHF
Novato**



APPENDIX A

PHOTO DOCUMENTATION

APPENDIX A PHOTO DOCUMENTATION

Appendix A presents photographs of DODHF Novato and the surrounding areas. The photos are meant to be used in conjunction with Figure A-1, which shows the location of each planning area.

Photo 1, Rafael Village (Planning Area 1): One of 503 similar housing units in Rafael Village. The housing units have landscaped lawns, fenced backyards, and mature trees in the front yards.

Photo 2, Rafael Village (Planning Area 1): Rafael Village is surrounded by typically newer residential neighborhoods.

Photo 3, Capehart Housing (Planning Area 2): The Hillside Housing subarea, which includes 150 two-story, sixplex units, is located in the southeast corner of Capehart Housing.

Photo 4, Capehart Housing (Planning Area 2): Capehart Housing includes a variety of housing types. Four wooded knolls are located in the central and southwestern portions of the area.

Photo 5, Capehart Housing (Planning Area 2): Capehart Housing includes a number of styles of multiple family housing units.

Photo 6, Capehart Housing (Planning Area 2): Hamilton School is an elementary school located in the Capehart Housing area.

Photo 7, Commissary Triangle (Planning Area 4): The Commissary Triangle consists of warehouse buildings and parking lots. Christmas Tree Hill borders the area to the west, separating it from US 101.

Photo 8, Commissary Triangle (Planning Area 4): The Commissary is still in use.

Photo 9, Exchange Triangle (Planning Area 5): The Exchange Triangle area contains the Navy Exchange, youth center, gas station, and credit union.

Photo 10, Town Center (Planning Area 6): The Chapel building, located along Palm Drive, is in use as a chapel and Sunday school.

Photo 11, Town Center (Planning Area 6): The Hamilton AFB Theater and NCO Club, two of the four building in the Town Center planning area, are part of the original base architecture and are eligible for nomination to the National Register of Historic Places.


Photo 12, Bowling Alley (Planning Area 8): The bowling alley building, one of two buildings in the planning area, was constructed in 1945 and renovated in 1982.

Photo 13, Bowling Alley (Planning Area 8): The gymnasium contains indoor racquetball courts.

Photo 14, Officers' Club (Planning Area 9): The former Officers' Club, located on a hill adjacent to Spanish Housing, now serves as the Community Center.

Photo 15, Ballfields (Planning Area 10): The planning area includes two regulation and two Little League fields.

Photo 16, Ballfields (Planning Area 10): The swimming pool and poolhouse are located on a hill next to the ballfields.



DODHF Novato Planning Areas

DOD Housing Facility
Novato, California


Figure A-1

The Hamilton Army Airfield Reuse Plan divides the former base into 10 planning areas. This EIS evaluates the disposal and reuse of the eight Navy-owned planning areas. The two remaining planning areas, Hospital Hill and Spanish Housing, are owned by the Army and USCG, respectively.


Source: Hamilton Reuse Planning Authority 1995




1: Rafael Village (Planning Area 1) - Typical single-story housing unit




2: Rafael Village (Planning Area 1) - Adjacent land use



3: Capehart Housing (Planning Area 2) - A typical multiple family housing unit in Hillside Housing



4: Capehart Housing (Planning Area 2) - Example of a single family housing unit




DODHF Novato Planning Areas

DOD Housing Facility
Novato, California


Figure A-1

The Hamilton Army Airfield Reuse Plan divides the former base into 10 planning areas. This EIS evaluates the disposal and reuse of the eight Navy-owned planning areas. The two remaining planning areas, Hospital Hill and Spanish Housing, are owned by the Army and USCG, respectively.

Source: Hamilton Reuse Planning Authority 1995




5: Capehart Housing (Planning Area 2) - Typical multiple family housing units




6: Capehart Housing (Planning Area 2) - Hamilton School



7: Commissary Triangle (Planning Area 4) - Overview from Christmas Tree Hill



8: Commissary Triangle (Planning Area 4) - The commissary building



DODHF Novato Planning Areas

DOD Housing Facility
Novato, California


Figure A-1

LEGEND:

| | | | |
|-----|---------------------|------|----------------|
| (1) | Rafael Village | (6) | Town Center |
| (2) | Capehart Housing | (8) | Bowling Alley |
| (4) | Commissary Triangle | (9) | Officers' Club |
| (5) | Exchange Triangle | (10) | Ballfields |

The Hamilton Army Airfield Reuse Plan divides the former base into 10 planning areas. This EIS evaluates the disposal and reuse of the eight Navy-owned planning areas. The two remaining planning areas, Hospital Hill and Spanish Housing, are owned by the Army and USCG, respectively.


Source: Hamilton Reuse Planning Authority 1995



9: Exchange Triangle (Planning Area 5) - The Navy Exchange Building




11: Town Center (Planning Area 6) - Hamilton AFB Theater is part of the original base architecture



10: Town Center (Planning Area 6) - The Chapel located along Palm Drive



12: Bowling Alley (Planning Area 8) - The bowling alley contains 10 lanes



DODHF Novato Planning Areas

DOD Housing Facility
Novato, California


Figure A-1

The Hamilton Army Airfield Reuse Plan divides the former base into 10 planning areas. This EIS evaluates the disposal and reuse of the eight Navy-owned planning areas. The two remaining planning areas, Hospital Hill and Spanish Housing, are owned by the Army and USCG, respectively.

Source: Hamilton Reuse Planning Authority 1995



13: Bowling Alley (Planning Area 8) - The gymnasium houses racquetball courts



14: Officers' Club (Planning Area 9) - The former Officers' Club serves as the Community Center




15: Ballfields (Planning Area 10) - The area includes two regulation and two Little League fields



16: Ballfields (Planning Area 10) - The swimming pool and poolhouse

**DODHF
Novato**



APPENDIX B

PUBLIC INVOLVEMENT

PUBLIC SCOPING

SCOPING LETTER B-2

NOTICE OF INTENT B-9

NEWSPAPER ADVERTISEMENT B-11

SCOPING SUMMARY B-12

DRAFT EIS PUBLIC REVIEW

NOTICE OF PUBLIC HEARING B-14

NOTICE OF AVAILABILITY B-16

NEWSPAPER ADVERTISEMENT B-18

APPENDIX B PUBLIC INVOLVEMENT

As discussed in Section 1.5 of this document, the NEPA process is designed to involve the public in the federal decision making process. Appendix B contains the public involvement materials used to inform federal, state, and local agencies, elected officials, organizations, and individuals about this EIS process.

Public Scoping

A scoping letter, including a project summary and location maps, was developed to announce the Navy's intent to prepare the DODHF Novato Disposal and Reuse EIS, the start of the public scoping period, and the scoping meeting. A Notice of Intent (NOI) was published in the Federal Register and a summary of the NOI and scoping meeting information was published in three local newspapers. The scoping summary presents the written and verbal comments received during the scoping period.

Draft EIS Public Review

A notice of public hearing and executive summary were mailed to elected officials, agencies, organizations, and individuals on the distribution list (Chapter 10). A Notice of Availability (NOA) was published in the Federal Register, and a summary of the NOA and public hearing information was published in three local newspapers. A transcript of the public hearing and comment letters received on the Draft EIS are included as Appendix C to the Final EIS.



DEPARTMENT OF THE NAVY

ENGINEERING FIELD ACTIVITY, WEST
NAVAL FACILITIES ENGINEERING COMMAND
900 COMMODORE DRIVE
SAN BRUNO, CALIFORNIA 94066-5006

IN REPLY REFER TO :

5090.1
Ser 185/P5-859

November 1, 1995

PUBLIC NOTICE

Subject: Notice of Scoping of Public Concerns regarding an Environmental Impact Statement on the disposal and reuse of the Department of Defense Housing Facility Novato, California

The United States Department of the Navy, with the City of Novato, is preparing a National Environmental Policy Act (NEPA) Environmental Impact Statement (EIS) on the disposal and proposed reuse of the Department of Defense Housing Facility (DODHF) property and structures located in Novato, California. The Defense Base Closure and Realignment Act (Public Law 101-510), as implemented by the 1993 base closure process, directs the U.S. Navy to dispose of DODHF. The EIS will be prepared in accordance with Section 102(2)(c) of the National Environmental Policy Act of 1969 as implemented by the Council on Environmental Quality regulations (40 CFR Parts 1500-1508).

DODHF is within the jurisdiction of the City of Novato in Marin County, approximately 20 miles north of San Francisco. DODHF is one of several facilities on a larger area formerly known as the Hamilton Air Force Base. DODHF consists of approximately 481 acres of Navy-owned land in two sites. The 383 acre primary DODHF includes military family housing, commissary, exchange, community service areas, bowling alley, officer's club, and recreational fields. An additional 98 acre Rafael Village military housing area is located one mile north of the main DODHF facility. Other portions of the former Hamilton Air Force Base adjacent to DODHF, and not included with the disposal of the DODHF property or in this disposal and reuse EIS, include the 720 acre former Hamilton Army Airfield, which was closed under the Defense Base Closure and Realignment Act of 1988, and a 415 acre site being developed under the New Hamilton Partnership Master Plan.

The EIS will address the disposal of the property and the potential impacts to the environment that may result from reuse development and a "No Action" alternative. The Hamilton Army Airfield Reuse Plan, developed by the Hamilton Reuse Planning Authority and adopted by the City of Novato on October 24, 1995, will serve as the basis for the preferred alternative. The Reuse Plan proposes 406 acres of housing with up to 1,490 total units, 51 acres of mixed use community support facilities, and up to 24 acres of recreational fields on the DODHF property. The alternatives analyzed in the EIS will include a less intensive development of the DODHF property, still based in large part upon the Reuse Plan, and such other reasonable alternatives as may evolve through the public involvement process. The No Action alternative would have DODHF remain federal government property in a caretaker status.

Probable environmental impacts that will be addressed in the EIS include such resources as: land use, public policy conformity, socioeconomics, cultural resources, transportation including traffic and parking, vegetation and wildlife, air quality, noise, aesthetics, geology and soils, hydrology, seismicity, hazardous materials, municipal services and utilities.

Federal, State, and local agencies, and interested groups and individuals, are encouraged to participate in the scoping process, to assist in determining the range and depth of issues and alternatives to be addressed.


A public scoping meeting to receive oral and written comments regarding the proposed disposal and potential reuse of the DODHF will be held on **Thursday, November 16, 1995**, from 7:00 p.m. to approximately 10:00 p.m., in the Student Center at San Marin High School, 15 San Marin Drive, Novato, California. Navy and City representatives will briefly summarize the environmental impact assessment and the reuse planning processes, and will then solicit public comments on the scope of environmental impact analysis studies. In the interest of allowing everyone a chance to participate, speakers will be requested to limit their oral comments to approximately five minutes or less, and may submit more lengthy or detailed comments in writing. All substantive comments will be addressed in the EIS.

Additionally, the Navy and City invite and encourage the public to express in writing their comments and concerns regarding the action above. Affected Federal, State, and local agencies and other interested groups and individuals should submit their written comments to:

U.S. Navy, Engineering Field Activity West
Naval Facilities Engineering Command
900 Commodore Drive
San Bruno, CA 94066-5006
Attn.: Mr. Gary Munekawa, Environmental Planning Branch, Code 185

Mr. Munekawa's fax number is (415) 244-3737, and telephone is (415) 244-3022. Written comments must be postmarked no later than **December 1, 1995**, in order to assure their full consideration in the EIS preparation. For information concerning the Hamilton Army Airfield Reuse Plan process, please contact Mr. Ken Bell at the City of Novato, Hamilton Reuse Planning Authority, telephone (415) 457-5661 or fax number (714) 472-8122.

Thank you for participating with the Navy and the City in the environmental planning process.


JOHN H. KENNEDY
Head, Environmental Planning Branch

ATTACHMENT A
DEPARTMENT OF DEFENSE HOUSING FACILITY NOVATO DISPOSAL AND REUSE

I. INTRODUCTION

The Department of Defense Housing Facility (DODHF) in Novato, California has been identified for closure under the Defense Base Closure and Realignment Act, as implemented by the 1993 base closure process. In accordance with the National Environmental Policy Act (NEPA), the Navy is preparing this Environmental Impact Statement (EIS) to evaluate the environmental effects of disposal and reuse of the DODHF property and structures.

II. HISTORY AND LOCATION

The former Hamilton Army Airfield is located in southeast Novato, eastern Marin County, approximately 20 miles north of San Francisco (Figure 1). The original installation was established in 1934 as the first West Coast Army Air Corps facility. The facility was transferred to the Air Force in the 1940s. Beginning in 1974, the Air Force discontinued its operations, and slowly excessed the property. The housing, personnel support, and recreation portions of the base were transferred to the Navy to form the DODHF. Small portions were also transferred to the Army, with the Army officially acquiring the Airfield in July 1984. In March 1976, parts of the base were declared excess property and assigned to the GSA for property disposal. The excessed portions are now being developed by the New Hamilton Partnership. The Army-owned portions of the base were slated for closure under the 1988 base closure decision.

DODHF, operated by the Navy Public Works Center San Francisco, is comprised of approximately 481 acres of Navy-owned land on two sites: 383 acres on the Main Site and 98 acres at Rafael Village, an off-site military housing area.

III. REUSE PLAN

Development of the Hamilton Army Airfield Reuse Plan was initiated in 1994 for the purpose of defining a community reuse plan for the entire Hamilton complex, including DODHF, the Army-owned parcels, and the New Hamilton Partnership development area. The Draft Hamilton Army Airfield Reuse Plan was approved by the City of Novato in October 1995.

The Hamilton Army Airfield Reuse Plan divides Hamilton into 10 planning areas (PAs). Nine of these are Navy-owned and include: Rafael Village (PA 1), Capehart Housing (PA 2), Spanish Housing (PA 3), Commissary Triangle (PA 4), Exchange Triangle (PA 5), Town Center (PA 6), Bowling Alley (PA 8), Officers Club (PA 9), and Ballfields (PA 10). The remaining planning area is the Army-owned Hospital Hill (PA 7). These areas are delineated on Figure 2. Navy-owned planning areas are described below.

Planning Area 1: Rafael Village

Rafael Village is a 98-acre off-site military housing area constructed in the early 1950s. Rafael Village consists of a community center building, a maintenance yard, and 503 one-, two-, and three-bedroom housing units situated in a linear configuration along Ignacio Boulevard. The site contains significant amounts of open space, and mature trees line the streets. San Jose Creek flows behind a number of the houses both north and south of Ignacio Boulevard (the creek crosses the roadway near Montura Way). The housing units are in poor condition and have been vacant since the fall of 1995.

Planning Area 2: Capehart Housing

Capehart Housing is a 183-acre site located in the southwestern-most portion of the Hamilton main site. The site contains substantial amounts of open space, and four large wooded knolls dominate the planning area. Capehart Housing consists of 558 single- and double-story multi-family housing units constructed in the late 1950s and

early 1960s. The units are in generally good condition. Primary access to the area is from Main Gate Road off Nave Drive.

Planning Area 3: Spanish Housing

Spanish Housing is located in the southeastern-most portion of the Hamilton main site. The site consists of 132 residential units and 16 other buildings on 125 acres with a high visual quality. Many of the Spanish-style residential units, constructed in the 1930s, are considered historic. The other buildings have been used primarily as recreational and support facilities. Primary access to the planing area is via Crescent Drive off Main Gate Road.

Planning Area 4: Commissary Triangle

The Commissary Triangle is located on the northernwestern portion of the Hamilton main site. The area is separated from Nave Drive and Highway 101 by Christmas Tree Hill. The remainder of the planning area is flat and completely urbanized. The 12-acre site contains 10 nonresidential buildings that have been used as dry cleaning facilities, vehicle maintenance shops, a morgue, offices, retail stores, storage warehouses, and the Commissary. Primary access is from State Access Road off Nave Drive.

Planning Area 5: Exchange Triangle

The Exchange Triangle, consisting of 26 acres and 16 nonresidential buildings, is located in the northwestern portion of the Hamilton main site. The site is flat and completely urbanized. The buildings have been used as vehicle maintenance shops, service stations, housing, mess halls, for exchange and commissary uses, education and daycare facilities, and recreational facilities. The area currently contains the exchange, thrift store, credit union, gas station, warehouses, youth center, playgrounds, and a skateboard ramp. Primary access is from Main Gate Road off Nave Drive.

Planning Area 6: Town Center

The Town Center is located in the central portion of the Hamilton main site. The area consists of four nonresidential buildings, including the historic Hamilton Theater and Noncommissioned Officer's Club, on five acres. The site is adjacent to the New Hamilton Partnership town center and Hospital Hill. Primary access is via Main Gate Road.

Planning Area 8: Bowling Alley


The Bowling Alley, a three-acre site located in the central portion of the main site, is dominated by the historic bowling alley and racquetball court building. The site is located in a valley area surrounded by hillsides. Primary access is via San Pablo Avenue.

Planning Area 9: Officer's Club


The Officer's Club is located on a hillside adjacent to Spanish Housing. The five-acre site includes two nonresidential building, including the Officer's Club and historic Bachelor's Officers' Quarters. The Officer's Club now serves as the Community Center. Primary access is via El Bonita Road.

Planning Area 10: Ballfields

The Ballfields area consists of two regulation ballfields, two little league fields, and a recreation center on 24 acres of land. The site is generally flat and located within the 100-year floodplain, with the exception of the pool area on a knoll overlooking one of the ballfields. Primary access is via Caliente Road.



Located approximately 20 miles north of San Francisco, the DOD Housing Facility Novato housed military personnel stationed at installations throughout the Bay Area.




Regional Location Map

DOD Housing Facility
Novato, California
Figure 1

0 11 500 23 000
Approximate 1" = 23,000'





Planning Areas 1 through 10 are owned by the Navy, with the exception of Planning Area 7, Hospital Hill, which is owned by the Army. The Army also owns the Runway area. The remainder of the site is being developed by the New Hamilton Partnership (NHP).

Source: Hamilton Army Airfield Reuse plan, 1995

TETRA TECH



Planning Areas

DOD Housing Facility Novato
Disposal and Reuse EIS
Novato, California


Figure 2

SAN MARIN HIGH SCHOOL


INDUSTRIAL ARTS
(F)




FINE ARTS
(K)




STUDENT CENTER
(H)




GYMNASIUM
(G)




MINI GYM



LIBRARY
(C)




BUSINESS-MATH
(E)



ENGLISH-SOCIAL STUDIES
(D)

PARKING LOT
ALONG SAN
MARIN DRIVE

NOVATO BOULEVARD



SAN MARIN DRIVE

NOTICE OF INTENT

The Notice of Intent to prepare the Department of Defense Housing Facility Novato Disposal and Reuse EIS appeared in the October 31, 1995, Federal Register, Volume 60, Number 210, p. 55366.

UCSD, SS&H Library, GPO Gate

http://ssdc.ucsd.edu/cgi-bin/SFgpo...a/1995_register/fr31oc95.dat wais:

[Federal Register: October 31, 1995 (Volume 60, Number 210)]

[Notices]

[Page 55366]

From the Federal Register Online via GPO Access [wais.access.gpo.gov]

=====

[[Page 55366]]

DEPARTMENT OF DEFENSE

Department of the Navy

Notice of Intent To Prepare an Environmental Impact Statement for the Disposal and Reuse of the Department of Defense Housing Facility, Novato, CA

Pursuant to Section 102(2)(c) of the National Environmental Policy Act (NEPA) of 1969 as implemented by the Council on Environmental Quality regulations (40 CFR Parts 1500-1508), the Department of the Navy in coordination with the City of Novato, is preparing an Environmental Impact Statement (EIS) for the proposed disposal and reuse of the Department of Defense Housing Facility (DODHF) property and structures at Novato, California. This proposed action is in accordance with the Defense Base Closure and Realignment Act (Public Law 101-510) of 1990, as implemented by the 1993 Base Closure process, which directed the Navy to close DODHF.

DODHF is within the jurisdiction of the City of Novato, Marin County, California, approximately 20 miles north of San Francisco. DODHF is one of several facilities on a larger area formerly known as the Hamilton Air Force Base. DODHF consists of approximately 481 acres of Navy-owned land in two sites. The 383 acre primary DODHF facility includes military family housing, commissary, exchange, community services areas, bowling alley, officer's club, and recreational fields. An additional 98 acre Rafael Village military housing area is located 1 mile north of the main DODHF facility. Other portions of the former Hamilton Air Force Base adjacent to DODHF and not included with the disposal of the DODHF property or in this disposal and reuse EIS, include the 720 acre former Hamilton Army Air Field, which was closed under the Defense Base Closure and Realignment Act (Public Law 100-526) of 1988, and a 415 acre site being developed under the New Hamilton Partnership Master Plan.

The EIS will address the potential impacts to the environment that may result from the disposal of the Navy's DODHF property and subsequent reuse. The Hamilton Army Air Field Reuse Plan, developed by the Hamilton Reuse Planning Authority, proposes 406 acres of housing with up to 1,490 total units, 51 acres of mixed use community support facilities, and 24 acres of recreational fields on the DODHF property.

The Reuse Plan will constitute the preferred alternative for the EIS. However, the EIS will also analyze alternatives to the Reuse Plan. The alternatives analyzed in the EIS will include a less intensive development of the DODHF property, still based in large part on the Reuse Plan, and a No Action Alternative. The No Action alternative would result in federal government retention of the DODHF property in an "inactive" status. Other alternatives may be evaluated if warranted.

Federal, state and local agencies, and interested individuals are encouraged to participate in the scoping process for the EIS to determine the range of issues and reuse alternatives to be addressed. A public scoping meeting to receive oral and written comments will be held on Thursday, November 16, 1995, at the Student Center, San Marin High School, 15 San Marin Drive, Novato, California at 7:00 p.m. In the interest of the available time, each speaker will be asked to limit their oral comments to five minutes.

In addition, written comments may be submitted no later than

DODHF Novato Disposal and Reuse Final EIS

NOTICE OF INTENT (cont'd)

December 1, 1995 to Mr. Gary Muneawa, Environmental Planning Branch, Code 185GM, Engineering Field Activity West, Naval Facilities Engineering Command, 900 Commodore Drive, San Bruno, California 94066-5006; telephone (415) 244-3022, fax (415) 244-3737. For further information regarding the Hamilton Army Air Field Reuse Plan which includes the reuse of the Navy's DODHF property, please contact Mr. K.H. Bell, Program Manager, Hamilton Reuse Planning Authority at (415) 457-5661, fax (714) 472-8122.

Dated: October 26, 1995.

M.A. Waters,

LCDR, JAGC, USN, Federal Register Liaison Officer.

[FR Doc. 95-26926 Filed 10-30-95; 8:45 am]

BILLING CODE 3810-FF-M

NEWSPAPER ADVERTISEMENT-EIS PREPARATION

The following newspaper advertisement announcing the preparation of the Department of Defense Housing Facility Novato Disposal and Reuse EIS and the start of the public scoping process was published in the San Francisco Chronicle and Marin Independent Journal on Sunday, November 5, 1995, and Monday, November 6, 1995, and in the Novato Advance on Wednesday, November 15, 1995.

PUBLIC NOTICE

The United States Navy announces its intent to prepare an Environmental Impact Statement (EIS) to evaluate the environmental impacts of disposal and proposed reuse of the Navy Public Works Center, Department of Defense Housing Facility (DODHF) in Novato, CA. DODHF includes all Navy-owned property and structures at the former Hamilton Air Force Base as well as the off-site Rafael Village Housing Facility. The Navy's Engineering Field Activity West, Naval Facilities Engineering Command will be the lead agency for the preparation of the EIS. This action is being conducted in accordance with the Defense Base Closure and Realignment Act of 1990 (Public Law 101-510) and the specific 1993 base closure decisions approved by the Congress in September 1993.

The EIS will address the disposal of the property and the potential impacts to the environment that may result from reuse development and a "No Action" alternative. The Hamilton Army Airfield Reuse Plan, developed by the Hamilton Reuse Planning Authority and adopted by the City of Novato on October 24, 1995, will serve as the basis for the preferred alternative. The Reuse Plan proposes 406 acres of housing with up to 1,490 total units, 51 acres of mixed use community support facilities, and up to 24 acres of recreational fields on the DODHF property. The alternatives analyzed in the EIS will include a less intensive development of the DODHF property, still based in large part upon the Reuse Plan. The No Action alternative would have DODHF remain federal government property in a caretaker status. Environmental issues that will be addressed in the EIS include, but are not limited to, land use, public policy conformity, cultural resources, transportation, vegetation and wildlife, air quality, noise, geology and soils, hydrology, hazardous materials, municipal services and utilities, and socioeconomics. The Draft EIS is due to be published in the Spring of 1996. A public hearing and a 45-day review period will follow the publication and distribution of the Draft EIS.

PUBLIC SCOPING HEARING

ENVIRONMENTAL IMPACT STATEMENT DISPOSAL AND REUSE OF THE NAVY PUBLIC WORKS CENTER

DEPARTMENT OF DEFENSE HOUSING FACILITY NOVATO, CALIFORNIA

Thursday, November 16, 1995 at 7:00 p.m.

at the following address:
SAN MARIN HIGH SCHOOL
STUDENT CENTER
15 SAN MARIN DRIVE
NOVATO, CA

The purpose of this hearing is to receive written and verbal comments regarding the potential environmental impacts of the disposal and proposed reuse of DODHF. A brief presentation will precede the request for public comment. Navy and City of Novato representatives will be available at this hearing to receive comments from the public regarding issues of concern to the public. It is important that federal, state, and local agencies and interested individuals take this opportunity to identify environmental concerns that should be addressed during the preparation of the EIS.

Agencies and the public are also invited and encouraged to provide written comments in addition to, or in lieu of, oral comments at the public hearing. To be most helpful, scoping comments should clearly describe specific issues or topics which the commentator believes the EIS should address. Written statements must be received no later than December 1, 1995. Please send written comments to: Mr. Gary Muekawa, Code 185GM, Engineering Field Activity West, Naval Facilities Engineering Command, 900 Commodore Drive, San Bruno, Ca 94066-5006, Telephone (415) 244-3022, Fax (415) 244-3737. For information regarding the Hamilton Army Airfield Reuse Plan, please contact Mr. K.H. Bell, Program Manager, Hamilton Reuse Planning Authority, telephone (415) 457-5661, fax (714) 472-8122.

No. 2171 Nov. 5, 6, 1995

SCOPING SUMMARY

Table B-1 contains a summary of the written and verbal comments received during the DODHF Novato scoping process. Verbal comments were received at the scoping meeting held November 16, 1995, in Novato, CA.

Table B-1
DODHF Novato Disposal and Reuse EIS Scoping Comment Summary

| Commenter | Form | Issues |
|---|--------|---|
| U.S. Environmental Protection Agency | Letter | <ul style="list-style-type: none"> • Include local, state, and federal agencies in process. • Provide information of air quality attainment status and criteria pollutant generation in the context of that status • Analyze reuse effects on water quality standards • Determine the need for a Section 404 discharge permit • Discuss effect to wetlands or wetland drainage areas • Describe biologically sensitive areas and the effects of reuse on these areas • Include survey of regional landfill capacity and analyze net increase/decrease in waste generation due to reuse • Discuss pollution prevention and energy conservation opportunities • Include a survey of regional water supplies available to DODHF and analyze net increase/decrease in water demand due to reuse • Include all direct and indirect traffic impacts from increased traffic associated with project buildout • Identify hazardous material storage, disposal, and contamination history • Describe proposed efforts to remove hazardous waste from the site • Describe measures taken to comply with Executive Order 12898 regarding environmental justice • Include analysis of potential cumulative effects in region of influence • Identify a Preferred Alternative and an Environmentally Preferable Alternative • Describe proposed mitigation measures • Define significance criteria and include a level of significance for each impact • Clearly define and describe baseline conditions |
| U.S. Department of Education | Letter | <ul style="list-style-type: none"> • Requested copies of all EISs prepared for DODHF properties |
| U.S. Coast Guard | Letter | <ul style="list-style-type: none"> • Requests that the EIS evaluate the environmental and socioeconomic impacts of their new housing request |
| CAL EPA, Dept. of Toxic Substance Control | Letter | <ul style="list-style-type: none"> • Identify characterization status of any contaminated areas • Address coordination of characterization and remediation actions with reuse scenarios • Discuss requirements of CERCLA for federal property transfers • Requested copies of Draft EIS |
| Historical Resources Information System | Letter | <ul style="list-style-type: none"> • Requested a copy of the Draft EIS and Final EIS |
| Marin Municipal Water District | Letter | <ul style="list-style-type: none"> • Provided facts concerning domestic water supply to DODHF |
| Sierra Club, Marin Group | Letter | <ul style="list-style-type: none"> • Describe demolition and renovation activities, including benefits and adverse impacts of demolishing Rafael Village housing units • Identify wetland and riparian areas • Describe areas of geologic or soil instability • Identify stands of native trees and rock outcroppings • Identify flooding potential • Describe interface between reuse and seasonal wetlands |
| Marin Audubon Society | Letter | <ul style="list-style-type: none"> • Describe native trees, rock outcroppings, and tree removal • Describe creeks, waterways, drainages, wetlands, and other aquatic resources • Identify flooding potential • Identify lands subject to landslides, seismic risk or other geologic instability |

Table B-1
DODHF Novato Disposal and Reuse EIS Scoping Comment Summary

| Commenter | Form | Issues |
|---|-----------------|---|
| | | <ul style="list-style-type: none"> Describe Spanish housing open space and drainage patterns |
| Marin Audubon Society (cont'd) | | <ul style="list-style-type: none"> Describe Capehart Housing open spaces and drainage patterns Show the drainage patterns at Hillside housing and discuss daylighting of undergrounded creek Describe traffic levels associated with reuse of the Town Center, Commissary, and Exchange Triangle areas and identify creeks and drainages in these areas Describe interface of ballfield lands with baylands and potential tidal marsh |
| Marin Conservation League | Letter | <ul style="list-style-type: none"> Identify impacts of demolition of Rafael Village housing units on air quality, traffic, and landfills Identify wetlands and riparian areas, native vegetation, and rock outcroppings Identify traffic impacts Identify wildlife corridors Identify reuse impacts on seasonal wetlands Identify areas subject to flooding |
| Mr. Stuart M. Flashman, for the Lanham Village Homeowners Association | Letter | <ul style="list-style-type: none"> Examine noise and air quality impacts on Lanham Village from potential development of corporation yards or semi-industrial uses Identify impacts from the mitigation measures proposed by the city and homeless providers regarding the proposed homeless shelter Discuss the compatibility of uses in Areas 4 and 5 with existing residential uses and proposed senior housing and homeless shelter uses |
| Ms. Debbie Taylor, Lanham Village Homeowners Association | Verbal Comment | <ul style="list-style-type: none"> Examine the compatibility of reuse of the Commissary and Exchange Triangle areas with the Lanham Village residential area Analyze traffic impacts |
| Mr. Alex Coutts, Hamilton Field Preservation Association | Letter | <ul style="list-style-type: none"> Expressed the opinion that Hamilton Field be returned to Marin County Provided a history of how Marin came to deed the property to the military |
| Mr. Robert Grice, Ignacio Neighborhood Committee | Verbal Comment | <ul style="list-style-type: none"> Expressed support for demolition of Rafael Village housing units Examine asbestos and lead issues connected with units to be demolished |
| Mr. Bruce Johnson, Novato Little League | Verbal Comment | <ul style="list-style-type: none"> Expressed concern for the continuing viability of using the Little League fields located in planning area 10, specifically access to the fields, the availability of adequate parking, whether utility construction at the fields will be completed in time for the 1996 spring season, and if electricity and water service will still be available to the fields after base closure |
| Mr. Donald Dunn | Letter | <ul style="list-style-type: none"> Requested that the Navy consider the impact of putting a corporate yard or bus transit yard next to Lanham Village housing development |
| Dr. Merton Shelton, M.D. | Verbal Comment | <ul style="list-style-type: none"> Expressed the opinion that the Hamilton property should be retained in public ownership for parks, sports, the arts, a small airport rather than housing developments that will generate more traffic on already crowded roads |
| Mr. Bill Long | Verbal Comments | <ul style="list-style-type: none"> Encouraged the Navy to maintain or accelerate the EIS base conversion process to avoid the problems that have hindered reuse at Hamilton in the past Requested that the EIS not waste time examining alternatives already rejected by the reuse authority through the community reuse planning process; rather, study the impacts of the adopted reuse plan in detail |
| Ms. Diane Dito | Verbal Comment | <ul style="list-style-type: none"> Supported conversion of airstrip to wetlands |
| Ms. Betty Pagett | Verbal Comment | <ul style="list-style-type: none"> Identify the process for evaluating the environmental impacts of homeless and transitional housing |



DEPARTMENT OF THE NAVY

ENGINEERING FIELD ACTIVITY, WEST
NAVAL FACILITIES ENGINEERING COMMAND
900 COMMODORE DRIVE
SAN BRUNO, CALIFORNIA 94066-5008

IN REPLY REFER TO:

5090.1B
1852GM/EP7-1190
30 January 1997

NOTICE OF PUBLIC HEARING

**Draft Environmental Impact Statement for the Disposal and Reuse
of the former Department of Defense Housing Facility, Novato, California**

7:00 P.M.

THURSDAY, FEBRUARY 27, 1997

SAN MARIN HIGH SCHOOL

STUDENT CENTER

15 SAN MARIN DRIVE

NOVATO, CALIFORNIA

A public hearing to receive oral and written comments concerning the Draft Environmental Impact Statement (EIS) will be held at 7:00 p.m. on Thursday, February 27, 1997 in the Student Center at San Marin High School, 15 San Marin Drive, Novato, California. Federal, state, and local agencies, and interested individuals are encouraged to participate in the environmental review process for the Draft EIS. In the interest of available time, each speaker will be asked to limit oral comments to five (5) minutes or less, and may submit lengthy or more detailed comments in writing to the address listed at the end of this announcement.

The former Department of Defense Housing Facility (DODHF), Novato closed on 30 September 1996 pursuant to the Defense Base Closure and Realignment Act, Public Law 101-510, as amended, Title XXIX, and specific base closure decisions approved by Congress in September 1993.

As part of this process, the Department of Navy has prepared a Draft EIS to evaluate the potential for significant environmental effects of the proposed federal disposal and community reuse of DODHF Novato. The Draft EIS has been prepared pursuant to Section 102 (2)(c) of the National Environmental Policy Act and the Council on Environmental Quality implementing regulations (40 CFR 1500-1508).

The Hamilton Reuse Planning Authority (HRPA) developed a Final Reuse Plan (Hamilton Army Airfield Reuse Plan) for the DODHF Novato property that was adopted by the City of Novato in October 1995. The Reuse Plan was subsequently revised in February 1996, and again in November 1996. The preferred reuse alternative in the Draft EIS is the revised Reuse Plan alternative. The revised Reuse Plan stresses adaptive reuse of existing facilities. It includes housing, open space, community facilities, and small amounts of neighborhood commercial development.

In addition to the Revised Reuse Plan Alternative, the other alternatives analyzed in the Draft EIS include an Open Space Alternative that would be similar to the Reuse Plan but would have 500

fewer housing units, more open space, and more community facilities, and a "No Action" alternative that would result in the DODHF Novato property remaining in federal ownership in a caretaker status.


The Draft EIS is available for review at the following public libraries in the vicinity of DODHF Novato:

Novato Public Library; 1720 Novato Blvd.; Novato, CA
Marin County Library; Marin Civic Center; San Rafael, CA
Petaluma Regional Library; 100 Fairgrounds Drive; Petaluma, CA
Sonoma County Central Library; 3rd and E Streets; Santa Rosa, CA

Written comments concerning the Draft EIS must be submitted no later than March 17, 1997 to:

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
Attn: Mr. Gary J. Munekawa, Environmental Planning Branch,
Code 1852GM,
900 Commodore Drive
San Bruno, California, 94066-5006

For additional information on the EIS, contact Mr. Munekawa at the address shown above, telephone (415) 244-3022 or fax (415) 244-3737. A limited number of copies of the EIS are available for individual review upon request. For information concerning the community reuse planning process, please contact Mr. Ken Bell at telephone (510) 906-1460 or fax (714) 472-8122. Thank you for your participation in this process.


JOHN H. KENNEDY
Head, Environmental Planning Branch

Enclosure

NOTICE OF AVAILABILITY

The Notice of Availability of the Department of Defense Housing Facility Novato Disposal and Reuse Draft EIS appeared in the January 31, 1997, Federal Register. The Notice of Public Hearing appeared in the February 6, 1997, Federal Register.

[Federal Register: January 31, 1997 (Volume 62, Number 21)]
[Notices]
[Page 4759]
From the Federal Register Online via GPO Access [wais.access.gpo.gov]
[DOCID:fr31ja97-58]

[[Page 4759]]

=====

ENVIRONMENTAL PROTECTION AGENCY

[ER-FRL-5476-9]

Environmental Impact Statements; Notice of Availability

EIS No. 970034, Draft EIS, USN, CA, Novato, California Department of Defense Housing Facility Disposal and Reuse, Implementation, City of Novato, Marin County, CA, Due: March 17, 1997, Contact: Gary J. Munkawa (415) 244-3022.

=====

DEPARTMENT OF DEFENSE

Department of the Navy

Notice of Public Hearing for the Draft Environmental Impact Statement (DEIS) for the Disposal and Reuse of the Department of Defense Housing Facility, Novato, CA

SUMMARY: Pursuant to Section 102(2)(c) of the National Environmental Policy Act (NEPA) of 1969 as implemented by the Council on Environmental Quality regulations (40 CFR Parts 1500-1508), the Department of the Navy has prepared and filed with the U.S. Environmental Protection Agency a Draft Environmental Impact Statement (DEIS) for the disposal and reuse of the Department of Defense Housing Facility (DoDHF) Novato property and structures in Novato, California. The DEIS is being prepared in compliance with the 1993 Base Realignment and Closure (BRAC) directive from Congress to close DoDHF Novato. DoDHF Novato closed on September 30, 1996.

The DEIS assesses the potential impacts to the environment that may result from Navy disposal of the DoDHF Novato property and subsequent community reuse. Surplus properties will be disposed of in accordance with the provisions of the Defense Base Closure and Realignment Act (Pub. L. 101-510) of 1990 as amended and applicable federal property disposal regulations. The "Spanish Housing" parcel will be transferred to the U.S. Coast Guard and therefore will not be included in this documentation.

The Hamilton Reuse Planning Authority (HRPA) developed a Final Reuse Plan (Hamilton Army Airfield Reuse Plan) for the DoDHF Novato

NOTICE OF AVAILABILITY (cont'd)

property that was adopted by the City of Novato in October 1995. The Reuse Plan was subsequently revised in February 1996, and again in November 1996. The Revised Reuse Plan stresses adaptive reuse of existing facilities. It includes housing, open space, community facilities, and small amounts of neighborhood commercial development. This "Revised Reuse Plan" was presented in the DEIS as the preferred alternative.

Another alternative analyzed in the DEIS is an "Open Space" option that would be similar to the preferred alternative Plan but would have 500 fewer housing units, more open space, and more community facilities. A "No Action" alternative that would result in the DoDHF Novato property remaining in federal government ownership in a caretaker status was also analyzed.

The DEIS is available for review at the following public libraries in the vicinity of DoDHF Novato: (1) Novato Public Library, 1720 Novato Blvd., Novato, CA; (2) Marin County Library, Marin Civic Center, San Rafael, CA; (3) Petaluma Regional Library, 100 Fairgrounds Drive, Petaluma, CA; and (4) Sonoma County Central Library, 3rd and E Streets, Santa Rosa, CA.

ADDRESSES: The Navy will conduct a public hearing on Thursday, February 27, 1997, at 7:00 p.m., at the San Marin High School Student Center, 15 San Marin Drive, Novato, California to inform the public of the DEIS findings and to solicit comments. Federal, state and local agencies, and interested individuals are invited to be present or represented at the hearing. Oral comments will be heard and transcribed by a stenographer. To assure accuracy of the record, all comments should be submitted in writing. All comments, both oral and written, will become part of the public record in the study. In the interest of available time, each speaker will be asked to limit oral comments to five minutes. Longer comments should be summarized at the public hearing and submitted in writing either at the hearing or mailed to the address listed below.

FOR FURTHER INFORMATION CONTACT: All written comments must be submitted no later than March 17, 1997 to Mr. Gary J. MuneKawa (Code 1852GM), Engineering Field Activity West, Naval Facilities Engineering Command, 900 Commodore Drive, San Bruno,

[[Page 5621]]

California 94066-5006, telephone (415) 244-3022, fax (415) 244-3737. For information concerning the community reuse planning process, please contact Mr. Ken Bell at telephone (510) 906-1460, or fax (714) 472-8122.

Dated: February 3, 1997.

D.E. Koenig,
LCDR, JAGC, USN, Federal Register Liaison Officer.
[FR Doc. 97-3008 Filed 2-5-97; 8:45 am]
BILLING CODE 3810-FF-P

NEWSPAPER ARTICLE-AVAILABILITY OF DRAFT EIS

The following newspaper advertisement announcing the availability of the Department of Defense Housing Facility Novato Disposal and Reuse Draft EIS was published in the San Francisco Chronicle and Marin Independent Journal on Sunday, February 16, 1997, and Monday, February 17, 1997, and in the Novato Advance on Wednesday, February 19, 1997.

| Public Notice | Public Notice |
|--|---------------|
| NOTICE OF PUBLIC HEARING DRAFT ENVIRONMENTAL IMPACT STATEMENT FOR THE DISPOSAL AND REUSE OF THE FORMER DEPARTMENT OF DEFENSE HOUSING FACILITY, NOVATO, CALIFORNIA 7:00 P.M. THURSDAY, FEBRUARY 27, 1997 SAN MARIN HIGH SCHOOL STUDENT CENTER 15 SAN MARIN DRIVE NOVATO, CALIFORNIA | |

A public hearing to receive oral and written comments concerning the Draft Environmental Impact Statement (EIS) will be held at 7:00 p.m. on Thursday, February 27, 1997, in the Student Center at San Marin High School, 15 San Marin Drive, Novato, California. Federal, state, and local agencies and interested individuals are encouraged to participate in the environmental review process for the Draft EIS. In the interest of available time, each speaker will be asked to limit oral comments to five (5) minutes or less, and may submit lengthy or more detailed comments in writing to the address listed below.

The former Department of Defense Housing Facility (DODHF), Novato closed on 30 September 1996 pursuant to the Defense Base Closure and Realignment Act, Public Law 101-510, as amended, Title XXIX, and specific base closure decisions approved by Congress in September 1993.

As part of this process, the Department of Navy has prepared a Draft EIS to evaluate the potential for significant environmental effects of the proposed Navy disposal and community reuse of DODHF Novato. The Draft EIS has been prepared pursuant to Section 102(2)(c) of the National Environmental Policy Act and the Council on Environmental Quality implementing regulations (40 CFR 1500-1508).

The Hamilton Reuse Planning Authority (HRPA) developed a Final Reuse Plan (Hamilton Army Airfield Reuse Plan) for the DODHF Novato property that was adopted by the City of Novato in October 1995. The Reuse Plan was subsequently revised in February 1996, and again in November 1996. The preferred reuse alternative in the Draft EIS is the Revised Reuse Plan Alternative. This alternative stresses adaptive reuse of existing facilities. It includes housing, open space, community facilities, and small amounts of neighborhood commercial development.

In addition to the Revised Reuse Plan Alternative, the other alternatives analyzed in the Draft EIS include an Open Space Alternative that is similar to the Revised Reuse Plan Alternative but contains 500 fewer housing units and, more open space, and more community facilities, and a "No Action" alternative that would result in the DODHF Novato property remaining in federal ownership in a caretaker status.

The Draft EIS is available for review at the following public libraries in the vicinity of DODHF Novato:

Novato Public Library: 1720 Novato Blvd.: Novato, CA
Marin County Library: Marin Civic Center: San Rafael, CA
Petaluma Regional Library: 100 Fairgrounds Drive:
Petaluma, CA
Sonoma County Central Library: 3rd and E Streets:
Santa Rosa, CA

Written comments concerning the Draft EIS must be submitted no later than March 17, 1997 to:

Commanding Officer
Engineering Field Activity West
Naval Facilities Engineering Command
Attn: Mr. Gary J. Muneawa, Environmental Planning
Branch
Code 1852GM
900 Commodore Drive
San Bruno, California, 94066-5006